

A TEXT-BOOK OF PRACTICAL PHYSICS

BY

THE LATE H. S. ALLEN, M.A., D.Sc., Hon.LL.D.,
F.Inst.P., F.R.S.

EMERITUS PROFESSOR OF NATURAL PHILOSOPHY, UNIVERSITY OF ST. ANDREWS
SOMETIME READER IN PHYSICS, UNIVERSITY OF LONDON, KING'S COLLEGE
AND READER IN PHYSICS, UNIVERSITY OF EDINBURGH

AND

H. MOORE, A.R.C.S., D.Sc., F.Inst.P.

EMERITUS PROFESSOR OF GLASS TECHNOLOGY, UNIVERSITY OF SHEFFIELD, LATELY DIRECTOR
OF RESEARCH, PILKINGTON BROS. LTD., FORMERLY DIRECTOR OF RESEARCH BRITISH
SCIENTIFIC INSTRUMENT RESEARCH ASSOCIATION, SOMETIME LECTURER
IN PHYSICS, UNIVERSITY OF LONDON, KING'S COLLEGE

THIRD EDITION

LONDON
MACMILLAN & CO LTD
NEW YORK • ST MARTIN'S PRESS

First Edition 1916
Reprinted 1918, 1920 (twice), 1924, 1926
With Additions and New Chapters 1928
Reprinted 1931, 1934
Second Edition 1938
Reprinted 1941, 1943, 1945
Third Edition 1948
Reprinted 1949, 1952, 1956, 1960

MACMILLAN AND COMPANY LIMITED
London Bombay Calcutta Madras Melbourne
THE MACMILLAN COMPANY OF CANADA LIMITED
Toronto
ST MARTIN'S PRESS INC
New York

PRINTED IN GREAT BRITAIN

PREFACE TO FIRST EDITION

IN teaching Practical Physics at King's College, London, we have employed for several years manuscript books of instructions for experiments, each providing a short description of the apparatus required together with the necessary theory. But we have felt the need of permanent records easily available for large numbers of students, and it is hoped that this book, based on these laboratory instructions, will prove of service not only to our own students but also to those of other teachers.

The work is designed primarily to cover the Intermediate Pass Courses in Science, Engineering, and Medicine of the University of London, but it is also suitable for Intermediate Honours candidates and for University Scholarships. Further, it meets the requirements of the Civil Service Commissioners in connection with Junior Appointments, the Post Office (Engineers), and the Army Entrance Examination.

No student could be expected to cover in one year the whole of this course, and a selection of suitable experiments to meet the needs of particular students should be made by the teacher. The fact that Engineering Students in the University of London are required to take a practical course in Applied Mathematics explains the presence of a larger number of experiments in practical mechanics than is usual in a text-book of Practical Physics.

For completeness, the scope of the book has been extended somewhat and a limited number of more advanced experiments has been included. For example, a description of the simpler phenomena of Surface Tension, and of the elementary methods by which it can be measured, has been incorporated though not usually studied in an Intermediate Course. In the part dealing with Electricity will be found a number of experiments suitable for students who are commencing the study of Electrical Engineering.

The volume in its present form covers the greater part of the work necessary for a Pass Degree in Science in most Universities.

The letterpress has been divided so as to separate descriptions and theoretical discussions from those parts of the nature of laboratory instructions; the latter are indicated by indenting the letterpress. The teacher should select for each meeting of the class experiments suitable for the individual students, and it is a good plan for the student to be informed at the end of the day's work what section he should read in preparation for the next practical class.

It is seldom that sufficient apparatus is available for all students to be working at the same experiment simultaneously, and it is usually impossible to arrange that each individual student should follow the exact order here given.

The student must be warned against a prevalent idea that an experiment is completed when the manipulations or observations are finished. It must be made clear to him that the results must be calculated and considered with care, and a record of the experiment be written in his own words.

Every experimental exercise should have for its object the elucidation of physical principles, and we have kept in view the theoretical aspect of the experiments throughout this work. Stress has been laid on the degree of accuracy obtainable in an experiment, and the student has been shown how to conduct the measurements so as to obtain the best results with the means at his disposal.

Most of the experiments described are such as can be carried out with simple apparatus. Many instrument makers advertise for laboratory use apparatus more adapted for lecture purposes. The apparatus used in a laboratory course should be such as will develop experimental and manipulative skill. Hence, although measuring instruments of precision are essential, the use of elaborate apparatus, sometimes almost automatic in its action, is to be deprecated in a laboratory for students.

An important educational aim, to be kept in mind by the teacher of Physics, is the development of men and women capable of doing good work in adverse or unfamiliar circumstances, and of carrying out original investigation and research. For this, facility in the handling of apparatus and co-ordination of hand, eye, and ear are essential.

Several additional exercises, many selected from College examination papers, have been given at the end of each Part.

Most of the diagrams have been drawn specially for this book, but we are indebted to Messrs. Macmillan & Co., Ltd., for a number of illustrations, and gladly thank the Cambridge Scientific Instrument Company and Messrs. R. W. Paul for several pictures of apparatus.

Mr. F. Castle has been good enough to grant permission for the inclusion at the end of the volume of mathematical tables selected from his *Logarithmic and other Tables for Schools*.

In conclusion, we desire to thank sincerely Sir Richard Gregory and Mr. A. T. Simmons for the great assistance they have rendered by invaluable suggestions and advice while the book was passing through the press.

H. S. ALLEN
H. MOORE

THE TEACHING OF PHYSICS

EVERY science student must deal with knowledge derived from general experience and also with that based on scientific observation, but the student of physics in a special degree is concerned with 'the systematic study of natural phenomena under conditions controlled by the investigator'. The scientific method is essentially *experimental* in character. In using this method we aim at studying one variable at a time. It is because of the difficulty of applying the principle of the isolation of the variables that the solution of social problems is so difficult.

In a well-known statement Lord Kelvin asserted that, until you can measure in numbers what you are speaking about, your knowledge is meagre and unsatisfactory; or as J. B. Biot said: 'All these things can be determined with certainty only by means of exact measurements which we shall seek later, but in the first place we must feel the necessity for this search'. In a stimulating lecture on the foundations of electrical measurement L. Hartshorn¹ accepts the definition of Norman Campbell: 'Measurement is the assignment of numerals to represent properties *in accordance with scientific laws*'. The last clause stresses the need for a close and direct connection between the choice of numerals and experimental laws. Measurements may well be called *fundamental* when they are made by operations which enable us to judge equality, and to determine whether the laws of addition are satisfied. 'These operations constitute the real definitions of the properties.' After a short account of the fundamental measurements of length, mass, time (or frequency), and angle the author goes on to show that there are at least three purely electrical properties which can be measured with the highest precision by fundamental operations—they are resistance, mutual inductance, and capacitance.

'The earlier investigators, owing to their following the conceptions of the ancients, generally obtained their propositions in the cumbersome form of proportions' (Mach). At the present time it seems quite natural for the scientific worker to state such a result in the convenient form of a simple equation expressing the fact that when the variable y is directly proportional to the independent variable x ; we may write $y = kx$, where k is 'a factor of proportionality'. We extend our observations over as wide a range as possible to find

¹ *Journal I.E.E.* 91, p. 377, 1944; *Nature*, 154, p. 534, 1944.

whether this factor or coefficient k is strictly a constant. In such an inquiry the familiar graphical method is of great advantage, and should be consistently used by the student, who should also be encouraged to apply the idea of a constant factor, k , to the so-called 'laws' which are met with. Even so simple a question as the acceleration of a falling body had never been stated clearly before the time of Galileo, who wrote: 'It is requisite to know according to what proportion such an acceleration is made; a problem that I believe was never understood hitherto by any philosopher or mathematician, although philosophers, and particularly the peripatetics, have written great and entire volumes touching motion'. This result serves as a good illustration of the danger of undue 'extrapolation'. We are not justified in extending the range of our 'law' beyond the range of our observations. In this particular instance the failure of the 'law' of Galileo led Newton to the law of gravitation, and the failure of Newton's law led to the development of the theory of relativity. It has been well said that we teach by the method of diminishing deception!

As in every physical laboratory there are students of very different mathematical knowledge and ability, it is desirable to select, so far as possible, experiments and method of treatment to suit individual students. As one illustration, two methods of approach are given to the subject of magnetometry (p. 340), the first being of an experimental character and the second being based on a more accurate mathematical development depending on the law of the inverse square of the distance. The difference in outlook between the two types of student corresponds to an important distinction in the development of natural philosophy. Some prefer to work from the particular to the general, while others find more mental satisfaction in following out the consequences of a general 'law' or principle. Both methods are valuable, and one should not be adopted to the entire exclusion of the other.

In this book the automatic use of a mathematical formula has been discouraged. The ability to substitute numerical values in a given formula has been termed 'the lowest order of mathematical intelligence'. The student should look for the basic principle, not for a formula.

In this connection there must be emphasised the further fact that the intermediate steps in a calculation frequently represent physical magnitudes of great importance, more particularly when definite amounts of energy are involved. This point is stressed in the Introductory chapter, which the student should study at the outset, before commencing experimental work.

There is another problem related to the question of accuracy

(see pp. 6-8) which may be mentioned here. In commercial and industrial affairs *rapidity* of measurement has become of the greatest importance. Now that physicists are often concerned in the scientific development of manufacturing processes, it is desirable that more attention should be paid to speed in obtaining a result. In aeronautics it is obviously essential that instruments used by the pilot or navigator should register the required quantity almost instantaneously. Even in the elementary laboratory the range of experimental work is continually increasing, and so it becomes desirable to shorten the time required for individual experiments provided sufficient accuracy is obtained. For example, there is a convenient type of gravity balance supplied under the name of the Butchart or Lever balance, which registers the weight of a body by the deflection of a pointer moving over a scale. The scale is empirical but may be calibrated by using a box of weights. This is particularly useful for class demonstrations, and it enables a student to carry out rapidly a number of weighings in illustration of the principle of Archimedes or for the determination of relative density. In more advanced work with an accurate balance considerable improvements have been made in order to reduce the time required for weighing, as for instance by using electromagnetic damping, or devices for recording the result almost automatically.

In the measurement of time very great advances have been made through improvements in pendulum clocks, the introduction of the quartz oscillator, and the radio-transmission of time signals. The broadcasting of such signals by means of the familiar six 'pips' has indeed brought about a revolution in the accurate determination of time. The interval between consecutive pips is one second, and it is the last of the series which indicates the exact time, the accuracy claimed being at least one-twentieth of a second. Counting seconds should be practised, and the further application of these signals in laboratory work, as for example in timing a compound pendulum, deserves careful study.

A question which often arises, and may cause difficulty to the director of a laboratory, is that of the provision of suitable apparatus for practical work. The answer must depend on such circumstances as the size of the class, the nature of the course, and the financial provision that can be secured. The present Lord Rayleigh (1944) asked the question: 'Are expensive appliances necessary?' His reply was: 'In the physical laboratory a great deal can be learnt about Wheatstone's bridge by means of a wire stretched along a rough board, graduated with ink or pencil marks, with a piece of metal held in the hand to make contact with it at any point. From a purely teaching point of view this is as good as, if not better than, a post-office box costing as many pounds as the other does pence. It is much less

likely to muddle the beginner and will in all probability give him more insight into the physics of what he is doing. If the student has rigged it up for himself he will further get a sense of independence and achievement which he never gets by handling the elaborate constructions of the instrument maker.'

For experiments in Light, 'mirrors and lenses may be mounted in a few minutes on two lumps of soft wax or attached with "plasticine" to a strip of wood'. It may be added that a fairly efficient optical bench may be constructed by fixing two or three metre scales to the edge of the bench by means of simple G clamps, and mounting the optical apparatus described in the chapters on Light on blocks of wood that can slide on the table in contact with these scales, not forgetting the essential 'distance piece'.

Manufacturers of scientific apparatus often overlook the fact that for teaching purposes the novice should not be given a merely automatic machine, carefully enclosed and concealed in a well-made case, even though the desired measurement may be obtained by simple inspection. It is of the greatest importance that the beginner should be able to study the mechanism and the arrangement of the parts, at least to the extent of understanding the principles involved.

There is, however, another side to this problem. In order to secure results of high accuracy, expensive instruments may be essential and they are frequently more durable and more reliable than cheaper forms of apparatus. Even the beginner is liable to be discouraged when he finds that it is practically impossible to secure consistent results by using the apparatus provided.

It is most desirable that students of physics, especially those who are likely to take up Applied Physics or proceed to research in Pure Physics, should have at an early period some experience in engineering drawing and in practical operations and processes, such as glass-blowing and soldering. It is said that Sir Charles Boys in a practical examination set the question: 'Repair the given leaky calorimeter and use it to find the specific heat of the given solid'. Other examiners have adopted similar methods in practical examinations.

The ideal physicist, as well as being a philosopher, should be also a 'craftsman' with sympathetic knowledge of tools and materials. Craftsmanship is creation, and in order to create it is necessary to understand. 'Why,' said the Dodo, 'the best way to explain it is to do it.'

CONTENTS

PART I

PROPERTIES OF MATTER

CHAP.	PAGE
I. INTRODUCTION	3
II. MEASUREMENT OF FUNDAMENTAL QUANTITIES	12
III. MEASUREMENT OF QUANTITIES IN DERIVED UNITS	27
IV. DETERMINATION OF SPECIFIC GRAVITIES	40
V. STATICS	51
VI. MACHINES	77
VII. ELASTICITY	86
VIII. DYNAMICS	101
IX. PERIODIC MOTION	123
X. GASES : THE BAROMETER AND BOYLE'S LAW	137
XI. SURFACE TENSION	150

PART II

SOUND

I. INTRODUCTORY THEORY	163
II. FREQUENCY	171
III. TRANSVERSE VIBRATIONS OF A STRETCHED STRING	180

PART III

LIGHT

I. THE LAWS OF GEOMETRICAL OPTICS	191
II. SPHERICAL MIRRORS	206
III. LENSES	211
IV. FURTHER EXPERIMENTS WITH MIRRORS AND LENSES	217
V. THE OPTICAL BENCH	224

CHAP.	PAGE
VI. OPTICAL INSTRUMENTS	230
VII. SPECTRA AND THE SPECTROMETER	239
VIII. PHOTOMETRY	247
IX. MEASUREMENT OF WAVE-LENGTH	254

PART IV

HEAT

I. THERMOMETRY	265
II. COEFFICIENTS OF EXPANSION	273
III. CALORIMETRY	286
IV. COOLING	297
V. THE COEFFICIENT OF THERMAL CONDUCTIVITY	304
VI. THE MECHANICAL EQUIVALENT OF HEAT	310
VII. HYGROMETRY	318

PART V

MAGNETISM

I. FUNDAMENTAL PROPERTIES AND LAWS	327
II. MAGNETOMETRY	337
III. THE OSCILLATIONS OF A MAGNET IN A MAGNETIC FIELD	347
IV. THE EARTH'S MAGNETIC FIELD	353

PART VI

ELECTRICITY


I. ELECTROSTATIC EXPERIMENTS	363
II. CURRENT ELECTRICITY — INTRODUCTORY	371
III. APPARATUS FOR THE MEASUREMENT OF CURRENT	381
IV. ELECTROMOTIVE FORCE AND INTERNAL RESISTANCE OF A CELL	395
V. MEASUREMENT OF RESISTANCE	411
VI. ELECTROLYSIS — ELECTROCHEMICAL EQUIVALENTS	432
VII. THE HEATING EFFECT OF AN ELECTRIC CURRENT	440
VIII. ELECTROMAGNETIC INDUCTION	444

CONTENTS

CHAP.	PAGE
IX. COMPARISON OF CAPACITIES	470
X. NOTES ON ELECTRICAL APPARATUS	473
XI. HIGH-FREQUENCY OSCILLATIONS — ELECTRO- MAGNETIC RADIATION	492
XII. THERMIONIC VALVES	504
SUPPLEMENT : NOTES ON GEOMETRICAL OPTICS	545
APPENDIX : PHYSICAL CONSTANTS AND MATHEMATI- CAL TABLES	559
INDEX	581

PART I

PROPERTIES OF MATTER



SYSTEMS OF UNITS

F.P.S. Foot-Pound-Second

Unit of force — POUNDAL

Unit of energy — FOOT-POUNDAL

C.G.S. Centimetre-Gram-Second

Unit of force — DYNE

Unit of energy — CM.-DYNE or ERG

M.K.S. Metre-Kilogram-Second

Unit of force — NEWTON (10^5 dynes)

Unit of energy — NEWTON-METRE
or JOULE (10^7 ergs)

PREFIXES

deci = 1 tenth 10^{-1}

centi = 1 hundredth 10^{-2}

milli = 1 thousandth 10^{-3}

micro = 1 millionth 10^{-6}

kilo = 1 thousand 10^3

mega = 1 million 10^6

CHAPTER I

INTRODUCTION

§ 1. GENERAL INSTRUCTIONS

IN the practical work of any branch of science, the results aimed at may be divided into two kinds : **qualitative** and **quantitative**. In physics, advance has been rapid mainly because quantitative experiments have been successful in co-ordinating the facts, and purely qualitative results are no longer sufficient. Almost every physical experiment involves the taking of one or more measurements, so that physics has been termed, somewhat contemptuously perhaps, 'the science of accurate measurement'. Even in the elementary stages the experimental work will often give quantitative results with little more trouble than would be required to obtain mere qualitative knowledge.

The fact that *measuring* is such an important part of the practical side of physics, sometimes leads to a student hurriedly taking certain measurements without studying the apparatus he uses, and without taking more than one series of observations. Too much stress cannot be laid on the really *practical* side of physics, as distinct from the mere taking of readings. To obtain full benefit from a course of practical physics, not only should the purpose of an experiment be understood thoroughly, but also some time must be spent in setting up the apparatus and studying carefully the construction and working of the component parts, before a single observation is taken.

The purpose of a course of practical physics is not fulfilled completely unless the student acquires dexterity in the manipulation of apparatus and sympathy with the instruments he uses.

Having realised the aim of an experiment and the general method to be adopted in carrying it out, the necessary apparatus must be assembled and arranged for use. It is of great importance that all observations and readings should be obtainable without necessitating awkward bodily positions ; also any part of the apparatus requiring frequent manipulation or adjustment should be placed within easy reach. Careful attention to these points will react indirectly on the accuracy of the experiment ; there will also be less likelihood of accidentally deranging the apparatus.

It may be convenient to go rapidly through an experiment to see that all is in order, before making any accurate observations.

§ 2. RECORDING RESULTS — NOTE-BOOKS

For a course of practical physics two note-books should be used. One of these is reserved for the 'fair' record; it should be a large note-book (quarto size is suitable) with alternate pages ruled in millimetre squares. An alternative method is to use a 'loose leaf' laboratory note-book for which regulation sheets and graph papers are provided. The sheets are clipped together by a rivet and collected in a cover. A smaller note-book is needed for recording observations, and for calculations; in this should be entered also a description of any noteworthy phenomena observed during an experiment, brief notes being taken in the laboratory to be amplified later in the fair record. The taking of these rough notes is quite as important as any other part of the work done, especially if there is any delay in writing up the final account; points which are of considerable importance may be forgotten if no record is made of them at the time they are observed. Rough notes on loose sheets of paper are mislaid easily, and for his own sake the student should avoid taking notes in this manner.

In taking observations and readings, *every measurement made should be recorded in the rough note-book immediately, and checked after it has been written down.* Each number should have written against it what it represents, and where a series of sets of observations is made, the observations should be arranged in tabular form. *All calculations required for working out the result must be done in the rough note-book, and must be shown clearly.*

In the large note-book a full record of each experiment should be given *in the student's own words.* The record should be made according to a definite scheme such as that given below.

1. A description of the apparatus, with diagrammatic illustrations drawn on squared paper, and lettered for reference.
2. A short account of the theory of the experiment.
3. A detailed account of the operations carried out, and of the observations taken. Each reading or observation must be entered; and where series of observations are made, these should be tabulated.
4. The result obtained from the experiment should be entered, *but not the arithmetical working.* In general, it is convenient to enter the result as a compound fraction, followed by the calculated value expressed as a whole number or as a decimal fraction.

The result should be entered *prominently*, preferably occupying the last line of the record. The units in which the result is expressed must be stated.

Wherever possible, the results should be expressed graphically; each graph should occupy one complete page, and the names of the

quantities plotted, with the units in which they are represented, must be given.

When a graphic construction forms part of an experiment, the original drawing (or a copy drawn to scale) should be inserted in the note-book.

§ 3. ACCURACY OF OBSERVATIONS — NULL METHODS AND DEFLECTION METHODS

'The whole system of civilised life may be fitly symbolised by a foot rule, a set of weights, and a clock.' Maxwell's symbols correspond to the measurement of the 'fundamental' quantities *length*, *mass*, and *time* described in Chapter II. We consider first the determination by direct observation of a quantity such as a length or a mass.

In this case, readings should be taken to the highest degree of accuracy obtainable with the apparatus provided. To test the degree of accuracy obtainable the adjustment should be repeated, and the reading taken again with the greatest possible care; any discrepancy between the two readings is attributable to errors inherent in the apparatus, provided sufficient care has been taken in adjustment and reading.

In dealing with 'derived' quantities (Chapter III) we usually have to measure a number of magnitudes; for instance, in finding the density of a solid we must measure both its mass and its volume. It is necessary to examine carefully the *relative* accuracy of the separate measurements, since it is useless to measure the mass to one part in ten thousand, if the volume is accurate only to one part in a thousand. Special attention must be directed to those measurements for which the accuracy is least.

It is good practice for a student to determine as before the degree of accuracy obtainable in various types of measurement during the earlier stages of a practical physics course. This experience will enable him later to estimate the proportional accuracy of most types of observations, without making an actual determination; though whenever a completely new kind of measurement has to be made, the proportional accuracy should be determined once or twice in this way.

Null methods are, in general, more accurate than deflection methods, in which the magnitude of an effect is usually measured by reading the position of a pointer on a scale. When using a null method in any experiment, we balance the effect of an unknown quantity against the effect of a known or standard quantity of the same type. The resulting effect is observed on an instrument which has to detect only the slight difference between the two effects. If we measured the effect of either quantity directly, we should require to use an instrument which gives

only a moderate deflection when subjected to the whole effect, or *an instrument of relatively low sensitiveness*. As a result of this low sensitivity, a small, unavoidable error in reading the deflection would have an appreciable effect on the result. If a null method were employed, a much more sensitive instrument could be used — an instrument of the highest sensitiveness possible. The possible error in adjusting the effects to reduce the reading to zero would probably be the same amount *on the scale of the instrument* as was the error of reading in the deflection experiment; it would, however, indicate a very much smaller error in the quantity under measurement.

An excellent example of this principle is afforded by the measurement of mass. A spring balance measures the mass by a deflection method, the quantity observed being the extension of the spring due to the weight of the body. An ordinary balance is an apparatus which depends on a null adjustment, and gives much greater accuracy than can possibly be obtained by a spring balance designed to weigh up to the same limit.

In an elementary physical laboratory observations which depend on weighing are much more accurate than determinations depending on either length or time. Wherever possible, experiments should be designed in such a way that the most important observations are made by means of a balance. As an example of this, the student is referred to the experiment on the expansion of liquids by means of a weight thermometer. This experiment is so arranged that the coefficient of increase of *volume* is found without a single determination of volume being made, every observation from which the result is calculated being a 'weighing'.

In the present century great progress has been made in the measurement of time, but this, like the determination of length by optical methods, requires elaborate apparatus. Without such aids no other physical determination can be made so accurately as the determination of mass or the comparison of masses, owing to the great sensitiveness which is obtainable with a well-designed balance. The only other simple physical measurement which approaches this in accuracy is the determination of electrical resistance by means of a Wheatstone's Bridge, again a *null* experiment.

§ 4. CALCULATION OF RESULTS

Since there is a limit to the accuracy obtainable in the determination of any physical quantity, it is obvious that there must also be a limit to the accuracy of any result calculated from such determinations. In calculating results, therefore, it is unnecessary to work to a greater number of significant figures than the observations merit; the final

result can only be trusted to a certain number of places, and any figures beyond this number are meaningless.

Much labour will be saved in arithmetical calculations if, at each stage in the calculation, the number of significant figures in the result of that stage is suitably cut down before proceeding to the next part of the calculation. For example, consider the determination of the volume V of a cylinder which is 2.37 cm. long, and 1.13 cm. in diameter.

Its volume is given by $\frac{\pi}{4} \times (1.13)^2 \times 2.37$ c.c.

Neither of the measured quantities is more accurate than 1 in 1000, and there is therefore no need to retain more than four figures after any arithmetical process; and π may be taken as 3.142, or even as 3.14.

$(1.13)^2$ is 1.2769, and may be taken as 1.277.

1.277×2.37 is 3.02649, and may be taken as 3.026.

$3.026 \times \frac{\pi}{4}$ is 3.026×0.7854 , which gives as the product 2.3766204,

and the final result is written down as 2.38 c.c.

Contracted methods of multiplication are of great value in simplifying the arithmetical work.

It has become customary to give results only to such a number of figures as can be claimed to be accurate. If therefore a result is stated to five figures, it is at once assumed that accuracy to five figures is claimed. To write down five figures in a result which is only accurate to 1 in 1000 is thus not only unnecessary but misleading, as giving an erroneous idea of the accuracy of the observations on which it is based.

If it should happen that the last significant figure is a cipher, this is included in the result even if it is after the decimal place, its inclusion indicating that accuracy is claimed to that number of significant figures, *e.g.* 1 in. = 2.5400 cm. indicates that this is true to 1 part in 25,000.

When the numbers dealt with are very large, powers of 10 are often put after a small number instead of writing a large number of ciphers after it. For example, the magnitude 28,000,000 may be written as 2.8×10^7 if accuracy of 3 or 4 per cent only is claimed, but 2.80×10^7 , 28.0×10^6 , or 280×10^5 if the accuracy is 1 in 300. Similarly negative powers of 10 are used for extremely minute quantities instead of writing a number of ciphers after the decimal point. Thus, 0.00003500, indicating accuracy of 1 in 3000, could be written as 3500×10^{-8} , but to write it as 3.5×10^{-5} would be incorrect, as claiming an accuracy of 3 per cent only instead of 1 in 3000.

In calculations made by logarithms the order of the approximations made depends on the number of figures in the tables of logarithms

used. Four-figure logarithms give an accuracy of about 1 in 2500 in a calculation involving four or five numbers, the possible error increasing with the number of factors to be multiplied together or divided. Five-figure logarithms are about ten times as accurate as this.

A slide-rule (10 inch) is useful for rough calculations, but if more than four factors are multiplied or divided, greater accuracy than 1 in 500 is not obtainable except with much care.

In most cases, before performing the accurate calculations, approximate calculations should be made in order to determine the *order of magnitude* of the result (or the position of the decimal point); *this precaution is of special importance when a slide-rule is used*, especially in inexperienced hands.

An example of this may be given, using the dimensions of the cylinder of volume V on p. 7. In that case $V = \frac{\pi}{4} (1.13)^2 \times 2.37$. Roughly this may be written down as $V = 1 \times 1.0 \times 1.2 \times 2.5$, or $V = 3$, approximately, so that the volume is of the order of 3 c.c.

The slide-rule gives the number 237 (5) as the result, and this can be written at once as 2.38 c.c., the position of the decimal point being determined by the rough approximation just given.

Physical Significance of the Steps of an Experiment.—It is of great importance that the experimenter should study the steps of his work and try to understand the physical meaning of each expression. This implies a marked distinction between the attitude of the physicist and that of the mathematician, whose aim is probably the attainment of a neat and compact final expression.

In calculating the results of an experiment where a certain quantity is to be determined from measurements of a number of independent quantities, it is *not* advisable, as a rule, to express that quantity explicitly in terms of the various measured quantities. This procedure often results in a complicated expression, which is difficult to work out and liable to occasion arithmetical errors. More important than this, however, is the definite loss of meaning the various quantities suffer when grouped together in this way. The physical significance of each step of the calculation should be kept in view. This general rule is of special importance in all experiments connected with **energy**, whether the form of the energy be mechanical, thermal, or electrical.

As a particular example of this, consider the expression on p. 115 for finding the moment of inertia, I . The equation $mgh = \frac{1}{2}I\omega^2 + \frac{1}{2}mv^2$ indicates three definite physical quantities, each an amount of energy, and if retained in this simple form it conveys a meaning at once, and can be written down from first principles immediately. To express 'I' explicitly would be to destroy the meaning of the equation to a very great extent.

The use of 'formulae', which often put a meaningless burden on the memory, should be avoided; and, wherever possible, an endeavour should be made to work out the solution of a problem by reasoning from first principles.

§ 5. GRAPHIC METHODS

The use of graphic methods is of great value both in theoretical and experimental physics. Whenever the observations taken in an experiment form series relating to two interdependent quantities, a graph should be drawn to illustrate the connection between them. The graph shows the way in which the dependent variable (y) depends on the independent variable (x). It is customary to plot the values of the independent variable as the abscissae horizontally from left to right, and the values of the dependent variable as the ordinates upwards, when the paper is held in a vertical plane.

As a typical example may be cited the experiment on the simple pendulum. In this, the period t of a pendulum of length l is measured, l being varied arbitrarily, and the corresponding values of t being determined. Here l is the independent variable and should be plotted horizontally, t being plotted on a scale running from the bottom of the page to the top.

The units in which the variable is expressed, and the designation of the variable, must be marked clearly along the corresponding co-ordinate axis. Great care must be taken in choosing the scale to which each variable is plotted, so that the resulting graph may cover as large a portion of the sheet as possible. It is assumed here that a sheet such as is found in the student's note-book is employed. On a large sheet, too large a scale would tend to exaggerate accidental errors of observation.

The points indicating the observations should be shown by dots with small circles drawn round them, or by small crosses. A smooth curve should then be drawn to represent the average distribution of the points, and the curve should pass as evenly as possible between the points so that there are about as many on one side of the line as there are on the other. A test should first be made to see whether the graph can be represented by a straight line. A line ruled on a long strip of glass or celluloid is useful for testing this, as it is possible to see the points on both sides of the line. A piece of cotton tightly stretched is also useful for testing linear graphs. If a straight line cannot be drawn through the points, a curve should be drawn, either free-hand or by means of a thin flexible strip of wood bent to fit the curve.

If the resulting graph is a straight line, the relation between the variables is of the form $y = mx + c$, where m and c are constants. If

the graph is not a straight line, the form of the curve may suggest the relation between the variables. Familiarity with curves corresponding to equations such as

$$y = x, y = x^2, y^2 = x^3, y = x^3, \text{ and } y = \log x,$$

will guide the student as to the *type* of curve most likely to fit the observations plotted. Then by plotting *powers* of one of the quantities against the other, a straight line may result. Or a straight line may be obtained by plotting the logarithm of one quantity against the other quantity, or against the logarithm of the other quantity. See Expt. 43—Friction of rope over a fixed pulley (p. 75). When a straight line graph has been obtained, the connection between the two physical quantities concerned can be expressed by means of an algebraic equation.

Results can often be obtained by means of graphic methods with much less labour than arithmetical calculations would entail. Reference should be made to the instances considered in the text, for example pp. 65–70, 197, 200, 226.

§ 6. UNITS EMPLOYED IN PHYSICAL MEASUREMENT

The measurement of any quantity is expressed in a phrase of two parts — the **number** and the **unit**. Thus '12 seconds' contains the number 12, and the unit of time, the second. Each of the various quantities dealt with in physical measurements requires a unit. It is, however, possible to express some quantities in terms of other quantities; we can, for example, express speed in terms of the distance travelled in a certain time, and it is obviously advantageous to measure speed in units which bear a *simple* relation to the units of length and time. All the physical quantities that are met with in mechanics may be expressed in terms of *three selected* quantities. The three independent units for these quantities are said to be the **fundamental units** of the **system of units**, the other units of the system being called **derived units**.

In scientific work the fundamental quantities chosen are **length**, **mass**, and **time**. The units employed for these quantities have been the **centimetre**, the **gram**, and the **second**, so that the system is known as the **C.G.S. system of units**.

The **centimetre** is one-hundredth part of the metre, which was defined as the distance between the ends of a certain rod of platinum preserved in Paris.

The **gram** is one-thousandth part of the kilogram, which was the mass of a certain cylinder of platinum preserved in Paris. The **kilogram** was intended to have the same mass as one cubic decimetre

(1000 c.c., or 1 litre) of distilled water at the temperature of its maximum density. Consequently the mass of 1 c.c. of water at 4° C. is almost exactly 1 gram.

The **second** is the mean solar second, defined as $1/86400$ of the mean solar day, which is determined by the time of rotation of the earth on its axis.

The **International Prototype Metre** is now defined as the distance, at the melting point of ice, between the centres of two lines engraved on a platinum-iridium bar of a nearly X-shaped section.

The **International Prototype Kilogram** is the mass of a certain cylinder of platinum-iridium.

These standards are kept at the International Bureau of Weights and Measures at Sèvres, near Paris.

For some purposes the **M.K.S. system of units** based on the **metre**, the **kilogram**, and the **second** is more convenient than the **C.G.S. system**.

The unit of energy in the **M.K.S. system** is the **joule**, and this is recommended as the unit of heat measured in terms of energy. The joule has the further important advantage that it is directly available for use in the *practical* system of units (based on the coulomb and the volt) employed in electricity.

CHAPTER II

MEASUREMENT OF FUNDAMENTAL QUANTITIES

§ 1. MEASUREMENT OF MASS

THE BALANCE

THE measurement of mass by means of an ordinary balance consists in balancing two forces against each other so that their turning moments on a lever are equal and opposite. When this is achieved, the forces themselves, if parallel to each other, are inversely proportional to the distances of their points of application from the fulcrum of the lever. The forces which act on the beam of a balance are the weights of the masses suspended from the beam, and thus the ratio of the *weights* of these masses is determined. As, however, the weight of a body is proportional to its mass, the ratio of the *masses* is the same as the ratio of the *weights*, or the ratio of the masses suspended from the beam of a balance when in equilibrium, is the reciprocal of the ratio of the 'arms' from which they are suspended.

In an ordinary balance, the beam is a stiff rod sometimes of girder construction, which is supported at some point on knife-edges resting on flat plates at the top of the pillar of the balance. At the two ends of the beam are mounted knife-edges from which the scale-pans are suspended; the two parts of the beam are called the arms of the balance. Knife-edges must be used for the fulcrum and for the points of suspension of the scale-pans in order that the arms of the balance shall be of a definite length. As the ratio of these two is the reciprocal of the ratio of the masses on the scale-pans when balanced, it is obvious that this ratio must be accurately known, hence the arms themselves must have exactly defined lengths. In general this ratio is one of equality, but occasionally a ratio of 10 to 1 is used.

The knife-edges have to support a considerable weight, and hence must be made of very hard material, so that they will not be deformed when the balance is loaded. Hardened steel is used for the knife-edges of balances of moderate accuracy, but agate is used for the more delicate balances for scientific work. In order to reduce wear of the knife-edges, a lever is generally fitted whereby the beam can be raised from the knife-edge supports, when the balance is not in use, and allowed to rest on a brass bar supported in a fork of brass. This same lever raises the scale-pans, so that their weight does not rest on the knife-edges at the ends of the beam. The arrangement is called the *Arrestment* of the balance.

In order to avoid chipping or otherwise deforming the knife-edges, it is essential that the beam should be raised or lowered so as to rest in the

brass fork, before moving the balance, or altering the weights on the scale-pans. The beam must be raised and lowered *gently* for the same reason.

For most purposes the arms of an ordinary balance may be assumed to be exactly equal, and therefore the mass of the body being 'weighed' may be taken as equal to the mass of the 'weights' which are required to balance it. Even if the arms are *not* exactly equal, this need not affect the accuracy of most experiments in the slightest, provided that the 'weights' are always used on one pan and the unknown mass on the other. If this is done, the 'weights' used, though not equal to the unknown masses,




FIG. 1.—Sensitive Balance

will bear a constant *ratio* to these, and since in most experiments the *ratio* of the various masses used is required, the actual result will be unaffected.

A good rule is to place the weights always in the right-hand pan, and the unknown mass in the left.

In using a balance for comparing masses, it is essential that the beam and scale-pans should be balanced accurately when unloaded. Then, when the masses have been adjusted till the beam is in equilibrium again, the masses in the two scale-pans can be taken as equal. The beam will rest horizontally or oscillate about a horizontal position when in equilibrium. In order that this may be tested, the beam is furnished with a long pointer rigidly fixed to it, the end of the pointer moving over a small scale fitted to the pillar supporting the beam. When the beam is horizontal, the end of this pointer oscillates about the middle of the small scale, and thus a sensitive method of testing the horizontality of the beam is provided. Before loading the balance, the balance case must be levelled by means of the levelling screws, so that the base may be horizontal as tested by the plumb-line or spirit-level attached to the apparatus. The beam should then be released so as to rest on the knife-edges, and the motion of the end of the pointer be observed. Usually these oscillations will not be exactly about the middle of the scale, but provided the mean position is not far from the centre, the balance can be used without further adjustment, *the weights being always adjusted until the pointer oscillates about the same position as when the beam was unloaded.* This is called working to a *false zero*.

If the pointer has a mean position several divisions from the centre when the balance is unloaded, it is advisable to correct this before commencing to weigh. This can be done usually by moving a small nut along a screw fitted to one end of the beam, or by altering the position of a 'flag' mounted on the beam. *This should not be attempted until the student has become familiar with the handling of balances, and care must be used in doing it, so as to avoid damaging any part of the balance, particularly the knife-edges.*

Having seen that the balance when unloaded oscillates about the zero position, or having determined the false zero if this is not the case, the beam should be lowered and the unknown mass placed gently on the left scale-pan. Weights from the box of weights should then be placed on the right-hand pan, commencing with the larger weights and proceeding downwards. *The beam should be lowered before touching the scale-pan either to add or remove weights.* This rule must be observed even for the *smallest* weights. In testing for balance at first, it is unnecessary to raise the beam completely, the want of balance being obvious as soon as the beam begins to rise. The beam need not be raised to the full extent until the centigram weights are being used.

In some cases weights smaller than 1 centigram are not supplied, and a 'rider' is used for getting the weight to milligrams or less. This rider is a wire bent so as to 'ride' on the top of the balance beam, the mass of the wire being usually 1 centigram. The beam is divided into parts equal to one-tenth of the length of the arm, and the position of the rider is noted when adjusted till it gives the exact balance required. Obviously, a centigram rider at a point one-tenth of the distance along the arm is equivalent to 1 milligram in the scale-pan at the end, and so on. Thus with a centigram rider the weight of a body can be determined to within 1 milligram or less, provided the arm of the balance is subdivided in this way and the balance is sufficiently sensitive to detect a difference of this order.

A box of weights requires as much care as the balance with which the weights are used. Any corrosion or oxidation will alter the mass of a 'weight'; great care should be taken therefore to keep the weights from contact with acids, mercury, or water. It is obviously absurd to weigh to 1 milligram if one of the larger weights is wrong through corrosion to an amount greater than this. *All* weights of any accurate box should be lifted with the forceps provided in the box, this rule being applicable to the largest weights as well as to the smaller. Care should be taken not to bend the smaller weights; they should be held by the corner or side bent up for this purpose. To facilitate handling the smaller weights, they can be put on the top of the larger weights when on the scale-pan.

The weights used in any experiment should as far as possible all come from one box. If two boxes must be used, the weights should be returned to their respective boxes.

In reckoning up the weights, having 'weighed' a body, the weights should be counted whilst on the scale-pan and the total recorded in the note-book. They should be removed one at a time, the total being checked as they are returned to their places in the box; in this way

any error will be observed and corrected. Failure to observe this precaution may frequently cause a weighing to have to be repeated, or may render a whole experiment useless.

The weight of a body cannot be determined accurately when there is an appreciable difference between the temperature of the body and that of the room, on account of the convection currents set up in the air. If the body is colder than the atmosphere, moisture may condense upon it and make the observed weight too large.

No corrosive liquid should be allowed inside the balance case except in a securely stoppered vessel, and all vessels containing liquid should be wiped clean on the outside before being put on the scale-pan.

EXPT. 1. Determination of the Mass of a Body by Means of the Balance.—Level the balance case by means of the levelling screws. Turn the handle of the arrestment so as to release the beam, and see that the beam rests without constraint on the knife-edges. If the beam does not begin to swing, start a gentle current of air by a rapid movement of the hand above one of the pans. Observe the mean position of the pointer on the scale as the beam swings from side to side. Use the arrestment to stop the swinging of the balance when the pointer is near the mean position. Place the unknown mass on the left-hand pan, and place in the middle of the right-hand pan a weight estimated to be large enough to counterbalance the load on the left. Release the beam and note whether the weight is too large or too small. Continue the process of weighing, passing from the larger to the smaller weights in regular order. Remember always to arrest the motion of the balance before adding or removing weights. When the pointer swings about the same mean position as at first, stop the motion by means of the arrestment, count the weights as they lie on the scale-pan, and record the result. Count the weights again as they are removed one at a time to their places in the box. Determine in this way the masses of two bodies A and B. Check the result by determining the mass of the two bodies together and seeing that this is the sum of the two separate masses.

NOTES ON ACCURATE WEIGHING

Weighing by Oscillations.—The pointer of a balance moves over a scale which usually has 20 divisions. Imagine these to be numbered from the left-hand end, subdividing each division mentally into 10 parts, so that the central mark is called 100, and the mark at the right-hand end is 200.

We must first determine the zero-point, or the position of rest of the beam when unloaded. To do this, the beam is allowed to swing freely without any load in the scale-pans. Five consecutive readings of the 'turning-points' are taken: three of these will be successive maximum swings to one side, and the other two will be the maximum swings to the other side occurring between them. The mean of the three swings to one side is taken, and also the mean of the other two swings. The zero-point lies midway between the two means thus obtained.

The object is placed in the left-hand pan, and weighed as already described (pp. 13-15). The centigram rider is placed on the divided beam, and moved until when it is on one division the pointer is to the right of the zero-point, while when it is on the next division the pointer lies to the left of the zero-point. The resting-point of the balance is determined for

each of these positions of the rider by taking five readings of the turning-points as in finding the zero. The weight of the body can then be found to a fraction of a milligram by the method of 'proportional parts'.

As an example, suppose the resting-points are—

Empty balance	112
Loaded with 47·634 gm.	114
Loaded with 47·635 gm.	98

The last two give the sensibility of the balance, i.e. the deflection of the pointer for 1 mgm. as $114 - 98 = 16$ divisions. When the balance is loaded with 47·634 gm., the resting-point is 2 divisions from the zero-point. This difference corresponds to $2/16 = 0.125$ mgm., and if this weight were added in the right-hand pan, the loaded balance would swing about the zero-point.

The weight of the object is thus obtained as 47·6341(2) gm.

To facilitate reading the positions of the turning-points, a low-power microscope is sometimes fitted to the front of the balance case.

Weighing by Substitution.—Borda employed a method in which the body is counter-balanced as accurately as possible. It is then removed and replaced by standard weights. When the balance again swings about its zero position, the weights in the pan must evidently have the same mass as the body.

Double Weighing.—In the method of Gauss, the body is first weighed in the left-hand pan, and then in the right-hand pan. If A and B denote the weights thus determined, the true weight W is given as $W = \sqrt{AB}$.

These two methods eliminate any error arising from inequality of the arms of the balance.

§ 2. MEASUREMENT OF LENGTH

The measurement of length is possibly the simplest exercise required of a student of physics, and the use of scales of length is familiar to every one before commencing any precise scientific work at all. The accuracy required in various kinds of length measurement is, however, widely different, and we must consider the methods of obtaining these various degrees of accuracy in typical cases.

It should be noted here that in all measurements of length *two* observations must be made, one at each end of the length measured, and that therefore the possible error in the value of the length obtained is *double* the error of each observation.




FIG. 2.—Error due to Parallax

The accuracy of observations made with an ordinary scale is limited, because the dividing lines have a finite thickness, and because the eye cannot estimate fractions of divisions to nearer than 0.1 mm.

In any estimation of length made with an ordinary scale, therefore, the accuracy is not greater than about 0.2 mm. If accuracy of a higher order than this is demanded, it is essential that apparatus should be used to assist the eye, and also that the divisions

on the scale should be marked with fine regular lines. The error in using an ordinary scale may be even greater than 0.2 mm. if the scale is used 'flat', for an appreciable *parallax error* is then possible owing to the thickness of the scale (Fig. 2). Parallax means an apparent change in the position of an object due to a change in the position of the observer (p. 191).

The *graduated edge* of the scale must always be placed in contact with the points whose distance apart is to be measured, the scale being stood on its side if necessary, as would, for example, be the case when measuring the distance between two marks on a sheet of paper (Fig. 3).




FIG. 3.—Correct Method of using Scale

When it is not possible to measure the size of an object by direct application of a rule, a pair of dividers, or *inside* or *outside* callipers, may be employed. In some cases a beam compass is useful; this is a rigid bar provided with two sliding pieces to which are fixed, at right angles to the bar, the points of the compass.

PRINCIPLE OF THE VERNIER

A very ingenious device for obtaining accuracy of a greater order than that obtainable by eye-estimation was invented by P. Vernier (1580–1637), and is known by his name. In this device a small auxiliary scale is provided, which slides along the ordinary scale, the divisions of this *vernier scale* being either a little longer or a little shorter than the divisions of the ordinary scale.

The great value of this device lies in its simplicity, and in the fact that it can be used to measure to any fraction of a division required, if the auxiliary scale is divided suitably.

The form most generally used is that in which the vernier divisions are slightly shorter than true scale divisions, and therefore this type only will be described, though the principle underlying both forms is the same.

The auxiliary scale is graduated from a division which may be called the zero of the vernier, this division being indicated by an arrow or some other distinguishing mark. The scale consists of n equal divisions on one side of the vernier zero, and in some cases it is continued one or two divisions on the other side of the zero. These n vernier divisions are exactly equal to $n - 1$ scale divisions. Consequently one vernier division is equal to $\frac{n-1}{n}$ or $1 - \frac{1}{n}$ of a scale division. Thus, each vernier division is shorter than a scale division by $1/n$ of a scale division. This quantity $1/n$ of a scale division is called the *Least Count* of the vernier; as we shall see, the vernier can be used to measure to the n th part of a scale division.

Suppose the vernier scale is moved along the main scale till the zero of the vernier is exactly opposite one of the divisions of the main scale, then the distance between the zero of the main scale and the zero of the vernier (which is the distance we want to find) is an exact number of scale divisions. The other vernier divisions will not exactly correspond with scale divisions, being respectively $1/n, 2/n, 3/n$, etc. of a scale division on the zero side of the consecutive scale divisions. Now suppose the vernier is moved a little further along the main scale until the zero of the vernier has moved through $1/n$ of a scale division. It is clear that the first division of the vernier will have moved till it is exactly in line with a certain division on the main scale. If the vernier is again moved so that the zero passes over $1/n$ of a scale division the *second* division of the vernier will be exactly

in line with a division on the main scale. If the total movement of the zero of the vernier is $3/n$ of a scale division, the *third* division of the vernier is brought opposite a division on the main scale, and so on. In general, if the n th division of the vernier comes into line with one of the divisions of the main scale, it indicates that the zero of the vernier has moved through n/n of a scale division from the division immediately before it.

In using a vernier scale, therefore, the least count must first be determined. The reading is then taken according to the following Rule: Read the scale division next before the zero of the vernier scale; find the number of the vernier division which is in line with a scale division, and add this number of n ths of a scale division to the scale reading.—The result gives the distance from the zero of the main scale to the zero of the vernier scale.

Consider the two following examples of the way in which a vernier should be examined and used :—




FIG. 4.—Vernier Scale

(1) A vernier scale has 10 divisions, the ordinary scale being a scale of millimetres, and the 10 vernier divisions are equal in length to 9 millimetres. The vernier is placed with its zero between the divisions 26 and 27 mm. on the ordinary scale, and the 7th division along the vernier is exactly in line with a division along the mm. scale. The reading is required.

The vernier reads to decimals of 1 mm., or the least count is 0.1 mm., because 10 vernier divisions are equal to 9 scale divisions, and the scale divisions are millimetres.

The reading of the scale division next before the vernier zero is 26 mm. The 7th vernier division is in line with a scale division (and the vernier reads to 10ths of scale divisions). Therefore the reading is 26.7 mm.

The scale division which is in line with the 7th vernier division has nothing at all to do with the reading.

(2) A circular scale is divided into angles of 1° , and each degree is divided into three equal parts, so that the scale may be said to consist of large divisions of 1° each, and small divisions each equal to $\frac{1}{3}^\circ$.

A vernier scale of 20 divisions moves over this, the 20 vernier divisions being equal to 19 small scale divisions. The zero of the vernier is between the large divisions marked 8° and 9° , and is in the last section of this large division. The coincidence between a vernier division and a scale division occurs at the 4th vernier division, and the angle reading is required.

The vernier reads to twentieths of the small scale divisions. The reading must therefore be made to the small scale division next before the zero of the vernier: in the example given this is $8\frac{1}{5}^\circ$.

The vernier reading is 4, therefore we must add to the scale reading an amount equal to $\frac{4}{20}$ of a small scale division.

The reading thus will be $8\frac{3}{4}^{\circ} + \frac{4}{20}$ of $\frac{1}{4}^{\circ}$. But $\frac{1}{4}^{\circ}$ is equal to $20'$, and therefore we can write the *scale* reading as $8^{\circ} 40'$ and the *vernier* reading as $4'$, so that the full reading is $8^{\circ} 44'$.

Thus the vernier and scale can be used to measure to one minute of




FIG. 5.—Angular Scale and Vernier

arc, the scale being graduated to $20'$ divisions, and the vernier reading to $\frac{1}{20}$ th of these small divisions, or to $1'$.

The method of reading any type of vernier can be worked out in a similar way.

An instrument called the Vernier Callipers is used for measuring the linear dimensions of bodies. It consists of a metal rule furnished with two jaws, A and B, projecting at right angles to the rule. Of these, one is fixed, whilst the other can slide backwards and forwards. On the rule is engraved a scale divided into millimetres. The sliding jaw is also provided with a short scale V called a vernier.

EXPT. 2. Measurement of the Length of a Rod by Means of the Vernier Callipers.—If the instrument is adjusted correctly, the zero of the vernier will coincide with the zero of the millimetre scale, when the sliding jaw is brought into contact with the fixed one. If this is not the




FIG. 6.—Vernier Callipers

case, the instrument possesses a 'zero error', which must be read and allowed for in making measurements. Determine the least count of the vernier.

To measure the length of an object, it is placed between the fixed and sliding jaws, and the latter is adjusted till it makes contact with one end of the object when the other is in contact with the fixed jaw. In dealing with small bodies it is convenient to adjust the pressure till it is just sufficient to hold the object between the jaws. The reading on

the millimetre scale, which is just before the zero of the vernier, is then taken.

This reading is the distance between the zero of the vernier and the zero of the millimetre scale, and since these should coincide when the jaws are closed, it should be the distance between the jaws, that is the length of the object.


In general, the zero of the vernier is not exactly opposite a division on the rule, and it is necessary to determine the value of the fraction of a millimetre. This is done by means of the vernier scale. Look along the vernier scale until a graduation is seen which is exactly in line with one of the marks on the millimetre scale. If the correspondence is at the third graduation of the vernier scale, and the least count is 0.1 mm., the fraction required is 0.3 mm.; if it is at the fourth graduation the fraction is 0.4 mm., and so on. The reason for this has already been discussed (p. 18): the actual distance required is obtained by taking the scale reading *next before* the zero of the vernier and adding to this the vernier reading as above described.

Measure carefully the lengths of two rods of glass or metal cut from a long uniform rod. Find the ratio of these two lengths. Weigh the two rods on a balance, and find the ratio of the two weights. Assuming the original rod to be uniform, these ratios will be the same.

PRINCIPLE OF THE MICROMETER SCREW

Another form of apparatus which enables determinations of length to be made with considerable accuracy is an accurately cut screw thread working in a close-fitting nut.

In general, there is a circular head of a large diameter fitted to the screw and moving past a scale fixed parallel to the axis. The head is subdivided into a definite number of equal divisions, so that the screw can be turned through fractions of a revolution and these fractions read on the micrometer head.



p = pitch of screw

FIG. 7.—Screw

In one complete revolution the point of the screw advances a distance equal to the pitch of the screw, this being the distance between *similar* points on consecutive turns of the thread. If, therefore, we turn the head of the screw through *one-hundredth of a revolution*, the point of the screw will advance by *one-hundredth of the pitch* and so on; hence the screw point can be moved forward by minute *known* amounts, provided the pitch is known. The accuracy obtainable by the use of micrometer screws is limited only by the accuracy with which the screw is cut and fitted to the nut. Where extreme care has been taken, as in grinding the screw for the ruling of Diffraction Gratings, it is possible to set off small distances accurate to the hundred-thousandth part of a centimetre.

It is worthy of note that, owing to wear between the screw and the nut, there may be an appreciable amount of slackness in the fit of these.

This causes what is called *back-lash*, and if the screw has been adjusted by turning it in one direction, and is then turned *back*, the head may be rotated through an appreciable angle before the screw begins to move along its axis. Error due to this may be avoided to a considerable extent by always turning the screw in the *same* direction when making the *final* adjustment to any particular position. Even this will not prevent error if the screw thread has worn unevenly in different parts, and a badly worn screw should therefore be replaced by a new screw *and nut* if accuracy is desired.

The **Micrometer Screw Gauge** is an instrument for measuring the linear dimensions of small objects. It depends on the fact that when a perfect screw works in a fixed nut, the motion of translation of the screw is directly proportional to the amount of rotation that is given to it. By using a screw of fairly fine pitch, and by arranging for the measurement of small fractions of a turn, very small distances can be measured with accuracy, as already described.

For scientific work, a screw the pitch of which is $\frac{1}{2}$ mm. or 1 mm. is frequently used. In engineering work the pitch is frequently $\frac{1}{40}$ inch (nearly but not quite the same as $\frac{1}{2}$ mm., since a metre is nearly 40 inches).




FIG. 8.—Micrometer Screw Gauge

EXPT. 5. Measurement of the Thickness of a Plate by Means of a Micrometer Screw Gauge.—In using the micrometer screw gauge it is necessary to find first of all the pitch of the screw, that is, the distance through which it travels for one complete turn. The screw itself is concealed in the nut A, but if the divided head is screwed out a little way a scale C will be found engraved on the nut, from which the pitch of the screw can be found readily. Determine the length of each division of this scale by comparing it with an inch or centimetre rule and notice how many complete turns of the screw are required to carry it from one division to the next.

Notice next the number of divisions on the cylindrical divided head S_2 , and determine the travel corresponding to rotation through one division.

For example, if the pitch is $\frac{1}{2}$ mm. and the head is divided into 100 parts, each division corresponds to a movement of $\frac{1}{200}$ mm. or 0.005 mm., and two divisions correspond to $\frac{1}{100}$ mm. or 0.01 mm.

In the micrometer screw gauge there is an 'anvil' or butting point P rigidly attached to the nut by means of a bent arm F. Both this butting point and the end of the screw (Q) are actually flat polished surfaces which should be square to the axis. When these surfaces P and Q are brought into contact by turning the head with a gentle pressure of the fingers, the zero of the scale on the divided head should correspond with the zero of the scale on the nut. If this is not the case, the instrument possesses a zero error which must be observed and allowed for.

Care must be taken to avoid screwing the point of the screw against the butting point with pressure. This treatment would damage the threads and distort the frame of the instrument. In some instruments there is a 'free wheel' device which allows the head to turn freely in the fingers when the pressure exceeds a definite limit. This arrangement tends to eliminate uncertainties in reading caused by differences in pressure.

To measure the linear dimensions of an object, the screw is turned back until the body can be inserted between the point of the screw and the butting point. The point is then screwed forward till the object is

held gently between the two, the pressure of the fingers on the head of the screw being as nearly as possible the same as that used in the first observation. It is convenient to make the adjustment by holding the smooth part S_1 of the head, not using the milled ridge H at all. The screw is turned till the fingers *slip* on S_1 when *lightly* gripping it.

Take the reading of the gauge in this position and add or subtract the zero error as the case may require, that is subtract *algebraically* the zero reading from the reading obtained. Repeat the observations several times and take the mean of the results.

Measure in this way the thickness of a metal plate, repeating the observations at different points of the plate so as to obtain the mean thickness. Measure also the mean thickness of a second plate of the same metal having the same outline and, consequently, the same area. Find the ratio of these two thicknesses. Weigh the two plates, and find the ratio of the two weights. Assuming the plates to be uniform and of the same density, the ratio of the thicknesses will be the same as the ratio of the weights.

MICROMETER MICROSCOPE

There are many optical methods of making accurate measurements of length, among them being the microscope with a **Micrometer Eye-piece**. A fine transparent scale is fixed near the focus of the eye-piece; in some instruments a spider line can be moved across the scale by means of a micrometer screw to measure fractions of a division. The microscope is used to give a magnified image of the object to be measured (see p. 231). A real image is formed near the focus of the eye-piece and is compared with the fine scale placed there, the scale being seen at the same time as, and superposed on, the image of the object viewed. A body of known size is then viewed with the microscope in order to find the magnification produced by the objective, and thus the size of the small object can be determined. It is essential that the adjustment of the microscope should remain unaltered for the two observations.

If, for example, the magnified image of the small object occupies 52.4 micrometer divisions, and a millimetre scale seen through the microscope, when in the same adjustment, covers 40.3 micrometer divisions per mm., it is obvious that the small object is 1.300 mm. across. The chief use of the microscope with a micrometer eye-piece is, however, for accurately *comparing* small distances, not for their actual determination in mm. or cm. It is largely used in some forms of investigation, for observing and measuring the minute motions of the gold leaf of an electroscope.

TRAVELLING MICROSCOPE

In the **Travelling Microscope** or **Vernier Microscope** a compound microscope is mounted so that it may be moved in a direction at right angles to its axis by means of a screw or a rack and pinion. The distance through which the microscope is moved can be read on a fixed scale with the aid of a vernier that moves with the microscope.

In the instrument illustrated in Fig. 9 the microscope has both a vertical and a horizontal traverse. It has also an angular motion so that it may be used with the axis vertical or horizontal, or inclined to the horizontal at any angle. The eye-piece should be provided with cross-wires, and in adjusting the focus on any object the intersection of the cross-wires should be brought into coincidence with the point of the object to be observed. To measure the distance between two points focus the microscope first on one and then on the other. It is necessary that the line joining the points should be parallel to the direction




FIG. 9.—Travelling Microscope

of traverse of the microscope. The difference between the readings in the two cases gives the distance required. Examples of this method will be found in Expts. 77 and 78.

The comparison of two lengths may be carried out by a **substitution method** using two vernier microscopes.

EXPT. 4. Comparison of the Yard and the Metre.—Set up securely two vernier microscopes so that the line joining them may be parallel to the direction of travel of each microscope. Arrange supports for the two scales so as to raise their engraved faces to the *same* height above the table, adjusting this height so as to be able to focus the divisions by the microscopes. Focus one microscope on a division at one end of the yard scale, and the second microscope on a division near the other end. Bring the centre of the cross-wires over the centre of the division in each case. Note the distance in inches between the cross-wires of the microscopes. Now remove the yard scale and substitute the metre scale. If the preliminary adjustments were made correctly, the divisions on

this scale should come into focus at both ends. Move the scale until a division near one end exactly coincides with the centre of the cross-wires at that end ; then the centre of the cross-wires at the other end will fall between two scale divisions. Move the microscope at this end by means of the slow adjustment *towards* the microscope at the other end till the centre of the cross-wires coincides with a scale division. Observe the distance through which it moves by means of the vernier and scale of the instrument, and note also the distance between the divisions of the metre scale. Then the number of inches in the first observation is equal to the number of millimetres in the second *plus* the distance measured on the scale of the microscope. From this result may be calculated the length of the inch or of the yard in centimetres.

§ 3. MEASUREMENT OF TIME

Of all the measurements with which we have to deal in elementary physics, that of Time is the most difficult. The scientific unit of time, the mean solar second, depends, as we have said, on the period of rotation of the earth on its axis. This period is determined by astronomical observations. To obtain multiples or submultiples, we employ a mechanism—a clock or watch—designed on the assumption that the oscillations of some body—a pendulum or balance-wheel—are *isochronous*, that is, of equal duration, and consequently mark equal intervals of time. This vibrating body is the essential part of the apparatus, the rest being merely an arrangement for counting the oscillations. No mechanism which is absolutely trustworthy and regular has yet been devised for the measurement of time. The clock rate can, however, be determined by astronomical methods. In order to measure an interval of time, the period is observed by means of a clock or watch, and this period is then corrected by the proper factor depending on the clock rate.

In all but the most exact determinations it may be assumed that the time intervals given by a well-regulated clock or watch, keeping civil time, correspond accurately with mean solar time.

Even if the clock or watch does keep correct time, there are unavoidable errors in time observations which are a direct consequence of the usual mechanism. In most cases the seconds-hand does not move uniformly but in a series of jerks, receiving an impulse each time the balance-wheel or pendulum passes through its position of rest. When therefore a stop-clock or stop-watch is started, there is a possible error equal to $\frac{1}{2}$ half the period of vibration, and a similar error exists when it is stopped again.

Suppose, for example, that the watch ticks every one-fifth of a second, then if it is just approaching the position of rest when it is started, the seconds-hand will jump forward one-fifth of a second immediately the watch starts. Or again, if the watch is stopped just as it is about to tick, the final one-fifth of a second will not be

recorded, whereas the slightest possible delay in stopping the watch would have recorded it.

It will be seen, therefore, that stop-watch and stop-clock determinations of time intervals cannot be relied upon to closer than one 'tick' of the watch or clock, even if the clock rate is quite accurate.

For accuracy of a given order it is therefore essential that the time observations shall be prolonged over a certain length of time determined by the duration of the 'ticks' and the accuracy required: accuracy of 1 in 1000 demands a period of more than three minutes if a watch ticking fifths of seconds is used, and so on.

EYE AND EAR ESTIMATIONS

If an ordinary clock or watch is used instead of a stop-watch the possible error is even greater, owing to the difficulty of estimating exactly the position of the moving seconds-hand. This may be got over to some extent by combining eye and ear observations, and as this method is used frequently in certain types of work, it will be described here briefly.

Suppose that observations are being made on the motion of a pendulum. In commencing the time observations the observer starts counting ticks as the seconds-hand commences a fresh minute or passes some other convenient point. This counting is then continued by *ear*, the *eye* being turned to observe the pendulum. If the pendulum passes the *middle* of its swing between the 17th and 18th ticks, it is easy to work out the exact moment when this passage took place, and hence the commencement of the set of swings to be observed is known to the nearest tick of the watch. When the last vibration of the pendulum is completed, and when the pendulum is moving through the *middle* of the last swing to be observed, the observer begins to count watch ticks again, and continues to do so until he can look at the watch face and observe the time corresponding to the ticks he is counting. An example will illustrate the method:—

Counting started at 2 h. 31 m. 0 s.

Pendulum passed middle point at 17th tick after this.

Counting started at completion of 100th complete vibration.

Watch indicated 2 h. 32 m. 20 s. at 31st count.

Each watch tick = $\frac{1}{5}$ th sec.

∴ First swing commenced at 2 h. 31 m. 3·4 s. and 100th swing was completed at 2 h. 32 m. 13·8 s.

Hence 100 complete swings take 1 m. 10·4 secs., or the period of one swing = 0·704 sec.

The possible error is 0·2 sec. at each observation.

The period = $0·704 \pm 0·004$ sec.

It will be observed that even using precautions of this type and taking a large number of swings, the possible error is more than $\frac{1}{2}$ per cent in this case. As in most cases the time has to be squared, this error usually is doubled. With a slower-ticking watch the error is correspondingly greater; an experienced observer, however, using a clock, or chronometer, ticking half-seconds is able to estimate to one-tenth of a second.

It is also worthy of note that the percentage error depends on the total time observed, and not on the number of oscillations taken, so that the same accuracy is obtainable with a smaller number of slow swings as with a large number of quick swings, provided the times occupied by the swings observed are approximately equal.

It is impossible accurately to estimate fractions of a vibration, and therefore the student must invariably find the time taken for a given number of swings, not the number of swings in a given time.

NOTES ON ACCURATE TIMING

Great improvements have been made during the past half century in the construction of clocks for timing both long and short intervals.

Free-Pendulum Clocks.—By making the pendulum more free throughout its swing much greater accuracy has been realised in a clock having a mechanical pendulum swinging under gravity. For periods longer than a day the Shortt clock is the best known. This has a 'free' pendulum swinging in a case exhausted of air and kept at a constant temperature. To maintain its oscillations this 'master' pendulum is subject to an impulse every half minute from a 'slave' pendulum. The latter liberates an impulse lever which actuates an electric circuit supplying the energy required. By means of a 'hit and miss' device the impulse lever also sends a current to keep the slave pendulum in exact step with the master. Electric signals may be obtained which are correct to a thousandth of a second at least. The Shortt clock is commonly used in astronomical observatories.

Quartz-Crystal Clocks.—A crystal of quartz when strained becomes electrified, and the resulting electrification may be employed in connection with valve amplifiers of the type described in the last chapter of this book to maintain the oscillations of the crystal. These oscillations, which are very rapid, are independent of gravity, and provide the most accurate time keeper known for periods of one day or less. The quartz clock ticks 100,000 times a second, and it is possible to send 1000 time signals every second along a telegraph wire 40 miles long. This clock can also be used for long periods in astronomy.

The use of radio signals for time keeping has been mentioned on p. xi.

CHAPTER III

MEASUREMENT OF QUANTITIES IN DERIVED UNITS

Of the quantities which are measured in 'derived' units, among the simplest to measure are areas, volumes, and densities.

§ 1. MEASUREMENT OF AREA

MEASUREMENTS OF AREAS BOUNDED BY STRAIGHT LINES

The unit of area used in scientific work is the square centimetre, that is the area of a square each side of which is 1 cm. long.

For the measurement of areas bounded by straight lines the ordinary rules of mensuration are applied, the lengths required being measured by means of a scale. It is possible to subdivide any figure of this type into triangles, and the total area is found by adding together the areas of the individual triangles, the area of a triangle being half the product of the base and the perpendicular height.

If the area of a sheet of metal with straight edges is required, vernier callipers (p. 19) may be used to obtain greater accuracy than is possible with an ordinary scale by eye estimation. Where convenient, part of the area may be subdivided into rectangular figures, and only the corners treated as triangles.

EXPT. 5. Measurement of the Area of a Rectilinear Figure.—Find, by measuring the base and the perpendicular height, the area of a triangle cut out of a thin metal sheet.

The area is one-half the product of these quantities. Since each side in turn may be chosen as the base, three independent determinations can be made. The three results should agree within the limits of experimental error. Take the mean of the three values as the area of the triangle.

Determine also the area of other figures, such as a quadrilateral, a pentagon, and a hexagon, by subdividing them into triangles as in Fig. 10.




FIG. 10.—Pentagon divided into
Triangles

MEASUREMENT OF AREAS WITH CURVED BOUNDARIES

In the case of certain figures with curved boundaries the relation between the area and the linear dimensions is known. Thus for a circle of radius r , the area is πr^2 , while for an ellipse of semi-major axis a , and semi-minor axis b , the area is πab .

I. The method of subdividing the area into triangles and rectangles can be adopted even with irregular areas in order to obtain approximate values for the area. The accuracy depends on the degree of subdivision to a certain extent, but if carried too far, the total possible error due to minute errors in determining the various small areas may more than discount the additional accuracy obtained by increased subdivision.




FIG. 11.—Measurement of Area

This method is the basis of that used in surveying.

II. If the figure is drawn on squared paper, the area can be found by counting the number of squares. It is clear that the accuracy obtained depends on the fineness of the ruling—the smaller the elementary squares, the more closely can the outline of the given figure be followed (Fig. 11).

III. Areas can be determined with considerable accuracy by making use of the balance. The figure is drawn on a sheet of cardboard or thin metal whose thickness should be as uniform as possible. The area is then cut out and weighed. From the same sheet is cut an area, of which the shape may conveniently be a rectangle or a triangle, and its weight is found. The area in this case can be determined from the linear dimensions. The unknown area is then calculated by simple proportion, assuming that the first area is to the second as the weight of the first figure is to the weight of the second.

Expt. 6. Measurement of the Area of a Circle.—Draw a circle of convenient radius (5 to 10 cm.) and determine its area by each of the three methods I, II, and III, and deduce a value of π in each case.

IV. The area can be found by means of Simpson's rules. These rules serve to determine approximately the area included between any regularly curving line and two ordinates drawn at the extremities of the curve perpendicular to some base line.

Divide the base line into a number of equal parts, and draw the corresponding ordinates, dividing the area into a number of strips.

First Rule.—Add together the halves of the extreme ordinates and the whole of the intermediate ordinates, and multiply the result by the common interval (the distance between consecutive ordinates).

Second Rule.—Add together the extreme ordinates, twice the sum of all the odd ordinates (omitting the first and last), four times the sum of all the even ordinates, and multiply by one-third of the common interval. In this case the number of strips must be even.

The first rule is easier to apply than the second, but is slightly less accurate. These rules are frequently employed by engineers in the measurement of indicator diagrams.

EXPT. 7. Measurement of the Area of a Semicircle.—Draw a semicircle of convenient radius and determine its area by the above rules. Compare the results with the area found by calculation.

V. The area can be measured with a **Planimeter**. This method is of great importance to the engineer or surveyor, but is of a more advanced character than the methods so far considered.

THE PLANIMETER

A number of instruments have been devised for the direct determination of plane areas of any contour, the general name **Planimeter** being applied to instruments of this class. Of these, probably the most elegant and simple is that due to Professor Amsler of Schaffhausen, and as this is the type in general use, we shall confine ourselves to describing the construction and the method of using this planimeter.

The instrument (Fig. 12) consists of two rods OA and AB hinged together at A; the rod OA is fixed at the end O, so that A can move




FIG. 12.—Amsler's Planimeter

In actual use the rod OA is generally on the far side of AB.

only in the path of a circle about O. At B is the tracing point, and the hinge at A is so arranged that the point B can move in any direction in the plane OAB, the motion being limited only by the lengths of the arms and the mechanical construction of the instrument. Somewhere along the arm

AB is mounted a wheel C, whose axis is parallel to the arm AB, this wheel being usually on the side of A remote from B, although this is not necessary for the working of the instrument. This wheel is fitted with a circular or cylindrical scale D subdivided into 100 equal parts, and a vernier scale E fixed to the frame enables the position of the wheel to be read to $\frac{1}{1000}$ of a revolution. Whole revolutions are registered on a small revolution counter connected to the wheel by a worm gearing.

The instrument rests on the fixed centre O (Figs. 12 and 13), on the edge of the wheel C, and on the tracing point B. If the point B is moved, the whole arm AB will move. Any motion of AB along its own direction will cause mere *sliding* of the wheel, no rotation being produced whatever. On the other hand, if AB moves *perpendicular* to its length, the wheel will *roll* a distance equal to the distance moved through by the arm AB perpendicular to its own length. However AB moves, the component of its motion perpendicular to its length will be registered by the rolling of the wheel, and therefore the distance rolled




FIG. 13.—Plan of Planimeter

through by the wheel due to any motion of AB, is the total distance through which AB has moved perpendicular to its own direction.

From this distance it is possible to determine the area of the figure round which B has been taken.

There is an important difference between the case where O is outside the figure round which B moves, and the case when O is included within this contour; and we shall first consider the case when O is outside the area to be determined.

Area not enclosing the Fixed Centre

Consider the arm AB to move from the position A_1B_1 to the position A_2B_2 (Fig. 14). A would move along the circle about O from A_1 to A_2 ,




FIG. 14.—Elementary Area traced by Planimeter

and B might traverse the path B_1B_2 . The same position would have been reached if AB had moved parallel to itself into the position A_2B_2 , and then had rotated about A_2 into the final position A_2B_1 .

If the perpendicular distance between A_1B_1 and A_2B_2 is a small amount δs , and the angle between A_2B_2 and A_1B_1 is a small angle $\delta\phi$, the area swept out by the arm AB in this motion would be equal to $b\delta s + \frac{1}{2}b^2\delta\phi$, where b = length of arm AB.

The actual area swept out, $A_1A_2B_2B_1$ will differ from this by the small area $B_1B_2B_3$, which will be negligible if δs and $\delta\phi$ are small, and hence we have that

$$\text{Small area swept out by AB} = b\delta s + \frac{1}{2}b^2\delta\phi.$$

Any motion of AB can be taken as the sum of a number of elementary motions of this type, and therefore, in any motion of the arm AB,

$$\text{Total area swept out by AB} = \Sigma(b\delta s + \frac{1}{2}b^2\delta\phi).$$

The symbol Σ (Greek, sigma) here, and elsewhere, is used to denote the sum of a series of terms which are all of the same type.

Suppose that the point B moves completely round an area not enclosing the fixed centre O.

Let the extreme positions of the arm be A_1B_1 and A_2B_2 (Fig. 15), B circulating round the area $B_1EB_2FB_1$ in the positive direction, so that the




FIG. 15.—Finite Area traced by Planimeter

area always lies on the right hand side of an observer moving round with the point B.

In traversing the path B_1EB_2 , the arm AB sweeps out an area $A_1A_2B_2EB_1$, while on the return journey via F, it sweeps out an area $A_1A_2B_2FB_1$. Thus, the net area swept out by the arm AB when B moves round the given contour, is the area enclosed by the contour.

Thus

$$\text{Area } B_1EB_2F = \Sigma(b\delta s + \frac{1}{2}b^2\delta\phi),$$

or

$$\text{Area required} = b\Sigma\delta s + \frac{1}{2}b^2\Sigma\delta\phi.$$

Now the arm AB returns to the same position as at first, when B goes completely round the area, and therefore $\Sigma\delta\phi = 0$.

Hence

$$\text{Area } B_1EB_2F = b\Sigma\delta s = bS,$$

where S = total distance rolled through by the wheel.

For areas not enclosing the fixed centre O, the area round which the tracing point is taken is equal to the distance through which the

wheel rolls, multiplied by the length of the arm from the hinge A to the tracing point B.

Areas enclosing the Fixed Centre O

The Zero Circle.—Before considering the general case of *any* area enclosing the fixed centre, it is essential to consider the special case of the 'zero circle'. If we clamp the two arms of the planimeter together in such a position that the plane of the wheel passes through the fixed centre, the point B can move only in a circle of radius OB about O (Fig. 17, p. 34).

If we cause B to trace out this circle, the wheel C will not roll any distance whatever, because it is moving perpendicular to its own plane the whole time. Thus, when this circle is traced out by B, the reading of the wheel is unaltered or the registration of the wheel is zero, hence the term 'zero' circle which is applied to this particular circle.

By placing the planimeter in this position (it is unnecessary to *clamp* it) the length OB can be measured, and hence the area of the zero circle can be determined.

General Case of any Area enclosing the Fixed Centre.—Consider the area ABCDEF (Fig. 16) enclosing the fixed centre O, and let the dotted line indicate the zero circle. If we take the tracing point from A to B along the curve, and then return to A along the zero circle, we shall have traced




FIG. 16.—Area enclosing the Fixed Centre

out the area AGBH in the positive direction, and therefore the reading on the wheel will correspond with this area AGBH, *since this does not include O*.

Now this reading of the wheel was all registered during the motion from A to B along the curve, since there is no rolling of the wheel when the tracing point travels along the zero circle. Hence the area AGBH is registered by the wheel while it is moving from A to B along the curve.

If now we start at B and go round BKCL we shall have traversed the contour of the area BKCL in the *negative* direction, and the wheel will have rolled *backwards* a distance corresponding with the area BKCL. Again, the whole of this movement was recorded while the tracing point was moving along BKC, and hence in moving along BKC, the area BKCL was recorded *negatively*.

It is obvious from the foregoing that the wheel automatically reverses its direction of rotation as the tracing point crosses the zero circle, and therefore the zero circle need not be drawn. It is therefore apparent that when the tracing point is taken round an area which includes the fixed centre, the total distance rolled through by the wheel corresponds with the algebraic sum of the areas outside the zero circle.

The area required is given by the area corresponding with the distance recorded by the wheel, *plus* the area of the zero circle; hence the zero circle must first be determined as described above.

Great care must be used to notice in what direction the instrument is recording when using it with the centre inside the area to be measured, and of course the positive or negative sign prefixed as required: the

tracing point must always be caused to go round the contour in the positive direction.

EXPT. 8. Calibration of the Planimeter.—The first thing to be done in using a planimeter is to find out what area corresponds with one whole revolution of the rolling wheel. This of course depends on the length of the tracing arm from the hinge to the tracing point, and also on the diameter of the wheel.

(i) **Determination of the Length of the Tracing Arm.**—Set the hinge carrier until the index on it is in line with one of the lines on the side of the tracing arm—the line marked 100 cm. \square is a convenient one, or if the planimeter gives inches it may be adjusted to the line marked 10 in. \square . We have now to find the length from the hinge to the tracing point. This is no easy matter, as usually the hinge is enclosed almost entirely by the hinge carrier and adjustments. The best way is to lay the instrument on its side on a sheet of squared paper, placing the tracing point on some definite line in the paper, and estimating to the nearest 0.1 mm. where the axis of the pivots lies. The tracing bar must be placed parallel to one side of the squared paper in order that the length may be obtained accurately.

In some forms of planimeter two points are carried on the *top* of the tracing arm; one of these is fixed near the end of the arm, and the other moves with the hinge carrier. They are so placed by the maker of the instrument that the distance between them is exactly equal to the distance between the tracing point and the axis of the hinge. Consequently this distance may be measured with a scale—a much simpler and more accurate observation than that already described. The distance thus obtained is the length b already referred to in the description of the instrument.

(ii) **Determination of the Circumference of the Wheel.**—The circumference of the tracing wheel is determined by measuring the diameter d with a micrometer screw gauge and multiplying by π , care being taken to adjust the micrometer screw till it touches the wheel edge very lightly only, otherwise the edge of the wheel may be deformed and the accuracy of the instrument destroyed.

The product of the length of the arm b and the circumference of the wheel πd is the area corresponding with one revolution of the wheel when the instrument is in this adjustment.

This product will be found to coincide very nearly with the indication 100 cm. \square or 10 in. \square on the side of the tracing arm to which the hinge carrier was adjusted. These graduations are made by the maker of the instrument, and are the areas corresponding with one revolution of the wheel with the instrument adjusted in this manner. It is obvious that the above methods for getting b and d are somewhat crude; the instrument maker has more accurate means of measuring these quantities, so that, unless the instrument is old, or has been handled severely and distorted, the values indicated on the tracing arm should be used.

EXPT. 9. Determination of Small Areas with the Planimeter.—The area considered is small enough for the fixed centre O to be taken outside the figure.

(i) **Percentage Error with Planimeter.**—Trace out a square of side 10 cm. and, having taken the tracing point round the contour, convert the reading of the planimeter into sq. cm.; express the difference between this and 100 sq. cm. as a percentage of the total area. This gives the percentage error of observation with this form of instrument.

(ii) **Area of a Circle with Planimeter.**—Draw a circle of 10 cm. radius and find its area by the planimeter; hence determine the value of π .

EXPT. 10. Determination of the Area of the Zero Circle of the Planimeter.—The use of the instrument for small areas, and the method of translating its indications being now thoroughly understood, it is essential that the zero circle should be determined in order that large areas enclosing the fixed point may be measured.




FIG. 17.—Position for Zero Circle

(i) **Calculation of the Area of the Zero Circle.**—Place the wheel on a piece of squared paper so that its point of contact with the paper is exactly on one corner of the squares, and its plane lies along one of the sides of the squares. Place the tracing point on one of the edges, and the fixed centre on the edge in the plane of the wheel, pricking both points into the paper.

The instrument is now fixed with the plane of the wheel passing through the fixed point, and therefore, as described in the foregoing investigation, the distance between the fixed point and the tracing point is the radius of the zero circle. This distance can be measured, and hence the area of the zero circle found, or, since in Fig. 17

$$x^2 + y^2 = R^2,$$

we can write

$$\text{Area of Zero circle} = \pi(x^2 + y^2),$$

and R need not be measured.

If the top of the tracing bar is examined, it will be found that there are various numbers marked on it at different points, each number being above one of the graduations on the side of the bar. These are the areas of the zero circles corresponding with the various positions of the hinge carrier, and are usually expressed in revolutions of the wheel in that position; e.g. if the index on the hinge carrier is set to the line marked 100 cm. \square , and the number on the top of the bar opposite to this line is 20.731, this means that the zero circle has an area equivalent to 20.731 revolutions of the wheel, i.e. an area of 2073.1 sq. cm.

Express the indicated zero circle area in sq. cm., and compare this with the area calculated from your observations, as described in the preceding paragraph. As before, the methods available to the instrument maker are probably much more accurate than the crude method described, and the indicated area should be used unless the instrument is obviously badly worn or distorted.

(ii) **Experimental Determination of the Zero Circle Area.**—The zero circle area can be determined quite simply by the indications of the planimeter itself. Take some area (regular or irregular) of such a size that it can be contoured without difficulty with the fixed point outside: a figure about 20 cm. across is suitable for most instruments when set to the 100 cm. \square graduation.

Go round this area with the tracing point, having the fixed centre outside, and write down the area as indicated by the planimeter: let this be A .

Next place the fixed centre inside the area and go round the figure again. This must be done slowly, as the wheel revolves very rapidly,

and may slip or jump from off the paper if care is not taken. Be careful to notice also that the reading is *diminishing* all the time, *i.e.* the area is giving a *negative* registration on the wheel: the area is of course being contoured in the positive direction.

When this registration has been obtained, we may use the equation already proved for the case where the fixed centre is inside:

$$\text{Area } A = \text{registered area} + \text{zero circle area.}$$

In general, this equation would be used to find the area A , but we can apply it in this special case to find the zero circle area. We have determined already the area A by means of the planimeter, using it with the fixed point outside, and we have just obtained the area, registered with this point inside, so that the zero circle area is equal to the *algebraic* difference of these two quantities, or, since one is negative, to their arithmetic sum.

As an example of this:—

Fixed point outside			
First reading	.	.	2.139 revolutions
Second reading	.	.	5.713 revolutions
Registration	.	.	<u>3.574 revolutions</u>
Area = 357.4 sq. cm.			

Fixed point inside			
First reading	.	.	(2) 5.781 revolutions
Second reading	.	.	8.633 revolutions
Registration	.	.	<u>- 17.148 revolutions</u>

The registration was negative all the time, and the wheel counting whole revolutions of the rolling wheel passed through its zero twice, hence the (2) in front of the first reading.

Thus

$$357.4 = (-1714.8) + \text{zero circle area,}$$

$$\text{or} \quad \text{Area of Zero circle} = 2072.2 \text{ sq. cm.}$$

The indicated value was 2073.1 sq. cm.

Find the area of the zero circle by these two methods, and compare their results with the area indicated on the top of the bar.

EXPT. 11. Determination of Large Areas with the Planimeter.—In this case the area is supposed to be so large that the fixed centre O must be taken inside it.

An ellipse is a closed curve every point of which has the sum of its distances from two fixed points (the foci) constant. The diameter through the foci is the major axis; the minor axis bisects the major at right angles. It may be drawn by constraining a pencil point by means of a continuous loop of thread passing round two pins as the foci.

Draw a large ellipse about 40 cm. \times 70 cm., using a loop of thread and two pins, and find its area, using the planimeter. Show that the area is $\frac{\pi}{4}$ times the area of the circumscribing rectangle, the sides of which are parallel to the major and minor axes of the ellipse.

§ 2. DETERMINATION OF VOLUME AND DENSITY

The **density** of a substance is defined as the mass per unit volume or the mass in grams of 1 c.c. (in the C.G.S. system). If M be the mass and V the volume, the density is given by the quotient M/V ; this will be expressed as gm. per c.c., or gm. cm.⁻³, if M is in gm. and V in c.c.

EXPT. 12. Determination of the Density of a Regular Solid by use of the Vernier Callipers.—Measure carefully the linear dimensions of a number of regular solids with the vernier callipers, reading to 0.1 mm., deducting (algebraically) the 'zero reading' of the callipers from each of the readings taken.

Repeat each observation at least three times, and if possible at different points of the object, and take the mean of the results, *e.g.* in getting the diameter of a cylinder it should be measured at each end, and in the middle as well, to correct for any 'taper'. At each place, two diameters at right angles to each other should be measured to correct for any ellipticity, the mean of these six observations being taken as the true diameter.

Calculate from your observations the volume of the body, expressing the results in cubic centimetres. (Formulae for this are given on p. 559 for various regular shapes.)

Find, by means of the balance, the mass of the body, and calculate its density.

EXPT. 13. Determination of the Density of a Regular Solid by means of a Micrometer Screw Gauge.—Determine the volume of a number of regular solids by measuring their linear dimensions with the micrometer screw gauge.

Find the mass of each solid by weighing it on a balance, and calculate the density, or the mass of unit volume, as in the preceding experiment.

§ 3. THE SPHEROMETER

The **Spherometer** is an instrument used for measuring the radius of curvature of a spherical surface. In many cases—as, for example, when dealing with a lens—the surface is only a small portion of a sphere. In such a case the radius of curvature is the radius of the (imaginary) sphere of which the surface forms a part.




Fig. 18.—A Spherometer

The instrument (Fig. 18) consists of a small table supported by three legs, A, B, C, placed as nearly as possible at the corners of an equilateral triangle. Through the centre of the table passes a screw of fine pitch (usually 0.5 mm. or 1 mm.) forming a fourth leg O. The position of this leg can be read by means of a scale fixed at right angles to the table and a circular scale attached to the head of the screw.

EXPT. 14. Measurement of the Thickness of a Plate by Means of the Spherometer.—In using a spherometer the first thing to be done is to determine the value of the graduations of the two scales, for all instruments are not graduated in the same way. Find out how far the screw advances when the head is turned through one complete revolution. This distance will probably be 0.5 mm. or 1.0 mm. Notice next the number of divisions on the circular disk and determine how far the screw advances when the disk is turned through one division. For example, if the pitch of the screw is 0.5 mm. and there are fifty divisions on the graduated head, each division corresponds with a movement of 0.01 mm. of the point of the screw (see p. 20).

When the zero on the graduated disk is opposite the zero on the linear scale, the point of the screw is supposed to be in the same plane as the three fixed feet. In general this is not exactly the case, and it is necessary therefore to determine the amount of 'zero error' of the instrument, or the 'zero reading'. To do this, place the spherometer on a plane surface such as an optically worked glass plate. Turn the head of the instrument till the point of the screw just touches the surface. The exact position can be determined by touching one of the outside legs with the finger tip or a pencil, and observing if the instrument will rotate about the screw point. The screw must be turned until the instrument rotates when touched in this manner, but will no longer do so if the screw is raised the slightest degree. Repeat the observation several times and take the mean of the readings as the zero reading. This quantity must be subtracted algebraically from all subsequent readings.

The thickness of a plate of glass can be measured as a preliminary experiment, by determining the zero reading on a plane surface, and then finding the reading when the screw point is resting on the top of a small plate, while the other feet still stand on the plane surface.

It is often convenient not to take any account of the vertical scale except to find the distance the point rises for one turn. Instead of the vertical scale reading, the number of whole turns of the divided head should be counted, each turn being reckoned as 50 or 100 of the graduated head divisions as the case may be, the travel of the point being stated in terms of these.

EXAMPLE.—Zero reading is 23 divisions on the circular head.

In order that the screw point should rest on the top of a small plate, four whole turns and part of a fifth were made and the reading on the circular head when correctly adjusted was 65.

There were 100 divisions on the circular head, therefore the number of divisions turned through

$$= 4 \text{ whole turns} + 65 - 23, \\ = 442 \text{ divisions.}$$

The pitch of the screw is 0.5 mm., therefore each division is equivalent to $\frac{1}{200}$ mm.

$$\text{Thickness of plate} = 0.221 \text{ cm.}$$

EXPT. 15. Measurement of the Radius of Curvature of the Surface of a Lens or Mirror.—Place the spherometer with the fixed feet resting on the surface, and adjust the central foot till it just touches the surface. Read the circular scale. Replace the instrument on the plane surface and find how many whole turns have to be made to bring the central foot back to the plane of the other three feet. From this and the readings of the circular head in the two adjustments find, as above, the distance through which the screw was moved. Take the mean of several adjustments and let the height be h cm.

We also require to know the distance between two fixed feet. Measure this carefully to 0.1 mm. with a millimetre scale for each side of the

triangle and take the mean of the results : let it be a cm.

Then the radius of curvature is given by the expression

$$R = \frac{a^2}{6h} + \frac{h}{2}.$$

N.B.—I. Since R depends on the square of a , a small percentage error in a means an error of twice this magnitude (per cent) in R .

II. If h is in cm., a must be in cm., and the value of R will be found in cm.

III. The term $h/2$ can often be neglected in comparison with $a^2/6h$.

The results should be entered as follows :—

Reading on Plane	Reading on Lens
22 divisions	48 divisions
24 divisions	47 divisions
23 divisions	46 divisions
Mean 23 divisions	Mean 47 divisions
Difference = 24 divisions	

The screw head was turned through two complete turns.

$$h = 2 \text{ turns and } 24 \text{ divisions} = 0.112 \text{ cm.}$$

Distance between Feet

3.01 cm.

3.03 cm.

2.99 cm.

Mean $a = 3.01$ cm.

$$R = \frac{(3.01)^2}{6 \times 0.112} + \frac{0.112}{2} \text{ cm.}$$

$$= 13.5 \text{ cm.}$$

Thus the radius of curvature is 13.5 cm.

It is useful to express the curvature of the surface in dioptries, this being the unit of curvature employed by opticians. A surface having a radius of curvature of one metre has a curvature of one dioptrie, and thus for any surface the curvature in dioptries is the reciprocal of the radius of curvature in metres. The curvature in the example given is $100/13.5 = 7.41$ dioptries.

Proof of the formula

$$R = \frac{a^2}{6h} + \frac{h}{2}.$$

In this formula a is the length of the side of the equilateral triangle formed by the three feet (Fig. 19).

Let x denote OB , the radius of the circumscribing circle.

Then, if OD be at right angles to BC ,

$$BD = \frac{a}{2},$$

and

$$OD = \frac{x}{2},$$

for $\triangle BOD$ is one half of an equilateral triangle.

Now

$$OB^2 = OD^2 + BD^2,$$

or

$$x^2 = \left(\frac{x}{2}\right)^2 + \left(\frac{a}{2}\right)^2,$$

$$x^2 - \frac{x^2}{4} = \frac{a^2}{4},$$

$$\frac{3x^2}{4} = \frac{a^2}{4},$$

$$x^2 = \frac{a^2}{3}.$$

To find the radius of curvature R , we consider a section of the sphere by a plane through its centre and through the line BO in Fig. 19. Thus we obtain




Fig. 19.—Plan of Spherometer




Fig. 20.—Section of Sphere

Fig. 20, in which only a portion of the circle of curvature is shown. If the diameter PQ meet this circle again in S (not shown in Fig. 20).

$$QS = QP = R,$$

$$OB = OB' = x \text{ and } OP = h.$$

We know that

$$OS \times OP = OB \times OB'.$$

Hence,

$$(2R - h)h = x^2,$$

$$2Rh = x^2 + h^2,$$

$$R = \frac{x^2}{2h} + \frac{h}{2}.$$

or, finally,

$$R = \frac{a^2}{6h} + \frac{h}{2}.$$

NOTES ON UNITS AND DIMENSIONS

Having chosen units of length (L), mass (M), and time (T), we may proceed to find in terms of them units for other mechanical quantities, such as the derived magnitudes just considered.

In this book, as in the earlier editions, we shall use the abbreviations cm. for centimetre, gm. for gram, and sec. for second for the fundamental units in the C.G.S. system. Many writers use the abbreviation g . for gram, but this is liable to cause confusion, because the same letter is required in dynamics for the acceleration due to gravity.

An area [A] is a quantity of a different kind from a length, but it is convenient to make use of the unit of length in defining the derived unit. We may select as the unit of area a square having each side of length 1 cm. The area of a rectangle having sides of length a cm. and b cm. is $a \times b$ square centimetres which may be written either as ab sq. cm. or as ab cm.². While a line has only one dimension, a plane surface has two dimensions. This is the origin of the term 'dimensions' as applied to other magnitudes.

A volume [V] may be measured by taking as unit volume a cube having each side of length 1 cm. A rectangular block having edges of a , b and c cm. would have a volume of $a \times b \times c$ cubic centimetres, or abc cm.³. The 'dimensions' of volume are 3 in respect of length.

Density [D] has been defined (p. 36) as mass per unit volume or $D = M/V$ so that the value is expressed in terms of gm. cm.⁻³. The 'dimensions' of density are 1 in respect of mass and -3 in respect of length.

DETERMINATION OF SPECIFIC GRAVITIES

§ 1. DEFINITION OF SPECIFIC GRAVITY

THE specific gravity, or relative density, of a substance is defined as the ratio of the weight of any volume of that substance to the weight of an equal volume of some standard substance. The standard substance usually chosen is water. For exact work it is necessary to specify the temperatures at which the measurements are made. Thus water is chosen at the temperature of 4°C ., that is, at the point of maximum density. For ordinary purposes, sufficient accuracy is attained by making the measurements at the temperature of the room.

§ 2. THE SPECIFIC GRAVITY BOTTLE

The Specific Gravity Bottle is a bottle constructed so as to contain a definite volume of a liquid. In a common form the bottle is fitted with a ground-in stopper pierced by a small hole. The bottle is filled completely, and when the stopper is inserted the excess liquid escapes and can be wiped away.




FIG. 21.—Specific Gravity Bottles

A simpler and more accurate form has a narrow neck on which a mark, AB, is made. The bottle is filled so that the bottom of the meniscus is level with the mark, any surplus liquid being removed by filter paper, or by a small pipette. The reason for the greater accuracy of this form of bottle is that the stopper in the first case, being a finely tapered cone, can be

wedged in farther sometimes than others, particularly if the bottle is slightly warmer than the stopper.

EXPT. 16. Determination of the Specific Gravity of a Liquid by using the Specific Gravity Bottle.—The bottle must first be dried thoroughly. Attach a glass tube, narrow enough to enter the bottle, to the nozzle of the foot-bellows by means of rubber tubing, and blow air into the interior of the bottle. At the same time warm the bottle very gently by holding it *above* (not in) the flame of a spirit-lamp or Bunsen burner. Hold the bottle by the neck and keep it constantly rotating so as to prevent unequal heating, which would be liable to crack the glass.

When the bottle is dry and cold, place it on the left-hand pan of the

balance and determine its weight correct to the nearest centigram. Let the weight be B gm.

Then fill the bottle to the mark with water, being careful to avoid an error due to parallax by holding the bottle with the mark on the same level as the eye. Weigh again and let the weight be W gm.

The weight of water filling the bottle is therefore $W - B$ gm.

Record (1) the weight of the bottle, (2) the weight of the bottle and water, (3) the weight of water filling the bottle.

Fill the bottle to the mark with the liquid the specific gravity of which is to be determined.

Weigh the bottle full of liquid and let the weight be w gm. The weight of liquid filling the bottle is $w - B$ gm.

Therefore the specific gravity of the liquid is

$$\frac{w - B}{W - B}$$

Record (1) the weight of the bottle, (2) the weight of the bottle and the liquid, (3) the weight of liquid filling the bottle, and lastly the specific gravity of the liquid.

SPECIFIC GRAVITY OF A GRANULAR SOLID

The method with the specific gravity bottle is applicable to solid substances that are heavier than water and insoluble in it. The specific gravity of sand or small shot may be found by this method. In the case of a substance like glass, the solid must be broken up into fragments small enough to go into the specific gravity bottle.

If the substance is lighter than water, or is soluble in it, we can use some other liquid in the determination, but in this case a separate experiment is necessary to determine the specific gravity of the liquid employed.

In determining the specific gravity of sand, it is not sufficient to fill the bottle with sand and proceed as though we were dealing with a liquid. By so doing we should find the specific gravity, not of sand, but of a mixture of sand and air; for a large amount of air is imprisoned between the sand grains.

EXPT. 17. Determination of the Specific Gravity of a Granular Solid, by using the Specific Gravity Bottle.—First determine the weight, B , of the empty bottle, as in the previous experiment.

Fill the bottle about one-third full with sand, being careful to use dry sand in a dry bottle. Weigh the bottle and sand and let the weight be W_1 gm.

The weight of sand alone is $W_1 - B$ gm. Fill up the space above the sand and between the grains with water, shaking the bottle *round and round* to get rid of air bubbles from among the sand. If great accuracy is required, the air must be removed by connecting the neck of the bottle with a vacuum pump by rubber tubing. Adjust the level of the water to the mark. Let the weight now be W_2 gm. Then the weight of water added is $W_2 - W_1$ gm.

Empty the bottle; fill it to the mark with water, and weigh again. Let the weight be W gm. Then the weight of water required to fill the bottle to the mark is $W - B$ gm. The difference between these two quantities of water (viz. $W - B$ and $W_2 - W_1$ gm.) represents the quantity of water required to fill the space occupied by the sand. Calculate this quantity and record the result.

Now the specific gravity of sand

$$= \frac{\text{Weight of sand}}{\text{Weight of equal volume of water}}$$

$$= \frac{\text{Weight of sand}}{\text{Quantity of water required to fill the space occupied by the sand}}$$

Calculate the specific gravity of sand and record the result.

§ 3. THE HYDROSTATIC BALANCE

FORCES BETWEEN BODIES IN CONTACT

When two bodies are in contact, the action and reaction constitute a pair of forces which, in accordance with Newton's Third Law, are equal and opposite.

If the force be at right angles to the surface of contact of the two bodies, it is called a **thrust**. A thrust is measured in dynes or in gm.-weight.

In any actual case the bodies must be in contact over a finite area. We speak of the **pressure** between two bodies in contact, when considering the forces as distributed over the surfaces in contact.

The **pressure** at a point is found by dividing the thrust on an element of area round that point by the number of units of area in the element. Pressure is measured in dynes per square centimetre.

When one of the substances in question is a fluid and the other a solid, the resultant force due to the fluid pressures on the solid can be determined in a simple way by a principle which we shall now consider.

PRINCIPLE OF ARCHIMEDES

The Principle of Archimedes is usually stated as follows:—When a body is immersed in a fluid, its weight is apparently diminished by the weight of the fluid displaced. A simpler and more direct statement of the principle is: When a body is wholly or partially immersed in a fluid at rest, it experiences an upward thrust equal to the weight of the fluid displaced.

The truth of this principle may be anticipated theoretically on certain assumptions as to the action of fluid pressure, or by a simple type of experiment it may be verified practically.

If we consider the equilibrium of any portion of a fluid at rest, it is obvious that this portion must be supported by the fluid surrounding it, otherwise its weight would cause it to sink. It is also obvious that this supporting force must be exactly *equal* to the weight of the portion considered.

The support is given by pressures exerted by the surrounding fluid (indicated by the small arrows in Fig. 22), the resultant of which is equal to the weight of the portion considered but acts vertically upwards. The resultant supporting force may be termed the *upthrust*.

If now a portion of the fluid be imagined removed, and a *solid* of exactly the same shape be put in its place, the surrounding fluid will still exert the same pressures as before; therefore the solid will be supported with a force *equal* to that which was exerted on the fluid which has been displaced.

But this supporting force is equal to the weight of the displaced fluid, therefore the solid will be supported by a force — the *upthrust* — equal to the weight of the fluid it has displaced, and its weight will apparently be diminished by this amount.




FIG. 22.—Principle of Archimedes

EXPT. 18. **Experimental Verification of the Principle of Archimedes.**—For the experimental demonstration of the truth of this principle two cylinders are used, one solid and the other hollow, the latter being made just large enough to allow the solid cylinder to be placed inside it.

The cylinders are provided with hooks so that the solid cylinder (A) may be suspended underneath that which is hollow (B): Fig. 23 gives a sectional view of B with A partly withdrawn.




FIG. 23.—Hollow and Solid Cylinder

A is suspended below B, and both are hung from the beam of a balance; in the hydrostatic balances generally used, they are hung beneath the short pan as shown on the left in Fig. 24, a short piece of thread or very fine brass wire being used to let A swing well clear of B.

A and B should then be counterpoised by weights placed in the other pan. If now a vessel of water is placed beneath A and raised (or A lowered) until A is immersed completely, it will be seen that the beam is no longer horizontal, the counterpoising weights being too great.

Equilibrium is restored completely, however, if B is filled to the brim with water, thus showing that the weight lost when A is immersed, is just made up by adding a quantity of water equal in volume to A, so that when A is immersed in water, it loses a weight equal to the weight of its own volume of water.

Remove the water from B and add weights in the small scale-pan until balance is restored again. Evidently the weight thus added is equal to the weight of water which fills B, or to the weight of water displaced by A.

Repeat the whole experiment, using methylated spirit, paraffin oil, or any other liquid convenient. Note that after immersing A equilibrium is restored, when B is filled with the *same kind of liquid* as that in which A is immersed, thus verifying the Principle of Archimedes.

It is important to note that the *apparent* loss of weight is not the same in the various cases. This must be so since the upthrusts are the weights

of equal volumes of different liquids. If one of the liquids is water, we can at once deduce the specific gravity of any of the other liquids, for

$$\begin{aligned}\text{Specific gravity} &= \frac{\text{Weight of any volume of liquid}}{\text{Weight of an equal volume of water}} \\ &= \frac{\text{Upthrust due to liquid}}{\text{Upthrust due to water}}\end{aligned}$$




FIG. 24.—Verification of the Principle of Archimedes

APPLICATIONS OF THE PRINCIPLE OF ARCHIMEDES

The Principle of Archimedes affords a most important method of determining the specific gravities of both solids and liquids. When a solid is completely immersed in a liquid, the upthrust on the solid is equal to the weight of a quantity of liquid which has the same volume as the solid. Hence by comparing the weight of the solid with the upthrust, we can compare the specific gravity of the solid with that of the liquid, for the volumes considered are the same in each case.

In particular, if we find the upthrust on a solid of known weight completely immersed in water, we know the weight of water having a volume equal to that of the solid, and can at once deduce the specific gravity of the solid.

EXPT. 19. Determination of Specific Gravities, using the Principle of Archimedes.—The specific gravity of a solid or of a liquid may be determined with the hydrostatic balance.

(a) **Specific Gravity of a Solid (insoluble in water).**—Suspend the solid by a fine thread or wire from the short pan of a hydrostatic balance, or from the hook carrying the pan of an ordinary balance. Counterpoise the body when hanging freely in air, and again when immersed in water, supporting the beaker of water on a specific gravity stool if an ordinary balance is used. Hence determine the upthrust, and calculate the specific gravity, which is the ratio of the weight of the body in air to the upthrust.

(b) **Specific Gravity of a Liquid.**—Weigh a solid in air and in water as described in (a), and find the upthrust due to the water. Then weigh the solid in the liquid whose specific gravity is required, and find the upthrust due to the liquid. Since the volume considered is the same in each case, the specific gravity of the liquid is the ratio of the upthrust due to the liquid to the upthrust due to water.

(c) **Specific Gravity of a Solid (soluble in water).**—Choose some liquid in which the solid is insoluble. Determine the specific gravity s of the liquid by method (b), using another solid (such as glass) which is insoluble both in water and in the liquid. Weigh the solid in air and in the liquid, and find the upthrust due to the liquid. This is the weight of liquid having the same volume as the solid. To find the weight of an equal volume of water we must divide this by s . The specific gravity of the solid can then be deduced.

(d) **Specific Gravity of a Solid less dense than Water.**—Weigh the body (say wax) in air.

As the body is less dense than water it would float on the surface of water. In order to find the upthrust when the body is completely immersed in water, we employ a 'sinker', that is a piece of metal of high specific gravity, sufficiently heavy to sink the wax.

First find the weight of the metal sinker alone in water. By adding these two results we find the weight of the wax in air and the sinker in water. Then attach the wax to the sinker and find the weight of the wax and sinker together, when both are in water. The difference between this result and the former is due to the upthrust on the wax, for the sinker was in water on each occasion. Knowing the weight of the wax in air, and the upthrust on the wax when it is immersed in water, we can at once deduce the specific gravity of the wax.

The following example illustrates the method of working out and recording the observations :—

Weight of wax in air	= 3.235 gm.
Weight of brass sinker in water	= 6.925 gm.
By addition we obtain—	
Weight of wax in air and sinker in water	= 10.160 gm.
Weight of wax in water and sinker in water	= 6.310 gm.
Upthrust on wax in water	= 10.160–6.310 gm. = 3.850 gm.
Weight of an equal volume of water	= 3.850 gm.
S.G. of wax = $\frac{\text{Wt. of wax in air}}{\text{Wt. of equal vol. of water}}$	= $\frac{3.235}{3.850}$ = 0.846.

The Principle of Archimedes may be applied conveniently in other experimental determinations; some typical applications will now be given.

EXPT. 20. Determination of Volume by the Hydrostatic Balance.—

Suspend the body by means of a fine wire or thread from one arm of the balance and find its weight in air. Let this be W .

Then find the weight of the body when it is completely immersed in water. Let this weight be W_1 .

The difference between W and W_1 is due to the upthrust of the fluid on the body. By the Principle of Archimedes this is equal to the weight of the fluid displaced by the body, that is, if W and W_1 are in grams weight,

$$W - W_1 = VD,$$

where V denotes the volume of the body and D the density (mass per unit volume) of the fluid.

In the C.G.S. system of units the mass of 1 c.c. of water is very nearly 1 gram, so that D is unity. In this way the volume is determined in cubic centimetres. If any other liquid of known density were used, the volume of the immersed solid could be obtained equally simply since

$$V = \frac{W - W_1}{D}.$$

EXPT. 21. Determination of the Thickness of a Plate.—If the body is a flat plate of area A and mean thickness t , we have $V = At$, and therefore $t = V/A$.

Weigh a plate in air and in water and thus find V . Measure the length and breadth of the plate, assuming it to be rectangular, and determine A .

Calculate the mean thickness of the plate, and confirm the result by measurements with the micrometer screw. As the thickness may not be uniform, measurements should be made at several different points and the mean found.

EXPT. 22. Determination of the Diameter of a Wire.—If the mean diameter is d , the area of cross section is $\pi d^2/4$.

If the length of the wire is l , the volume is

$$V = \frac{\pi d^2}{4} \times l,$$

$$d^2 = \frac{4V}{\pi l},$$

$$d = \sqrt{\frac{4V}{\pi l}}.$$

Weigh a known length l of wire in air and in water, and thus determine its volume V .

Calculate the mean diameter of the wire, and confirm the result by measurements with the micrometer screw.

EXPT. 23. Determination of the Length of a tangled Piece of Wire.—Weigh the wire in air and in water. Calculate its volume from the result; measure the diameter of the wire with a micrometer screw, and hence calculate its length l .

§ 4. HYDROMETERS

The **Common Hydrometer** is an instrument for determining the specific gravity of a liquid by a flotation method. It consists of a weighted bulb provided with a vertical stem. When placed in a liquid of suitable density, the hydrometer floats with part of the stem above the surface, the condition of equilibrium being that the weight of the instrument should equal the weight of liquid displaced. The stem is graduated so as to indicate the specific gravity of the liquid.

This is a simple method of determining rapidly the specific gravity of a liquid, when only approximate results are required. Owing to the effects of surface tension, many precautions must be taken if accurate results are required.

NICHOLSON'S HYDROMETER

Nicholson's Hydrometer consists of a cylindrical float, preferably with conical ends (Fig. 25). Above this rises a stiff brass stem carrying a small scale-pan (A), while underneath the float is fixed a small basket (B). The basket is usually loaded with lead so that the instrument floats vertically, with part of the upper cone projecting out of the water. A perforated cap is sometimes fitted so that the basket can be covered over at will.

EXPT. 24. Determination of the Specific Gravity of a Solid by using Nicholson's Hydrometer.¹—In using the instrument it is floated in water, and weights are placed on the scale-pan A, the weights being adjusted until the hydrometer is immersed as far as the mark filed on the upper brass stem. It is advisable to place a slotted sheet of metal across the top of the jar or cylinder containing the water, the stem supporting the scale-pan being in the slot, which should be wide enough for the stem to move quite freely up and down. This sheet of metal prevents the hydrometer from sinking into the water if too heavily loaded, thereby avoiding wetting the scale-pan and the weights (see Care of Weights, p. 14). It also prevents the hydrometer from coming into contact with the sides of the jar. The weight required to sink the hydrometer to the mark having been determined (say W_0 gms.), the solid of which the specific gravity is required is placed on the scale-pan and the weight *now* required to sink the hydrometer to the mark is determined. Let this be W_1 ; then the weight of the body in air is $W_0 - W_1$.

The body is now placed in the basket B, and the hydrometer is sunk again to the mark by placing weights W_2 in the pan A.

The difference between the last two cases is due simply to the body being in air in the one determination, and in water in the other; that is, the difference is due to the *upthrust* of the water on the body. Hence

$$\begin{aligned} W_2 - W_1 &= \text{the upthrust,} \\ &= \text{weight of water having a volume} \\ &\quad \text{equal to that of the wax.} \end{aligned}$$

$$\begin{aligned} \text{And } \text{S.G.} &= \frac{\text{weight in air}}{\text{weight of this equal volume of water,}} \\ &= \frac{W_0 - W_1}{W_2 - W_1}. \end{aligned}$$

Determine the specific gravity of each of two bodies, one more dense, the other less dense than water. In the second case it will be necessary

¹ If the hydrometer provided is *dry*, find its weight W in this state. This weight is required in Expt. 25.




FIG. 25.—Nicholson's Hydrometer

to tie the body into the basket if no cover is used, otherwise it will float to the top of the liquid.

It is important to see that no air bubbles are entangled with the hydrometer in all these experiments.

The determinations of specific gravity made with this form of apparatus are not nearly so accurate as those obtained by the methods already described, considerable errors being introduced by forces due to surface tension acting round the stem where it leaves the liquid ; to minimise this action the stem should be as thin as possible.

EXPT. 25. Determination of the Specific Gravity of a Liquid by using Nicholson's Hydrometer.—Weigh the hydrometer dry, and let its weight be W .

Float the hydrometer in water, and determine what weight must be added to sink it to the mark : let this be W_0 .

Thoroughly wipe the hydrometer, then float it in the liquid the specific gravity of which is required, and find the weight needed to sink it to the mark : let this be W_1 .

Then $W + W_0$ is the weight of water displaced when the hydrometer is sunk to the mark, and $W + W_1$ is the weight of the corresponding volume of liquid.

Thus :

$$\text{Specific gravity of liquid} = \frac{W + W_1}{W + W_0}.$$

§ 5. DETERMINATION OF SPECIFIC GRAVITIES OF LIQUIDS BY COLUMNS EXERTING EQUAL PRESSURES

The pressure exerted by a column of liquid is independent of the shape of the containing vessel, if any effect due to surface tension be neglected ; the pressure then depends solely on the vertical height of the column and its density.

The pressure in dynes per sq. cm., exerted by a column of liquid of height h cm. and density D gm. per c.c., is equal to hDg , g being the acceleration due to gravity.

Thus, if two columns of different liquids exert equal pressures, the relation between their heights and densities can be expressed as $h_1 D_1 = h_2 D_2$, when h_1 and h_2 are the heights, and D_1 and D_2 the corresponding densities of the two columns of liquid respectively. Hence $D_1/D_2 = h_2/h_1$. If the second liquid be water, the ratio of the densities is the specific gravity ; for D_2 is then the density of water. Thus, the specific gravity of the liquid $= h_2/h_1$ where h_1 is the height of a liquid column which exerts the same pressure as a column of water h_2 cm. high. This property may be used for the determination of the specific gravity of a liquid in the following manner.

EXPT. 26. Determination of the Specific Gravity of a Liquid by the U-tube Method.—If two liquids do not mix, their specific gravities may be compared by balancing two columns, one of each liquid, in the sides of a U-tube, the heights of the columns being measured vertically from

the level of the surface of contact C, to the free surfaces A and B (Fig. 26). If the liquids to be compared would mix together, they must be separated by some other liquid with which neither mixes, such as oil or mercury, placed in the bend of the U. In this case the quantity of the liquid used in each tube must be adjusted until the level of the intervening liquid is the same in each of the side tubes.

The heights of the columns are measured from the top of the intervening liquid to the free surfaces. The ratio of the specific gravities of the liquids is the inverse ratio of the heights of the columns.




FIG. 26

The U-tube method just described has several disadvantages. The adjustment of the two surfaces of the intervening liquid to the same level demands the use of a 'spirit level' if any accuracy is to be obtained, and as this has to be used *outside* the tube, the accuracy even then is not very great. If the intervening liquid is mercury, a slight error in this adjustment leads to considerable errors in the results obtained, on account of the high density of mercury. In addition to this difficulty, there is also an actual error due to capillarity, the surface tension of the intervening liquid being different on the two sides, because its surfaces are in contact with different liquids.

These objections are, however, got over completely in a simple form of apparatus known as Hare's Apparatus.

EXPT. 27. Determination of the Specific Gravity of a Liquid by means of Hare's Apparatus.—In this apparatus the U-tube is inverted, the open ends of the U dipping, one into water, the other into the liquid whose specific gravity is to be found. In the bend of the U is fitted a branch tube, and by means of this a little air is withdrawn from the bend of the U so that a column of each liquid rises up the corresponding side of the tube. These columns communicate with the same air space at their top surfaces, while the free surfaces of the liquids outside the tubes are both open to the atmosphere. Hence the column in each tube adjusts its height until the column *above the level of the outside liquid* exerts a pressure equal to the difference between the external and internal pressures.




FIG. 27.—Hare's Apparatus

Measure the heights of the two columns above the corresponding external surfaces of the liquids, for several different adjustments of the internal pressure.

Show that the ratio of the heights is the same in each case.

Tabulate the observations so as to show in parallel columns of the table, the corresponding heights of the liquids in the tables, and the ratios of these heights. The specific gravity of the liquid used is the mean value of this ratio, since the densities of the liquids are *inversely* proportional to the heights.

In a narrow tube the height of the liquid column is appreciably affected by capillarity. Consequently the internal diameter of the U tube should not be less than 5 mm. The errors introduced by capillarity may, however, be eliminated by treating the observations in the following manner. If h_1 and h_2 , h'_1 and h'_2 , are corresponding pairs of readings for two different internal pressures, the specific gravity is equal to $(h_2 - h'_2)/(h_1 - h'_1)$, since the capillary elevation or depression is constant in each limb provided the tubes are of uniform bore (p. 150). The same result can be obtained by plotting h_2 against h_1 and obtaining the required fraction from the gradient of the graph.

NOTES ON UNITS OF VOLUME

In the C.G.S. system the unit of volume is the cubic centimetre (1 c.c. or 1 cm.³). The practical unit now generally used is the millilitre. The litre was originally intended to be 1 cubic decimetre or 1000 c.c. It is now defined as the volume of 1 kilogram of pure water at 4° C. and 760 mm. of pressure. The present accepted experimental relation is

$$1 \text{ litre} = 1000.028 \text{ c.c.}$$

or

$$1 \text{ c.c.} = 0.999972 \text{ millilitre.}$$

In the previous chapter 1 c.c. and 1 ml. have been treated as practically equal.

CHAPTER V

STATICS

§ 1. COMPOSITION OF VECTORS

PHYSICAL quantities can be divided into two groups, Scalars and Vectors.

A Vector quantity differs from a Scalar quantity in that it possesses direction as well as magnitude ; a Scalar quantity has magnitude only. A vector quantity can be represented by a straight line of a definite length drawn in a definite direction. Two scalar quantities of the same kind are added together by simple addition. Two vector quantities of the same kind cannot, in general, be added in this way, but must be ' compounded ' by means of the Parallelogram Law. By the Resultant of two vectors we understand the single vector which would produce the same effect as the two vectors considered.

The Principle of the Parallelogram of Vectors may be stated as follows :—

If two vectors be represented in magnitude and direction by the two adjacent sides of a parallelogram, the Resultant of those two vectors is represented in magnitude and direction by the diagonal of the parallelogram drawn through the point where those sides meet. This principle applies to all vectors, such as displacement, velocity, acceleration, force, etc. In the following discussion, the word *force* will generally be used, but it should be understood that wherever *force* is printed, the word *vector* could be read, or any particular type of vector, such as displacement or velocity.

In the case of forces, any unbalanced force acting on a body will cause it to move. Hence we have a simple method of detecting whether the forces acting on a body balance each other or not : if the body is at rest, the forces acting on the body constitute a balanced system. We may state the following proposition ; When a body is under the action of two forces which are equal and opposite, the body is in equilibrium.

Suppose three forces are acting on a small body at O and the body is at rest under their united action (Fig. 28).

Represent the three forces by lines drawn from O, drawing the lines along the directions of the forces, and of lengths proportional to

their respective magnitudes : let A, B, and C be these lines. By the above proposition, the body O would be at rest if we removed A and B and replaced them by a *single* force D (shown dotted in Fig. 28)




FIG. 28.—Three Forces in Equilibrium

which is equal and opposite to C, or the action of A and B together is equivalent to that of a single force D equal and opposite to C. This imaginary force D is the **Resultant** of A and B ; C, the force which keeps O at rest when A and B are acting also, is called the **Equilibrant** of A and B.

It is evident that the equilibrant and the resultant are equal and opposite forces.

Method of proving the Principle of the Parallelogram of Forces.—The principle of the parallelogram of forces states that if a parallelogram be constructed with the lines representing forces A and B as adjacent sides, the resultant of those two forces will be represented in magnitude and direction by the diagonal of that parallelogram drawn from O.

If this diagonal represents the resultant of A and B, it must be equal and opposite to the line representing C since the forces D and C are equal and opposite. If, therefore, the diagonal of this parallelogram is found to be equal and opposite to the line representing C, the principle of the parallelogram of forces is demonstrated.

Method of proving the Principle of the Triangle of Forces.—The construction of the complete parallelogram is not necessary to determine the magnitude of the resultant D. If we draw *ob* representing B in magnitude and direction, and from *b* draw *bc* parallel to A and of length proportional to A, we have now drawn one-half the parallelogram. Joining *o* and *c* gives us the diagonal representing D without further construction ; thus by means of a triangle the required resultant can be obtained.

The principle of the triangle of forces is more usually expressed in the following way : If three forces having magnitudes proportional to the lengths of, and directions parallel to, the sides of a triangle, act on a body, the body will be at rest under their action, provided that the arrows indicating their directions are in cyclic order round the triangle.

Consider the triangle *obc* ; the arrow indicating the direction of action of the force A in the side *bc* is in the same cyclic order as that indicating the direction of action of B. The resultant is represented by the line completing the triangle with its arrow *opposite* to this cyclic order.

Now the same line *oc* which represents the resultant of A and B will represent the force C if the arrow is pointed towards *o*. Under the action of these three forces A, B and C the body is at rest.

This principle is proved by the experimental verification of the Principle of the Parallelogram of Forces.




FIG. 29.—Triangle of Forces

The principle just discussed can readily be extended to the case of any number of forces acting on a small body. This general principle, known as the **Principle of the Polygon of Vectors**, is stated as follows : **If a number of forces A, B, C, D, E acting on a body keep the body at rest, the lines representing them in magnitude and direction, drawn end to end, with the arrows indicating the direction of the forces following each other in cyclic order, will form a closed polygon.**

This can be shown from the principle of the triangle of forces in the following way. Draw the triangle *oab* representing the forces A, B, and




FIG. 30.—Five Forces in Equilibrium




FIG. 31.—Polygon of Forces

their resultant. Construct on the line *ob* a triangle *obc* such that *bc* represents the force C. The line *oc* is the resultant of *ob* and C ; hence *oc* is the resultant of the *three* forces A, B, and C.

The line *ob* is evidently unnecessary ; for by drawing *oa*, *ab*, and *bc* as directed, *oc* is found, being the line closing the quadrilateral figure thus obtained.

The fourth force D can be added to A, B, and C by adding another line to the polygon, starting from *c* ; and similarly any number of forces can be compounded by this polygon method. Thus to obtain the resultant of any number of forces acting together at a point, a figure is constructed by drawing lines representing the forces, end to end, with the arrows indicating the direction of the forces following each other in cyclic order.

The line closing the figure with its arrow *opposite* to the cyclic order represents the *resultant* of all these forces.

The same line, with the arrow *following* the cyclic order, represents the *equilibrant* of all these forces.

This is an alternative statement of the principle of the Polygon of Forces.

If the figure is already closed, the resultant force is zero, and the body is in equilibrium under the action of the forces given.

The order in which the forces are taken is entirely immaterial.

APPARATUS FOR EXPERIMENTS ON FORCES

To verify these various principles relating to forces, a convenient apparatus can be constructed in the following way :—

Round the edges of a blackboard arrange a number of light, frictionless pulleys, over which light strong cords (fishing-line) are passed (Fig. 32). These should have loops at one end, and, if possible, watch-chain clips at the other. The board is mounted vertically on the wall or on a rigid stand,




FIG. 32.—Apparatus for Experiments on Forces

or if the pulleys are arranged with their planes perpendicular to the board, the board can lie horizontally on a table, the ends of the strings hanging well clear of the edges.

Sometimes the pulleys, instead of being fixed to the edges of the board, are attached to capstan blocks mounted on tripod stands.

A light ring is used as the small body, being clipped to the cords by the watch-clips.

When any forces whatever are applied through the cords, the ring will move into a position of equilibrium, and the directions of the various strings can be marked on the blackboard with finely pointed chalk, or on a sheet of drawing-paper fixed to the board with a pencil. These lines give the directions of the forces acting, and by measuring lengths along them proportional to the weights hanging from the other ends of the cords, we obtain lines representing the forces in both direction and magnitude.

From these force lines the various propositions already stated can be proved experimentally by using two, three, and larger numbers of forces.

It may be noted that, on account of friction, the position of the ring when in equilibrium under a given set of forces may vary over a small area. To obtain the true position, the position taken up should be marked, the ring disturbed, and the new position of rest observed. The middle of the area covered by the positions taken up after several disturbances may be taken as the true position of equilibrium.

Also, if the pulleys are mounted with their planes perpendicular to the board, they must be free to swivel about a vertical axis so as to follow

the various directions of the cord passing over them. This introduces friction in addition to the friction due to turning about the axle, and hence the vertically mounted board is preferable.

EXPT. 28. Determination of the Conditions of Equilibrium under the Action of Two Forces.—Attach two cords to the ring, and hang on to the cords various weights. Note that the two cords always draw out into one straight line, and that the ring only comes to rest if the weights hanging from the two cords are equal.

EXPT. 29. Verification of the Principle of the Parallelogram of Forces and the Principle of the Triangle of Forces.—Fasten to the ring three cords with weights attached. Draw lines representing the forces acting on the ring when in the position of equilibrium as already described.

Construct a parallelogram with any two of the force lines as adjacent sides and show that its diagonal is equal in length to the third line, and that the diagonal and this third line are in continuation of one another.

Draw a triangle at the side of the board with two sides parallel to two of the forces, their lengths being proportional to these forces respectively, and the arrows indicating their directions following each other in cyclic order. Complete the triangle and show that the third side is parallel to the third force, and represents the magnitude of the third force on the same scale as the other two forces are represented by the other lines.

EXPT. 30. Determination of the Weight of a Body by Means of the Parallelogram of Forces.—Using two known weights and one unknown, proceed as in Experiment 29, constructing the parallelogram with the lines representing the known forces as adjacent sides. From the length of the diagonal, determine the weight of the unknown body. Verify this with an ordinary balance.

EXPT. 31. Verification of the Principle of the Polygon of Forces.—Use four or five weights and proceed as in Experiment 29, but construct at the side of the board a figure consisting of lines parallel and proportional to the forces, the arrows indicating the directions of the forces following each other in cyclic order. When all the forces but one have been represented, close the polygon and show that the closing line represents the remaining force in both magnitude and direction, provided the arrow follows the same cyclic order as the others. Do this for the same set of forces two or three times, taking the forces in different orders in each case so as to get polygons of different shapes. Show that the length of the closing line and its direction is entirely independent of the order in which the other lines are taken, and that in every case it represents the remaining force.

§ 2. RESOLUTION OF VECTORS

We have seen how two vectors acting on one body can be compounded into one equivalent vector. It is necessary now to consider the resolution of one vector into two other vectors which together shall be equivalent to the original vector.

If B and C represent two such vectors it is evident from the previous results that they are equivalent to A , if A is represented by the diagonal of the parallelogram constructed on B and C (Fig. 33).

If B were perpendicular to C , B would have no effect whatever along the line of action of C , nor would C have any effect along the

direction of B, hence we could say that *C* represents the total effect of *A* along the direction of *C*, while *B* represents the total effect of *A* along the direction of *B*.

B and C would in such a case be called the **Resolved Parts** of A




FIG. 33.—Resolution of Vectors




FIG. 34.—Resolved Parts of a Vector

along their respective directions, or B and C are the **Components** of A along these directions (Fig. 34).

Now

$$B = A \cos \phi, \text{ and } C = A \cos \theta,$$

therefore we may say that the **Resolved part** of any force acting along a given direction, is equal to the magnitude of the force multiplied by the cosine of the angle between the direction of the force and the given direction.

Direct verification of this principle is given in the experiment called the **Static Inclined Plane** described on p. 57 (Fig. 36). In this a mass of weight *W* is maintained at rest, on a plane inclined to the horizontal at an angle θ by a force *P* acting along the plane.




FIG. 35.—Inclined Plane

Evidently the effect of the weight *W* along the plane is only equal to *P*, since *P* keeps the mass from moving down the plane under the action of its weight *W*. That is, *P* is equal to the resolved part of the weight acting parallel to the plane.

But *P* is shown to be equal to $W \sin \theta$, therefore the resolved part of the weight *W* acting parallel to or along the plane must be equal to $W \sin \theta$.

Now the angle between the plane and vertical is an angle ϕ (Fig. 35), such that $\phi = 90^\circ - \theta$, and $\cos \phi = \sin \theta$.

$$\therefore W \sin \theta = W \cos \phi.$$

Thus the resolved part of *W* acting along the plane at an angle ϕ to the direction of the weight *W*, is equal to $W \cos \phi$.

STATIC INCLINED PLANE

If a load *W* is resting on an inclined plane, it may be maintained in equilibrium on the plane, or pulled without acceleration up the

plane, by a force P acting parallel to the surface of the plane. The force P is much smaller than the weight of the body W , the value of P diminishing as the inclination of the plane diminishes.

Consider the forces acting on a body of weight W , which is just maintained in equilibrium on a plane inclined to the horizontal, at an angle θ , by a force P acting along the plane. We have first its weight W acting vertically downwards, secondly the force P acting along the plane, and in addition to these there is a force exerted by the plane called the reaction R of the plane. This force acts perpendicular to the surface of the plane, if the plane be smooth (Fig. 36).




FIG. 36.—Static Inclined Plane

These three forces together keep the body at rest ; their directions are all known, and hence if the magnitude of one of them is known, the other two can be determined by applying the principle of the triangle of forces.

Let the line AB denote the weight W . Draw AC perpendicular to the plane, and parallel to the reaction R , and BC parallel to the plane, and parallel to P .

They intersect at C ; hence AC and BC represent R and P respectively.

The angle CAB is equal to the angle θ ; since AC is perpendicular to the plane and AB is perpendicular to the base. Thus

$$\frac{BC}{AB} = \sin \theta. \quad *$$

But BC and AB represent P and W ,

therefore

$$\frac{P}{W} :: \sin$$

or

$$P = W \sin \theta$$

A somewhat simpler proof is obtained if we consider the **energy gained** by the weight when pulled up the plane, and the **work done** by P in pulling it up the plane.

WORK AND ENERGY

The work done by a force is measured by the product of the magnitude of the force and the *effective* displacement, or the distance moved by the point of application *in the direction of the force*. Suppose the force P pulls the body through a distance l , measured along the inclined plane, and in so doing raises it through a vertical distance h , which we may call the height of the plane.

The height of the top of the plane above the bottom is h , hence the weight gains an amount of potential energy $= Wh$ when raised to the top.

The force P acts through a distance l in its own direction when pulling the weight up the plane, if l is the length of the plane, hence the work done by the force is Pl .

By the principle of the conservation of energy

energy gained = work done,

so that

$$Wh = Pl,$$

or

$$P = \frac{Wh}{l} = W \sin \theta.$$

The apparatus used in this experiment consists of a plane board hinged at its lower end, and supplied with some means of adjusting its inclination to several different values. At the upper edge is usually fixed a pulley, over which a cord passes. To the end on the plane the load W is attached, while from the hanging end weights can be suspended to exert the force P on the cord. In order to eliminate friction between the load W and the plane, W is usually a small roller, supported on an axle carried by a suitable framework, to which framework the cord is attached. In some forms of apparatus the pulley and hanging weight are replaced by a spring balance which automatically adjusts itself to exert the required force P at any inclination, and P can be read off directly.

The angle θ can be measured by means of a protractor placed with its edge along the horizontal base and its centre at the centre of the hinge, but it is better to have a graduated quadrant fitted near the top of the plane, with a plumb-line hanging from its centre. If the zero line of the quadrant stands out at right angles to the plane, the angle θ is read off as the angle between the plumb-line and this zero line. This method is preferable to the first, as it is necessary to level the base by means of a spirit-level if the first method is used, and other errors easily creep in when measuring the angle θ .

Expt. 32. Static Inclined Plane.—Apply different forces P over the pulley, using different inclinations of the plane. Adjust P in each case *until the roller moves equally freely up or down the plane* when given a slight push. This effectively gets rid of the effect of any friction at the pulley and enables very accurate readings to be taken. Note corre-

sponding values of P and θ , taking five or six different inclinations. Tabulate your observations thus :—

P	θ	$\sin \theta$	$\frac{P}{\sin \theta}$

Mean
 $\frac{P}{\sin \theta}$

Since the same roller is used, W is constant. But $P = W \sin \theta$, therefore the values of $P/\sin \theta$, the quotients tabulated in the last column, should be constant and equal to W . The mean value of $P/\sin \theta$ should be equal to the weight of the roller quite accurately ; verify this by actually weighing the roller.

If the quadrant for measuring θ is not fitted to the apparatus employed, measure h and l directly, taking the same point on the plane each time and measuring its height above the base and its distance *along the plane* from the centre of the hinge. The table of observations would then be arranged under the headings $P, h, l, \frac{h}{l}, \frac{P}{l}$.

Find the mean value of Pl/h . This should be equal to W measured directly.

If the weights exerting the force P are put in a scale-pan suspended from the cord, the weight of the scale-pan must be included in the force P .

§ 3. GENERAL CONDITIONS FOR THE EQUILIBRIUM OF ANY BODY UNDER ANY FORCES

MOMENT OF A FORCE

The turning effect of a force about any axis is called the moment of the force about the given axis, and is defined as the product of the force and the perpendicular distance from the axis to the line of action of the force.

The direction of rotation, 'clockwise' or 'anti-clockwise', is termed the *sense* of the moment : it is immaterial which sense is chosen as positive, provided the convention made is retained throughout.

If a body is acted upon by any system of forces, the body will remain at rest only if the two conditions given below are satisfied.

1. The Resultant Force in any direction must be zero.
2. The Resultant Moment of all the forces about any axis must be zero.

Condition 1 is included implicitly in condition 2, but it is so important that an explicit statement is of value.

PRINCIPLE OF THE LEVER

The first of the above conditions has been proved experimentally in considering the composition of forces ; it is purposed now to demonstrate the truth of the second statement by experiment. The simplest way to do this is by pivoting the body on which the forces are to act about a suitable axis called the *fulcrum*. Then the forces required to prevent the body from moving *as a whole* are introduced at the fulcrum, and condition 1 is satisfied without further trouble : a body pivoted in this way is called a lever.

Since we cannot determine easily the force brought into action at the fulcrum, we can only find its *moment* about *the fulcrum itself*. The moment of any force about its point of application is zero, hence the forces brought into action at the fulcrum have no moment about the fulcrum itself. Thus in considering the equilibrium of the lever, we can leave out of consideration the forces brought into action at the fulcrum, so long as we consider the moments about the fulcrum alone.

The condition of equilibrium of a lever may therefore be stated thus : A lever will be in equilibrium, if the moments of all the applied forces about the fulcrum have a zero resultant.

LEVERS

A convenient apparatus for demonstrating the principle of the lever, and therefore verifying the law of moments, may be constructed in the following way. A rigid framework of wood carries at a point near the




FIG. 37.—Experiments on Levers

middle of one of the uprights, a round rod of brass projecting horizontally. On this rod is placed a metre scale with holes drilled about every 2 cm.

along its length, the rod passing through the hole at the *middle* of the scale. By this means the centre of gravity of the rod is at the point of support, and the effect of the weight of the rod is eliminated (*see Centres of Gravity*, p. 63).

Pulleys are mounted on the top bar of the framework, with cords passing over them. The cords can be attached to the metre scale at any point by means of brass hooks tied to the ends. The other ends of the cords carry scale-pans, so that various forces can be applied to the lever by weights placed in the scale-pans. Other scale-pans can be hung from the holes in the metre scale directly, so that the forces can be applied vertically upwards or downwards, or inclined at different angles to the horizontal.

Since friction of the pulleys and at the fulcrum cannot be eliminated, the apparatus should be given a slight initial velocity when approximately




FIG. 38.—Levers

adjusted, the weights being adjusted finally until the lever turns equally freely in either direction. If one of the forces acts obliquely, this slight motion given to the lever should not deflect it to any great extent from the horizontal position, otherwise the angle at which the force acts will be altered, and its moment about the fulcrum will thereby be changed.

When the lever turns equally freely in either direction, the moments of the various forces about the fulcrum must be calculated, and their senses noted. This is done by multiplying each force by the perpendicular distance from the fulcrum to the line of action of the force, positive or negative signs being prefixed according as the sense of the moment is clockwise or anti-clockwise. The moments of all the forces must then be added together *algebraically*; the sum of the moments in each case should be zero.

NOTE.—The weights of the scale-pans must be included in each of the forces considered.

EXPT. 33. Levers.—Perform the experiment for each of the following cases, applying forces as indicated in Fig. 38:—

Case I, frequently referred to as a lever of the *first order*.

The force F causes clockwise rotation, and its moment Fd about the fulcrum is *positive*.

The force F' causes anti-clockwise rotation ; its moment $F'd'$ about the fulcrum is therefore *negative*.
Show (algebraically) $Fd + F'd' = 0$.

EXAMPLE. $F = 350$ gm. weight $d = 48$ cm.
 $Fd = +16800$,
 $F' = 750$ gm. weight $d' = 22$ cm.
 $F'd' = -16500$,
 $Fd + F'd' = 16800 - 16500 = 300$,
 Error 2 %.

Case II, frequently referred to as a lever of the second order.

F causes anti-clockwise rotation, and its moment Fd about the fulcrum is negative.
 F' causes clockwise rotation, and its moment $F'd'$ about the fulcrum is positive.
 Show as before $Fd + F'd' = 0$.

Case III, generally known as a lever of the third order.

Fd is again negative, and $F'd'$ positive.
 Show $Fd + F'd' = 0$.

The general principle is applicable to any number of forces, acting at any angle to the lever, as is shown in the two following cases. Any other sets of forces can be substituted for these, and the total moment about the fulcrum will in all cases be found to be zero.

Case IV.

Fd is positive.
 $F'd'$ is negative.
 $F''d''$ is negative.
 Show algebraically $Fd + F'd' + F''d'' = 0$.

Case V.

Fd is positive.
 $F'd'$ and $F''d''$ are both negative.
 Show $Fd + F'd' + F''d'' = 0$ as before.

Enter all results for each of the five cases as indicated in Case I, stating any observed error as a percentage of the total moment in one direction. It is advisable to use fairly large weights—200 to 300 gm. at the ends of the scale and up to 1 kgm. nearer the middle. By this means the effect of the friction at the fulcrum is made a comparatively small proportion of the actual turning moments applied, and greater accuracy is obtained.

EXPT. 34. Weighing a Metre Scale by Application of the Principle of the Lever.—Support the metre scale at a point about 10 cm. from one end. Hang a scale-pan from the end hole in the short side of the scale, and adjust weights in the scale-pan until the scale is just balanced. The weight of the scale acts downwards at its Centre of Gravity, assumed to be at the middle of the scale. Let the weight of the metre scale be W gm. and the weight in the scale-pan (including the scale-pan itself) w gm. The distance of the fulcrum from the centre of the scale being D , and from the scale-pan d , we have

$$WD = wd.$$

Measure D and d and observe w . Calculate W , the weight of the metre scale.

Repeat this for two or three positions of the fulcrum and check the result by weighing the metre scale on a balance.

§ 4. CENTRE OF GRAVITY OR CENTRE OF INERTIA

When two parallel forces act upon a rigid body they can, in general, be replaced by a single resultant force. Thus the two forces P and Q acting at the points A and B are equivalent to a single force $R = P + Q$.

The line of action of this force cuts AB in a point C such that

$$P \times AC = Q \times CB.$$

The *direction* of the forces does not affect the position of the point C . It is called the **centre of the parallel forces**.




FIG. 39.—Resultant of Parallel Forces

Similarly, when any number of parallel forces act upon a rigid body, their resultant passes through a certain point whose position does not depend on the direction of the forces. The position of this point — the **centre of the parallel forces** — is fixed when the magnitudes and points of application of the forces are known.

All bodies are attracted towards the centre of the earth by the force of gravity. We may suppose a rigid body made up of particles each one of which is attracted by the earth. We thus obtain a system of *approximately* parallel forces acting on the body. The centre of these parallel forces is called the **Centre of Gravity** of the body.

Accordingly the **Centre of Gravity** of a body may be defined as that point, fixed with relation to the body, through which the resultant of the earth's attraction on all the particles passes, whatever be the position of the body.

Centre of Inertia or **Centre of Mass** is a more general term, not depending on gravity. If a particle of mass m_1 is placed at A and a particle of mass m_2 at B , the **Centre of Inertia** of the two particles is *defined* as a point C in the line joining them such that $m_1 AC = m_2 BC$. If a third particle of mass m_3 is placed at any other point in space, the centre of inertia of the three particles is found by supposing a single particle of mass $m_1 + m_2$ placed at C and then determining as before the centre of inertia of this imaginary particle and m_3 . This process may be continued for any number of particles.

When a heavy body is supported at a single point, the only forces acting on the body are its weight and the reaction at the point of support. If the body remain at rest, these two forces must be in

equilibrium, and consequently must have the same line of action. Hence the point of support must be in the same vertical line as the Centre of Gravity.

EXPT. 35. Experimental Determination of the Centre of Gravity.—To find the Centre of Gravity of a body, suspend it by a string attached to any point A and mark the position of the vertical line AB (Fig. 40). The




FIG. 40.—Determination of Centre of Gravity

vertical may be determined by means of a plumb-line. Then suspend the body from another point C and mark the vertical CD. The Centre of Gravity must be in AB, and also in CD, and so must be at the point of intersection G. Confirm this by suspending from a third point.

The Centre of Gravity of a body depends on the distribution of mass throughout the body, as can be shown in the following manner. The body used for this experiment consists of a uniform plate of wood,

to which may be attached a load formed by a brass nut and screw P.

Find the Centre of Gravity of the plate alone, and then the Centre of Gravity with the load fixed to the plate. Repeat the latter determination for several positions of the load.

Plot a graph showing how the position of the Centre of Gravity varies as the load is moved along the diagonal of the plate, taking as




FIG. 41.—Loaded Plate

abscissae the distances (OP) of the load, and as ordinates the distances (OC) of the Centre of Gravity C, all measured from the original Centre of Gravity O of the unloaded plate.

It will be noticed that the Centre of Gravity of the compound body moves from the position of the Centre of Gravity of the plate of wood, through a distance proportional to the displacement of the brass weight from that point. The gradient of the graph obtained is the ratio OP/OC , and this ratio is equal to the ratio of the sum of the weights of the brass nut and the plate of wood to the weight of the load. Verify this.

§ 5. GRAPHIC METHODS OF COMPUTATION

A considerable number of quantities can be determined by purely graphical, as distinct from numerical, methods. It is also possible to investigate by such methods the conditions of equilibrium of a body or the force required to keep it in equilibrium. These are the methods of **Graphic Statics**.

Two properties of a flat uniform body which are readily found by a simple graphical construction are the position of the **Centre of Gravity** or **Inertia** of a uniform plate, and the value of the **Moment of Inertia** of that plate about any axis. These methods not only enable the **Moment of Inertia** of the cross-section of a beam to be found, but also give a useful exercise on the use of the planimeter.

GRAPHIC METHOD OF DETERMINING THE CENTRE OF GRAVITY OR INERTIA OF A UNIFORM PLATE

Consider a plate of any contour; draw at one side of it a line XX' and another line YY' parallel to the first, tangential with the curve at the extreme point on the opposite side (Fig. 42). From any point O on the first line draw a number of lines radiating in different directions. It is convenient to arrange the radiating lines so that pairs, such as OA , OC , intersect the contour at equal distances from the original line XOX' .




FIG. 42.—Graphic Method for Centre of Gravity

Through each of the points of intersection, A , B , C , etc., draw a line parallel to the base line XOX' . From each point A , B , C draw a line perpendicular to XOX' , meeting YY' in points A' , B' , C' , etc., respectively.

Join OA' , OB' , OC' . Each of these lines cuts its corresponding parallel in some point A_1 , B_1 , C_1 . Draw a curve passing through all the points A_1 , B_1 , C_1 , etc., and find the area of this figure and of the original plate.

The Centre of Gravity of the plate is at a distance h from XOX' such that

$$h = \frac{\text{Area of figure } A_1B_1C_1 \text{ etc.}}{\text{Area of original figure } ABC \text{ etc.}} \times \text{Perpendicular distance between } XX' \text{ and } YY'.$$

PROOF.—Consider a small portion of the original figure enclosed between the parallels AC and BD, imagining these to be quite close together.




FIG. 43.—Proof of Graphic Method for Centre of Gravity

The corresponding area of the figure $A_1B_1C_1$, etc., constructed as already described, has the same vertical dimension, but its length is reduced in the ratio of x/y ,

and so

$$\frac{\text{Area } ABCD}{\text{Area } A_1B_1C_1D_1} = \frac{y}{x}.$$

The moment of the mass of the original figure ABCD about the axis XOX' is equal to

$$ABCD \times x,$$

and thus is equal to

$$A_1B_1C_1D_1 \times y.$$

Thus, for any narrow element ABCD of the original figure, the moment of its mass about the axis XOX' is equal to the area of the corresponding element of the constructed figure multiplied by the distance between the lines XOX' and YY'.

Now if the Centre of Gravity of the plate were at a distance h from the axis XOX', the whole area of the plate multiplied by the height h would be equal to the sum of the products of the elemental areas, such as ABCD, multiplied by the corresponding distances (x) from the same line XOX'.

Thus

$$\text{Area of plate} \times h = \Sigma(ABCD \times x).$$

Now the value of $ABCD \times x = A_1B_1C_1D_1 \times y$,

Hence

$$\begin{aligned} \Sigma(ABCD \times x) &= y \times \Sigma A_1B_1C_1D_1, \\ &= y \times \text{Area of constructed figure.} \end{aligned}$$

Hence

$$\text{Area of plate} \times h = \text{Area of constructed figure} \times y,$$

so that

$$h = \frac{\text{Area of constructed figure}}{\text{Area of original plate}} \times \text{Distance between XOX' and YY'}.$$

By taking a different base line, say perpendicular to the line XOX', and carrying out a similar construction, the distance h' from this second base line can be found by the same process, and therefore the exact position of the Centre of Gravity is known.

When the plate is symmetrical about any one line, the C.G. must of course be in the axis of symmetry, and thus one construction only is required for the determination of the position of the Centre of Gravity.

EXPT. 36. Graphic Determinations of the Centre of Gravity.—Construct an isosceles triangle. Take its base as the axis XOX' and show that the Centre of Gravity of the triangle is one-third of the way up the triangle, using a planimeter for measuring the necessary areas. Find also the position of the Centre of Gravity of a semicircle.

GRAPHIC DETERMINATION OF THE MOMENT OF INERTIA OF A UNIFORM PLATE

(For definition of Moment of Inertia, see p. 112)

The construction for this determination is similar to that for the determination of the position of the Centre of Gravity of a plate (p. 65).

When the points A_1, B_1, C_1 , etc., have been found, lines from these points are drawn to YY' , meeting YY' in A'', B'', C'' , etc., the lines A_1A'' being drawn perpendicular to XOX' .

Join OA'', OB'' , etc.

These lines cut the corresponding parallels in points A_2, B_2, C_2 , etc.

Draw the contour A_2, B_2, C_2 , etc., and find the area of the figure thus obtained.

The Moment of Inertia of the plate about the axis XOX' is equal to the area of this figure multiplied by the square of the distance between the lines YY' and XX' .

PROOF.—Consider an elemental area $ABCD$ of the original figure enclosed between two parallels very close together.




FIG. 45.—Proof of Graphic Method for Moment of Inertia

The length of the element between A_1C_1 is equal to

$$AC \times \frac{x}{y}.$$




FIG. 44.—Graphic Method for Moment of Inertia

The length of the element between A_2C_2 is equal to

$$A_1C_1 \times \frac{x}{y},$$

so that

$$\frac{A_1C_1}{AC} = \frac{x^2}{y^2}.$$

The vertical dimension of the various parts of the element is unaltered. Hence

$$\frac{\text{Area of element of plate}}{\text{Area of corresponding element of constructed figure}} = \frac{y^2}{x^2} = \frac{ABCD}{A_2B_2C_2D_2}.$$

Now the Moment of Inertia I of the whole plate about XOX' is the sum of the products of the mass of each element by the square of its distance from the axis XOX' , that is

$$I = \Sigma ABCD \times x^2.$$

But

$$ABCD \times x^2 = A_2B_2C_2D_2 \times y^2,$$

so that

$$I = \Sigma ABCD \times x^2 = y^2 \times \Sigma A_2B_2C_2D_2,$$

or

$$I = \text{Area of constructed figure} \times y^2.$$

EXPT. 37. Graphic Determination of the Moment of Inertia of a Circular Plate.—Draw a semicircle, taking its diameter as the axis XOX' ; find the Moment of Inertia of the semicircle about a diameter. Twice this will be the Moment of Inertia of a circular plate about a diameter. Show that this is equal to $\frac{\pi a^4}{4}$, where a is the radius of the circle (10 cm. is a convenient radius to take).

EXPT. 38. Graphic Determination of the Moment of Inertia of a Rectangular Plate.—Draw a rectangle of length b and breadth d (10 cm. and 15 cm. are convenient lengths to take). Using a line across the middle as the base line XOX' , find the Moment of Inertia of one half of the rectangle about this line. Twice this is evidently the Moment of Inertia of the whole rectangle about an axis through the middle. Show that this is equal to $bd^3/12$.

Do this for the same rectangle about an axis through the middle but parallel to the other pair of sides.

It will have been noted in the foregoing that the mass of the plate has not been mentioned. The contour is marked out on the paper and the construction deals merely with the area of the plate. The result obtained is what is usually known as the **Moment of Inertia of the area** about the given axis. This is the quantity generally required in engineering problems. If, however, the Moment of Inertia of an actual plate of matter is required, it may be found from the Moment of Inertia of the area in the following way :—

The Moment of Inertia of the area is numerically equal to the Moment of Inertia of a plate of that same shape whose surface density is unity. If, therefore, the Moment of Inertia of the area is found graphically in the foregoing manner, the **Moment of Inertia of a plate of the same shape about a similar axis** is found by multiplying the result thus obtained by the surface density of the plate, or by its mass divided by its area. This form of result is very rarely required.

§ 6. GRAPHIC STATICS

Whether a body will be in equilibrium or not under the action of a given system of forces can be tested by purely graphic construction. The forces can produce motion of two kinds: (a) translation, (b) rotation. The first of these will be zero if there is no resultant force in any direction, the second will be zero if there is no resultant moment about any axis.

The graphic construction to test for no motion of translation is to construct the polygon of forces. If the polygon is closed, there is no resultant force in any direction, and the body will have no motion of translation.

If now we can devise a graphic construction to test whether the resultant moment about any axis is zero, we shall have a complete graphic method for testing the equilibrium of a body under any system of forces.

The graphic method for testing for zero moment is known as the **Link Polygon** or the **Funicular Polygon**.

Let A, B, C, D and E (Fig. 46) represent a system of forces acting on a body in such a way as to produce neither translation nor rotation. The force polygon will be of the shape shown in full lines in Fig. 47, and will be a closed polygon.

Choose some point O and draw lines from O to the corners of the force polygon, *ab*, *bc*, *cd*, etc. From some point P on the line of action of A (Fig. 46) draw PQ parallel to the line *Oab*.

From the point Q, where this cuts the line of action of B, draw a line QR from B to C parallel to *Obc*. From C to D draw RS parallel to *Ocd* and so on. By this means a figure will be obtained, shown by the dotted lines drawn between the lines of action of these forces A, B, C, D and E. This is called the **Link Polygon** or the **Funicular Polygon**, and if it is closed the forces acting on the body will have no turning moment on the body. The conditions of equilibrium of a body may therefore be expressed by saying that, for equilibrium of any body, the force polygon must be closed, and the link or funicular polygon must be closed.

If, when these polygons are constructed, they are not found to be closed, the line closing the force polygon must be drawn; this gives the magnitude and direction of the equilibrating force. Its line of action is found by producing the open ends of the funicular polygon until they meet. The point of intersection is on the line of action of the force. The direction and magnitude of the force are known already, hence the force required to maintain the whole body in equilibrium is determined completely.

The magnitude and line of action of the force E in the diagram (Fig. 46) was found by means of these methods, ABC and D being supposed known.

For the proof of the statements made in connection with the funicular polygon, and for its further applications, reference must be made to textbooks of Applied Mathematics.

EXPT. 39. Construction of the Force Polygon and the Link Polygon.—Hang up a light cardboard or metal plate on the apparatus used for verifying the Polygon of Forces, suspending it by means of four cords applied at different points and carrying weights at the other ends,

arranging the cords over pulleys so as to act in different directions. Make a copy of the plate on drawing-paper on a drawing-board, putting in lines




FIG. 46.—Link Polygon

to represent the directions and magnitudes of *three* of the four forces acting on the body.

Construct the force polygon and the link polygon on these three forces, and find the line of action and the magnitude of the force re-




FIG. 47.—Force Polygon

quired to keep the body at rest when under the action of these three forces. Verify that the fourth force actually acting on the plate is of this magnitude, and that its line of action coincides with that obtained by this graphic construction.

EXPT. 40. Graphic Determination of the Weight of a Plate.—As an additional exercise in graphic statics a heavy plate may be used, supporting it by three strings, so as to obtain three forces — acting in different directions, and applied at different points, but all in one plane. Determine the force which must be acting on the plate to keep it in equilibrium under these three forces ; this will be equal to the weight of the plate. The line of action of the force obtained graphically must pass vertically through the centre of gravity of the plate. Verify these results by determining the position of the centre of gravity (p. 64) of the plate, and also by weighing it.

§ 7. FRICTION

Whenever an attempt is made to move relatively to each other two bodies which are in contact, forces are introduced which oppose the motion. Such forces are grouped together generally under the title of frictional forces, though they differ very widely in their nature. The investigation of fluid friction is generally dealt with in experiments on viscosity and is beyond the range of this book.

SOLID FRICTION

When two solid bodies are in contact, the forces between them can be resolved, in general, into two components. The component in the direction of the common normal may be called the **thrust** between the bodies ; the other component, at right angles to the normal, may be called the **friction**. When an external force is applied to one of the bodies tending to move it in a direction at right angles to the normal, the force of friction is called into play and tends to prevent sliding motion. So long as no relative motion takes place the friction just balances the applied force. If the applied force is gradually increased, a stage will be reached at which sliding motion is just on the point of commencing. The friction is then called **limiting friction**.

The limiting friction between solid surfaces pressed together by a given thrust is practically independent of the area of contact, provided the surfaces are not appreciably deformed by applying too large a force on too small an area.

The friction between two solid surfaces, when motion takes place, and one surface slides over the other, is nearly independent of the relative velocity of the two surfaces.

In the case of two solid surfaces in contact, the limiting friction between the surfaces depends solely on the nature and condition of the two surfaces and on the force pressing the two surfaces together. The limiting friction is proportional to the force pressing the two surfaces together, and we obtain from this relation the quantity known as the **Coefficient of Friction** between two surfaces.

COEFFICIENTS OF FRICTION

The Coefficient of Friction between two surfaces is defined as the force of friction, divided by the force pressing the two surfaces together.




FIG. 48.—Friction

Thus if the thrust, or the force acting perpendicular to the two surfaces, is F , and the force resisting their relative motion is f , the coefficient of friction between the two surfaces is f/F . This is usually indicated by the symbol μ , so that

$$\mu = \frac{f}{F}.$$

STATIC AND DYNAMIC (OR KINETIC) FRICTION

The force required to *start* two surfaces slipping over each other when pressed together with a given force is greater than the force necessary to keep them moving over each other when once they are started. We thus have two frictional forces for a given force perpendicular to the faces. One of these is called the **static frictional force**, being equal to the force that has to be exerted to start the motion, or the force exerted on each other by the two surfaces when at rest. The other force is called the **dynamic frictional force**, being equal to the force required to keep the surfaces in steady motion over each other when once the motion has commenced. Corresponding to these two forces there will be two coefficients of friction. The coefficient of static friction is invariably greater than the coefficient of dynamic (or kinetic) friction.

EXPT. 41. Determinations of the Coefficients of Friction by moving a Block over a Horizontal Table.—Adjust the table so that the surface is horizontal. On it place a block of wood or metal whose weight has been determined. Attach a cord to a hook in the side of the block, and pass the cord over a pulley adjusted so that this part of the cord may be horizontal. To the free end of the cord attach a scale-pan on which various weights can be placed.

(i) **Determination of the Coefficient of Static Friction.**—Place a known load on the block, and adjust the weights in the scale-pan till the block just moves; find the ratio between the force required to move the block and the force pressing the two surfaces together. This ratio is the coefficient of static friction for the pair of surfaces used. Repeat this for several different weights on the block, and show that the ratio is approximately constant.

The force f , applied to the scale-pan, must include the weight of the scale-pan, and the force F , pressing the surfaces together, includes the weight of the block.

Record the observations giving F , f , and μ in tabular form. The mean value of μ is the coefficient of static friction.

(ii) **Determination of the Coefficient of Dynamic Friction.**—Place weights on the block and adjust the weights in the scale-pan until the block continues to move *without acceleration* when given a slight start. Find the ratio between the force required to keep the block in motion and the force pressing the two surfaces together. This ratio is the coefficient of dynamic friction for the two surfaces used. Do this for several different weights on the block to show that the ratio is approximately constant but smaller than the coefficient of static friction already obtained. Find the mean value of the coefficient of dynamic friction. Enter the results as in the determination of the coefficient of static friction.




FIG. 49.—Determination of Coefficient of Friction

By covering the table with a flat plate of brass or of zinc and using blocks of different materials the coefficients of friction between several different pairs of surfaces can be determined. A suitable selection, as giving fairly considerable differences in the values of the coefficients is : wood on wood (*a*) with, (*b*) across the grain, zinc on zinc or brass on brass, and wood on brass or wood on zinc.

It is essential for consistent results that the surface of any one plate shall be in a uniform state of polish all over. If this is not the case, the experiment must be carried out so that the portion of the lower surface moved over is always the same. This is done by marking a line on the fixed surface and starting the block always from that line.

It is also essential that the surfaces be in the same condition in all the experiments with a given pair of surfaces. If the surfaces are pressed together before applying the force, the coefficient of friction will be changed to some extent ; if moisture condenses on the surfaces the coefficient will be changed entirely.

LIMITING EQUILIBRIUM ON AN INCLINED PLANE

When a body is resting on an inclined plane, and the angle θ between the plane and the horizontal is increased till the body is just on the point of sliding down the plane, the force of friction assumes its limiting value. As in the Static Inclined Plane (p. 57), the force pulling the body down the plane is equal to the force, P , required to keep the block at rest on the plane in the absence of friction. The force pressing the two surfaces together is equal to the reaction, R , of the plane. The coefficient of friction, μ , is therefore P/R .

Now

$$P = W \sin \theta \text{ and } R = W \cos \theta.$$

Therefore

$$\mu = \frac{P}{R} = \frac{W \sin \theta}{W \cos \theta} = \tan \theta.$$

EXPT. 42. Determination of the Coefficients of Friction by means of an Inclined Plane.—Place a block of material on an inclined plane and gradually increase the slope of the plane. At a certain inclination the block will slip; note the angle of inclination when slipping takes place.




FIG. 50.—Friction on Inclined Plane

Place weights on the block and raise the plane again; note that the block slips at approximately the same inclination as before. Let this angle be θ_1 .

Repeat the experiment, and find the inclination at which the block will just continue to move down the plane if given a slight start—do this with the block loaded and unloaded, and show that the inclination is the same in either case.

Let this be θ_2 . The inclination required in this case is not so great as that required for the block to start of its own accord.

The coefficient of static friction is $\tan \theta_1$: the coefficient of dynamic friction is $\tan \theta_2$.

By facing the plane with sheets of different materials, and using different blocks, the coefficients of friction between several different sets of surfaces can be found in the same way.

THE FRICTION OF A ROPE OVER A FIXED PULLEY

When a belt or rope is stretched over a fixed cylinder, equilibrium can occur with unequal tensions on the two sides on account of the friction between the surfaces in contact.

Suppose the string in Fig. 51 is just on the point of slipping from B towards A—the tension T being greater than the tension T_0 —then it can be shown theoretically that

$$T = T_0 e^{\mu \theta},$$

where μ is the coefficient of friction, θ is the angle ACB (Fig. 51), and $e = 2.71828 \dots$

e is the base of the Napierian or Hyperbolic logarithms and is represented by the series

$$e = 1 + \frac{1}{1} + \frac{1}{1 \cdot 2} + \frac{1}{1 \cdot 2 \cdot 3} + \frac{1}{1 \cdot 2 \cdot 3 \cdot 4} + \dots$$

Taking logarithms to base e of both sides of the equation $T = T_0 e^{\mu \theta}$, we obtain

$$\log_e T = \log_e T_0 + \log_e e^{\mu \theta},$$

$$\log_e T - \log_e T_0 = \mu \theta.$$

For purposes of calculation convert to logarithms to base 10

$$(\log_{10} T - \log_{10} T_0) \log_e 10 = \mu \theta.$$




FIG. 51 —Rope over Pulley

The value of $\log_e 10$ is 2.30258 . . . , or with sufficient accuracy for the present purpose 2.3.

Hence the coefficient of friction is given by

$$\mu = \frac{\log_{10} T - \log_{10} T_0}{\theta} \times 2.3,$$

where θ is measured in radians. Note that π radians = 180° .

EXPT. 43. Determination of the Coefficient of Friction between a Rope and a Pulley.—The apparatus used to illustrate these results consists of a metal cylinder on the surface of which is stretched a string or belt. Tensions are applied to the ends of the string by attaching weights to them. It is convenient to use a known weight of say 100 gm. at one end and to adjust the weight at the other end by putting weights into a scale-pan tied to the string. The weight of this scale-pan must be taken into account, and in some cases it may be necessary to take into account the weight of the suspending string.

The 'angle of contact' for the string and the cylinder can be varied by passing the string over a small fixed pulley whose position can be adjusted as desired (Fig. 52). The friction of this pulley can be neglected.

The circumference of the cylinder may be marked off into a number of equal parts, corresponding say to 90° , 180° , 270° , 360° , 450° , 540° , etc. The string may then be wound round the cylinder so that the arc in contact corresponds with one of these angles.

For any particular angle determine what weight must be placed in the scale-pan just to start the string moving over the cylinder.

Tabulate the results as follows :—

Angle	Tension T	$\log_{10} T$	$2.3 \frac{\log_{10} T - \log_{10} T_0}{\theta}$
90°			
180°			
270°			
etc.			

The figures in the last column should be constant.

Plot two curves to show these results.

(1) Plot the value of $T - T_0$ as ordinate against the value of the angle as abscissa. This will illustrate the fact that the tension increases with the angle in the same manner as a sum of money put out at compound interest.

The importance of this curve in practical and in theoretical physics is considerable, for example in damped oscillations, or in Newton's law of cooling (p. 298), a curve of exactly the same form is used to express some of the results obtained.

(2) Plot the value of $\log_{10} T - \log_{10} T_0$ as ordinate against the value of the angle as abscissa. The graph should be linear.




FIG. 52.—Friction between Rope and Pulley

NOTES ON THE UNITS OF FORCE, WORK AND POWER

FORCE

Force may be measured either in gravitational or in absolute (dynamical) units.

The **gravitational unit of force** is the attractive force of the earth on a mass of one gram, or 1 gm.-weight.

The **dynamical unit of force** is the force which, acting on a mass of one gram, produces an acceleration of one cm. per sec. per sec. or 1 cm. sec.⁻² (see Chapter VIII, p. 102). This C.G.S. unit of force is called 1 **dyne**.

If g denote the acceleration in cm. per sec. per sec. produced by the earth's attraction, 1 gm.-weight = g dynes.

In the **M.K.S.** system unit force is 1 **newton** (10^5 dynes).

WORK

Work is measured by the product of the force acting, and the distance moved through by the point of application in the direction of the force.

The **gravitational unit of work** is the work done in lifting a mass of one gram through a vertical distance of one centimetre. It is called 1 **gm.-cm.**

The **dynamical unit of work** is the work done when a force of one dyne moves its point of application through one centimetre. 1 dyne-cm. is called 1 **erg**.

In the **M.K.S.** system a larger unit of work, the **joule**, is used. The joule is 1 newton-metre. 1 joule = 10 million ergs = 10^7 ergs.

POWER OR ACTIVITY

Power is the rate of doing work.

The **gravitational unit of power** is 1 gm.-cm. per sec.

The **dynamical unit of power** is 1 erg per sec.

The **M.K.S.** unit is more convenient. It is 1 joule per sec. or 1 watt.

MACHINES

§ 1. EFFICIENCY, FORCE RATIO AND VELOCITY RATIO

ANY apparatus by which work may be done as a result of mechanical energy supplied is called a machine. When work is done as a result of a supply of energy other than mechanical, the term 'engine' is generally used; we shall limit our study here to the consideration of machines, or 'contrivances' for doing useful work.

EFFICIENCY

In any form of machine, a certain portion only of the energy supplied is actually employed in useful work; the remainder is lost in friction inside the machine. The more 'efficient' the machine, the greater is the proportion of energy employed usefully; we therefore say that the efficiency of a machine is the ratio of the work usefully performed to the total energy supplied, so that

$$\text{Efficiency} = \frac{\text{Work usefully performed}}{\text{Energy supplied}}.$$

A perfect machine would utilise all the energy supplied; thus the efficiency of a perfect machine is denoted by unity.

In any type of machine the energy is supplied by some force P exerted on the machine and acting through some distance d_1 , while work done is by the machine exerting some force W , through a distance d_2 (Fig. 53). It is convenient to suppose that the force W is used in lifting a load through a vertical distance d_2 .

When the Applied Force P moves through a distance d_1 , the energy supplied to the machine is Pd_1 . The quantity Wd_2 gives the amount of work usefully performed in the same time.

Thus the Efficiency of the machine is given by

$$\epsilon = \frac{Wd_2}{Pd_1}.$$




FIG. 53.—Principle of a Machine

MECHANICAL ADVANTAGE OR FORCE RATIO

A machine is generally designed so that by applying a smaller force P , a load W of considerably greater magnitude can be overcome.

The ratio $\frac{\text{Load overcome by Machine}}{\text{Force applied to the Machine}}$ is known as the **Mechanical Advantage**, since it usually represents a *gain of force*.

This is not, however, invariably the case; a very large force P , acting only through a short distance, may be used to raise a small load W through a considerable distance. In this case the ratio W/P is less than unity.

To avoid what is perhaps a misuse of the term Mechanical Advantage in cases like this, the more general name **Force Ratio**, suitable for *all* cases, is sometimes used to indicate the ratio W/P .

$$\text{Force Ratio or Mechanical Advantage} = \frac{\text{Load overcome}}{\text{Force applied to Machine}}$$

VELOCITY RATIO

The distances moved through by the Applied Force and the Load are in general not equal. *If the machine were perfect*, we should have $Wd_2 = Pd_1$, so that

$$\frac{d_1}{d_2} = \frac{W}{P} \text{ in a perfect machine.}$$

This ideal is, however, never realised, and *always*

$$Wd_2 < Pd_1,$$

and

$$\frac{W}{P} < \frac{d_1}{d_2}$$

Now, in general, the distances d_1 and d_2 can be obtained by inspection of the mechanism, or by measurement of its parts; even if these be enclosed, the distance d_2 corresponding with any given distance d_1 can be measured. It is thus possible always to determine the ratio d_1/d_2 by simple inspection or actual measurement.

The ratio d_1/d_2 is the ratio of the distances moved through by the Applied Force and the Load in the same time; it is, therefore, the same as the ratio of the *velocities* of the Applied Force and the Load. *Rate of working* is an idea which is more important to an engineer than actual work performed, and therefore the study of *rate of motion* is more in accordance with engineering ideas than is that of the actual distance moved. The term **Velocity Ratio** therefore is applied generally

to the ratio of these *distances*, since the velocities are in the same proportion as the distances, that is

$$\text{Velocity Ratio} = \frac{\text{Distance Applied Force moves}}{\text{Distance Load is overcome}}.$$

In choosing a machine for any purpose, the Mechanical Advantage, or Force Ratio, required should be estimated, and the machine chosen should have a Velocity Ratio greater than this by an amount sufficient to allow for the frictional losses in the machine itself (see note at end of § 1).

It must be remembered that frictional forces are very variable in character, and depend to a large extent on *lubrication*.

RELATION BETWEEN VELOCITY RATIO, MECHANICAL ADVANTAGE (OR FORCE RATIO), AND EFFICIENCY

We have seen that the Efficiency can be expressed as:—

$$\epsilon = \frac{Wd_2}{Pd_1}.$$

This is conveniently re-written as—

$$\epsilon = \frac{W/P}{d_1/d_2},$$

$$\begin{aligned} \text{so that Efficiency} &= \frac{\text{Useful Work}}{\text{Energy supplied}} = \frac{\text{Mechanical Advantage}}{\text{Velocity Ratio}} \\ &= \frac{\text{Force Ratio}}{\text{Velocity Ratio}}. \end{aligned}$$

Thus if the Mechanical Advantage of a machine is determined experimentally, and its Velocity Ratio by inspection or measurement, the Efficiency is obtainable as the quotient of these two.

NOTE.—After some experience, the probable efficiency of various types of machines can be estimated with fair accuracy. If the Velocity Ratio is determined as already described, the probable Mechanical Advantage of a machine can be calculated roughly by the relation—

$$\text{Mechanical Advantage} = \text{Velocity Ratio} \times \text{Efficiency},$$

and hence its suitability for a given purpose can be judged.

§ 2. DETERMINATION OF THE EFFICIENCY, ETC., OF VARIOUS TYPES OF MACHINES

A few types of mechanism in common use will now be considered, together with the way in which their Velocity Ratios can be obtained by inspection. The method of obtaining the Mechanical Advantage is practically the same for all types of machines.

PULLEY BLOCKS

The set of pulley blocks considered is one consisting of two blocks of three pulleys each (Fig. 54). The upper block is fixed to a beam, the lower block being suspended from the upper one by a continuous cord which passes over each pulley. The one end A of the cord is attached to the framework of the upper block, while the other end hangs downward and is pulled by the applied force P. The load W is hung from the framework of the lower block.

EXPT. 44. Efficiency of a Pair of Pulley Blocks.—To find the efficiency two determinations must be made.

(i) **Determination of the Velocity Ratio by Inspection.**—If the cord is pulled down a distance d_1 , the total length of cord wrapped over the pulleys from B to A is shortened by a distance d_1 . This shortening is taken up equally by all the vertical portions of the cord between B and A, since all the lower pulleys move upwards together. Hence each of the portions of the cord between the upper and lower pulley blocks will be shortened by an amount $= d_1/6$, since there are six vertical portions.

But the centre of the lower pulley block will be raised a distance equal to the shortening of each of the vertical cords, so C will rise a distance $d_1/6$. This is the distance through which the load W is raised, and the distance $d_2 = d_1/6$, or the Velocity Ratio $d_1/d_2 = 6$.

In a similar way the Velocity Ratio of any system of pulleys can be determined easily.

(ii) **Experimental Determination of the Mechanical Advantage.**—In most types of apparatus designed for laboratory use, the weight of the lower pulley block is a considerable proportion of the actual loads employed. The weight of the blocks used in engineering works is, on the other hand, quite inappreciable compared with the loads lifted.

If therefore the weight of the lower pulley block is not included in the load, or the part of the applied force required to raise it is not deducted from the total force P, an erroneous

idea of the practical efficiency of such a system would be given, the value obtained being too low.

We therefore deduct from P the force P_0 required to lift the pulley block alone, or include the weight of the pulley block in W when calculating out the Mechanical Advantage, although, strictly speaking, the work done in raising the block is *not* employed usefully.

If the weight of the pulley block is known, the obvious way is to include it in the load W, and to find the ratio W/P , considering the pulley block as part of the load.

If the weight of the pulley block is not known, find the force P, required to operate the machine when there is no load hanging from the pulley block. This force P_0 is evidently required to raise the pulley block alone. Now when a known load W is suspended from the pulley block,




Fig. 54.—Pulley Blocks

a total force P_1 is required to raise the load W and the pulley block ; hence the force P required to raise the *known* part of the load is given by

$$P = P_1 - P_0.$$

P_0 and P_1 should be adjusted until the machine just continues to work when given a slight start.

Determine the Mechanical Advantage of the pair of pulley blocks, using five or six different loads. Arrange the observations in one of the following ways :—

(a) Weight of Pulley Block known = 70 gm. (say).

Load suspended from Block, W , (in gm.)	Applied Force, P	Total Load including Block, W	$\frac{W}{P}$
200	110	270	2.45
400	190	470	2.47
600	270	670	2.48
800	370	870	2.35
1000	450	1070	2.38

Mean of last column = Average Mechanical Advantage = 2.44.

(b) Weight of Pulley Block not known.

Force required to raise block alone = P_0 = 30 gm. (say).

Load suspended from Block, W	Total Applied Force, P_1	Force required for Load W , $P_1 - P_0 = P$	$\frac{W}{P}$
200	110	80	2.50
400	190	160	2.50
600	270	240	2.50
800	370	340	2.35
1000	450	420	2.38

Mean of last column = Average Mechanical Advantage = 2.45.

NOTE.—If a scale-pan is used either to hold the load W or the applied force P , its weight must be included in the corresponding force.

Having determined the Mechanical Advantage and the Velocity Ratio of the set of pulley blocks, express the Efficiency as—

$$\epsilon = \frac{\text{Useful Work}}{\text{Energy supplied}} = \frac{\text{Mechanical Advantage}}{\text{Velocity Ratio}} = \frac{\text{Force Ratio}}{\text{Velocity Ratio}}.$$

The Velocity Ratio is 6, the Mechanical Advantage is 2.45.

$$\therefore \text{Efficiency } \epsilon = \frac{2.45}{6} = 0.41 = 41\%.$$

DIFFERENTIAL WHEEL AND AXLE

This apparatus is frequently met with in laboratories, and the 'differential' principle it embodies is applied not infrequently in practical forms of gearing; it forms therefore a suitable type of machine to consider in detail. The applied force P is exerted on a cord which wraps round a wheel of large diameter (Fig. 55). The wheel is fixed to an axle whose diameter is different in two parts, and round these two parts the two ends of another cord are wound in opposite directions. In the hanging loop of this cord is carried a pulley from the framework of which the load W is supported as shown in the accompanying sketch. The whole apparatus is mounted on a metal spindle supported on a suitable pair of brackets.

EXPT. 45. Compound Wheel and Axle or Differential Wheel and Axle.

—The experiment is in two parts:—

(i) **Calculation of the Velocity Ratio.**—When the cord round the large wheel is pulled downwards so as to unwind it from the wheel, the apparatus rotates so that the other cord is wound *up* on the axle of large diameter but is wound *off* the narrower part of the axle.

Consider one complete revolution of the apparatus. Let the diameter of the wheel be A , and the diameter of the large and small portions of the axle be b and c respectively.

The applied force acts through a distance equal to the circumference of the wheel when the apparatus makes one complete revolution, and

$$d_1 = \pi A.$$

In the same time, there is a change in the length of that part of the other cord which hangs free of the axle. An amount equal to πb is wound up on the large part of the axle, but an amount πc is wound off the small part, so that the free length is actually shortened an amount—

$$\pi b - \pi c \text{ or } \pi(b - c).$$

FIG. 55.—Compound Wheel and Axle

This shortening is taken up equally on the two sides of the hanging loop, so that the pulley rises a distance only one-half the shortening of the loop, and the load rises a distance

$$= \frac{1}{2} \pi(b - c), \text{ or}$$

$$d_2 = \frac{\pi(b - c)}{2}$$

The Velocity Ratio is thus

$$\frac{\pi A}{\frac{\pi(b - c)}{2}} = \frac{2A}{b - c}.$$

Note the factor 2 in the numerator of this expression.

Measure the diameters of the wheel and the two parts of the axle with a pair of large callipers, or measure the actual circumferences with string and scale or with a flexible tape measure, and calculate the Velocity Ratio.

(ii) **Determination of the Mechanical Advantage.**—Determine the Mechanical Advantage as already described in the case of the pulley blocks, allowing for the weight of the pulley and scale-pans as detailed there (Expt. 44).

Calculate the value of the Efficiency of the apparatus; this will probably be as high as 85 or 90 per cent.

THE SCREW

The employment of a screw mechanism for various types of machines is extremely common, especially where a very large mechanical advantage is required. In practice a screw is often incorporated as part of a more complicated mechanism, though it is sometimes met with alone. Common examples are the screw lifting-jacks used for raising the axle of a motor-car when replacing a tyre, or for raising any heavy weight where hand-labour alone is available.

The experimental form of screw is usually fitted with a large diameter pulley round which a cord is wound, the cord being pulled by weights placed in small scale-pans hanging over small pulleys at the side of the apparatus as shown in Fig. 56. The large diameter pulley and the attendant cords are usually replaced by a T-shaped handle in the practical forms just referred to.

On the screw is carried a large nut fitted with a yoke which carries the load W . The screw is supported at the lower end by a bearing on which it freely turns, and near the top by a collar through which it just passes freely. A usual type of apparatus is illustrated in Fig. 56, though the framing which supports the smaller pulleys over which the cords pass is not shown. Other forms are frequently met with in laboratories. Sometimes the large pulley is only pulled by one weight, in other cases two cords are fitted and two weights are used as shown in the diagram.

The second type is to be preferred, as, if P_1 and P_2 are equal, the screw is not pulled towards either side; if an unbalanced, single force is used, the screw is pulled to one side of the collar, and additional friction and wear are caused thereby.

The nut would tend to turn with the screw as it revolved, unless suitable means were taken to prevent this; a guide or a pair of guides must therefore be fitted. The usual type of guide is a rod fixed to the main framework, passing down from the collar to the footstep bearing, and fitting into slots cut in the nut. As the screw rotates, the nut cannot turn with it, being prevented by the guides, and hence it must move along the screw thread. The load is thus raised or lowered according to the direction in which the screw is turned. These guides are not shown in the diagram.




FIG. 56.—The Screw

EXPT. 46. Determination of the Efficiency of a Screw.—If the screw is to work efficiently, it is essential to keep the two bearings and the guides well oiled, and *particularly to oil the thread of the screw itself*, as most of the friction is between the screw and the nut.

(i) **Calculation of the Velocity Ratio.**—Let the diameter of the pulley at the top of the screw be D . Then in one revolution the applied force (or forces) moves downwards a distance equal to the circumference of the pulley, so that considering one revolution of the screw—

$$d_1 = \pi D.$$

In the same time, the screw advances one turn in the nut, and the nut is raised a distance equal to the 'pitch' of the screw.

If the pitch of the screw is p , evidently

$$d_2 = p,$$

and the Velocity Ratio

$$\frac{\pi D}{p}.$$

Measure the diameter of the pulley with large callipers, taking care to measure the diameter across the bottom of the grooves where the cords lie, or measure the circumference with string and a scale. Measure the pitch of the screw by pressing a piece of clean paper into contact with the thread for some distance along the screw, and measure the length of, say, 20 threads. Do not forget that the pitch of the screw is the distance between two similar points on successive turns of the same thread (Fig. 7).

Calculate the Velocity Ratio.

(ii) **Determination of the Mechanical Advantage.**—Determine the Mechanical Advantage as described in Expt. 44. In this case, the weight of the nut and yoke cannot be found, as the nut is fixed to the screw; it must therefore be allowed for by finding P_0 the force required to lift the nut and yoke alone, and deducting this from the total force required when a load is suspended from the yoke.

If two cords are fitted to the large diameter pulley, the applied force is equal to the sum of the two weights suspended from the cords.

Find the Efficiency of the screw; it will be found rarely to exceed 20 per cent even if kept well oiled, and may be as low as 7 or 8 per cent if the screw has got rusty through lack of care.

WHEEL GEARING

No account of machines would be complete without some reference to the most common of all types of gearing — gearing by means of toothed wheels. This type of gearing is of great adaptability and




FIG. 57.—Wheel Gearing

appears in various forms in all kinds of machinery — in watches, motor-cars, lathes, travelling-cranes, etc. We shall limit ourselves to considering a simple train of wheel gearing, and, to avoid complication, a numerical case will be taken.

Spindle A carries a large diameter drum of radius 15 cm. On the same spindle, rigidly fixed to the drum, is a toothed wheel with 20 teeth.

This engages with the teeth of a wheel mounted on B having 80 teeth in its circumference, so that the large wheel on B rotates once for every four revolutions of A. Fixed to this large wheel on B, is a small wheel with 20 teeth which engage with the teeth on a large wheel on spindle C. This has 100 teeth in its circumference, so that the spindle C revolves once for every five revolutions of B, or every twenty revolutions of A. On the third spindle C, is a small drum of radius 2.5 cm., round which passes the cord supporting the load W, the cord being wound so that as P falls, W is raised.

It is simplest in this case to consider the effect of one revolution of spindle C.

In one revolution of C, the load W rises a distance equal to the circumference of the small drum, so that $d_2 = 2\pi \times 2.5$ cm.

For every revolution of C, A revolves twenty times, and hence P acts through a distance equal to twenty times the circumference of the large drum, so that $d_1 = 20 \times 2\pi \times 15$ cm.

The Velocity Ratio is therefore $\frac{20 \times 2\pi \times 15}{2\pi \times 2.5} = 120$.

EXPT. 47. Determination of the Efficiency of a System of Wheel Gearing.—Calculate the Velocity Ratio of a system of wheel gearing, as described in the foregoing example. Determine experimentally its Mechanical Advantage as in Expt. 44 and deduce its Efficiency.

The Efficiency of a wheel gear train depends very largely on the accuracy with which the teeth are cut: a well-cut set of gear wheels may have an efficiency of 95 per cent in a simple train such as that described.

NOTE.—The terms **Weight** and **Power** are used frequently for the quantities W and P dealt with in this chapter under the names **Load** and **Applied Force**. The use of a general term **Weight** for a particular and special quantity is objectionable; the term '**Load**' has no special scientific meaning, and its use is preferable to the use of '**Weight**' in this connection. The term '**Power**' has a definite and particular scientific significance, namely the '**rate of doing work**'. It must not therefore be used in the sense of *force*. The term '**Effort**' is used sometimes to indicate this quantity P, but it is not by any means universally employed.

CHAPTER VII

ELASTICITY

§ 1. GENERAL THEORY

WHEN a force of any kind acts on a body, the body is deformed to a greater or less extent. This deformation will, in general, disappear if the force ceases to act. The restoration takes place as a result of that property of the body itself, which is called its **elasticity**.

HOOKE'S LAW

The foundations of the subject were laid by Robert Boyle and his assistant Hooke, and the most important law connecting the force acting and the deformation produced is known as **Hooke's Law**. This may be stated as **Tension is proportional to extension**, or in more exact language, **Stress is proportional to strain**. Hooke's Law is only true up to a certain point; if the stress acting on the body exceeds a certain value, the body will not return to its original dimensions when the stress is removed. The largest deformation which does not leave permanent distortion is called the **elastic limit** of the substance. Up to the elastic limit, Hooke's Law holds good to a close degree of approximation.

DEFINITION OF MODULUS OF ELASTICITY — STRESS AND STRAIN

In order to compare the elastic properties of different materials, it is necessary to obtain quantitative knowledge of the deformations produced by various types of forces.

Stress.—So far as the amount of deformation produced is concerned, the effect of a force is found to depend on the magnitude of the force and also on the area over which it is spread, the effect being proportional to the *force per unit area*.

Stress is defined as the force exerted per unit area.

Strain.—A given stress produces a deformation depending on the size of the body on which it acts. Tensile stresses of equal magnitude acting on similar wires of different lengths will produce elongations in the wires in the same proportion as their lengths. The effect of a stress,

then, is to produce a certain *deformation per unit dimension* of the deformed body.

Strain is defined generally as the *distortion per unit dimension*, or, Strain is the fractional distortion.

Any Modulus of Elasticity is defined as the quotient of the Stress acting and the Strain it produces.

$$\text{Modulus of Elasticity} = \frac{\text{Stress}}{\text{Strain}}$$

Definitions of the Various Moduli.—1. **Young's Modulus**, or **Coefficient of Tensile Elasticity**.—The stress considered in this case is a linear tensile stress, the strain being the corresponding *elongation per unit length*.

If a tensile force F acts on a fibre of length L and of cross section A , the tensile stress exerted on the wire is F/A . If the whole length is elongated on amount x , the strain is x/L . Young's Modulus is therefore expressed as

$$E = \frac{F/A}{x/L} \quad \text{or} \quad E = \frac{FL}{Ax}$$

2. **Modulus of Rigidity**, or **Modulus of Shear Elasticity**.—Imagine a block of material (say indiarubber) in the form of a rectangular parallelepiped, fixed down at one side to a horizontal bed and with a plate firmly fixed to the upper horizontal face.

If this plate be pulled horizontally with a force F , the whole block will be deformed so as to have the shape shown by dotted lines in Fig. 58.

The force F is distributed through the plate so as to act uniformly over the whole of the top area A ; the stress is therefore F/A . This is




FIG. 58.—Shear Stress and Shear Strain

called a **Shear Stress**. The top layer of particles is displaced horizontally a distance d from its original position relative to the particles in the lower surface. The lateral displacement between two surfaces unit distance apart is called the **Shear Strain**. Thus the Shear Strain $= d/D$.

The Modulus of Shear Elasticity is therefore

$$\frac{F/A}{d/D} = \frac{FD}{dA}$$

NOTE.—Only a solid can possess tensile and shear elasticities.

3. Bulk Modulus, or Coefficient of Volume Elasticity.—If a pressure p is impressed upon a body having a volume V , and the resulting change of volume is v , the force applied per unit area is p , since pressure is force per unit area; hence the Stress = p .

The Strain is given by v/V , since the distortion produced is v , and the dimension distorted is V .

The Bulk Modulus is therefore $= \frac{p}{v/V} = \frac{pV}{v}$.

It is not always possible to take a body initially in an unstressed condition, and hence a slight modification of the original definition of a Modulus of Elasticity is required.

If Hooke's Law is true, the Modulus of Elasticity is a constant property of a given material under fixed conditions. It is therefore true to say that if the stress is increased,

$$\frac{\text{Increase of Stress}}{\text{Increase of Strain}} = \frac{\text{Stress}}{\text{Strain}} = \text{Modulus of Elasticity.}$$

The first of these fractions is used frequently in measuring a Modulus of Elasticity.

In the case of a gas, where Hooke's Law does not hold good, we use the quotient increase of pressure divided by the corresponding volume strain to express the Bulk Modulus of the gas in any given conditions.

It is unnecessary to measure the Bulk Modulus of a gas, as it can be calculated from theoretical considerations. To measure it for solids or liquids presents great difficulties. We shall limit ourselves therefore to considering the experimental methods of determining Young's Modulus and the Modulus of Rigidity.

NOTE.—A Stress is always a force per unit area and must be expressed in dynes per sq. cm. or other units of similar dimensions. A Strain is a ratio and has no dimensions.

A Modulus of Elasticity $= \frac{\text{Stress}}{\text{Strain}}$, and is therefore expressed in the same units as those used for the Stress considered, that is in dynes per sq. cm. if C.G.S. units are used.

§ 2. YOUNG'S MODULUS

YOUNG'S MODULUS FOR A MATERIAL IN THE FORM OF A WIRE

The apparatus required for the experiment consists of two vertical wires with their upper ends fixed close together on the same support. One is stretched by a constant load which need not be known, while the other carries a scale-pan A, in which any desired *suitable* load may be placed. The first wire carries a short scale C, while on the second wire is mounted

a vernier B which slides freely over the scale C.¹ The two wires should be of the same material and size.

By this method of using two exactly similar wires, serious sources of error are avoided :—

Any yielding of the point of support when the load A is increased, will depress the scale C to the same extent as the vernier B is depressed, and hence will not be recorded. Similarly any change in the length of the wire due to temperature variations is not registered, as both wires are affected equally.

If we maintain a steady force on one wire, and apply different forces to the other, any elongation due to these additional forces will be registered by a motion of the vernier B along the scale C.

The length of the wire and its radius may be measured by ordinary methods ; hence the elongation strain produced by a known stress can be found, and the value of Young's Modulus for the material determined.

EXPT. 48. Determination of Young's Modulus for a Wire.—Place a suitable load,² say 2 kgm., on the scale-pan attached to the wire under test, to take out any slight bends in the wire. Note the reading of the scale C and the vernier B.

Increase the load by suitable steps,³ say 2 kgm., to a maximum of 12, noting the reading for each load. Diminish the load by steps of 2 kgm. till the original load of 2 kgm. is reached, taking the reading for each load again before it is diminished. Take the mean of the observations for each load as the actual reading corresponding to that load.

If the reading at the end of the experiment differs appreciably from the initial reading (with 2 kgm. suspended), it is possible that the wire has been stretched beyond the elastic limit, though the change may be due merely to straightening. Repeat the observations in this case : if a further elongation remains permanently after removing the load, the experiment must be again repeated with a new wire, applying a maximum load of not more than 8 kgm.

Measure the diameter with great care at several points on the wire, using a micrometer screw gauge. The accuracy of this measurement is of great importance. An error of 0.01 mm. in the diameter is of the order of 1 per cent, and will affect the final result with an error of 2 per cent, since the radius occurs to the second power. An error of 1 or 2 cm. in measuring the length of the wire is of less importance than 0.01 mm. in measuring the radius.

Measure the length of the wire from the point of support to the point where the wire is clamped to the vernier.

Plot a curve showing how the extension of the wire varies with the weight suspended from it. Show that the plotted points follow approximately a straight line.

Attention must be directed to two points in the following. First, note the way in which the extension is worked out in the last column of the table.

¹ We believe that this arrangement of the scale and vernier on two parallel wires originated in the Wheatstone Laboratory of King's College, London.

² The numerical values here given were obtained for particular wires, and must be modified so as to suit the actual wires examined.




FIG. 59.—Young's Modulus for a Wire

Tabulate the observations as follows :—

Load	Readings		Mean Reading	Extension for an Increase of 6 kgm. in mm.
	Load increasing	Load diminishing		
2 kgm.	1.13 mm.	1.15 mm.	1.14 mm.	
4 "	1.33	1.35 "	1.34	(2 to 8) 0.53
6 "	1.50	1.55 "	1.53	(4 to 10)= 0.51
8 "	1.67	1.67 "	1.67	(6 to 12)= 0.57
10 "	1.83	1.87 "	1.85	
12 "	2.10		2.10	

Mean extension for 6 kgm. = 0.537 mm.

= 0.0537 cm.

Radius of wire (mean of four determinations) = 0.075 mm.

= 0.0675 cm.

Length of wire from support to vernier = 250 cm.

The Stress produced by a load of 6 kgm. suspended from this wire

$$= \frac{\text{Force}}{\text{Area of cross section of wire}}$$

The force is the weight of 6 kgm., i.e. = 6000 × 981 dynes.

The area of cross section is $\pi \times (0.0675)^2$ sq. cm.,

so Stress due to 6 kgm. = $\frac{6000 \times 981}{\pi \times (0.0675)^2} = 404,000,000$ dynes per sq. cm.

or Stress = 4.04×10^8 dynes per sq. cm.

The Strain produced by the addition of a load of 6 kgm.

Mean elongation for 6 kgm.

$$= \frac{\text{Length of wire from support to vernier}}{0.0537}$$

$$= \frac{250}{0.0537}$$

$$= 0.000215 \text{ or } 2.15 \times 10^{-4}.$$

Young's Modulus for the wire is therefore

$$\frac{\text{Stress}}{\text{Corresponding strain}} = \frac{4.04 \times 10^8}{2.15 \times 10^{-4}} \text{ dynes per sq. cm.}$$

$$= 1.88 \times 10^{12} \text{ dynes per sq. cm.}$$

It is said frequently that the average elongation for 2 kgm. should be taken, and this value used for determining the Modulus of Elasticity. This is done by taking successive differences between the numbers in the last column but one, adding together these successive differences and taking their mean. By this method, however, any additional accuracy which might have accrued through taking six observations is lost completely, the result depending entirely on the first and last observations. Each of the intermediate observations is taken into account twice, once positively and once negatively, and is thus without effect on the result. If the six readings are denoted by A, B, C, D, E, and F, successive differences are A - B, B - C, etc., and their mean is

$$\frac{(A - B) + (B - C) + \dots + (E - F)}{5} = \frac{A - F}{5}.$$

That the difference in the result may be considerable is shown in the

sample set of observations given, the extension for 6 kgm. by this method being 0.576, as against 0.537 by the method opposite.

In the method given in the table each observation is taken into account once only, the result therefore depends on *all* the readings taken and is correspondingly more accurate.

The second point to which attention must be directed is concerned with the measurement of the length of the wire. The whole wire is stretched by the load on the scale-pan A, but the extension *measured* is only that suffered by the part of the wire between the point of support and the vernier. In calculating the *strain* this length is therefore the length to be used as the denominator.

N.B.—*The loads must be chosen to suit the wires under test.*

YOUNG'S MODULUS FOR A MATERIAL IN THE FORM OF A BEAM

The apparatus required for this experiment consists of two knife-edges across which the 'beam' can be rested, a scale-pan or hook supported from the middle of the beam, and some convenient method of determining the extent to which the centre of the

beam is depressed. If the rod is very thin so that the depression for (say) 1 kgm. is considerable, a metre scale placed vertically behind the rod can be used for measuring the depression of the centre, the division opposite to the top or bottom face of the rod being observed. If the

rod were fairly stiff, very large forces would be required to produce a bending which could be measured with sufficient accuracy in this way. It is preferable to use moderate forces and employ some more delicate method of measuring the depression. For this purpose a vertical scale may be attached to the centre of the rod and observed by a fixed low-power microscope. As the centre of the rod is depressed, the scale moves downwards relatively to the microscope. The reading of the scale seen coincident with the cross wire of the microscope eye-piece is taken for various loads, and thus the depression of the centre of the rod is measured. Or the scale may move over a fixed vernier and its depression may thus be measured with a fair degree of accuracy.



FIG. 60.—Young's Modulus for a Beam

EXPT. 49. Determination of Young's Modulus for a Beam.—Apply various loads on the scale-pan or hook and note the corresponding positions of the centre of the beam. Increase the load by equal amounts, taking six or eight observations both with increasing and with decreasing loads: the maximum load applied should be approaching the highest load which the beam can carry in safety, but should not exceed this amount.

Tabulate your observations as in finding Young's Modulus for a wire, and find the mean depression y for a load W by the method described therein for determining the elongation for 6 kgm.

Measure the length of the beam between the knife-edges; also the breadth and thickness of the beam.

Let these be L , b , and d respectively. Then it can be shown that for a bar of rectangular section, the relation between the depression of the centre y , the load W , and the dimensions of the beam is given by

$$y = \frac{WL^3}{4Ebd^3}$$

where E is Young's Modulus for the material of the beam.

Calculate Young's Modulus from the expression

$$E = \frac{WL^3}{4bd^3y}.$$

As an alternative method of working out the observations, the depressions y_1, y_2, y_3 , etc., of the centre of the beam corresponding with loads W_1, W_2, W_3 , etc., may be obtained, and the mean of the quotients $\frac{W_1}{y_1}, \frac{W_2}{y_2}, \frac{W_3}{y_3}$, etc., taken as the mean value for $\frac{W}{y}$.

This is substituted for $\frac{W}{y}$ in the expression

$$E = \frac{L^3}{4bd^3} \left(\frac{W}{y} \right),$$

and the value of E is calculated.

W must be expressed in dynes, and the other quantities on the right-hand side of the equation in centimetres.

As additional exercises on this type of experiment the following are suggested :—

EXPT. 50. For a given load the depression of the centre of a beam varies directly as the cube of its length.

This is shown by finding y for the same load when the supporting knife-edges are at different distances apart. If the depressions are y_1, y_2, y_3 , etc., for distances apart equal to L_1, L_2, L_3 , etc., the values of $\frac{y_1}{L_1^3}, \frac{y_2}{L_2^3}$, etc., should all be equal. The load must be acting at the point midway between the knife-edges in each case.

EXPT. 51. The stiffness of a rectangular beam varies directly as its breadth and directly as the cube of its thickness (depth).


Find y for the same load exerted on the same beam with the knife-edges kept at a constant distance, but with the beam resting first on the 'flat' side and then on the 'edge'. In the first case the flat side is the breadth (b) and the edge is the depth (d), these quantities being interchanged in the second case.

Show that bd^3y has the same value in the two cases.

YOUNG'S MODULUS FOR A CANTILEVER

A Cantilever is a loaded beam fixed horizontally at one end.

If a cantilever has a load W suspended at the extreme end, the depression y of the end is given by the equation



$$y = \frac{4WL^3}{Eb d^3},$$

if the beam is of rectangular section.

FIG. 61.—Young's Modulus for a Cantilever

EXPT. 52. Determination of Young's Modulus for a Cantilever.

—Clamp one end of a metre scale to the top of a table so that the metre scale extends horizontally about 90 cm. beyond the table edge. Place various loads at the extreme end of the scale and measure the depression of this end for each of the loads applied. One of the methods already described for a beam on two supports may be used for this measurement. Measure the length of the

beam beyond the table, and also its breadth and thickness. Deduce the value of Young's Modulus, E , for the material (usually boxwood) by means of the equation above.

§ 3. MODULUS OF RIGIDITY

MODULUS OF RIGIDITY FOR A MATERIAL IN THE FORM OF A CYLINDRICAL WIRE

The Modulus of Rigidity has been defined earlier in the chapter, taking the case of a block fixed at the base and subjected to a tangential shearing force F distributed over its upper face. It is impossible, however, to determine the Modulus of Rigidity of any material (except india-rubber) in this way, as the deformation d produced by any practicable force F would be too small to measure.

Twisting a Wire.—When a couple is applied to one end of a wire, the other end being kept fixed, the wire is twisted through an angle which is proportional to the twisting couple applied.

The wire may be considered as consisting of a number of thin concentric cylindrical layers. Each of




FIG. 62.—Twisting a Wire

these is in a state of shear when the wire is twisted. Thus a layer of particles originally along AB is displaced into the dotted line $A'B$, when the upper end is twisted through the angle θ (Fig. 62).

If the cylindrical layer could be spread out flat, it would form a rectangular sheet when the wire was not twisted, but its shape when the twist was produced would be as shown dotted ($A'BBA'$).

The relation between the angle of twist, the dimensions of the wire, and the twisting couple may be expressed by saying that to twist a wire l cm. long and of a cm. radius through an angle θ radians requires a couple C , given by

$$C = \frac{\pi n a^4 \theta}{2l},$$

where n is the Modulus of Rigidity of the wire.

In general, we measure the twist in degrees. Let the twist in the length l be ϕ° .

Then

$$\theta \text{ radians} = \phi^\circ \times \frac{\pi}{180}.$$

Thus

$$C = \frac{\pi n a^4}{2l} \left(\frac{\pi}{180} \phi^\circ \right), \text{ or } C = \frac{\pi^2 n a^4}{360l} \phi^\circ$$

APPARATUS FOR DETERMINING THE MODULUS OF RIGIDITY OF A WIRE BY TWISTING IT

The wire may be fixed either vertically (Figs. 63 and 64) or horizontally (Fig. 65). One end A is clamped rigidly to the supporting framework (not





FIG. 63.—Modulus of Rigidity Apparatus with Movable Pointer




FIG. 64.—Modulus of Rigidity Apparatus with Fixed Pointer




FIG. 65.—Modulus of Rigidity Apparatus with Horizontal Wire

completely shown), and the other, passing through a suitable bearing to keep it steady, is clamped to the middle of a pulley B. A pointer C on the wire moves over a scale of degrees mounted near to the pulley end of the

wire, and by its means the twist ϕ° produced in *that part of the wire between the pointer and the fixed end* by couples exerted on the pulley can be measured readily; sometimes the scale of degrees is mounted on the pulley, and a fixed pointer is used (Fig. 64).

The couple applied to twist the wire is exerted by weights suspended from cords which wrap round the pulley, as shown in the diagrams. It is preferable to use two equal forces, acting along parallel lines in opposite directions, so that there is no 'side pull' on the wire, though in the case where the wire is fitted horizontally the usual method is to use a single force only, as shown. The effect of 'side pull' is to introduce friction between the bearing and the wire, which impedes somewhat the free turning of the wire under the twisting couple.

The twisting couple exerted on the wire by equal masses M hanging from cords passing round the pulley of diameter D is given by

$$C = MgD.$$

If a single cord is used,

$$C = \frac{MgD}{2}.$$

We have seen already that

$$C = \frac{\pi^2 a^4 n}{360l} \phi^\circ,$$

therefore, considering the case where the pulley is fitted with two cords carrying equal masses M , we have

$$MgD = \frac{\pi^2 a^4 n}{360l} \phi^\circ.$$

Whence

$$n = \frac{360lgD}{\pi^2 a^4} \left(\frac{M}{\phi^\circ} \right).$$

If a single cord is fixed to the pulley and carries the load M ,

$$C = \frac{MgD}{2} = \frac{\pi^2 a^4 n}{360l} \phi^\circ,$$

and

$$n = \frac{180lgD}{\pi^2 a^4} \left(\frac{M}{\phi^\circ} \right).$$

EXPT. 53. Determination of the Modulus of Rigidity of a Wire.—Note the zero reading of the pointer C , or the reading of the pointer on the scale of degrees when the wire is subjected to no twisting couple. Attach various loads to the cords and note the corresponding twists produced. The load should be increased in equal steps up to the largest used. If the pulley is twisted by two cords, the loads attached to the cords should be equal. Take the readings of the angle of twist as the couple is being increased, and again for the same values of the couple when the loads are being removed.

If the observations taken with the couple decreasing do not correspond with those taken when the couple was being increased, the rod has either been twisted beyond the elastic limit, or else the clamps do not grip the rod sufficiently firmly and the rod has turned a little in the clamps.

These results should be discarded and a new series taken, using a smaller maximum load, the maximum being reduced to such a value that the two sets of readings are identical (within limits of experimental error).

Measure the diameter of the pulley B , the radius of the wire twisted, and the distance AC between the fixed end of the wire and the pointer.

Tabulate the observations as shown below :—

Load on (each) Cord M	Twist in degrees ϕ		Mean Twist ϕ°	$\frac{M}{\phi^\circ}$
	M increasing	M diminishing		

$$\text{Mean } \frac{M}{\phi^\circ} =$$

Length of wire from A to C = $l =$. . . cm.

Radius of wire (mean of 4) = $a =$. . . cm.

Diameter of pulley B = $D =$ cm.

If preferred, the mean value of ϕ° corresponding with an increase in the suspended masses equal to M can be found in the manner detailed in the determination of Young's Modulus for a wire.

Substitute the mean value of M/ϕ° in the appropriate equation given above for n and calculate the value of n .

Plot a graph showing the way in which the angle of twist ϕ° varies, as M is increased.

CALIBRATION OF A SPRING AND METHOD OF USING A CALIBRATED SPRING AS A BALANCE

Hooke's law, that tension is proportional to extension, holds generally, even where the strain imposed on a body is not so simple as the strains in the cases just considered.

A typical case is offered by a spiral spring subjected to a tension along the axis of the spiral, the movement of the index along the scale (indicating the elongation of the spring) being accurately proportional to the applied force.

The object of the present experiment is to calibrate a **Spring Balance**; that is, for any point on the scale to determine the force required to elongate the spring till the index is at that point. The axis of the spring is vertical and the force is due to a load at its lower end.

EXPT. 54. Calibration of a Spring Balance.—The apparatus employed usually consists of a frame of wood or metal to one end of which is attached the end of a spiral spring. At the other end of the spring is an index which moves freely over, and just in contact with, a scale screwed to the frame. A small scale-pan is hung at the end of a wire attached to the end of the spring.

Fix the framework so that the spring and scale are vertical, with the index just touching the scale, and note the zero reading, that is the reading when no load is applied to the spring.

Then take a series of readings of the position of the index for gradually increasing loads and tabulate the results.

Be careful not to exceed the elastic limit; the spring must never be stretched to such an extent as to bring the index beyond the scale, for the length of the scale is usually arranged to give almost the maximum motion allowable.

The results of the observations must now be plotted on squared paper, taking the load as abscissa and the scale reading as ordinate. The graph should be drawn on as large a scale as possible.

If the strain be exactly proportional to the load, the points should lie on a straight line. Draw a straight line passing between the observed points.

The graph may now be used to determine an unknown load. Find the extension which the load produces when attached to the spring, and read off from the graph the load corresponding to the observed scale reading.

A spiral spring of this type may serve many useful purposes in experimental work. When constructed of suitable material and of dimensions adapted for the purpose in view, it can give results of considerable accuracy with careful manipulation. It may be used in finding the energy stored in an elastic body (Expt. 55), in the determination of surface tension, in dynamical experiments on oscillating systems (Expt. 70), or in the construction of a simple attracted-iron ammeter (Expt. 221).

In one modification of the apparatus (the Jolly balance) it is the upper end of the spring which is raised by suitable mechanism controlled by the observer until he finds that a pointer attached to the lower end of the spring returns to a fixed index line. The distance the top is raised can be read on the scale of the instrument. The fixed reference line may be a horizontal circle traced on the *inside* of a glass tube through which the pointer passes. This pointer may be a horizontal line traced on a small plate attached to the bottom of the spring. The scale-pan hangs lower down within easy reach of the experimenter.

§ 4. THE ENERGY OF A STRAINED BODY

If a body is deformed by a force, the force producing the deformation has acted through a certain distance. A certain amount of work has thus been done on the body by the force; this work is stored up in the body as Strain Energy. The C.G.S. unit of work is the Erg, which is defined as the work done when a force of 1 dyne moves its point of application through 1 cm.

When a wire is stretched l cm. by a force F dynes applied gently, it might appear at first sight that the force F acts through the whole distance l , and that therefore an amount of work equal to Fl ergs

should be stored in the wire due to its strained condition. Actually, however, the full force F does not act on the wire until the full elongation l has been produced; it is applied *gently* to the wire, and at first the major part of the force is supported by the experimenter, and only a




FIG. 66.—Work done in straining a Body

small fraction is allowed to act on the wire. As the wire stretches, the experimenter takes less and less of the force, allowing a continually increasing proportion to be supported by the wire until eventually the wire supports the whole force and is elongated the full amount l .

While the force F has been acting, it has certainly done an amount of work equal to Fl ergs, but part of this has been taken by the experimenter in allowing the force to come into action gently, only a portion of the total work Fl having been done on the wire. Actually, *half* the total energy Fl is absorbed by each.

Consider the work done by a variable force f whose magnitude changes with the displacement of its point of application in the manner shown in the curve (Fig. 66). This curve is drawn irregular of set purpose so that the result obtained from its consideration may be taken as true generally.

When the point of application is at A, the force has a certain magnitude $f_1 = AC$; in moving its point of application to B, the force increases to a value $f_2 = BD$, its average value during the displacement being equal to some quantity \bar{f} (called ' f bar'). If AB is very small, $\bar{f} = \frac{f_1 + f_2}{2}$ (approximately). The work done in this displacement is very nearly equal to $\bar{f} \times AB$, and is represented by $ABCD$, the area under the curve between the ordinates considered.

The work done in any other displacement would similarly be equal to the corresponding area under the curve, and hence the total work done by the force up to any displacement is equal to the area under the curve from the origin to the ordinate at the point considered. This rule is true for any force-displacement diagram, however the force may vary.




FIG. 67.—Strain Energy in a Wire

In dealing with strains, the force producing an elongation is proportional to the elongation produced, hence the ideal force-displacement curve is a straight line. The area under the curve up to the ordinate corresponding with any given displacement is triangular; its area is $\frac{1}{2}Fl$ (Fig. 67).

Hence the Strain Energy in a wire when a force F causes an elongation l cm. is equal to $\frac{1}{2}Fl$.

If E represents the strain energy in the wire,

$$E = \frac{1}{2}Fl = \frac{1}{2} \text{ stretching force} \times \text{elongation}.$$

It is impossible to prove by simple experiment that $E = \frac{1}{2}Fl$ in the case of an ordinary straight wire, but with a spiral spring the truth of this statement can be demonstrated without difficulty.

The Energy stored in a spiral spring is equal to half the product of the force it exerts and its elongation

Steady Application of a Force.—Allow a mass M_1 to hang from a wire spring, letting its weight come into action gradually upon the wire: a steady elongation is produced equal to l_1 (say). The force now exerted by the spring is some force F_1 , which is equal to M_1g , since the mass remains motionless at the end of the spring.

We wish to show that the energy now stored in the spring as Strain Energy is given by $E_1 = \frac{1}{2}F_1l_1$.

Sudden Application of a Force.—Suppose we allow a mass M_2 to rest lightly at the end of a spring which is entirely unstrained, the mass M_2 being supported by a small platform. If the platform is now removed quite suddenly, the whole of the weight of the mass M_2 comes into action on the spring. As the spring stretches, the Potential Energy lost by the falling mass is partly converted into Kinetic Energy of the mass and partly is stored in the spring as Strain Energy. After moving some distance the mass begins to slacken in its fall, and eventually comes to rest *momentarily* after falling some distance l_2 .

It now has no Kinetic Energy, and therefore at the instant when the mass first comes to rest, the whole of the Potential Energy it has lost in falling is stored in the spring as Strain Energy.

The Potential Energy lost by the mass in falling this distance is M_2gl_2 , and we know, therefore, that when the spring is stretched a distance l_2 , the amount of strain energy stored in the spring is M_2gl_2 ergs.

If we so adjust this mass M_2 that its sudden fall produces a maximum elongation equal to that produced by a mass M_1 applied steadily, we can test the truth of the equation $E = \frac{1}{2}Fl$ quite easily, for, writing l for l_1 or l_2 , these being equal, the energy in the spring (E_1) is M_2gl , and the tension in the spring is $F_1 = M_2g$. If therefore $M_2 = \frac{1}{2}M_1$, we have verified experimentally that the energy of a strained body elongated an amount l by a force F is equal to $\frac{1}{2}Fl$.

EXPT. 55. Determination of the Energy of a Spiral Spring.—Remove the scale-pan from a spiral spring. [If the scale-pan is *not* removed, its mass must be included in both M_1 and M_2 .] Apply a load sufficient to stretch the spring nearly to the end of the scale when applied gently. Note the steady elongation and the mass used, M_1 .

Adjust another load, M_2 , so that when it is allowed to drop suddenly from a point where the spring is just *not* supporting it, the *first sudden* elongation of the spring may be equal to the steady elongation produced by the load M_1 .

Repeat these observations for several different elongations.

Arrange your observations in tabular form thus :—

Elongation, cm.	Load required to produce it		$\frac{M_2}{M_1}$
	(a) Applied steadily, M_1 gm. wt.	(b) Applied suddenly, M_2 gm. wt.	
10.3	107	52	0.486
8.4	87	45	0.517
6.5	67	33	0.493
4.5	47	25	0.532
2.6	27	15	0.555

It will be found that M_2/M_1 is approximately equal to 0.5, the accuracy being much less with the smaller masses and elongations than with the larger, owing to the *relatively* larger value of the errors of observation. The possible errors in reading being practically the same throughout, they will have a greater *proportional* value in the cases where the total quantities to be measured are smaller.

Thus since M_2/M_1 is found to be equal to 0.5 (within limits of experimental error), this experiment verifies the statement that $E = \frac{1}{2}F\ell$.

CHAPTER VIII

DYNAMICS

§ 1. THE LAWS OF MOTION

UP to the present we have been concerned mainly with matter at rest, or, when we have allowed motion to take place, we have studied the results of the motion rather than the motion itself. In the division of the subject known as Dynamics, we are concerned with the motion itself, as well as with the forces producing the motion and the mass moved.

The idea of force is derived from the sensations we experience in connection with muscular action. Newton's First Law of Motion is sometimes regarded as equivalent to a definition of Force as that which tends to change the state of rest or uniform motion of a material body.

Practically the whole of Dynamics may be said to be an application, more or less direct, of Newton's Second Law of Motion, or a study of one or other of the quantities mentioned in that law.

NEWTON'S SECOND LAW OF MOTION

The change in the quantity of motion possessed by a body when under the action of a force is proportional to the magnitude of the force and to the time during which it acts : it takes place in the direction of action of the force.

Quantity of Motion, or Momentum.—The quantity of motion possessed by a body is now called the Momentum of the body ; it is defined as the Mass of the body multiplied by its Velocity.

The Momentum of a body possesses direction and sense as well as magnitude, so that Momentum is a Vector quantity.

The second law may be rewritten as **Rate of Change of Momentum is proportional to Force.**

We define our Force unit to be such that Unit Force produces unit rate of change of momentum, or

$$\text{Force} = \text{Rate of Change of Momentum.}$$

Now if a force acts on a body of constant mass the Momentum change is due solely to the resulting change of Velocity. Hence

$$\text{Force} = \text{Mass} \times \text{Rate of Change of Velocity,}$$

or finally

$$\text{Force} = \text{Mass} \times \text{Acceleration.}$$

The C.G.S. unit of force is called one dyne, the M.K.S. unit one newton (p. 2 and p. 76).

THE PRINCIPLE OF THE CONSERVATION OF MOMENTUM

If two bodies A and B come under the action of each other so that the motion of B is changed due to the action of A, and *vice versa*, these two bodies are said to have been in Collision: they need not necessarily have come into physical contact with each other.

The Principle of the Conservation of Momentum states that: In any collision, there is, on the whole, neither gain nor loss of momentum. This principle is in accordance with Newton's Third Law of Motion that Action and Reaction are equal and opposite. We shall deal here with its experimental illustration, limiting ourselves to experiments dealing with actual physical contact, and to bodies moving in one straight line.

In considering the total momentum of the moving bodies, their directions of motion as well as the magnitudes of their momenta must be taken into account. Thus if two bodies are moving with velocities v_1 and v_2 along the same straight line, one moving to the right and the other to the left, one of the bodies has a positive, the other a negative momentum, the total momentum being the *algebraic sum* of the momenta possessed by the two bodies. It is immaterial which direction is considered positive so long as this convention, once made, is adhered to during the whole of one experiment.

Consider a collision between two masses m_1 and m_2 moving along the same straight line with velocities v_1 and v_2 respectively. Their velocities after collision may be indicated by v_1' and v_2' . The principle of the conservation of momentum states that

$$\text{Total Momentum before} = \text{Total Momentum after impact,}$$

or

$$m_1v_1 + m_2v_2 = m_1v_1' + m_2v_2';$$

the velocities being reckoned positive in one direction and negative in the other.

THE BALLISTIC BALANCE

This apparatus (Fig. 68) is designed for the experimental illustration of the principle of the conservation of momentum. It is very difficult to satisfy the ideal conditions required by theory.

Two scale-pans, usually of wood, are suspended by sets of cords in such a way that they move over the arc of a circle of *large* radius. The suspend-




FIG. 68.—Hicks's Ballistic Balance




FIG. 69.—Motion of Scale-pan

ing cords should be so arranged that the scale-pans have no motion of rotation as they swing, their upper surfaces remaining *horizontal* in all positions (Fig. 69).

In one form, the scale-pans are supplied with pointers which move over a scale stretching horizontally across the base of the apparatus, the pointers being clear of, but close to, the scale.

EXPT. 56. The Ballistic Balance.—By placing known masses on the two pans, the total mass in motion can be altered in various ways. Strictly any added mass should be rigidly attached to its scale-pan. If this is not possible the masses added should always be placed close to the ledge which is fitted at the 'front' of each scale-pan, otherwise they will slide about when the pans collide, and this will diminish the accuracy of the result. In computing the masses of the moving systems, m_1 and m_2 , the masses of the scale-pans must be taken into account.

If one scale-pan is drawn aside through a known distance and then released it will return to its equilibrium position with a velocity that is proportional to the initial horizontal displacement. The proof of this statement will be given later.

When the first scale-pan strikes the second (supposed to be at rest at the start) the velocity of each pan will be altered.

It is necessary to determine the velocity of each pan after the blow by observing the horizontal distance through which it travels; the horizontal distances may indeed be taken as the actual velocities in some arbitrary units not specified. As it is impossible to watch both pointers at the same time, it is necessary to repeat each experiment a number of times, noticing in one set of experiments the maximum horizontal displacement (after collision) of the first pointer, and in the other set the maximum displacement (after collision) of the other: the initial displacement and the masses must of course be made the same each time.

Tabulate the results in the following manner :—

Before Impact

After Impact

Total
Momen-
tum,
 $m_1 v_1$

Momen-
tum,
 $m_1 v_1$

ntum,
 $m_2 v_2$

Since the mass m_2 was at rest at first, v_2 is zero. The third column $m_1 v_1$ thus represents the total initial momentum, and the tenth column $m_1 v_1' + m_2 v_2'$ is the total momentum after collision.

Express the difference between these columns as a percentage of either, and enter this in the last column as the percentage error of each set of observations.

In the ideal case the two bodies must have motions of pure translation along the line joining their centres of mass, and the impact must take place on this line. Since the addition of an extra mass to a scale-pan alters the position of the centre of mass, it is better to make very careful observations with a small number of masses.

In the type of apparatus where a clip is supplied which locks the two scale-pans together after collision, the two move on with a common velocity, and $v_1' = v_2'$. In this form the pointers can be dispensed with, and the scale-pans can be made to move a small rider along a bar of wood to indicate the first maximum horizontal displacement of the two masses after collision.

In this case the table of observations is somewhat simplified, as is also the taking of the observations and the experiment generally.

Before Impact			After Impact			Percentage Error
Mass, m_1	Velocity, v_1	Total Momentum, $m_1 v_1$	Combined Mass, $m_1 + m_2$	Common Velocity, v_1'	Combined Momentum, $(m_1 + m_2) v_1'$	

The last column in this case is the difference between the third and sixth columns expressed as a percentage of either.

Proof that the velocity in the equilibrium position is proportional to the horizontal displacement.—Suppose the mass m to be displaced from its equilibrium position A to a point B along the arc AB: the point of support is the point O (Fig. 70), and the radius of the arc is $OB = R$.

In moving from B back to A, A loses an amount of potential energy $= mgh$. It possesses at A a velocity v in the direction shown, its kinetic energy at A being

the result of the potential energy lost from B to A. Hence $\frac{1}{2}mv^2 = mgh$, or v^2 is proportional to h .

Now $OB^2 = OC^2 + BC^2$, or $R^2 = (R-h)^2 + BC^2$, whence $2Rh = h^2 + BC^2$.

Now BC is large compared with h , and to a close degree of accuracy h^2 can be neglected compared with BC^2 ; h^2 is rarely equal to 1% of BC^2 .

Hence *very closely* we may say that

$$BC^2 = 2Rh,$$

BC^2 is proportional to h .

Now v^2 and BC^2 are both proportional to h , hence v must be proportional to BC , so that the velocity as the body passes through its equilibrium position is proportional to the original horizontal displacement $B.C$.

It may be shown, by reversing the proof, that the horizontal distance to which a body will swing after leaving its equilibrium position is proportional to the velocity it possessed when in its equilibrium position, or the velocities *after* collision are proportional to the maximum horizontal displacements reached after colliding.

The importance of ensuring that there is no motion of rotation of the scale-pans will be seen from the above proof. If there were motion of rotation, the potential energy at B would not appear entirely as linear kinetic energy at A but would partly exist as kinetic energy of rotation. Hence the statement $\frac{1}{2}mv^2 = mgh$ would be untrue and the proof invalid.

The way in which motion of rotation is prevented will be seen from Fig. 69.




FIG. 70.—Velocity in Ballistic Balance

§ 2. METHODS EMPLOYED FOR THE EXPERIMENTAL ILLUSTRATION OF THE SECOND LAW OF MOTION

If a body move with a constant acceleration a , the *distance* through which it moves in a time t is given by the equation

$$s = v_0 t + \frac{1}{2}at^2,$$

where v_0 is the initial velocity of the body.

If the body is initially at rest, v_0 is zero and we have

$$s = \frac{1}{2}at^2, \text{ when the initial velocity is zero.}$$

The *velocity* at the end of any time t is given by

$$v = v_0 + at,$$

which reduces to

$$v = at, \text{ when the initial velocity is zero.}$$

These equations are *absolute*; they are derived from the definitions of the various quantities involved, and *cannot be verified by experiment*. They may be used to determine whether a body is moving with uniform acceleration or not. Thus, if the distance s moved over by a body in time t starting from rest obeys the law $\frac{s}{t^2} = a$ constant, that body is moving with uniform acceleration, and the value of the acceleration is *twice* the value of the constant obtained, for

$$a = \frac{2s}{t^2}.$$

WEIGHT AND MASS

As an example of the use of these equations, the case of a body falling freely under its own weight may be taken. Any body, if allowed to drop quite freely towards the earth, will describe in a time t from the start a distance s which is proportional to t^2 . Thus in the first second it will fall 5 metres approximately, while in the first two seconds it falls 20 metres. Thus $s/t^2 = 5$ approximately for any body falling freely under its own weight, starting from rest, that is the **acceleration due to gravity is the same for all bodies** and is equal approximately to 10 metres per sec. per sec.—more accurately this acceleration is 9.81 metres per sec. per sec. in the British Isles.

Now from the second law of motion we define the unit of force in the C.G.S. system to be such that

Force in dynes = Mass in gm. \times Acceleration produced (in cm. per sec. per sec.).

If we denote the acceleration due to gravity by the symbol g , in cm. per sec. per sec. when dealing with C.G.S. quantities, we have

$$\left. \begin{array}{l} \text{Force in dynes acting on} \\ \text{a body when falling freely} \end{array} \right\} = \text{Mass in gm.} \times g.$$

Now the force in dynes acting on a falling body is its **Weight**. Hence

$$\left. \begin{array}{l} \text{The Weight} \\ \text{of a body in} \\ \text{dynes} \end{array} \right\} = \left\{ \begin{array}{l} \text{The Mass of} \\ \text{the body in} \\ \text{gm.} \end{array} \right\} \times \left\{ \begin{array}{l} \text{The acceleration due to} \\ \text{gravity in cm. per sec.} \\ \text{per sec.} \end{array} \right.$$

In the M.K.S. system the Weight of the body is in newtons, the Mass in kgm., and the acceleration in metres per sec. per sec. The newton = 10^5 dynes.

If W indicate the weight in dynes, of a body having a mass m gm., we have

$$W = mg,$$

g being 981 cm. per sec. per sec. in the British Isles.

The simplest way of obtaining a uniform force is by suspending known masses from light cords, passing the cords over pulleys in order to direct the action of the force in any desired direction. The force acting along the cord in *dynes* is equal to the mass of the suspended body in gm. multiplied by g , the acceleration due to gravity in cm. per sec. per sec.

§ 3. EXPERIMENTS TO ILLUSTRATE THE SECOND LAW OF MOTION

FLETCHER'S TROLLEY APPARATUS

W. C. Fletcher, Fellow of St. John's College, Cambridge, was appointed Headmaster of Liverpool Institute in 1896.

In this apparatus (Fig. 71), a trolley is mounted on very light wheels so as to move in an almost frictionless manner along a horizontal table. To it is attached a cord which, passing over a pulley mounted at the edge of the table, carries a small suspended mass. By hanging different masses from the cord, the trolley can be subjected to various forces, and its motion under these forces can be studied; the mass moved can also be varied by placing known masses in the holes in the side of the trolley.

The method of recording the distance moved through, and the time taken for this motion, is interesting. A long spring is mounted in a firm clamp and carries a light brush at the free end. Fixed on the trolley is a sheet of paper which is touched lightly by the brush. When the trolley




FIG. 71.—Fletcher's Trolley Apparatus (Cusson's)

is set in motion, the same mechanism which releases it sets the long spring in vibration, and a wavy trace is drawn on the paper, the brush having been moistened with ink.

The time taken to make a complete vibration is constant for the spring, and therefore the number of complete vibrations made between two given points may be taken as a measure of the time taken to move from one point to the other.

By taking the distances travelled from the start, during the time taken to make different numbers of vibrations, it is possible to find from the wavy trace if the relation s/t^2 is constant.

The Mass moved is the sum of the masses of the trolley, cord, and hanging mass, together with a small quantity which may be called the *equivalent mass of the pulley*, and another small quantity, the equivalent mass of the wheels. The trolley is usually sufficiently massive for these other masses to be neglected.

The Force acting is evidently the weight of the hanging mass, *plus* the weight of that part of the cord which is hanging over the pulley. In order to reduce the error due to the weight of the cord, an extremely fine, strong line (fishing-line) should be used, so that its weight is negligible compared with that of the hanging mass. Its effect may be allowed for, if necessary, by adding to the weight of the suspended mass a quantity equal to the weight of the *average* length of the cord hanging beyond the pulley.

The Acceleration produced.—The quotient s/t^2 will be found constant, therefore the trolley is moving with constant acceleration, the value of this acceleration being $2s/t^2$.

If only *relative* values are required, the units in which the time is measured may be taken as the time for one vibration of the spring.

For *absolute* results, the period of vibration of the spring must be known in order that the accelerations may be calculated in cm. per sec. per sec.

The period of vibration is usually stamped on the spring, having been determined by the maker of the apparatus, and this marked period may be used for this purpose. The spring seldom makes a sufficient number of vibrations for the period to be checked by simple means, and the calibration made by the maker has to be accepted: this constitutes a serious drawback to this method of timing when *absolute* results are required.

A method of finding the acceleration is described on p. 121.

Experiments with Fletcher's Trolley Apparatus

EXPT. 57. Acceleration is proportional to Force.—Fix a sheet of paper on the trolley and attach small masses 10, 20, 30, 40 gm., etc., to the cord, obtaining traces for the motion of the trolley under the action of each force. It is interesting to get all the traces on the same sheet of paper, starting from the same point in each case.

The mass moved is approximately the same in each case, being altered only by the change in the hanging mass.

The forces acting are proportional to the hanging masses in the various cases.

Show (a) that the distances travelled in equal times are proportional to the suspended masses; (b) that for each case $2s/t^2$ is a constant, and that the values of the constants in the different cases are proportional to the suspended masses used.

Friction Correction.—It is necessary to eliminate or neutralise the friction forces if accuracy is to be obtained. To do this a small mass is suspended from the cord, and adjusted until the trolley just continues to move when once started. The weight of this small mass is then just sufficient to overcome the friction of the apparatus for the particular load on the trolley. A piece of copper wire is a very convenient form of 'friction rider'; it should be twisted to the cord and cut to the required length with wire-cutters.

EXPT. 58. The Acceleration under a given Force is Inversely proportional to the Mass moved.—Using the same hanging mass each time, place different masses on the trolley, obtaining separate traces for each mass used. Calculate the value for the acceleration of each mass when under the action of this constant force, and show that

$$\text{Mass moved} \times \text{Acceleration}$$

is constant; or For a given force, acceleration is inversely proportional to the mass moved.

In this experiment the equivalent masses of the pulley and wheels may be included if known, though, in general, they may be neglected.

Let M = mass of trolley and load placed on it,
 m = mass of hanging weight,
 x = equivalent mass of pulley,
 and y = equivalent mass of wheels.

Total mass moved is taken as $(M + m + x + y)$.

NOTE.—It is possible to calculate a value for the acceleration due to gravity from the observations already made, provided the acceleration $2s/t^2$ has been calculated in cm. per sec. per sec. Thus in any case taken, $mg = (M + m + x + y) (2s/t^2)$, since the force is the weight of the hanging mass; hence g can be calculated.

The method is not, however, a good one for this purpose on account of the fact that the quantities x and y are not accurately known, and also on account of the difficulty in measuring t already discussed.

Another method of using the apparatus is to place the trolley on a plane inclined at an angle θ to the horizontal. In this case the force tending to produce motion along the plane is $mg - (M + y)g \sin \theta$.

ATWOOD'S MACHINE

This is an apparatus more widely known than Fletcher's Trolley Apparatus, and one of great historic interest. It was designed by

Atwood (1746–1807), a famous English mathematician, for the purpose of illustrating the laws of motion, and for the determination of the acceleration due to gravity. In it, the weight of a small rider is compelled to move two much larger masses which, suspended at opposite ends of a cord moving over a pulley, counterpoise each other exactly. The weight of the small rider causes only a very small acceleration in the moving masses, since the total mass set in motion is large. Hence this acceleration can be measured with much greater accuracy than the acceleration the rider would have if falling freely alone.

Atwood's Machine: Pillar Type.—The two equal masses A and B are suspended from a cord. The cord passes over a pulley W supported on fine bearings at the top of a pillar from 2 to 2.5 metres in length. Attached beneath A and B there may be a compensating cord of the same type as the suspending cord; this keeps the masses of string on the two sides of the machine accurately balanced whatever the positions of the masses A and B: it is, however, inconvenient in practice, and is rarely used. The mass A carries a small rider which can be slipped on over the string, so that the only unbalanced force in the whole system is the weight of this small rider.

To perform the experiment, B is fixed lightly in the clip, so that the top of A is level with a known mark on the scale. The ring C is adjusted to some convenient distance below this zero position of A, so that A will traverse a known distance under the action of the weight of the rider. A stop-watch is started and simultaneously the clip is opened, thereby releasing B with no *initial* velocity. When the rider on A is heard to strike the ring C, the watch is stopped, and thus the time t required to traverse a known distance s is determined.

Another method of making the experiment is to use a metronome, and to adjust the distance so that the time of fall occupies an exact number of beats of the metronome.

In some forms of machine a pneumatic release is fitted to the clip; in others the clip is replaced by a small electromagnet, and the mass B is held magnetically, iron masses (A and B) being used. All types of release are equally good provided B is released without any vertical motion, though simplicity in use and construction is generally associated with certainty of action, and therefore is to be recommended.




FIG. 72.—Atwood's Machine
Pillar Type

Experiments with Atwood's Machine

EXPT. 59. A Body moving under the Action of a Uniform Force moves with Uniform Acceleration.—Place a small piece of copper wire on the mass A, adjusting its size so that the masses just continue in motion

without other rider when gently started. Then the weight of this piece of copper wire just overcomes the friction of the machine — it is called the 'friction rider' and is kept on A all the time.

Adjust the ring C to different positions, so that the masses move through distances of 50, 100, 150, and 200 cm. under the action of the various riders.

Find the times taken for the masses to move through these various distances, when under the action of riders of different weights (say 2 gm., 4 gm., 6 gm., etc.). *At least three values of t should be taken for each distance, and each rider, used.*

Find the quotients $2s/t^2$ for each set of observations, and show that for a given rider $2s/t^2$ is constant.

That is, when acted on by a constant force, a mass moves with uniform acceleration.

Arrange the observations as in the following table :—

Mass of Rider used	Distance s	Time t	$\frac{2s}{t^2}$	
2 gm. rider . .	50			Mean acceleration with 2 gm. rider $a_1 =$
	100			
	150			
	200			
4 gm. rider . .	50			Mean acceleration with 4 gm. rider
	100			
	150			
	200			
6 gm. rider . . (if used)	50			Mean acceleration with 6 gm. rider $a_3 =$
	100			
	150			
	200			

It will be found that the sets of figures in the last column will approximate to a constant value for each of the riders, the value of the constant increasing as the mass of the rider is increased.

EXPT. 60. Acceleration is proportional to the Force acting.—This can be shown without further experiment from the results in the foregoing table. The total mass moved by any of the riders is practically the same, differing only by the small differences between the masses of the riders themselves. Thus if the acceleration produced in a mass is proportional to the magnitude of the force acting on the mass, the accelerations a_1, a_2, a_3 , should be in the same proportions as the masses of the riders used, or proportional to 2, 4, 6, etc., in the case considered.

EXPT. 61. Acceleration for a Given Force is inversely proportional to Mass.—By using pairs of masses A and B of different sizes, it is possible to show that a given force produces acceleration inversely proportional to the mass on which it acts.

This is done by finding from measurements of s and t the acceleration produced in different pairs of masses, when they move under the action of the same rider. The products (Total mass moved \times acceleration) should be constant.

It is necessary in this case to know the value of the 'equivalent' mass of the pulley.

The total mass moved in any one case is given by $(2M + m + x)$ gm. (see below).

EXPT. 62. Acceleration due to Gravity.—(i) Assuming the value of the equivalent mass of the pulley and cord.

Let the mass of each of the masses A and B = M gm.

Let the mass of the rider = m gm.

Let the equivalent mass of the pulley (and cord) = x gm.

Let the acceleration produced = a cm. per sec. per sec.

Then Force acting = Wt. of rider = mg dynes,

Mass moved = $(2M + m + x)$ gm.

Force = Mass \times Acceleration.

Therefore $mg = (2M + m + x)a$,

from which g can be determined.

Calculate g from the sets of observations for each of the riders used in Experiment 59.

(ii) Calculation of a value of the acceleration due to gravity, eliminating the equivalent mass of the pulley.

If the same rider is used for different pairs of masses A and B, the value of g can be calculated without assuming the equivalent mass of the pulley to be known.

Thus if the acceleration produced with a pair of masses each equal to M' is a' , and the acceleration produced by the *same* rider on a pair of masses each equal to M'' is a'' , then

$$\left. \begin{aligned} mg &= (2M' + m + x)a' \\ \text{and } mg &= (2M'' + m + x)a'' \end{aligned} \right\} x \text{ being unknown,}$$

$$\text{whence } mg \left\{ \frac{1}{a'} - \frac{1}{a''} \right\} = 2(M' - M'').$$

Calculate g , using the values of a' and a'' corresponding with the different masses used in Experiment 61.

The instrument was designed originally for the determination of g , the accurate pendulum methods of Kater having not then been invented. Its main use nowadays is to demonstrate the laws of motion, determinations of g by its means being of a relatively low order of accuracy though possessing historic interest.

Atwood's Machine: Ribbon Pattern.—In this apparatus the equal masses are suspended by a paper ribbon which passes over the flat rim of the pulley. A compensating ribbon is attached below the masses as in Fig. 73. A steel spring is fixed at one end and at the other carries a fine brush, charged with ink, which marks the paper at the top of the pulley. A simple release sets free the spring and the moving masses simultaneously. Each wave traced on the ribbon represents a known period of time.




FIG. 73.—Atwood's Machine
Cusson's Ribbon Pattern:

The same type of experiment can be performed with this form as with the pillar form of machine, taking the distances and times as recorded on the ribbon. The value of the acceleration in each case can be obtained from the wavy trace, as already explained in Fletcher's Trolley Apparatus. (See also page 121.)

Carry out experiments exactly as with the pillar type of machine, using the ribbon and spring to measure the acceleration in the various cases instead of adjusting the distance s to different values and noting the corresponding times.

A way of using Atwood's machine which is sometimes employed is to find the velocity of the mass A after the rider has been removed by the ring and the system is supposed to be moving with constant velocity. This method, however, is neither so convenient nor so accurate as that detailed.

§ 4. ROTATION OF A RIGID BODY ROTATIONAL INERTIA OR MOMENT OF INERTIA

The 'effect' of a mass in rotation about an axis depends not only on the mass moving but also on the way in which the mass is distributed about the axis of rotation. Thus, consider the Kinetic Energy of a body as shown in Fig. 74, rotating with angular velocity ω radians per second, about an axis through O perpendicular to the plane of the paper.

Velocity of particle m_1 at $P_1 = r_1\omega$,

Velocity of particle m_2 at $P_2 = r_2\omega$, etc.

Kinetic Energy of particle m_1 , at $P_1 = \frac{1}{2}m_1(r_1\omega)^2$,

Kinetic Energy of particle m_2 , at $P_2 = \frac{1}{2}m_2(r_2\omega)^2$, etc.

Total Kinetic Energy of the Body due to Rotation about O

$$= \frac{1}{2}\omega^2 \{m_1r_1^2 + m_2r_2^2 + m_3r_3^2 + \dots\};$$

or indicating the sum of the quantities in the bracket by the symbol I,

$$\text{Kinetic Energy of Rotation} = \frac{1}{2}I\omega^2.$$

The sum represented by I is a property of the body which has a perfectly definite value for that body with reference to the given axis O, its magnitude depending on the distribution of the mass about that axis. It is called the **Moment of Inertia** of the body about the **given axis**, or the **Rotational Inertia**, and is defined by

$$I = m_1r_1^2 + m_2r_2^2 + m_3r_3^2 + \dots$$

or

$$I = \sum mr^2,$$

where Σ denotes the sum of a number of terms of the same type, taken for all the particles in the body.

It can be shown that the **Angular Momentum** or the **Moment of Momentum** $= I\omega$.

The *dimensions* of I are *mass* \times *length*². It may be in gm. cm.² or kgm. metre.² See also pp. 67-68.

The Radius of Gyration.—If the total mass M of the body were concentrated into a single particle, and if this particle were constrained to move in a circular path of radius k by means of a light rod with its centre at O , the Moment of Inertia of the particle about the given axis would be Mk^2 . By properly choosing k the Moment of Inertia of this




FIG. 74.—Moment of Inertia




FIG 75.—Parallel Axes through O and G

particle may be made the same as that of the given body. For this value of k , $Mk^2 = I$; this length k is called the **Radius of Gyration** of the body about that particular axis. The value of I would be the same if the matter were arranged in the form of a ring of radius k .

THEOREM OF PARALLEL AXES

The Moment of Inertia of a body about any axis is equal to its Moment of Inertia about a parallel axis through the Centre of Gravity *plus* the product obtained by multiplying the mass of the body by the square of the distance between the axes.

Thus if I_o is the Moment of Inertia about an axis through O , and I_g is the Moment of Inertia about an axis through G (Fig. 75),

$$I_o = I_g + Mk^2.$$

But

$$I_o = Mk_o^2, \quad I_g = Mk_g^2,$$

so

$$Mk_o^2 = Mk_g^2 + Mk^2,$$

or

$$k_o^2 = k_g^2 + h^2.$$

Consequently, if we know the Moment of Inertia, or the Radius of Gyration, for an axis through the Centre of Gravity, we can calculate the corresponding quantity for any parallel axis.

For a list of Moments of Inertia see the Appendix, p. 560.

Perpendicular Axes Theorem for a Lamina.—Let O be any point in the plane of the lamina, OX and OY two perpendicular axes in its plane, OZ an axis perpendicular to its plane. Then the moments of inertia I_z , I_y , I_x about these axes satisfy the relation $I_z = I_x + I_y$.

LINEAR MOTION AND ANGULAR MOTION

The following parallels between quantities concerned with **Translation**, or linear motion, and quantities concerned with **Rotation**, or angular motion, should be studied very carefully :—

Translation		Rotation	
Quantity	Symbols	Quantity	Symbols
Displacement or Distance	s	Angular Displacement	θ
Velocity . . .	$v = \frac{ds}{dt}$	Angular Velocity	$\omega = \frac{d\theta}{dt}$
Acceleration . . .	$a = \frac{dv}{dt}$ $= \frac{d^2s}{dt^2}$	Angular Acceleration	$\alpha = \frac{d\omega}{dt}$ $= \frac{d^2\theta}{dt^2}$
Mass or Inertia . . .	m	Moment of Inertia	I
Momentum . . .	mv	Angular Momentum	$I\omega$
Force	$F = m.a$	Couple	$G = Ia$
Kinetic Energy of Translation	$\frac{1}{2}mv^2$	Kinetic Energy of Rotation	$\frac{1}{2}I\omega^2$
Work	Force \times Distance $W = Fs$	Work	Couple \times Angle $W = G\theta$

This table is of great value in dealing with angular motion. If a general expression be obtained connecting certain quantities in the case of linear motion, an exactly similar expression can be written at once for the corresponding quantities for angular motion. For examples of this, see Simple Harmonic Motion, Chapter IX.

§ 5. MEASUREMENT OF MOMENT OF INERTIA

The idea of Moment of Inertia has been obtained above from a consideration of the Kinetic Energy of a rotating body. It is by measurement of the Kinetic Energy of a rotating body that we usually measure its Moment of Inertia. The experimental determination of the Moment of Inertia of a rotating body is usually carried out by

giving to the body a definite or measurable quantity of energy, and measuring the resulting angular velocity.

MOMENT OF INERTIA OF A FLYWHEEL

When the body is in the form of a wheel with a long axle, the following method is one of the most suitable for determining its Moment of Inertia about the axis of rotation. At some point in the axle, or in a cylindrical rim on the wheel itself, either a small hole or a small peg will be required.

A brass pin is made to fit into the hole and is tied firmly to a good length of cord. If, instead of a hole, a peg be found, a simple loop is made in the end of a cord and this is slipped over the peg. The cord having been attached in one of these ways, the wheel is turned so as to wind the cord round the rim a few times. The cord is passed over a pulley if the axis of the wheel is vertical, or allowed to hang straight down if the axis is horizontal; to the free end is attached a mass of suitable size.

If now the mass be allowed to fall, it will lose Potential Energy; the Potential Energy lost will be converted partly into Kinetic Energy of translation due to the motion acquired by the falling mass itself, and partly into Kinetic Energy of rotation of the flywheel. If we neglect any frictional losses for the time being, we may state from the principle of the conservation of energy that

$$\left\{ \begin{array}{l} \text{Potential Energy lost} \\ \text{by the falling mass} \end{array} \right\} = \left\{ \begin{array}{l} \text{Kinetic Energy} \\ \text{gained by mass} \end{array} \right\} + \left\{ \begin{array}{l} \text{Kinetic Energy} \\ \text{gained by wheel} \end{array} \right\}.$$

Now if the mass suspended be m gm., and if it fall through a vertical distance h cm. before the string is released from the wheel, the Potential

Energy lost is mgh ergs. Just as the end of the string is pulled off from the rim, the mass has acquired a velocity equal to v cm. per sec. (say), and the wheel an angular velocity equal to ω radians per second. The Kinetic Energy of the falling mass at this instant is thus $\frac{1}{2}mv^2$, and the Kinetic Energy of rotation of the wheel is $\frac{1}{2}I\omega^2$.

Thus, neglecting friction, we have

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2.$$

In this equation m and g are both known.

Determination of h .—The most convenient way of getting an accurate value of h is to arrange the length of the cord so that the end separates from the wheel just as the bottom of the falling mass touches the ground. If the mass be started with its base level




FIG. 76.—Flywheel with Axle vertical




FIG. 77.—Flywheel with Axle vertical

with the table, the height through which it falls while attached to the wheel is equal to the height of the table above the floor.

Determination of v and ω .—There are two ways in which v and ω may be determined; both these are described below, but the *second* method is preferable as giving much greater accuracy than the first. It also affords a useful means of correcting for friction losses (see later).

METHOD I.—The length of time taken for the falling mass to reach the ground is measured by means of a stop-watch. Let this be t_1 seconds.




FIG. 78.—Flywheel with Axle horizontal

During this time the mass falls a distance h cm. with a uniformly increasing velocity. Since the *initial* velocity is zero the final velocity, v , will be double the *average* velocity.

$$\text{The Average Velocity } \bar{v} = \frac{h}{t_1}.$$

The final velocity, the velocity the mass has when it reaches the ground, is *double* this value, or

$$v = 2\bar{v} = \frac{2h}{t_1}.$$

The time t_1 is usually very short, and cannot be measured with great accuracy.

The quantities v and ω are connected by the relation $v = \omega r$, where r is the radius of the cylindrical rim round which the string is wound. If r be measured and v be determined as above, we can find ω , since

METHOD II.—After the string has become detached from the wheel the wheel continues to revolve for a considerable time. Its angular velocity decreases, however, on account of friction, and eventually the wheel comes to rest again.

If the friction be assumed constant, the wheel will be retarded uniformly, and the average angular velocity taken over the whole time required to come to rest will be equal to *one-half* the initial angular velocity ω .

If the wheel make n_2 revolutions after the string has become detached, and take t_2 seconds to come to rest, the average angular velocity, while coming to rest, is given by

$$= \frac{2\pi n_2}{t_2} \text{ radians per second.}$$

Therefore ω , the angular velocity at the moment when the string became detached, is given by

$$\omega = 2\bar{\omega} = \frac{4\pi n_2}{t_2}.$$

The value of t_2 is much greater than that of t_1 in Method I, and can therefore be determined with much greater accuracy; thus the resulting values of v and ω obtained by this method will be more accurate than those obtained by Method I.

Having found ω , v is calculated by means of the relation

$$v = \omega r.$$

Determine v in cm. per second and ω in radians per second.

EXPT. 63. Moment of Inertia of a Flywheel.—Set the wheel in rotation by allowing different masses to hang from the string, adjusting and measuring the heights of fall as already described; this gives m and h .

Measure the radius of the cylindrical rim round which the cord is wound, adding half the thickness of the cord to this if the cord is an appreciable thickness compared with the radius of the rim; this gives r .

Count the number of revolutions made by the wheel after the string has become detached, n_2 .

Find the time taken to come to rest, t_2 .

Repeat the observations three times each, taking the *means* of the observed values of n_2 and t_2 , if these vary for the same m and h .

Calculate mean values of ω and v corresponding with each value of m and h , and substitute in the equation

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2.$$

Calculate each of the quantities mgh , $\frac{1}{2}mv^2$, and $\frac{1}{2}I\omega^2$ *separately* before solving for I .

Express the Moment of Inertia in *gm. cm.²*

Correction for Friction.—If the friction of the supporting bearings is considerable, it must be allowed for. Suppose a certain amount of work f is done against friction every time the wheel revolves *once*. While the mass was falling, a certain number of revolutions n_1 were made, and therefore an amount of work n_1f was done against friction.

The equation $mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2$ is therefore no longer quite true: it must be modified to

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2 + n_1f,$$

since the work n_1f was done while the falling mass was losing its Potential Energy.

Now, after the string was detached from the wheel, the wheel possessed a certain amount of Kinetic Energy $= \frac{1}{2}I\omega^2$. This energy was gradually lost in overcoming friction, the whole amount being absorbed in a certain number of revolutions n_2 . Hence

$$\frac{1}{2}I\omega^2 = n_2f.$$

We thus have a value for f expressed in terms of known quantities,

$$f = \frac{\frac{1}{2}I\omega^2}{n_2},$$

and therefore

$$n_1f = \frac{n_1}{n_2} \frac{1}{2}I\omega^2.$$

The equation may now be rewritten as

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2 + \frac{n_1}{n_2} \frac{1}{2}I\omega^2,$$

or

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2 \left(1 + \frac{n_1}{n_2} \right),$$

the friction correction being represented by the term $\frac{n_1}{n_2}$ in the bracket.

Determine n_1 , the number of turns made by the wheel while the mass is falling, and recalculate I , introducing this small correction.

SOLID OF REVOLUTION ROLLING DOWN AN INCLINED PLANE

When a body is allowed to roll down an inclined plane, the Potential Energy it loses is converted into Kinetic Energy. When the body reaches the foot of the plane it possesses two kinds of motion—

- (a) Motion of translation,
and (b) Motion of rotation.

Hence the Kinetic Energy of the body is made up of two parts—

- (a) Kinetic Energy of linear motion = $\frac{1}{2}mv^2$,
and (b) Kinetic Energy of rotation = $\frac{1}{2}I\omega^2$.

Where m = Mass of body,

v = Linear Velocity,

I = Moment of Inertia about the axis through the Centre of Gravity,

ω = Angular Velocity.

If the top of the plane where the body starts be h cm. above the place where the body is stopped, the body loses Potential Energy = mgh .

Hence

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2.$$

Actually the motion is one of rotation about the *instantaneous* axis of contact with the plane, as it is assumed that no slipping takes place here. This can, however, be shown (see p. 119, and Fig. 81) to be equivalent to a linear motion of the C.G., together with an angular motion about the parallel axis through the C.G.




FIG. 79.—Proof that $v = \omega r$

If r is the perpendicular distance between the *axis of contact* through O and the Centre of Gravity, the linear velocity of the Centre of Gravity v is given by the equation

$$v = \omega r,$$

as is readily seen by reference to Fig. 79, where both axes are perpendicular to the plane of the paper.

Now v may be determined by observing the time taken for the rolling body to traverse a length s on the plane; let this be t secs.

Final Velocity = twice Average Velocity.

$$\therefore v = 2\bar{v} = \frac{2s}{t}.$$

Thus ω also is known, for $\omega = \frac{v}{r}$; so that $\omega = \frac{2s}{tr}$.

h and m may be determined directly, so that everything in the equation is known except I .

Substituting the known values for the various quantities in the equation

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2,$$

the value of I may be obtained.

EXPT. 64. Wheel and Axle on an Inclined Plane.—A large disk fitted with a steel axle is allowed to roll down a set of rails on an inclined plane, and the time taken for the disk to roll down the plane is noted; let this be t sec.

The length of the plane traversed by the axle is also determined; call this s cm. The total height fallen through by the axle is measured




FIG. 80.—Wheel and Axle on Inclined Plane

by means of a simple cathetometer; let this be h cm. Then the Potential Energy lost = mgh . Weigh the disk, and calculate the value of mgh .

The linear velocity of the disk as it reaches the foot of the plane is $2s/t = v$.

Calculate the value of v in cm. per sec.

Calculate the value of $\frac{1}{2}mv^2$, the Kinetic Energy of translation at the foot of the plane.

In this case, the distance from the fixed axis to the Centre of Gravity is equal to the radius of the axle.

Measure the radius of the axle, using a micrometer screw gauge; let this be r cm.

The angular velocity at the foot of the plane = $\omega = \frac{v}{r} = \frac{2s}{rt}$.

Calculate the value of ω in radians per second.

Substitute these values in the equation

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2,$$

and solve for I .

Repeat the experiment, using various values of h (5, 10, 15, and 20 cm.).

Verify your result by calculation, assuming the Moment of Inertia of the disk is $\frac{1}{2}ma^2$, where a is the radius of the disk.

It has been mentioned in the foregoing that although the actual motion is one of rotation about the axis of contact with the plane, this motion is equivalent to a linear motion of the Centre of Gravity together with an angular motion about an axis through the Centre of Gravity.

The proof of this is as follows: Consider the body A to be subject to an angular velocity ω about the fixed axis O, and let B be an exactly similar body with a linear velocity v of the C.G., and an angular velocity ω about the axis through the C.G.

Let the distance from the Centre of Gravity to O be r , and let the linear velocity of the C.G. in case B, be at right angles to this line and equal to ωr .

Consider the motion of the C.G. in the two cases.

Case A. Linear velocity of C.G. = ωr , from right to left, due to angular motion about O.




FIG. 81. Motion about Instantaneous Axis of Rotation

Case B. Linear velocity of C.G. = $v = \omega r$, from right to left, by hypothesis.
Motion due to rotation is zero.

Next consider the motion of the point O in the two cases.


Case A. Motion is zero.

Case B. Motion is $v = \omega r$, from right to left, due to linear motion and ωr from left to right due to rotation, and therefore O is at rest.

Thus in either case two points of this rigid body have the same motion. Therefore the motion of *all* points is the same, or a motion of rotation about an axis distant r from the C.G. may be resolved into an equal motion of rotation about a parallel axis through the C.G., together with a linear motion of the C.G. = ωr .

DISK SUPPORTED BY CORDS PASSING ROUND AN AXLE THROUGH THE DISK

The disk is mounted on a steel spindle suspended by strings in such a way that the axle is horizontal. The disk is raised by turning the axle so as to roll the string evenly on the two sides of the axle as shown in Fig. 82. When released the disk falls, acquiring a motion of rotation, due to the unwinding of the cord, as well as a motion vertically downwards.



If it falls a distance h , its mass being m , then as before

$$mgh = \frac{1}{2}mv^2 + \frac{1}{2}I\omega^2,$$

v being the linear, and ω the angular velocity of the disk, when it has fallen through this distance h .

The relation between v and ω is $v = \omega r$, where r is the radius of the axle plus half the thickness of the string. This is easily seen from Fig. 82. The point O' is at rest, and the centre of the axle O will therefore have a velocity $v = \omega OO'$.

Determination of v and ω .—The linear velocity of the disk as it reaches the bottom of the string is double the average linear velocity during the fall, for it starts with zero velocity and is accelerated uniformly throughout.

The average velocity of fall is obtained by finding the time t taken for the disk to reach its lowest position. The distance moved through is h , therefore the average velocity

$$\bar{v} = \frac{h}{t},$$

or

$$v = 2\bar{v} = \frac{2h}{t}.$$

From this ω is obtained, since $\omega = \frac{v}{r}$.

EXPT. 65. Determination of the Moment of Inertia of a Disk suspended by Strings.—See that the axle is horizontal when the disk is in its

lowest position. Rotate the disk about its axis so that the strings are wound evenly round the spindle, and the disk is raised to its highest point. Release the disk and start a stop-watch simultaneously, and take the time of descent from the highest to the lowest point. This observation must be repeated several times, and the mean value found. Measure the distance h through which the disk falls, and calculate the final velocity v in cm. per sec. from the formula

$$v = \frac{2h}{t}.$$

Measure the diameter of the spindle and the diameter of the cord with a micrometer screw, and determine r , which is the sum of the radii of the spindle and the cord. Determine the angular velocity ω from the formula $v = \omega r$, expressing the result in radians per second.

The mass of the disk (and axle) is determined by actual weighing, and thus the data necessary for the calculation of I are all known. Calculate the value of I from the energy equation.

An approximate value of I can be calculated from the mass and dimensions of the disk,

$$I = \frac{ma^2}{2},$$

a being the radius of the disk.

This calculated value is only approximate; the formula is only true if the mass of the disk is distributed uniformly throughout its volume, and, of course, this is not the case, the axle having an appreciable mass which is obviously not distributed uniformly throughout the disk.

§ 5. THE STUDY OF VIBRATOR TRACES

The following method of determining acceleration from the vibrator traces obtained when using Fletcher's Trolley and Atwood's Machine is due to Dr. L. F. Richardson. This trace will resemble that made by a tuning-fork, shown in Fig. 119, p. 174. Draw the middle line through the trace by setting the paper in motion with the vibrator at rest, taking care that the tracing point is not bent. Measure distances, from the first clear intersection of this line and the trace, to each of the succeeding twelve *alternate* intersections. Let these distances be $a, b, c, d \dots j, k, l$.

Tabulate these 12 measurements as 4 sets, in groups of 3 :—

Measurements	First Differences	Second Differences
$a \quad . \quad e \quad . \quad i$	$(e - a) \text{ and } (i - e)$	$(i - e) - (e - a) = a - 2e + i$
$b \quad . \quad f \quad . \quad j$	$(f - b) \text{ and } (j - f)$	$(j - f) - (f - b) = b - 2f + j$
$c \quad . \quad g \quad . \quad k$	$(g - c) \text{ and } (k - g)$	$(k - g) - (g - c) = c - 2g + k$
$d \quad . \quad h \quad . \quad l$	$(h - d) \text{ and } (l - h)$	$(l - h) - (h - d) = d - 2h + l$

Mean second difference = $\frac{1}{4}\{a + b + c + d - 2(e + f + g + h) + i + j + k + l\} = D$.

In finding this mean, all the twelve readings are utilised. If the periodic time of the vibrator is T , we then have

$$\text{Acceleration} = D/16T^2.$$

PROOF.—Let any two *consecutive* sets of four waves occupy lengths s_1 and s_2 on the trace, and let v_0 be the velocity at the beginning of the first wave, and v_1 the velocity at the end of the fourth wave (or at the beginning of the fifth). The acceleration being a , we then have

$$s_1 = v_0(4T) + \frac{1}{2}a(4T)^2,$$

$$v_1 = v_0 + a(4T),$$

$$\text{and } s_2 = v_1(4T) + \frac{1}{2}a(4T)^2 = v_0(4T) + \frac{3}{2}a(4T)^2.$$

$$\text{Whence } s_2 - s_1 = a(4T)^2, \text{ or } a = (s_2 - s_1)/(4T)^2.$$

The lengths s_1 and s_2 represent any pair of first differences such as $(e - a)$ and $(i - e)$, while $(s_2 - s_1)$ represents the corresponding second difference.

The same method may be used for any number of readings provided the correct time interval is employed. At high speeds it may be convenient to use *successive* points of intersection, or half wave-lengths.

PERIODIC MOTION

§ 1. LINEAR SIMPLE HARMONIC MOTION

IN all branches of Physics cases occur in which the motion of a point or particle is of the nature of an oscillation or vibration. The motion of a point is said to be **periodic** when the same series of movements is repeated at regular intervals of time. The **Period** of the motion is the time required for the complete series of movements, or one complete cycle. The **Frequency** of the oscillation is the number of cycles per second. The simplest type of periodic motion is that which is known as **Simple Harmonic Motion (S.H.M.)**.

Linear Simple Harmonic Motion may be defined geometrically as the projection of uniform circular motion on a diameter of the circle.




FIG. 83.—Simple Harmonic Motion

Imagine a point **P** moving round a circle with uniform speed. Take *any* diameter **AA'** of the circle, and draw **PN** the perpendicular from **P** to this diameter. Then the point **N**, the foot of the perpendicular, executes **S.H.M.** across the diameter **AA'**. The **Displacement** of the point **N** is **ON**, the distance from its mean position **O**. The **Amplitude** of the motion is the **maximum displacement** from the mean position **O**. It is equal to **a** or **OA**, the radius of the circle of reference. The **Phase** of the motion is the time, or the fraction of a period, that has elapsed since **P** passed some fixed point, such as **A**. It may be expressed also as the angle **POA**. The **Period** of the motion is the time taken for the point **N** to travel backwards and forwards along the diameter **AA'**; it is the same as the time taken by the point **P** to travel round the 'reference circle' of radius **a**.

Let the velocity of **P** at any point be **v**, and let the angular velocity of **OP** be ω radians per second, then $v = a\omega$ and the Period **t** is given by

$$t = \frac{2\pi a}{v} = \frac{2\pi}{\omega}.$$

The displacement of **N** = $a \cos \text{PON}$.

The point **N** has a velocity along **AA'** which is always equal to the

component of the velocity of P parallel to AA'. Hence the velocity of N = $v \sin \text{PON}$.

Any change in the velocity of P which affects its velocity parallel to AA' also affects the velocity of N. Thus the acceleration of the point N along AA' is equal to the component of the acceleration of P parallel to AA'. But the acceleration of P can be shown to be equal to $\frac{v^2}{a}$ in the direction PO. Hence the acceleration of N

$$\begin{aligned} &= \frac{v^2}{a} \cos \text{PON, towards O,} \\ &= \frac{v^2}{a} \times \frac{\text{ON}}{\text{OP}} \\ &= \left(\frac{v}{a}\right)^2 \times \text{Displacement of N} \\ &= \omega^2 \times \text{Displacement of N.} \end{aligned}$$

Hence we see that in Linear Simple Harmonic Motion a point moves along a straight line with an acceleration that is always directed towards a fixed point in that line, and is directly proportional to the distance from that fixed point.

This statement gives an alternative definition of S.H.M.

Whenever a point moves in a straight line with an acceleration of this type, so that

$$\frac{\text{Acceleration}}{\text{Displacement}} = \text{a constant,}$$

and the Acceleration is directed towards a fixed point in the line, we know that the moving point executes a S.H.M. with this fixed point O as its mean position. The period of this S.H.M. can be expressed in terms of the acceleration at any known distance from O, even if no other property of the motion is given.

The moving point would correspond with the point N in Fig. 83. For any given value of the amplitude a of the motion of N, we may imagine a point P moving round in a reference circle of radius a .

The angular velocity ω of the radius will require to be such that the Acceleration of N = $\omega^2 \times \text{Displacement of N}$.

Notice carefully that it is the *square* of the angular velocity which corresponds to the constant ratio of Acceleration to Displacement. Now $\omega = 2\pi/t$ and so ω represents the number of complete cycles in 2π seconds. It has been called the *pulsatance* of the periodic motion and is sometimes represented by p .

This important magnitude ¹ is determined by the equation

$$\omega = p = \sqrt{\frac{\text{Acceleration}}{\text{Displacement}}}$$

¹ Anticipating later work we may point out that the graph of S.H.M. is a sine or cosine curve represented by the equation $x = a \cos (pt - \alpha)$ or by $y = a \sin (pt - \beta)$.

and the period t is given by

$$t = 2\pi \sqrt{\frac{\text{Displacement}}{\text{Acceleration}}}.$$

In Dynamics it is frequently found that the force acting on a particle is directed towards a fixed point for all positions of the particle, and is directly proportional to the distance of the particle from that point. It is easy to see that if the particle move in a straight line passing through the fixed point its motion must be S.H.M.

For let the force be μx , where μ is a constant and x is the displacement. The constant μ is the value of the force when the displacement is unity. If the mass of the particle be m , the acceleration a , in accordance with Newton's Second Law, is given by

$$ma = \mu x,$$

or

$$a = \frac{\mu}{m} x,$$

so that the acceleration is directly proportional to the displacement, and the motion is S.H.M.

We see that μ/m replaces ω^2 , or $(v/a)^2$ in the preceding discussion.

The Period, t , can be written down at once for $t = \frac{2\pi}{\omega}$.

so that

$$t = 2\pi \sqrt{\frac{m}{\mu}}.$$

Notice that the period t is independent of the amplitude a .

This equation for the period is of far-reaching application. If we know the mass of a body, and the force acting on it in terms of the displacement of the body from its mean position, the period can be determined at once from this relation.

The constant μ is called the force for unit displacement, for it is the value of the force in dynes that would act on the body if it were displaced one centimetre from its mean position. Its value may often be determined by a simple statical method. In elastic problems μ represents the *stiffness* of the constraint.

§ 2. ANGULAR SIMPLE HARMONIC MOTION

The analogy between certain quantities connected with linear motion and other quantities connected with angular motion has already been pointed out (see the table on p. 114). This may be made use of in dealing with linear and angular S.H.M.s. Thus we may at once deduce the following statement:—

When a body rotates about an axis under a couple which is proportional to the angular displacement from a certain position, the body executes an Angular S.H.M.

Again by simple analogy, if the couple or 'torque' G acting on a body is related to its angular displacement by the equation

$$\text{Couple} \equiv G = c\theta,$$

where c is *constant* the period of the Angular Simple Harmonic Motion executed is

$$t = 2\pi\sqrt{\frac{I}{c}},$$

I being the **Moment of Inertia** of the body about the axis of rotation.

The coefficient c is frequently spoken of as the **couple for unit twist**, for c is the value of the couple that would act on the body if it were displaced *one radian* from its mean position. It may be regarded as the **stiffness** of the constraint when that is due to elasticity.

§ 3. EXAMPLES OF PERIODIC MOTION

The types of periodic motion met with in practice are rarely pure Simple Harmonic Motions. They may, however, be considered as Simple Harmonic Motions in many cases, provided the extent of

motion allowed does not exceed certain small limits. The oscillations of a pendulum give one illustration. Not only is the pendulum widely used for time-keeping purposes, but very important results in Physics can be obtained from determinations of pendulum periods.




FIG. 84.—Forces on Bob of Simple Pendulum

PERIOD OF A SIMPLE PENDULUM

A simple pendulum consists of a heavy particle of matter suspended from a perfectly rigid point of support by a flexible, weightless, inextensible string. When displaced to one side of its mean position O , the 'bob' swings back towards O along the arc, under the action of the forces on the bob (Fig. 84).

The only force which has any component along the arc is the weight of the bob, and the component of this tending to set the body moving back towards O is $mg \sin \theta$.

Thus the tangential force on the bob is given by

$$f = mg \sin \theta.$$

If the angle of displacement θ is very small we may write $\theta = \sin \theta$, approximately, and then

$$f = mg \theta.$$

Now if the displacement of the bob along the arc is x and the length of the pendulum is l , $\theta = \frac{x}{l}$, and $f = \frac{mg}{l}x$.

This is an equation of the form $f = \mu x$, and hence the motion of the bob is a Simple Harmonic Motion if the displacement x is never large. The value of μ , the force for unit displacement, is $\frac{mg}{l}$, and is inversely proportional to the length of the pendulum. The period is given (approximately) by

$$t = 2\pi\sqrt{\frac{m}{\mu}} \text{ where } \mu = \frac{mg}{l}.$$

Hence

$$t = 2\pi\sqrt{\frac{l}{g}}.$$

PERIOD OF A COMPOUND PENDULUM

A body the mass of which is distributed throughout its volume can be used as a pendulum by allowing it to oscillate about some axis. Suppose a body to be suspended from the axis through O (Fig. 85).

If displaced sideways, its weight acts downwards through its Centre of Gravity and exerts a restoring moment on the body, the restoring moment about the axis O being $mgh \sin \theta$, when the body is displaced through an angle θ .

If θ is small we may write $\theta = \sin \theta$, approximately, and then the

Restoring Couple = $mgh \theta$.

This is of the form, couple = $c\theta$, where $c = mgh$. The body thus executes an angular S.H.M. about the axis through O, its period being given by

$$t = 2\pi\sqrt{\frac{I_0}{mgh}}.$$

I_0 is the Moment of Inertia about the axis through O, and can be expressed as $I_0 = m(k^2 + h^2)$, where k is the radius of gyration about the Centre of Gravity (p. 113).

Hence

$$t = 2\pi\sqrt{\frac{m(k^2 + h^2)}{mgh}}$$

or

$$t = 2\pi\sqrt{\frac{k^2 + h^2}{hg}}.$$




FIG. 85.—Compound Pendulum

PERIOD OF AN OSCILLATING MAGNET

When a magnet of pole strength m is suspended in a uniform field of strength H , each pole is subject to a force mH .




FIG. 86.—Couple on Magnet

When the magnet is displaced through an angle θ from its mean position, these forces exert a mechanical couple on the magnet. $G = mH \times NS \sin \theta$, where NS is the distance between the poles of the magnet.

The product $m \times NS$ is called the Magnetic Moment of the magnet, and is denoted by M . Hence

$$\text{Restoring Couple} = MH \sin \theta.$$

This reduces to $MH\theta$, if the swings are small, and we find at once for the period of swing

$$t = 2\pi \sqrt{\frac{I}{MH}},$$

I being the Moment of Inertia of the magnet about its axis of rotation.

PERIOD OF A TORSION PENDULUM

In all the foregoing examples of periodic motion, the motion has only been a Simple Harmonic Motion if the angle of swing has been small. In the case of a Torsion Pendulum the motion is accurately Simple Harmonic, even for large angular displacements.

If the upper end of a wire is fixed, and the lower end twisted through an angle θ radians, the restoring couple exerted by the wire is equal to $\frac{\pi n r^4 \theta}{2l}$, where r = radius of wire, l = its length and n is the Modulus of Rigidity (p. 93). Hence a body of Moment of Inertia I , supported from a wire in this way, would execute a Simple Harmonic Motion, the period of which is given by

$$t = 2\pi \sqrt{\frac{I}{\pi n r^4 / 2l}}$$

or

$$t = 2\pi \sqrt{\frac{I}{\pi n r^4 / 2l}}$$



FIG. 87.—Torsion Pendulum

When I is known, this result could be used for measuring the modulus of rigidity n by an oscillation method.

PERIOD OF MASS SUSPENDED FROM SPIRAL SPRING

The periodic motion of a mass suspended from a spiral spring furnishes another example of a pure Simple Harmonic Motion. Suppose a mass M , suspended from a spring, extends the spring l cm. Then the force exerted by the spring is just equal to the weight, Mg , of the suspended mass, and the force for unit extension is Mg/l . If the spring is stretched a little further, say 1 cm., the extension being now equal to $l + 1$ cm., the spring will pull upwards on the mass with a force equal to

$$\frac{Mg}{l} \times (l + 1) \text{ dynes.}$$

The forces acting on the mass are now (a) the *upward* force, $Mg \left(1 + \frac{1}{l}\right)$, exerted by the spring, and (b) its weight, Mg , acting *downwards*, the resultant being Mg/l *upwards*. Thus, when displaced 1 cm. from its steady position, the mass is pulled upwards by a force $= Mg/l$ dynes. This is the force for unit displacement.¹

The period of vibration will therefore be

$$2\pi\sqrt{\frac{M}{Mg/l}} = 2\pi\sqrt{\frac{l}{g}},$$

where l is the steady elongation produced by the suspended mass.

§ 4. EXPERIMENTS ON PERIODIC MOTIONS

EXPT. 66A. Restoring Force for a Simple Pendulum.—This force is *approximately* proportional to the displacement (pp. 126-127). To test this result suspend a *heavy* 'bob' by a *very long* string from a rigid support. Apply a known horizontal force to the bob by a second thread passing over a pulley and having a weight attached to its other end. Measure the displacement of the bob for various weights and plot a graph. This should be nearly linear. From it find μ , the force in dynes for a displacement of 1 cm. See whether the period calculated from the formula $t = 2\pi\sqrt{m/\mu}$ agrees with that found by observation.

In all simple harmonic motions the period t is expressed in terms of a group of quantities under a square-root sign. Hence in determining any one of those quantities by observing the period of the vibration, the accuracy obtained will depend on the accuracy of t^2 , an error of 1 per cent in t introducing an error of 2 per cent in the result, and so on.

With any given timing device the probable error has the same

¹ Compare this result with that on p. 127 for the simple pendulum, but notice that l here is *not* the length of the spring.

absolute value whether the total interval is long or short. Consequently the *percentage* error is reduced, in proportion as the measured interval is increased. The interval should therefore be long enough to be measured with *twice* the degree of accuracy required in the final result (see also pp. 24, 25).

With a watch ticking $\frac{1}{4}$ th seconds, the possible error is $\frac{1}{8}$ th seconds, and for 1 per cent accuracy *in the result* observations should extend over a period of not less than 80 seconds. It is advantageous to count swings until the desired period has elapsed, *then to continue counting until a convenient number of swings has been made before stopping the watch or stop-clock.*

DETERMINATION OF g BY USING A SIMPLE PENDULUM

The acceleration due to gravity, g , cannot be determined with great accuracy except by indirect methods. Of these the simple pendulum is the easiest, g being obtained from observations of l , the length of the pendulum, and t , its period of *full* swing, by means of the formula (p. 127) $t = 2\pi\sqrt{l/g}$.




FIG. 88.—Simple Pendulum

EXPT. 66B. Determination of g by the Simple Pendulum.—As a near approach to the ideal simple pendulum (p. 126) we use a small heavy 'bob' suspended from a fine strong thread or fishing line clamped rigidly at its upper end. The length of the pendulum is measured from the *lower* edge of the clamp to the *centre* of the 'bob' (Fig. 88).

The time occupied by a complete vibration is the interval between the 'bob' passing through the centre of its swing *in the same direction* on two consecutive occasions. The centre of the swing should be marked in some convenient way. Swings should then be counted over some pre-determined interval and the counting be continued *until some convenient number is reached before the total time is observed* (p. 26).

In timing the swings with a stop-watch it is advisable to start counting at 3 and to count *backwards* to zero, when the watch is started. Then if the total minimum interval chosen is 80 secs., and the approximate period of swing is $\frac{2}{3}$ sec., counting and timing proceed thus :—

$$3, 2, 1, 0, 1, 2, 3 \dots (121) \dots 130, \text{ or } 140, \text{ or } 150$$

80 secs. approx.

The watch is started at 0 and stopped at 130 or 140 or 150.

Take not less than six different lengths ranging from about 30 cm.

to 100 cm. or 120 cm. and observe the period for each length. The angle of swing must be small. Enter the observations thus :—

Length l in cm.	Number n of Swings	Time T secs. observed	Period $t = T/n$	l/t^2 cm. sec. ⁻²	Mean of l/t^2
----------------------	-------------------------	----------------------------	---------------------	-----------------------------------	--------------------

From the mean of l/t^2 (given in the last column) a value of g is calculated in cm. per sec. per sec. or

$$\text{Acceleration due to gravity, } g = 4\pi^2 \left(\frac{l}{t^2} \right) = \quad \text{cm. sec.}^{-2}$$

Plot a graph using values of l as abscissæ, and the corresponding




FIG. 89 —Graph for Simple Pendulum

values of t^2 as ordinates. This should be a straight line passing through the origin, showing that l is proportional to t^2 .

DETERMINATION OF g BY SPHERE ON CONCAVE MIRROR

An interesting example of periodic motion, involving the Moment of Inertia of the moving body, is afforded by the present experiment, in which a sphere rolls on a concave spherical surface. The motion of the 'bob' of a simple pendulum is along the arc of a circle of radius equal to the length of the string, and the bob is assumed to be so small that only its translational or to-and-fro motion need be considered.

A sphere rolling over a concave mirror has a motion similar in all respects to the motion of the bob of a simple pendulum, with the exception that the sphere *rolls*, or rotates as it moves forward. Thus, in dealing with a sphere rolling over a concave mirror, we must take the motion of rotation into account, as well as that of translation. In either case, the Kinetic Energy of the moving body at any point is equal to the Potential Energy it has lost in falling from the end of its swing to the point in question.

In the case of the simple pendulum, where the motion is one of pure translation, the Kinetic Energy is $\frac{1}{2}mv^2$ and the Potential Energy lost = mgh ;

$$\therefore \frac{1}{2}mv^2 = mgh,$$

$$v^2 = 2gh.$$

or

In the case of the sphere rolling on the mirror the Kinetic Energy $= \frac{1}{2}mv_1^2 + \frac{1}{2}I\omega^2$, and the Potential Energy lost $= mgh$;

$$\therefore \frac{1}{2}mv_1^2 + \frac{1}{2}I\omega^2 = mgh;$$

Now the Moment of Inertia (I) of a sphere about its centre is $\frac{2}{5}ma^2$, and the equation becomes

$$mgh = \frac{1}{2}mv_1^2 + \frac{1}{2}\left(\frac{2}{5}ma^2\right)\omega^2.$$

Again, the point of contact with the surface is at rest, therefore the linear velocity of the centre (v_1) is equal to the angular velocity (ω) times the radius of the ball (a), so that as on p. 119,

$$\begin{aligned} v_1 &= \omega a, \\ v_1^2 &= \omega^2 a^2. \end{aligned}$$

The equation with regard to the motion of the sphere on the concave mirror thus reduces to the form

$$\begin{aligned} mgh &= \frac{1}{2}mv_1^2 + \frac{1}{2} \cdot \frac{2}{5}m(a^2\omega^2), \\ &= \frac{1}{2}mv_1^2 + \frac{1}{5} \cdot \frac{2}{5}mv_1^2, \\ &= \left(\frac{7}{10}\right)\frac{1}{2}mv_1^2, \\ \text{or} \quad v_1^2 &= \left(\frac{5}{7}\right)\frac{1}{2}gh. \end{aligned}$$

Thus, if a simple pendulum bob and a sphere on a concave mirror trace out similar paths, the velocity of the sphere is always less than the velocity of the pendulum bob in the same position.




FIG. 90.—Simple Pendulum and Sphere on Concave Mirror

If v = the velocity of the pendulum bob, and v_1 = the velocity of the sphere at the same point, then $v^2 = 2gh$, and

$$v_1^2 = \frac{5}{7}(2gh) = \frac{5}{7}v^2,$$

so that at all points in its path the velocity of the rolling sphere is only $\sqrt{\frac{5}{7}}$ of the velocity of the pendulum bob.

Therefore, to complete any given motion, the sphere will take $\sqrt{\frac{7}{5}}$ the time taken by the more rapidly moving pendulum bob.

Now the period t of a simple pendulum $= 2\pi\sqrt{\frac{l}{g}}$.

Therefore in going over a similar path, the period of the rolling sphere (t_1) will be $t \times \sqrt{\frac{7}{5}}$, or $t_1 = 2\pi\sqrt{\frac{l}{g}} \times \sqrt{\frac{7}{5}}$.

The path traced out by the sphere is a curve of radius $(R - a)$ where R = the radius of curvature of the mirror and a = the radius of the sphere.

The length of the simple pendulum, the bob of which would trace out a similar path, is $(R - a)$.

The period of the similar simple pendulum is thus

$$t = 2\pi\sqrt{\frac{(R - a)}{g}}.$$

The period of the sphere on the mirror is $\sqrt{\frac{1}{k}}$ of this, so that

$$t_1 = 2\pi\sqrt{\frac{\frac{1}{k}(R - a)}{g}}.$$

EXPT. 67. Determination of g by Sphere on Concave Mirror.—Measure the radius of curvature of the mirror by means of a spherometer, and the radius of the ball by callipers. Wipe away all dust from the surfaces of the sphere and the mirror. Take the time for 10 or 20 complete oscillations of the ball on the mirror by means of a stop-clock, and deduce the time of oscillation. Repeat these observations for determining the period three times.

Calculate g in cm. per sec. per sec. from the formula

$$t_1 = 2\pi\sqrt{\frac{\frac{1}{k}(R - a)}{g}},$$

or

$$4\pi^2\left(\frac{\frac{1}{k}(R - a)}{t_1^2}\right) \text{ cm. sec.}^{-2}$$

COMPOUND PENDULUM

When a rigid body is supported so that it can turn about a horizontal axis, it will oscillate about an equilibrium position (see the discussion on p. 127).

Let $I_0 = Mk^2$ denote the Moment of Inertia of the body about a horizontal axis through its centre of gravity, G (Fig. 85).

The body is supposed to be oscillating about an axis at right angles to the plane of the paper through O. The point O is called the **Centre of Suspension**. The Moment of Inertia about the axis through O is given by $I_0 = I_G + Mh^2 = M(k^2 + h^2)$, where $h = OG$.

The time of vibration of the compound pendulum has been shown on p. 127 to be

$$t = 2\pi\sqrt{\frac{I_0}{mgh}}, \text{ or } 2\pi\sqrt{\frac{k^2 + h^2}{hg}}.$$

The length of the simple pendulum that vibrates in the same period is

$$l = \frac{k^2 + h^2}{h}.$$

This is called the length of the **simple equivalent pendulum**.

If the whole mass of the body could be concentrated at this distance from the axis of suspension, at a point in the line joining OG produced,

the period of oscillation and the equilibrium position would be unaltered. In Fig. 91 the distance $OG = h_1$ and the length of the corresponding simple pendulum is $l_1 = (k^2 + h_1^2)/h_1$. If the distance OO_1 is equal to l_1 O_1 is called the Centre of Oscillation corresponding with the Axis of Suspension at O.

The distance h_2 from G to O_1 is given by the relation $h_1 + h_2 = l_1$, so that

$$h_1 + h_2 = \frac{k^2 + h_1^2}{h_1},$$

or

$$h_1 h_2 = k^2. \quad (1)$$

This symmetrical relation is important. Adding h_2^2 to each side, we have

$$h_2^2 + h_1 h_2 = k^2 + h_2^2,$$

or

$$h_2 + h_1 = \frac{k^2 + h_2^2}{h_2}. \quad (2)$$




FIG. 91.—Compound Pendulum

Now $\frac{k^2 + h_2^2}{h_2}$ is the length l_2 of the simple pendulum, which has the

same period as that of this body when suspended about O_1 . Equation (2) shows that $l_1 = l_2$ and so the period will be the same whether the body is suspended about O or O_1 . This is equivalent to saying that the centre of suspension and the centre of oscillation are interchangeable.

Locus of points for which t is constant.—There are other axes about which the body will oscillate in the same period as about O and O_1 .

If we describe two circles with centre G and radii h_1 and h_2 , any parallel axis of oscillation taken on either of these circles would give the same value for t .

Variation of t with h —Minimum Period.—When the axis of suspension passes through the Centre of Gravity, the periodic time becomes infinitely great. If the axis is at an infinite distance the periodic time is again infinite. Consequently there must be some intermediate position for which the periodic time is a minimum. Now t will be a minimum when $\frac{k^2 + h^2}{h}$ is a minimum.

$$\text{But } k^2 + h^2 = (k - h)^2 + 2kh \dots \frac{(k - h)^2}{h} + 2k.$$

This is clearly a minimum when $h = k$.

The length of the simple equivalent pendulum in this case $= 2k$, and $OG = O_1G = k$, or $h_1 = h_2 = k$.

The minimum period is $t_0 = 2\pi\sqrt{\frac{2k}{g}}$.




FIG. 92.—Locus of Points for which t is constant

More than a century ago Captain Kater constructed a pendulum which could swing about two knife-edges at unequal distances from G, but adjusted so that the periods were very nearly equal. Very accurate determinations of g could be obtained by using his method.

A simple form of pendulum designed by D. Owen in 1939 was in the form of a bar along which could slide a light carriage carrying the knife-edge. With a stop-watch showing tenths of a second g could be determined quickly within a few parts in 10,000.

EXPT. 68. The Compound Pendulum.—To illustrate these results, a bar about 1 metre long, in which holes have been bored at equal distances (about 2 cm.) along its length, may be suspended from an axis which must be made horizontal (Fig. 93).

i. Take the periodic time for every third hole, starting from one end of the bar, noting the time for 50 complete swings.

ii. Plot a curve showing the periodic time at different distances from the Centre of Gravity. It will consist of two symmetrical branches corresponding to the two halves of the bar, showing a minimum period for the points A and B.

iii. Find the holes on the bar corresponding to these minimum periods and determine *very accurately* the period for the two holes on either side of that giving t a minimum, and also for the hole corresponding




FIG. 93.—Bar Pendulum




FIG. 94.—Graph for Compound Pendulum

with the minimum itself. At least 100 swings should be taken for each of these five holes, so as to get very exact points on the curve in this part. Find k from the positions of A and B :

$$k = AK = BK.$$

iv. Find points such as C, D, E, and F in Fig. 94, for which the periodic time is the same.

Then if CH is taken as h_1 , HE is h_2 .

Also $HF = h_1$ and $HD = h_2$.

Calculate the radius of gyration from the formula

$$k^2 = h_1 h_2.$$

Find the length of the simple equivalent pendulum

$$l = h_1 + h_2,$$

and calculate g from the formula

$$t = 2\pi\sqrt{\frac{l}{g}}.$$

v. Find the minimum periodic time t_0 corresponding to the points A, B in the graph and calculate k from the formula

$$t_0 = 2\pi\sqrt{\frac{2k}{g}},$$

assuming $g = 981 \text{ cm./sec.}^2$.

vi. Find the mass M of the body and calculate its Moment of Inertia

$$I = Mk^2.$$

The values of k obtained in iii, iv, and v should all agree, and should be approximately equal to the length of the bar divided by $\sqrt{12}$, if the breadth of the bar is negligible compared with its length (Appendix, p. 560).

EXPT. 69. Determination of Modulus of Rigidity by Oscillation.—Suspend a bar or a disk, or some other body of *known* Moment of Inertia, from a wire which is fixed firmly at its upper end.

Determine the period of oscillation of the body when moving as a torsion pendulum.

Measure the length of the wire and its radius. Calculate the Moment of Inertia of the suspended body from its mass and dimensions.

Deduce the value of the Modulus of Rigidity from the equation

$$t = 2\pi\sqrt{\frac{2Il}{\pi nr^4}},$$

or

$$n = \frac{8\pi Il}{t^2 r^4}.$$

Compare the Moments of Inertia of two bodies by using them as torsion pendulums from the *same* wire.

$$t_1 = 2\pi\sqrt{\frac{2l}{\pi nr^4} I_1},$$

$$t_2 = 2\pi\sqrt{\frac{2l}{\pi nr^4} I_2}.$$

The same wire is used, therefore $\frac{I_1}{I_2} = \frac{t_1^2}{t_2^2}$.

EXPT. 70. Determination of g by observing the Period of Oscillation of a Mass suspended from a Spiral Spring.—Suspend a mass from a spiral spring. Note the elongation l it produces when applied gently. Observe the period of oscillation of the mass when vibrating vertically.

Calculate g from the expression $t = 2\pi\sqrt{l/g}$ (p. 129).

CHAPTER X

GASES : THE BAROMETER AND BOYLE'S LAW

§ 1. PROPERTIES OF GASES

A gas differs from the other forms of matter in that it **tends to fill any space in which it is confined**. However small the quantity of gas contained in an enclosed volume, the gas distributes itself so as to fill the volume. This property is the most striking property possessed by substances in gaseous form, and may be described as their **expansibility**.

In the present chapter we shall study only the gaseous phenomena associated with constant temperature, leaving the investigation of the effects of change of temperature to the section on Heat.

BOYLE'S LAW

When the volume of a fixed mass of gas is changed, the *pressure* exerted by the gas alters in a definite way, and, **provided the temperature is maintained constant, the pressure varies inversely as the volume**. This relation may be stated conveniently in the form

$$\text{Pressure} \times \text{Volume} = \text{Constant.}$$

This law was first enunciated by Robert Boyle in 1662, and is known generally as Boyle's Law. It was stated, however, by the French physicist Mariotte fourteen years later, and was known on the Continent of Europe as Mariotte's Law.¹

It will be seen that, in order to investigate the phenomena presented by a gas at constant temperature, we must be able to measure its **volume** and its **pressure**.

The measurement of volume presents little difficulty, but that of **pressure** requires some explanation.

§ 2. MEASUREMENT OF ATMOSPHERIC PRESSURE

Before dealing with the measurement of the pressure of gases in confined volumes, the first point to realise is that the air exerts a considerable pressure.

¹ See Tait's *Properties of Matter*, Appendix IV.

THE BAROMETER

To show this, a long tube of glass about 1 metre in length is closed at one end; it is then filled with mercury, and inverted so that the unclosed end is beneath the level of a bath of mercury in a trough.




FIG. 95.—Simple Forms of Barometer

At once the mercury falls down a little way from the top of the tube, although no air or any other substance is admitted. The mercury does not run out of the tube entirely; a considerable column, about 75 cm. in height, remains in the tube, this column being supported by the pressure of the atmosphere. A Tube of this construction is called a **Barometer Tube**.

Consider the pressure at the point A in the tube (Fig. 95) at the same level as the *free surface* of the mercury outside. Above this point is a column of mercury h cm. high and of density ρ , exerting a pressure at the point A equal to $h\rho g$ dynes per sq. cm. Above the mercury inside the tube, the space B is vacuous, except for a minute trace of mercury vapour, the effect of which is negligible. The total pressure exerted at the point A is therefore that due to the column of liquid alone, that is Pressure inside tube at A = $h\rho g$ dynes per sq. cm.

Outside the tube, at the surface of the liquid, the only pressure acting is the pressure of the external atmosphere.

Now, at all points on the same level in a liquid, there is the same pressure, hence the pressure at A inside the tube is exactly equal to the pressure at the surface outside, since A is at the same level as the external surface.

The pressure at A is $h\rho g$; the pressure at the surface of the liquid outside is the atmospheric pressure.

Therefore the Atmospheric Pressure = $h\rho g$ dynes per sq. cm.

The Density of Mercury is approximately constant over the small range of temperature through which the atmosphere varies, and it is customary, therefore, to speak of the pressure in cm. of mercury. Strictly speaking, the expression of the pressure in this way should be in terms of the length of a column of mercury at 0°C. , but for ordinary purposes the variation of density is so small that the correction for temperature need not be applied. When required, it can be calculated without much difficulty (p. 142).

Further, the value of g is not uniform over the whole of the earth's surface, and a correction for latitude and height above sea-level should be introduced, to bring the height of the mercury column to what it would be at sea-level in latitude 45° . This correction is never required except in work of the highest degree of accuracy.

Since ρ and g may be considered approximately constant, the Atmospheric Pressure can be described as equivalent to a certain height h of mercury, this height being called the Barometric Height. It is the height of the column of mercury supported by the atmosphere in a barometer tube constructed as described.

The Meteorological Office now expresses atmospheric pressure in units that are multiples of the absolute C.G.S. unit, and some modern barometers are graduated so that the pressure can be read directly in such units.

The unit of pressure used in practice is called the bar, and is equal to one million dynes per sq. cm. Two smaller units are also used, the centibar and the millibar, being respectively one-hundredth and one-thousandth of a bar.

The bar is equivalent to a pressure of 75.01 cm. of mercury at 0° C. in latitude 45° .

A standard atmosphere (76 cm. of mercury) is rather greater than one bar, being equal to 1013.2 millibars.

COMMON TYPES OF BAROMETER

U-Tube Form.—For rough work a simple U-tube form of barometer is sufficiently good (Fig. 95). The free surface in A corresponds with the surface in the trough in the type already described. The tube is bent near the top, so that the two mercury surfaces of which the difference in level is to be measured are in the same vertical line.

These portions of the tube should be of fairly wide diameter, and equal to each other in bore, so as to avoid any error in the height observed due to surface tension effects. The heights are read on a scale usually engraved on the tubes themselves, and the Barometric Height is the difference between the levels B and A.

The accuracy obtainable with this form is not very great: the error in each reading may be as much as half a millimetre. As two readings have to be taken, the possible error is thus equal to one millimetre.

Fortin's Barometer.—This barometer is usually to be found in physical laboratories where accurate observation of atmospheric pressure is required. The apparatus does not differ from that of the simple type of barometer tube first described (p. 138), except in the manner of taking the readings of the two levels of mercury.

EXPT. 71. Reading Fortin's Barometer.—To determine the height of the mercury column two adjustments are necessary.

(i) **Adjustment of the Reservoir.**—At the bottom end of the tube the

mercury is carried in a leather bag, which can be altered in shape by a screw A (Fig. 96) bearing against its base. Fixed to the framework of the barometer is a small ivory point P which is the zero of the barometer scale.

The mercury surface is adjusted up to this ivory point by turning the screw A, the adjustment being made until the point and its image (reflected in the mercury) are just seen to touch *without any depression being visible in the mercury surface at the point* (Fig. 98). An extremely fine adjustment is thus rendered possible, if the mercury surface is suitably illuminated.

(ii) **Adjustment at the Upper Surface.**—At the upper surface the adjustment is not quite so simple. Round the glass tube is fitted a brass tube S, which is moved up and down by a milled head B (Fig. 96) at the side of the apparatus. This tube has the bottom edge cut so that the back D and front C of the bottom edge are exactly on the same level (Fig. 100). If the eye is placed *below* the level of these two, the back edge can be seen as well as the front. As the eye is raised, the back edge gradually shows less and less, until *when the eye is exactly level with the bottom of this movable tube, the back edge is just covered by the front edge.*

The eye should be placed in such a position that the back edge is just covered by the front edge in this way.

The brass tube should then be moved until the front edge is just on a level with the top B (Fig. 100) of the curve or 'meniscus' formed



FIG. 96.—Fortin's Barometer




FIG. 97.—Reservoir of Fortin's Barometer




FIG. 98.—Adjustment of Reservoir

by the mercury surface, keeping the eye exactly level with the edge of the tube as it moves.

NOTE.—If the eye is placed too high, the back edge will be covered by the front edge and the adjustment will be inaccurate. It is therefore important to *raise the eye until the back edge only just disappears behind the front*: this is the *only* test of accurate level.

When the movable tube has been adjusted accurately, the slightest movement of the eye downwards should bring the back edge of the

tube into view. When the eye is raised to the correct level again, the middle of the front edge should just be tangential to the surface of the mercury, a little light being seen through between the edge and the mercury surface at the sides.

The small brass tube carries a vernier scale the zero of which is level with the lower edge: this edge usually projects downwards just at the sides to avoid wear on the corner. The frame of the instrument carries a scale along which the vernier slides, and the reading of the vernier on this scale will give the position of the surface of the mercury. The scale is graduated only over a few centimetres near the top, but its zero is the ivory point in the lower reservoir. Hence the reading of the scale shown by the vernier gives the Barometric Height.

Read and record the Barometric Height as given by the scale and vernier.

Among other forms of barometer in common use is the recording U-tube type, which records the motion of the level in the lower tube by a float which is geared to a pointer. Another form is like Fortin's in construction, but has no adjustment of the reservoir, the divisions on the scale at the top being made not quite true inches or cm., in order to compensate for the alteration in level in the reservoir. Neither type is of any value for scientific work.




FIG. 99.—Barometer Scales and Verniers

The Aneroid Barometer.—A very convenient type of barometer, and one which, in its modern form, is capable of considerable accuracy, is the Aneroid. It consists of a metal vessel which is evacuated completely and hermetically sealed. Any variation in barometric pressure will deform this vessel somewhat, the deformation produced being proportional to the change of pressure (see Hooke's Law, p. 86). By levers and watch-gearing, this slight deformation is magnified so as to move a pointer over a scale, and




FIG. 100.—Adjustment of Vernier

by the motion of this pointer the variation in the Barometric Height can be obtained.

The apparatus is of course not *absolute*; it has to be calibrated by comparing its indications with a mercury barometer of the Fortin type, but when once calibrated, it can be relied on to give consistent readings for an almost unlimited time, and with well-made watch-gearing is quite free from 'back-lash'. As it can be constructed in a compact form, it is extremely

useful where portability is desirable, though if subjected to considerable variations of temperature its readings will not be quite accurate, as the elasticity of the metal vessel is affected by temperature.

EXPT. 72. Measurement of the Height of a Building using an Aneroid Barometer.—Take an Aneroid Barometer with a finely divided scale and observe the *difference* between its readings when at the bottom and at the top of a building. Let the observed difference be x cm. of mercury.

This difference corresponds with a difference of level in air equal to the height of the building h (say). For small differences in level the air may be treated as a fluid of approximately uniform density. The difference in pressure between the two points would then be $h\rho_1g$, ρ_1 being the density of the air.

This difference in pressure has been measured by the Aneroid Barometer, and found to be that exerted by a column of mercury x cm. long.

Thus $h\rho_1g = x\rho g$, where ρ is the density of mercury.

Neglecting slight variation of ρ_1 due to temperature, we may with sufficient accuracy take $\rho = 13.6$ and $\rho_1 = 0.00129$, both in gm. per c.c., and we obtain

$$h = x \cdot \frac{13.6}{0.00129} \text{ cm.}$$

Verify the result obtained by actual measurement.

Aneroid Barometers for mountaineering are often graduated directly in *feet* or *metres*.

CORRECTION OF A MERCURY BAROMETER FOR TEMPERATURE

The reading of a barometer requires correcting for temperature, in order to express the pressure of the atmosphere in cm. of mercury at 0°C. , or in dynes per sq. cm.

Let the Barometer Reading be H cm. This reading is really not obtained in cm. but in *scale divisions*, the scale divisions being cm. only at some temperature $t_0^\circ \text{C.}$ (usually 15°C.). If the temperature of the room is $t^\circ \text{C.}$, each division is of length $\{1 + b(t - t_0)\}$ cm., where b is the coefficient of *linear* expansion of the scale (usually of brass).

The *actual height* of the mercury column is thus

$$H_1 \text{ cm.} = H\{1 + b(t - t_0)\} \text{ cm.}$$

We have therefore a column of mercury of height H_1 cm. at a temperature $t^\circ \text{C.}$

It is required to find what height of mercury H_0 at 0°C. would exert the same pressure as this column H_1 exerts at $t^\circ \text{C.}$

The pressure of H_0 cm. of mercury at 0°C. is

$$H_0\rho_0g \text{ dynes per sq. cm.,}$$

ρ_0 being the density of mercury at 0°C.

The pressure of the column H_1 cm. high at $t^\circ \text{C.}$ is

$$H_1\rho_1g \text{ dynes per sq. cm.,}$$

ρ_1 being the density of mercury at $t^\circ \text{C.}$

We have to find H_0 such that

$$H_0\rho_0g = H_1\rho_1g.$$

Now $\rho_0 = \rho_1(1+at)$, where a is the coefficient of cubical expansion of mercury.

$$\text{Hence} \quad H_0 = \frac{H_1 \rho_1}{\rho_0} = \frac{H_1}{1+at},$$

so that substituting for H_1 in terms of the reading H we have

$$H_0 = \frac{H(1+b(t-t_0))}{1+at}.$$

When this value H_0 , the equivalent height of mercury at 0°C. , has been calculated, the pressure in dynes per sq. cm. can be obtained from the equation

$$P = H_0 \rho_0 g.$$

ρ_0 is 13.596 gm. per sq. cm., g is 981.18 dynes per gm. or cm. per sec. per sec. (in London).

$$\text{Hence} \quad P = H_0 \times 13.596 \times 981.18 \text{ dynes per sq. cm.}$$

A numerical example may be of assistance in explaining this method of correcting the Barometric Height for temperature.

A barometer with a brass scale reads 75.933 cm. at 18°C. The scale is graduated to be accurate at 15°C. What is the height of the barometer reduced to 0°C. ? Also what is the pressure of the atmosphere in dynes per sq. cm.?

The coefficient of linear expansion of brass = 0.000189 per 1°C.

The coefficient of cubical expansion of mercury = 0.000180 per 1°C.

$$\begin{aligned} H_0 &= \frac{75.933(1+0.000189(18^\circ-15^\circ))}{(1+0.00018 \times 18)} \\ &= \frac{75.933(1+0.000567)}{1+0.00324}. \end{aligned}$$

This can be written as

$$H_0 = 75.933(1+0.000567)(1-0.00324),$$

and then as

$$H_0 = 75.933(1+0.0000567-0.00324)$$

to a very close degree of accuracy, and we obtain

$$H_0 = 75.933(0.99682),$$

whence

$$H_0 = 75.690 \text{ cm.}$$

The pressure in dynes per sq. cm. in the example given is

$$\begin{aligned} P &= H_0 \rho_0 g \text{ dynes per sq. cm.} \\ &= 75.690 \times 13.596 \times 981.18 \\ &= 1,009,700 \text{ dynes per sq. cm.} \\ &\text{or } 1009.7 \text{ millibars.} \end{aligned}$$

EXPT. 73. Determination of the Atmospheric Pressure in Absolute Units.—Read the height of the barometer as in Expt. 71. Read the temperature of the barometer by means of the thermometer attached. Apply the correction for temperature as in the foregoing example, so as to find the pressure of the atmosphere in cm. of mercury at 0°C. , and deduce the pressure in absolute units.

Correction Table for Thermometer Reading.—It is convenient to calculate in this way the correction that has to be applied at each temperature from 0° to 25°C. , and to have this arranged by the side of the thermometer for reference. If the corrections are calculated for a reading assumed to be 76.0 cm., they will be sufficiently accurate to apply to all ordinary barometric readings without modification.

Formula for Correction at any Temperature.—The correction is expressed sometimes also in the form : deduct B cm. from the reading obtained, and from the remainder subtract C cm. for every degree above 0°C . A formula of this type can be worked out without much difficulty as an exercise on the equation

$$H_0 = \frac{H(1 + b(t - t_0))}{1 + at}.$$

This gives

$$H_0 = H(1 - bt_0 - (a - b)t).$$

B (above) is Hbt_0 , an approximately constant quantity, and is worked out for $H = 76$ cm.

C (above) is $H(a - b)$, and is also approximately constant; it is worked out on the supposition that $H = 76$ cm.

§ 3. PRESSURE OF A GAS IN A CLOSED VOLUME

The measurement of the pressure of a gas in a closed volume is usually achieved by means of a U-tube containing mercury. One side of this communicates with the chamber within which the pressure is to be measured, and the other is open to the atmosphere, Fig. 101.

The difference in level between the mercury surfaces in the U-tube indicates the difference between the pressure inside the space and the atmospheric pressure outside.

Thus, if the pressure inside the space C is P (cm. of mercury), and the atmospheric pressure (or Barometric Height) is H , the relation between P and H is given by

$$P = H + (B - A).$$




FIG. 101.—Measurement of Pressure

If B is below A , $(B - A)$ is a negative quantity, so that the pressure P is less than H .

If desired, the above expression can be rewritten as $P = H - (A - B)$ to suit this case : the two expressions are algebraically identical, and both perfectly general.

Sometimes, where it is desired to avoid reading the Barometric Height, the surface B is exposed to an evacuated chamber, when

$$P = B - A,$$

but this method is rarely used.

When the tube B is open to the atmosphere it is necessary to read the barometer as well as the difference in level between B and A before the pressure in the chamber C can be measured—this point must be noted specially. If during the course of an experiment the Barometric Height

varies, the quantity H used in the later readings will be different from that used earlier.

Strictly speaking, the barometer should be read *immediately after every observation* of corresponding values of B and A , though this is not required except in the most accurate work. The barometer should, however, be read both *before and after* any experiment on gases, and the difference distributed among the observations, according to the order in which they were made.

§ 4. VERIFICATION OF BOYLE'S LAW

To verify Boyle's Law (p. 137) a quantity of gas is enclosed in a glass tube, and is separated from the external atmosphere by a column of mercury. This mercury is contained in a flexible rubber tube, joining the tube containing the gas to a glass tube in which the level of the mercury exposed to the air can be seen; or, as an alternative arrangement, the two glass tubes may be sealed together, and both connected with a movable reservoir as shown in Fig. 102.

In the best forms of instrument the closed tube containing the air is graduated in c.c., a burette calibrated to the tap being convenient for this purpose. If this form of burette is not available, however, a square-ended glass tube of uniform bore may be used, the volume of air it contains being proportional to the length of tube between the level of the mercury and the square end.

The apparatus of the burette type is more convenient to adjust and to read than this simpler form. If great precautions are to be taken, it may be fitted with a drying tube, so that the air in the tube can be quite dry before closing the tap. It is important that the tap should fit very accurately, otherwise leaks will occur at high pressures, and the quantity of gas experimented on will be changed, thus vitiating all the readings.

EXPT. 74. Verification of Boyle's Law (Apparatus I).—The method of using this type of apparatus is as follows:—

The taps A and B are both opened, and mercury is forced up the burette to the tap B by raising the reservoir C . Air is then allowed to enter through these taps by lowering C again, till the burette is filled to D with air. About 30 c.c. of air should be admitted between B and D .

The tap A is closed, and the air all forced up into the drying tube again by raising C till the mercury reaches B .

The gas is left between A and B for a few minutes to dry it completely, and C is then lowered till the level of the mercury in the burette is at D again: by this means BD is filled with air which is practically




FIG. 102.—Boyle's Law (Apparatus I)

dry. B is then closed so as to confine a definite quantity of air between B and D, and the apparatus is ready for the experiment.

By raising and lowering C, various pressures can be exerted on the gas in the burette, and the volume of the gas will be altered until its pressure is equal to the pressure exerted on it.

The level of the mercury in the other tube (F) will be the same as the level in the reservoir C, since both surfaces are exposed to the atmosphere.

If for any position of the reservoir the level in the side tube is F and the level in the burette is E, the pressure on the gas inside the burette is given by

$$P = H + (F - E),$$

where H is the Barometric Height.

The levels F and E are read on a vertical scale placed immediately behind the tubes.

Pressures both above and below atmospheric can be used in this form of apparatus if the burette and the side tube are both long enough, the levels F' and E' being two corresponding values, when the pressure is below atmospheric. Such a case is obtained by lowering C to some position such as that shown dotted (Fig. 102).

The volumes V are the spaces between B and E, B and E', etc.

Adjust the level of the reservoir to several different heights, so that half the observations are made with pressures below and half with pressures above atmospheric.

Calculate the total pressure in the burette in each case (the barometer must be read before this can be done), and note also the *volume* of the gas in the burette under each pressure. Show that the product PV or Pressure \times Volume is the same for each adjustment made.

Arrange your observations thus—

$$\text{Barometric Pressure} = H = \dots \text{ cm.}$$

Reading in Side Tube F	Reading in Burette E	F - E	Total Pressure = H + (F - E) = P	Volume of Gas V	PV
		(Half these quantities will be negative.)			

Be careful not to add F - E in cm. to H measured in mm. Both H and (F - E) must be in cm.

If the tube enclosing the gas is not provided with a tap at the top it may be filled with gas and the experiment then carried out as already described. If, however, it is required to obtain observations at pressures below atmospheric, the tube will have to be heated considerably before closing with mercury.

The tube must be allowed to get quite cold again before the experiment is commenced.

Adjustment of the quantity of air in the tube in this way is not very easy, and frequently leads to fracture of the tube: *it should never be attempted by the student.*

Where the apparatus with the burette and tap is not available, it is often preferable to use two forms of apparatus for verification of Boyle's Law instead of adjusting the quantity of air as described above. One form of apparatus may be used for pressures above, and the other for pressures below atmospheric. It is advantageous to use apparatus of these two forms even where the first type described is also used. A greater *total* variation of pressure is possible when two such forms of apparatus are used than with the single form described, and thus the law is verified over a wider range. The student is also made familiar with different forms of apparatus which may be used for the measurement of gas pressure. □ □

EXPT. 75. Verification of Boyle's Law, Apparatus II (for Pressures above Atmospheric Pressure).—The present apparatus is used for verifying Boyle's Law for cases in which the pressure is *greater than* the pressure of the atmosphere.

The air to be experimented on is contained in the glass tube A. The lower part of this tube is in connection with a reservoir of mercury C and a pressure tube B. A certain mass of air is enclosed in A at a pressure equal to the atmospheric pressure plus the pressure due to difference of levels in A and B. The atmospheric pressure must be found by reading the barometer; let it be H cm. of mercury. The volume of the gas may be taken to be proportional to AE measured on the scale attached to the apparatus. The position of the top of the tube A containing the gas is noted on the scale.

FIG. 103.—Boyle's Law (Apparatus II)

If we raise the reservoir the pressure on the air in A is increased and the volume diminished.

The pressure is equal to the pressure of the atmosphere plus the pressure due to the column of mercury FE, that is,

$$P = H + (F - E).$$

The new volume is equal to V, and is proportional to AE.

In the same way determine the values of P and V corresponding to other positions of the mercury reservoir.

Calculate the values of the products $P \times V$. These should be constant if Boyle's law is obeyed.

Enter the results in tabular form as for Apparatus I (p. 146).

Plot a curve showing the relation between the pressure (as ordinate) and the volume (as abscissa). This should be a rectangular hyperbola.

EXPT. 76. Verification of Boyle's Law, Apparatus III (for Pressures below Atmospheric Pressure).—This third type of apparatus used for the verification of Boyle's Law enables us to work over a wide range from atmospheric pressure *downwards*.

A very convenient form consists of a uniform glass tube, which can be raised or lowered inside an iron tube filled with mercury. The iron tube widens at the top into a bowl-shaped vessel, this widening enabling the inner tube to be raised or lowered considerably, without causing any *large* change in the level of the external surface of mercury.

The pressure of the gas in the inner (glass) tube is less than atmospheric pressure, by the height to which the mercury in the inner tube stands above the level of the mercury outside.

This is measured by adjusting a steel pin, fixed to a vertical metre scale (Fig. 104), until its point just touches the surface of the mercury in the bowl.

The height of the column inside the tube is given by the reading B (Fig. 104) *plus* the length of the pin (x cm.). This is the amount by which the pressure of the gas inside is *less* than the atmospheric pressure.




FIG. 104.—Boyle's Law
(Apparatus III)

The volume of the gas is proportional to the length of tube it fills, if the bore is uniform.

A mark on the neck of the tube just beneath the tap represents the 'equivalent top' of the tube, or where the top of the tube would be if it were of uniform section all the way up, and of the same volume as the actual volume.

The distance between this mark and the level of the mercury in the tube is proportional to the *volume* of the gas enclosed.

Depress the glass tube, with the tap *open*, until the top of the tube stands about 15 cm. above the level of the mercury in the trough.

Close the tap carefully, pressing it inwards gently whilst turning it, and *do not touch it again during the whole of the experiment*, otherwise more air will be admitted into the tube, and the mass of gas used will thus be altered.

The pressure of the air enclosed in the tube is now equal to the atmospheric pressure.

Adjust the metre scale so that the point of the steel pin just touches the surface of the mercury in the bowl, and find the reading on the scale, level with the 'equivalent top' of the tube.

Raise the tube until the mercury level inside the tube is above the zero of the metre scale. Adjust the pin until it just touches the mercury surface in the bowl, and take the reading (A) on the scale level with the 'equivalent top' of the tube; also read the level B of the surface of the mercury in the tube.

Raise the tube a few centimetres at a time and repeat readings A and B, *taking care to adjust the pin until it touches the mercury in the bowl before taking each set of readings.*

Continue this until, if the tube were raised any higher, there would be no mercury left in the bowl.

At least *six* sets of observations should be taken, distributed uniformly over the range of pressures used.

Depress the tube again to the first position in which readings were taken. If the first readings are not repeated, some air must have leaked in through faulty closing of the tap, and the experiment must be repeated after seeing that the tap is properly closed and air-tight.

Read the barometer and express the pressure of the atmosphere in *centimetres* of mercury.

Tabulate the results of the observations :—

Length of pin, $x = \dots$ cm.

Reading A	Reading B	Pressure P = $\text{Atm.} - (B + x)$	Volume V = $A - B$	PV

The values in the last column should be constant.

Plot a graph taking the values of the pressure as ordinates and the values of the volume as abscissæ. The curve should be a rectangular hyperbola.

It is also instructive to plot a graph showing the relation between the density of the gas and its pressure. Take the values of the pressure as ordinates and the reciprocals of the volume as abscissæ. This graph should be a straight line.

In this way it is possible to verify the law of Boyle that the volume of a fixed mass of gas varies inversely as the pressure when the temperature is kept constant.

The law of Boyle is equivalent to saying that the product PV is constant at constant temperature. This applies to a *fixed mass* of gas, and, in fact, the product PV is directly proportional to the mass of gas considered. For *unit mass* (say 1 gram) of gas this product will have some definite value at a particular temperature. Let the density of the gas at the chosen temperature be ρ , then by definition $\rho = 1/V$, and consequently V may be replaced by $1/\rho$ and Boyle's law stated in the form

$$P/\rho = \text{a constant (at the temperature).}$$

The results of experiments on gases at *different temperatures* are discussed on p. 285, where it is shown that the laws of Boyle and of Charles may be combined in a single expression.

CHAPTER XI

SURFACE TENSION

§ 1. DEFINITION OF SURFACE TENSION

THE surface of a liquid acts everywhere as though it were in tension ; the analogy of a stretched rubber membrane is frequently used to illustrate this, but there is one important difference to be noted. If a rubber membrane is stretched, the tension exerted across any line in the membrane is increased as the extension is increased, while no such increase of tension occurs in the case of a liquid surface.

The tension in dynes exerted across unit length of any line imagined in the surface of a liquid is called the Surface Tension of that liquid. It is measured in dynes per cm.

Recent work has emphasised the view that in any interface between a solid, a liquid, or a gas there is a quantity of energy associated with each unit of area. This surface energy may be divided into a thermal part and a mechanical part, the latter corresponding to surface tension.

The surface tension depends not only on the liquid itself but also on the medium on the other side of the surface. Thus the surface tension of a mercury surface exposed to air is entirely different from the surface tension in a surface between mercury and water. The effect of the second medium is extremely marked if the mercury is put in a weak solution of potassium dichromate. The mercury then loses its 'mercurial' character and exhibits a sluggishness entirely different from its mobility when in contact with air.

Whenever we speak of '*the* surface tension' of a liquid, therefore, it must be understood that we refer to the surface tension in a surface bounded by the liquid and by *air*.

§ 2. EFFECTS OF SURFACE TENSION

CAPILLARITY

When a fine tube is filled with liquid and its lower end is placed beneath the surface of some of that liquid in a large vessel, at first the liquid will flow down and out of the tube, but eventually a column

of liquid of measurable height will be left in the tube, projecting above the level of the liquid in the large vessel.

This column of liquid is supported by the tube as a result of surface tension of the liquid, and the surface tension can be determined from the height of the liquid column and the dimensions of the tube.

Let the radius of the tube be r cm. and the surface tension of the liquid be T dynes per cm. At the line where the liquid surface and the tube meet there is exerted at right angles to their line of contact a force T dynes on each centimetre of that line.

This force is exerted on the wall of the tube by the surface of the liquid, and acts in the liquid surface at right angles to the line of contact. Thus, if the tangent to the liquid surface at this line is at an angle α with the side of the tube (Fig. 105), we have a force acting at an angle α to the vertical, the magnitude of this force being T dynes per cm.




FIG. 105.—Force due to Surface Tension

This force which is acting at all points at an angle α to the vertical may be resolved into vertical and horizontal components. We are concerned with the vertical component only since at any point the horizontal component is balanced by the molecular forces in the wall. There will thus be a total vertical force equal to $2\pi rT \cos \alpha$ exerted by the liquid on the tube across the line of contact, this force being exerted *downwards* by the liquid on the tube.

There is therefore an *upward* force of this magnitude exerted by the tube on the liquid since action and reaction are equal and opposite, and the tube exerts forces on the liquid, across the line of contact, of length $2\pi r$, such that the total upward force exerted on the liquid by the tube is

$$2\pi rT \cos \alpha \text{ dynes.}$$

This force supports the column of liquid raised above the level outside, hence, if we can find the weight of the liquid column, its weight must be equal to the above force.




FIG. 106.—Effects of Surface Tension of Mercury

Weight of Column raised.—The column is cylindrical up to the base of the meniscus. Above this its volume is approximately the difference between a hemisphere of radius r and the circumscribing cylinder.

If the bottom of the meniscus is at a height h above the free surface outside, we have

$$\text{Volume of column raised} = \pi r^2 h + \frac{1}{3} \pi r^3 = \pi r^2 \left[h + \frac{1}{3} r \right].$$

Let $h + \frac{1}{3}r$ be indicated by h' .

Then if ρ is the density of the liquid, the *Mass* of the column raised is $\pi r^2 h' \rho$ grams, and its *Weight* is $\pi r^2 h' \rho g$ dynes.

Thus

$$2\pi r T \cos \alpha = \pi r^2 h' \rho g,$$

whence

$$T = \frac{h' r \rho g}{2 \cos \alpha}.$$

For all liquids which *wet* the surface, $\alpha = 0$, and therefore $\cos \alpha = 1$, so that, in this case,

$$T = \frac{h' r \rho g}{2}$$

The chief exception is mercury, for which α is greater than 90° , so that $\cos \alpha$ is negative; thus h is negative in the case of mercury, due to the negative value of $\cos \alpha$.

EXPT. 77. Determination of the Surface Tension of Water by the rise in a Capillary Tube.—Clean a capillary tube carefully with caustic soda and then with nitric acid,¹ washing out the nitric acid with considerable quantities of water. Place the tube in a *thin* glass beaker with vertical




FIG. 107.—Rise of Liquid in Capillary Tube

sides containing water, depressing the tube so as to fill it with water and then raising it till a column of water is supported in the tube. The water should never be *sucked* up the tube. Tap water should be used rather than distilled water, as the surface of the latter is often contaminated with a film of grease.

Measuring the Height of the Column.—This may be measured directly with dividers, setting the dividers so that when one point is just at the surface of the liquid in the beaker the other is at the level of the meniscus in the tube.

Frequently, however, a cathetometer microscope is used. The microscope is focused first on the meniscus, then on the point of a pin which is just *not* touching the water, the microscope being set so that when the images of the pin and its reflection are viewed through it, the cross-hair is exactly between them. The vertical distance through which the microscope has to be raised between these two positions, is measured on the cathetometer stand of the microscope, and h is thus obtained quite accurately.

Measuring the Bore of the Tube.—The bore of the tube is measured by drying the tube, drawing a thread of mercury into it, and measuring the length of the thread while in the tube. The thread is then run out into a weighed watch-glass and its mass determined. From this mass the radius of the tube may be calculated, assuming a knowledge of the density of mercury.

Mass of mercury thread = $\pi r'^2 l' \rho'$, ρ' being the density of the mercury and l' the length of the thread.

In measuring the length of the thread, it will be noted that the ends of the mercury are not flat, but curved. Measure l the length of the *cylindrical* part of the mercury thread and also $l+x$ the *total* length of the




FIG. 108.—Mercury Thread

¹ Caustic soda is used first to remove any grease in the tube; it is used *before* the acid because the latter can be washed out more easily with water. To avoid cleaning an old capillary new capillaries may be drawn out after heating a clean glass tube with a blowpipe.

thread. Find by subtraction x the length of the *two* curved ends together. Then the volume of the mercury thread may be taken as $\pi r^2 l + \frac{2}{3} \pi r^2 x$, or $\pi r^2 \left[l + \frac{2}{3} x \right]$. The volume of the curved ends is obtained on the *assumption* that the ends are hemispheroidal (oblate like an orange).

The quantity $\left[l + \frac{2}{3} x \right]$ takes the place of the quantity denoted by l' in the formula on p. 152.

The tube can be tested to see whether the bore is uniform or not by measuring the thread in different positions. This might be done before carrying out the rest of the experiment, any tube which exhibits marked inequalities in the bore being discarded.

Another method is to cut off the tube at the place where the meniscus stood, and to mount this in a stand so as to view it in section with a microscope. The size of the image of the hole as viewed in the microscope is measured on a micrometer scale in the focal plane of the eye-piece. This micrometer is then calibrated by viewing a standard scale, and finding the number of divisions of the micrometer eye-piece which correspond with one millimetre of the standard scale, the scale being viewed with the microscope in the same adjustment as when viewing the tube section. (See p. 22.)

This method may not be as accurate as that in which the mercury thread is used, but it is more suitable for an elementary laboratory. It is good practice to draw out capillary tubes from a glass tube that has previously been well cleaned. Capillaries which have not the same diameter in different directions should be rejected.

The experiment should be performed for 4 tubes of different bore, and h should be shown to be inversely proportional to r .

If any liquid other than water be used, its density must be determined before T can be calculated.

PRESSURE DUE TO CURVED SURFACES

Pressure inside a Soap Bubble.—Inside a soap bubble, the pressure is greater than atmospheric by a small quantity p . The bubble is assumed to be spherical and of radius r . Considering the equilibrium of the upper hemisphere, this excess pressure acts on the upper hemisphere, and produces a resultant *upward* force on the hemisphere of magnitude $p\pi r^2$, tending to blow the upper and lower hemispheres apart.




FIG. 100.—Pressure in Soap Bubbles

The two hemispheres are kept together by the surface tension forces acting in the *two* surfaces of the film round the line of contact, and the bubble expands until the resultant of these forces just neutralises the resultant disruptive force $p\pi r^2$.

The line of contact between the hemispheres in *each* surface is of length $2\pi r$, and hence the *total* force due to surface tension keeping the hemispheres together is $2(2\pi rT)$, since the film has two surfaces.

Thus

$$4\pi rT = p\pi r^2,$$

or

$$T = \frac{pr}{4}.$$

EXPT. 78. Surface Tension of Soap Solution by Pressure in Soap Bubble.—Blow a small bubble on the end of an apparatus as depicted in Fig. 110, by gently pushing a glass rod A into the rubber tube B attached to the side.

By means of a travelling microscope with vertical and horizontal scales, measure the dimension of the bubble across a horizontal diameter,




FIG. 110.—Apparatus for Pressure in Bubble

using the vertical cross-hair of the microscope adjusted tangentially, first on one side, then on the other, of the image of the bubble.

Measure the difference in height h between the levels of the water in the tubes C and D, using the vertical scale of the cathetometer.

Then the pressure excess inside the bubble over the atmospheric pressure is

$$p = h\rho g \text{ dynes per sq. cm.}$$

ρ = density of water in bend of U-tube ; r = radius of bubble in cm. found from the diameter measured already.

Calculate the value of the surface tension in dynes per cm. from the equation

$$T = \frac{pr}{4}.$$

Make observations on two or three bubbles of different sizes.

Soap Solution.—The following method for preparing a soap solution is based on the directions given by Sir Charles Boys in *Soap-Bubbles and the Forces which Mould Them*. Fill a clean well-stoppered bottle three-quarters full with distilled water or the softest water obtainable. For each litre of water add 25 gm. of sodium oleate (Plateau) and leave for a day, when the soap will be dissolved. Add 300 c.c. of pure glycerine for each litre. Shake well, and let the stoppered bottle remain for a week in a dark place. Draw off the *clear* liquid by means of a siphon, leaving behind the scum collected at the top. Add two or three drops of liquid ammonia, and carefully keep the solution in a stoppered bottle in a dark place. In making the liquid do not warm or filter it, and never put any used liquid back into the stock.

MEASUREMENT OF SURFACE TENSION BY MEANS OF A BALANCE

The pull due to surface tension is so great that it may be measured directly by means of a sensitive balance. For this purpose a balance formed from a *long* spiral spring as described on p. 97 may be used. Sometimes an ordinary gravity balance is employed, some form of hydrostatic balance such as that shown in Fig. 24, p. 44, being convenient. A simple torsion balance due to Dr. Searle of Cambridge has some advantages. In the apparatus (Fig. 110A) the torsion wire is



FIG. 110A.—Searle's Torsion Balance
(By courtesy of Messrs. W. G. Pye & Co.)

horizontal, its ends being fixed by adjustable clamps to the frame of the instrument. To the centre of the wire is attached a light metal beam, one end of which serves as a pointer that moves over a graduated scale. The other and shorter end of the beam carries a counterpoise, the position of which can be adjusted. A small scale-pan can be suspended from a fixed point near the end of the longer arm, and in some experiments it is convenient to calibrate the scale by placing weights in this pan. The height of the frame which carries the torsion wire can be adjusted by means of a vertical sliding rod, and a fine adjustment is possible by using a levelling screw at one corner of the base.

EXPT. 78A. Surface Tension of a Soap Film.—A frame of wire having two vertical sides separated by a distance l cm. is suspended from the scale-pan of the balance. The exact shape of the remainder of the frame does not affect the result, but it is convenient to use a frame in the form of a complete rectangle so as to ensure two *parallel* sides that may hang

in a vertical plane. A soap film is formed over this frame either by lowering the whole frame into the soap solution contained in a beaker, or by raising the beaker until the upper wire is immersed. The film is allowed to drain for a few seconds, and then the counterpoise required to give equilibrium is found *while the soap film is present*. The film is then broken and the *new* value of the counterpoise is found. If m gm. is the difference between the two values of the counterpoise, mg dynes represents the pull due to surface tension. Since the soap film has two sides we may take $2l$ cm. as the length of the surface contact between the film and the liquid. Hence the surface tension is given by the equation

$$2lT = mg \text{ dynes.}$$

Calculate the surface tension in dynes per cm.

The measurement of the surface tension of a clear liquid, such as water, may be made by using a clean glass plate (a microscope slide) fixed in a clip and suspended from one arm of a balance. The object in view is to measure the pull on the lower horizontal edge of this plate when it is just touching the surface of the liquid. Both the beaker and the glass plate must be carefully cleaned by washing first with caustic potash solution and then with clean water. This determination is more difficult than the measurement made with a soap film, because of the uncertainty in the value of the upthrust when the edge of the plate is slightly below the level of the liquid.

EXPT. 78B. Surface Tension of Water by means of a Gravity Balance.—Suspend a clean glass plate from one arm of the balance provided so that the plane of the plate is vertical and its lower edge is horizontal. Place weights in the other pan of the balance so as to produce equilibrium. A beaker of clean water is brought up gradually below the plate until contact is just made between the water surface and the lower edge of the glass. A convenient way of lifting the beaker is by supporting it on an adjustable table which can be raised slowly by a screw motion. When the edge of the plate touches the water surface, a jerk of the pointer of the balance is observed because of the downward pull due to surface tension. Additional masses are now added carefully to the second pan of the balance until contact between water and glass is broken. Assuming that no correction is needed for the upthrust of the liquid, the weight mg dynes of the additional mass m may be equated to the pull of surface tension. If l is the length and t the breadth of the plate, the force acts over a length $2(l+t)$ cm., and if T is the surface tension we find

$$2(l+t)T = mg \text{ dynes.}$$

From this equation T is found in dynes per cm.

The pull to be measured may be increased by having several glass plates mounted side by side in a frame, but *not* in contact with one another.

EXPT. 78C. Surface Tension of Water by means of Searle's Torsion Balance.—The method of procedure is somewhat similar to that described in the last experiment, but it will be convenient to find *first* the position of equilibrium of the balance when the lower edge of the plate is exactly level with and touching the surface of the water. It may be necessary to change the position of the counterpoise so as to get the pointer on the scale. The levelling screw at the base may be used in making the final adjustment.

The beaker of water is then removed and the plate allowed to dry, or it may be dried very carefully with filter paper. Masses are then placed in the scale-pan so as to give the same reading of the pointer as before. If m gm. is the mass added to the scale-pan, the surface tension T is found from the equation

$$T = \frac{mg}{2(l+t)} \text{ dynes per cm.,}$$

where l cm. is the length and t cm. is the breadth of the plate.

THE ANGLE OF CONTACT BETWEEN MERCURY AND GLASS

When liquid mercury is in contact with glass, there is a finite angle between the tangents to the two surfaces, and for clean surfaces the




FIG. 110B.—Determination of Angle of Contact

angle is large (approximately 135°) so that in a narrow tube the mercury surface is depressed (Fig. 106). This angle of contact α may be even larger than 135° for a freshly formed interface, but the value tends to diminish with the time that has elapsed since the surfaces were prepared. It is difficult to obtain a perfectly clean and *dry* glass surface, the simplest plan being to wash first with potash solution followed by clean water, and then to dry the glass in a desiccator. The mercury used should be taken from the *interior* of a supply of pure liquid, and as the surface changes on exposure to the atmosphere of a laboratory the first observation should be made as soon as possible. The angle α may be determined by a simple method, the details of which have been worked out by the staff of the physical laboratory in St. Andrews.

EXPT. 78D. Determination of the Angle of Contact.—Place about 300 gm. of clean mercury in a small clean dish about 4 cm. in diameter. Fix the upper end of a clean dry microscope slide in a special clamp so that its lower end may dip into the mercury. This clamp is attached to an apparatus (Fig. 110B) arranged so that the plate can be rotated about a horizontal axis which is adjusted so that the *axis of rotation* shown by the dotted line *passes through the surface of the mercury*. With this arrangement the section of the plate in contact with the mercury surface remains stationary while the inclination of the plate is altered. The angle through which the long edge of the plate is rotated can be measured by a pointer P moving over a circular scale S.

The plate is rotated until the surface of the mercury is horizontal on one side of the plate as on the left in Fig. 110c. The angle α is then the required angle of contact. Since α cannot be measured accurately, the



FIG. 110c.—Angle of Contact

plate is rotated through an angle β until the mercury is horizontal on the other side as on the right of the diagram. Then $\alpha = 90^\circ + \beta/2$, where β can be accurately found. (Prove this expression.)

In order to test when the plate is correctly adjusted in each of the above positions, the following method may be used. A straight line




FIG. 110d.—Plan

inclined at an angle of about 20° to the vertical is drawn on a vertical screen which is brightly illuminated. The image of this line in the mercury surface can be seen without the observer having to change his position. In general, the image will be curved where it approaches the plate owing to the curvature of the surface (Fig. 110n). This curvature will, however, disappear when the mercury is horizontal up to the edge of the plate.

Rotate the plate away from the screen and observe the image of the line on the *near* side of the plate. In position *a* the image will be curved, say to the right; in position *b* it will be straight; while in position *c* in Fig. 110e it will be curved to the left owing to the change in the curvature of the mercury surface where it meets the plate. Rotate the plate until position *b* is accurately found, and note the reading of




FIG. 110e.—Three positions of plate

the pointer. Then rotate the plate towards the screen and observe the image on the *far* side of the plate, adjusting until the image is once again straight up to the edge of the plate. Determine the angle and evaluate. Two or three determinations should be made and the mean value taken. It is also of interest to find how the angle of contact varies with lapse of time.

PART I

ADDITIONAL EXERCISES ON PROPERTIES OF MATTER

1. Draw a sector of a circle (radius 15 cm.), containing an angle of 150° , measure its area with the planimeter, and verify the result by means of the balance.
2. Draw an ellipse of major axis 20 cm. and minor axis 10 cm. and measure its area with the planimeter.
3. Find the area and density of the given plate by weighing it in air and water and measuring the thickness.
4. Find the average area of cross section of the given wire by means of a metre scale and a hydrostatic balance.
5. Find the length and specific gravity of a given tangle of wire, using a hydrostatic balance and a micrometer screw.
6. Find the specific gravity of a solid by weighing it in a liquid whose specific gravity is given.
7. Weigh the given solid in air, in water, and in the given liquid. Deduce the specific gravity of the metal and of the liquid.
8. Make a solution of sugar and water which contains accurately 10 per cent by weight of sugar, and determine the specific gravity of the solution.
9. Prepare a solution of common salt in water containing 15 gm. of salt in 100 gm. of solution and find its density.
10. Find the density of a liquid which is denser than water and does not mix with it, by preparing a salt solution of equal density and determining the density of this solution.
11. Calibrate the given burette by means of a balance.
12. Find the internal volume of a definite length of the narrow bore tube provided, and calculate the mean internal diameter.
13. Measure the radius of the sphere provided by means of the spherometer, find its weight and deduce the density of the material.
14. A body is supported on an inclined plane by a force acting parallel to the plane. Plot a graph showing the relation between the magnitude of the force and the height of the plane.
15. Find the mass of the roller supplied, using an inclined plane.
16. Support a metre scale from various points along its length, and balance it by hanging weights on the shorter side. Deduce the weight of the metre scale.
17. Find the angle of static friction between the given surfaces.
18. Find the velocity ratio and the force ratio for the given machine and deduce the efficiency.
19. A bar is supported at its ends and loaded at its centre. Plot a curve showing how the depression of the centre varies with the load.
20. Plot a curve showing the relation between the angle of twist and the length of wire twisted, when a given couple is applied to the end of the wire.
21. A ball is projected horizontally with a given velocity by allowing it to roll down one quadrant of a circle. Plot a curve showing the relation between the horizontal range and the height of the point of projection.
22. Find the relation between the distance traversed and the time when a body starts from rest and moves with uniform acceleration, using Atwood's machine.
23. Find the combined mass of the two weights and the pulley of an Atwood's machine, given $g = 981$ cm. per sec. per sec.
24. Find the relation between the distance traversed and the time when the given body rolls down an inclined plane, starting from rest.

25. Prove that the acceleration of a body rolling down an inclined plane of given length is proportional to the difference in height between the ends.

26. Plot a graph showing how the acceleration of a body rolling down an inclined plane varies with the height of the plane.

27. Calculate the kinetic energy of the given body when it is rotating with unit angular velocity about its axis.

28. Plot a curve showing the relation between the time of swing of a simple pendulum and the square root of the length. Deduce a value of g from the results.

29. Find the length of the simple pendulum supplied by determining the time of swing, assuming $g = 981$ in C.G.S. units. Adjust the length so that the time of one complete swing is 2 sec.

30. Plot a curve showing the variation of period with length for a simple pendulum, and deduce the length of a 'quarter seconds' pendulum, that is a pendulum requiring *half* a second to swing both ways.

31. Find the period of swing of a pendulum 20 inches long, without actually using one of that length.

32. Plot a graph showing the relation between the length of the simple pendulum and (a) the time of swing, (b) the square of the time of swing. Deduce the value of g , the acceleration due to gravity.

33. Plot a graph showing how the time of oscillation of the given torsion pendulum varies with the distance from the axis of the added symmetrical load.

34. A thin lath is fixed horizontally at one end and loaded at the other. Plot a curve showing how the time of vibration varies with the load.

35. From observations on the oscillations of a loaded spring prove that the square of the time of oscillation divided by the load is approximately constant.

36. The two ends of a heavy bar are connected by a string whose middle point is attached to a fixed support. Find how the time of oscillation of the system under gravity depends on the length of the string, when the bar remains in the same vertical plane during the oscillation.

37. Verify Boyle's law by pouring mercury into the open limb of a U-tube the other limb of which is closed.

38. A U-tube contains mercury in the bend and air in the closed limb; use it to find the height of the barometer.

PART II

SOUND

NOTES ON SOUND

It is well to distinguish between two uses of the word **sound**, which may be applied either to the definite sensation that is produced by stimulating the ear or to the external physical cause of this sensation. In this book we are concerned mainly with the *objective* use of the word, as distinct from the *subjective*. Here again a distinction may be drawn between the vibrating motion of the source of sound and the wave-like disturbance of the air or other medium acting upon the mechanism of the ear. Every musical note has three subjective characteristics—*pitch*, *loudness*, and *quality*; and to these correspond three physical or objective characteristics,—*frequency* (sometimes called 'physical pitch'), *intensity*, and *wave-form* respectively. There is, however, some evidence to show that the subjective quality described as pitch depends to a certain extent on loudness as well as on frequency.

By **frequency** is meant the number of complete vibrations (or *cycles*) in unit time (1 second), so that frequency is the reciprocal of **period** (p. 123), and is expressed in 'cycles per second' (c.p.s.). In scientific work it is often convenient to take the frequency of middle C as 256 c.p.s. (pp. 164-165). In 1939 an International Conference agreed on a standard of musical pitch, and assigned to the note A (or *a'*) in the treble clef the frequency of 440 cycles per second, at a temperature of about 20° C. (68° F.). On the diatonic major scale this would correspond to a frequency for middle C equal to $\frac{3}{5} \times 440$, or 264 c.p.s.

In recent years great progress has been made in the subject of musical acoustics, and it is now possible to measure not only the power, expressed in watts (p. 76), required to drive the source, but also the power actually radiated as sound. For further information reference may be made to *The Physics of Music*, by Alexander Wood (Methuen, 1944), where the relation between loudness and intensity (power transmitted across 1 sq. cm.) at the point considered is clearly treated.

CHAPTER I

INTRODUCTORY THEORY

§ 1. VELOCITY : FREQUENCY AND WAVE-LENGTH

SOUND is propagated through any material medium as a wave-motion, the disturbance being produced by the sounding body and causing the sensation of sound when it reaches the ear. Most of the simple experimental determinations in sound are either determinations of the velocity of sound in different media or else determinations of the associated quantities, frequency, and wave-length.

The Velocity of Sound varies with the medium through which it travels. It can be shown that the velocity with which sound is propagated through a medium of elasticity E and density ρ , is given by the equation

$$V = \sqrt{\frac{E}{\rho}}.$$

E is the modulus of elasticity corresponding with the particular strain caused by the wave-motion.

EFFECT OF TEMPERATURE ON THE VELOCITY OF SOUND IN A GAS

The modulus of elasticity concerned when a sound wave travels through a gas, is equal to γP , where γ is the ratio of the specific heats of the gas (a constant) and P is its pressure. Hence the velocity, V , of sound in the gas is equal to $\sqrt{\gamma P/\rho}$, where ρ is the density.

Now $P/\rho = RT$ (see section on Heat, p. 285; therefore V , the velocity of sound in the gas, is equal to $\sqrt{\gamma RT}$, or is proportional to the square root of the absolute temperature T . Let T_0 be the absolute temperature of the ice-point, 0°C .

If α the gas coefficient is taken as $\frac{1}{273}$, $T_0 = 273^\circ$ and

$$T/T_0 = 1 + \alpha t,$$

where t is temperature in degrees centigrade.

$$\therefore \frac{\text{Velocity of Sound at } t^\circ \text{C}}{\text{Velocity of Sound at } 0^\circ \text{C}} = \sqrt{\frac{T}{T_0}} = \sqrt{1 + \alpha t},$$

or

$$V_t = V_0 \sqrt{1 + \alpha t}.$$

When t is not large, this is written as

$$V_t = V_0 \left(1 + \frac{1}{2} \alpha t\right);$$

and hence the velocity of sound at any temperature can be calculated if the velocity at 0°C. is known.

PITCH AND FREQUENCY

The musical pitch of a note depends on the number of vibrations made by the sounding body in one second or the vibration frequency of




FIG. 111.—Musical Scale. From Barton's Sound



FIG. 113.—Wave-Length



FIG. 112.—Velocity and Frequency

the note. The note called middle C on a piano is taken to correspond with a vibration frequency of 256. This is called the *scientific pitch*

of middle C. The middle C of *concert pitch* now adopted (p. 162) has a frequency considerably above this. Other standards of pitch formerly used were some above and some below this scientific standard.

The reason for the choice of 256 as middle C in scientific work is in order that the number of vibrations corresponding with any C shall be a whole number, 256 being equal to 2^8 (see below).

Musical Interval depends on the ratio of the vibration frequencies of the two notes, the ratios for various intervals being :

octave	.	.	1 : 2	minor third	.	.	5 : 6
fifth	.	.	2 : 3	major tone	.	.	8 : 9
fourth	.	.	3 : 4	minor tone	.	.	9 : 10
major third	.	.	4 : 5	semitone	.	.	15 : 16

The Relation between Velocity, Frequency, and Wave-length.—Let the velocity of sound in any medium be indicated by V cm. per sec. Choose two points A and B (Fig. 112), such that their distance apart is V cm.

At A an observer is stationed, and at B a body is set into vibration, emitting a note the vibration frequency of which is n .

The time taken for the first wave to reach A will be one second, since the distance AB is equal to V ; thus the observer at A will just be receiving the first wave as the n th wave is emitted from B.

Between A and B there will thus be n waves moving towards A. If each wave is of length λ (Fig. 113), then the length AB must be equal to $n\lambda$, and we obtain the important result that

$$V = n\lambda.$$

§ 2. RESONANCE

THE PRINCIPLE OF RESONANCE

If two neighbouring bodies have identical frequencies and one of them is set in vibration, the other will take up a rhythmic vibration due to the vibration of the first. This vibration, which is communicated to the second body, may attain considerable amplitude ; so that if the first body is stopped the second may continue to vibrate for some time afterwards.

This principle is not limited to sound but is common to all forms of vibratory motion. It can be understood readily by considering a simple case, such as that of two accurately attuned tuning-forks. One of these is set in motion, and wave disturbances from it reach the other. The prongs of the second fork are alternately pressed away from and drawn towards the first fork, in consequence of the alternate com-

pressions and rarefactions reaching the prongs through the air. These occur exactly in step with the natural motion of this second fork, which is just starting to spring back into its mean position after the first pressure wave, when the rarefaction commences, its backward motion being thereby assisted. The fork moves beyond its equilibrium position under its own momentum and this assisting force, and is just turning




FIG. 114.—Stationary Vibrations

to move forward again when the next pressure wave arrives ; under the pressure wave it is *urged* forward instead of being merely allowed to move forward under its own elastic forces. Thus every vibration of the fork is assisted by a force exerted by the air near to it, and the succession of light impulses, insignificant when considered singly, has a cumulative effect which results in the fork taking up a vibration of considerable amplitude. All other cases of resonance can be explained in a similar way.

Numerous examples of periodic motion have been given in Part I (pp. 126-136). When a system which can execute a free vibration in one particular way, is acted on by a periodic force, it will be constrained to make forced vibrations ; resonance will occur if the frequency of

the applied force is in approximate agreement with the frequency of free vibration. The effect is cumulative, and may become excessive, but in general cannot be increased indefinitely because of frictional forces. This phenomenon is important not only in mechanical but also in electrical oscillations.

STATIONARY VIBRATIONS

When two wave-trains of equal intensity are passing through the same medium in opposite directions, stationary vibrations are set up. If, in each row of Fig. 114, the thin wavy line represent a wave motion moving to the left, and the dotted line a similar motion moving to the right, their *resultant* action on the medium between A_1 and A_5 is represented by the *thick* line in each case considered. Certain points N_1, N_2, N_3 are never disturbed at all, while points A_1, A_2, A_3 are disturbed more than any other points in the whole line. N_1, N_2, N_3 are called *nodes*, and A_1, A_2, A_3 are called *antinodes*.

It will be seen that the distance between two consecutive nodes or between two consecutive antinodes is equal to half a wave-length; or, from a node to the next antinode is a quarter of a wave-length.

This result is employed in the experiments described below.

THE RESONANCE TUBE

The column of air in a tube open at the upper and closed at the lower end can vibrate in any way which permits of free motion at the opened end and zero motion at the closed end. This means that there must be an antinode (place of maximum disturbance) at the open end, and a node (place of zero disturbance) at the closed end. Different modes of vibration, corresponding to different frequencies, are illustrated diagrammatically in Fig. 115. The sound vibrations are actually longitudinal, and not transverse, as the diagram might suggest. Since the distance from a node to an antinode is one quarter of a wave-length, it will be seen that the length of the pipe is respectively $\lambda_1/4, 3\lambda_2/4, 5\lambda_3/4$, etc., $\lambda_1, \lambda_2, \lambda_3$ being the wave-lengths of the possible vibrations.

When a tuning-fork is placed over the open end of the tube, resonance occurs provided the frequency of the fork is in agreement with any one of the possible modes of vibration of the column of air in the tube. The air in the tube is set in stationary




FIG. 115.—Modes of Vibration in Resonance Tube of fixed length

vibration, being under the action of the waves sent out by the fork, and of the waves reflected from the closed end. Fig. 115 may be taken to represent resonance for a tube of fixed length using three different tuning-forks.

The resonance tube is usually arranged so that its length can be varied readily. If a fork of given pitch be held over the end of the tube, and the tube be adjusted to resound to the note emitted by the fork, the shortest length of tube which will give resonance is a length l_1 , such that $l_1 = \lambda/4$, λ being the wave-length in air of the note emitted by the fork.

The next length giving resonance will be l_2 , such that $l_2 = 3\lambda/4$, and so on ; so that we can determine the wave-length in air of the note emitted by the fork.

A slight correction has to be applied for the diameter of the pipe ; the length l_1 is not exactly equal to $\lambda/4$, nor is l_2 exactly $3\lambda/4$. The correction for a cylindrical pipe is approximately $3/5$ the radius, when the pipe contains air.

$$\text{Thus} \quad l'_1 = l_1 + \frac{3R}{5} = \frac{\lambda}{4},$$

$$\text{and} \quad l'_2 = l_2 + \frac{3}{5}R = \frac{3\lambda}{4}.$$

These corrected lengths l'_1 and l'_2 should be used in calculating λ .

The correction need not be known if l_1 and l_2 can both be found ; for

$$l_2 - l_1 = \frac{\lambda}{2}$$

quite accurately, the correction being eliminated by taking the difference between l_2 and l_1 .

If λ is found by this means for a fork of known frequency, the velocity of sound in the air in the pipe can be calculated, for

$$V = n\lambda.$$

λ , the wave-length in the air in the pipe, is known, and n is given ; therefore V can be obtained. Or if V is given, n can be calculated.

If two forks are used, the ratio of their frequencies can be determined by obtaining the values of λ corresponding with the notes they emit.

$$\begin{aligned} V &= n_1 \lambda_1, \\ V &= n_2 \lambda_2, \\ \therefore \frac{n_1}{n_2} &= \frac{\lambda_2}{\lambda_1}. \end{aligned}$$

EXPT. 79. The Resonance Tube.—The Resonance Tube may be conveniently constructed in either of the forms shown in Fig. 116. The first consists of a counterpoised brass tube which projects from a tall standard tube containing water.

A scale of cm. is graduated on the movable brass tube, the zero of the scale being at the top of the tube. The level of the water can be read on the scale by a window in the standard tube, and hence the length of tube giving resonance can be determined conveniently.

The other form is so simple that it needs little explanation. The level of the water is adjusted by moving the reservoir, and the length of the tube containing air is measured with a metre scale.

Adjust the resonance tube to give resonance with several different




FIG. 116.—Resonance Tubes

forks, obtaining both the first and second resonance length, if possible, with each fork.

(i) Calculate the velocity of sound in the air in the pipe from the known frequency of one of the forks. Observe the temperature of the room and reduce the value of V obtained at this temperature to give the velocity at 0°C. , by means of the formula (p. 164)

$$V_t = V_0(1 + \frac{1}{2}at).$$

Or (ii) Being given the velocity of sound in air at 0°C. , calculate the velocity of sound in air at the room temperature, and hence deduce the frequency of a given tuning-fork.

(iii) Compare the frequencies of two forks from observations with the resonance tube, and check the values so calculated by means of the frequencies marked on the forks.

(iv) Find two positions of resonance using a fork of known frequency,

and then calculate the end correction. Compare the result with the value $3R/5$ given in the text.

(v) Find two positions of resonance for a number of forks of known frequency, and plot a graph showing the relation between $l_2 - l_1 = \lambda/2$ and $1/n$. If the temperature remains constant during the observations the graph should be a straight line. If the temperature changes, each value should be corrected to 0°C .

Repeat Experiment 79 with the resonance tube filled with carbon dioxide (CO_2), and find

(a) the velocity of sound in CO_2 ,

(b) the end correction to be applied when the tube is filled with CO_2 .

Experiments may also be carried out with a resonance tube open at both ends. For this purpose two tubes, one sliding inside the other, may be employed. Note that for a tube open at both ends an end correction must be applied for each end of the tube.

NOTE.—The velocity of sound in dry air at 0°C . is 331·3 metres per second or 1087 feet per second.

CHAPTER II

FREQUENCY

§ 1. DETERMINATIONS OF FREQUENCY

THE SIREN

Frequency is defined as the number of *complete* vibrations or cycles in unit time (1 second). The production of a musical tone of controllable frequency by using a regular succession of puffs of air was described by John Robison of Edinburgh in 1801. The method was developed by Cagnard de la Tour (1819) who called his apparatus the *Siren*, because it could sing under water. Modifications were made by L. Seebeck about 1841 in order to increase the loudness of the sound and the accuracy of measurement. The apparatus (Fig. 117) contains a cylindrical box called the wind-chest, connected below to bellows for producing a blast of air. A better plan, if available, is to use a large reservoir of air maintained at constant pressure. The siren should be connected to the air source by a rubber pipe fitted with a *screw-clip* to regulate the wind pressure.

The wind-chest has a number of perforations distributed at equal distances round a circle in the top surface of the box, the holes being drilled at an angle to the surface as indicated in the part section shown in Fig. 117. Above this box, and very close to it, is a circular plate drilled with a similar set of holes, inclined the opposite way to those in the top of the chest. This plate is mounted so that it can rotate on the wind-chest in such a manner that the one set of holes passes over the other as the plate rotates.

When the chest is filled with air under pressure, the air emerges through the holes, and, impinging on the holes in the disk, sets the latter in rotation about its axis.

The holes in the chest are thus covered and uncovered at regular intervals, puffs of air escaping periodically as the two sets of holes coincide momentarily, and thus periodic pressure waves are sent out into the air, producing the periodic disturbance called 'sound'.

In each rotation of the disk there are as many puffs of air produced as there are holes in the rotating plate, n say.

A worm gearing and toothed wheels in the case at the top cause the revolutions to be recorded on the dials shown. By measuring the time required for a definite number of revolutions the rate of revolution of the disk can be obtained.

Suppose that the disk and the top of the chest have n holes in the ring, and N revolutions of the disk are made in t seconds, the total number of 'puffs' made is nN in t seconds, and the frequency is therefore nN/t cycles per second.

By adjusting the speed of revolution till the note of the siren is in unison with the note of the vibrating body, we can obtain the vibration frequency of this body, as it is then equal to that of the note given by the siren, namely Nn/t cycles per second.

EXPT. 80. Determination of Frequency by means of a Siren.—Adjust the siren to unison with a vibrating tuning-fork or to a sounding organ.

pipe.¹ Keep the rate of revolution constant by adjusting the tap and the pressure in the bellows, and find the vibration frequency of the siren.




FIG. 117.—The Siren

This is given by Nn/t , and is the same as the frequency of the note of the fork or organ-pipe used.

Other methods of determining frequency are employed in the following experiments :—

EXPT. 81. Determination of the Frequency of a Tuning-fork by the Dropping Plate Method.—Place a light style of stiff hair on the prong of a tuning-fork, fixing it in place with wax. Suspend a smoke-blackened sheet of glass in a heavy frame from a stand (Fig. 118), using a piece of cotton passing over two pins for this purpose. Mount the fork so that the hair gently touches the glass near its bottom end, bow the fork with a violin-bow, and release the glass by burning the cotton thread between the pins.

When the glass is examined, a wavy trace will be found on the blackened surface, the trace being made in the soot by the style as the plate fell. From the trace thus formed, the vibration frequency of the fork can be found as follows :

(i) If the beginning of the trace is quite clearly defined, measure the distance s from the beginning to the last wave shown on the glass, and count the number of complete waves in this distance ; let this be N .

The glass falls under its own weight, and in t seconds it will fall a distance $s = \frac{1}{2}gt^2$, since it has no initial velocity. Thus the time t required to fall the measured distance s can be calculated,

$$t = \sqrt{\frac{2s}{g}}.$$

¹ See notes on tuning, p. 185.

During this time the fork made N vibrations, therefore the vibration frequency of the fork is N/t .

(ii) If the trace is not clear at the beginning, start at the first clearly defined crest and count off a certain number of waves n (say 20) marking the n th crest. Count beyond this a further set of n waves. Measure the length s_1 of the first set, and s_2 the length of the second set of n waves.




FIG. 118.—Dropping Plate Apparatus

If the velocity of the glass when passing the first crest was v_0 , and the time taken to make n waves is t , we have (Fig. 119)

$$s_1 = v_0 t + \frac{1}{2} g t^2.$$

When the second of the marked crests was being passed, the velocity of the glass was $v_1 = v_0 + gt$.

The distance s_2 is given by

$$s_2 = v_1 t + \frac{1}{2} g t^2$$

or

$$s_2 = v_0 t + g t^2 + \frac{1}{2} g t^2,$$

since s_2 is described in the same length of time as s_1 .

Thus

$$s_2 - s_1 = g t^2$$

or

$$t = \sqrt{\frac{s_2 - s_1}{g}}.$$

In this time n vibrations are made ; therefore the vibration frequency = n/t .

EXPT. 82. Kundt's Tube.—A glass tube, about 1 metre long and 5 cm. internal diameter, is dried thoroughly over a Bunsen flame. The tube, closed at one end with a cork, is lightly dusted inside with *dry* cork powder or lycopodium dust. Rotate the tube about a horizontal axis till the dust is just on the point of slipping down the walls. A rod, fitted with a light disk of cork or ebonite at the end, is fixed with this end just projecting into the tube. The disk is made rather smaller than

the tube, so that the end of the rod and the attached disk can vibrate freely inside the tube.

The rod is clamped exactly at its middle point, and is set into longitudinal vibration by stroking lengthways with a resined leather or cloth. By this means the air in the tube is set in vibration, waves being sent down the tube, which gives rise to returning waves by reflection from the fixed cork at the other end of the tube.


The tube is pushed by *very small* amounts over the end of the rod, the rod being stroked so as to cause it to sound after each fresh adjustment. A position is reached where the air or gas in the tube resounds to the note of the rod. When this is the case the dust in the tube is caught up in the swirl of the air, which is set in violent vibration. After the motion has died down, the dust settles in characteristic ridges at the *antinodes*.¹ Several antinodes are thus fairly clearly marked, and the distance between two at some considerable distance apart is measured.

From the number of heaps between these two, the number of intervening antinodes is found, and the wave-length of the note in the gas in the tube is obtained, the distance between two consecutive antinodes being half a wave-length.

The pitch of the rod is now found by means of a sonometer (see experiments with sonometer, p. 184), using a tuning-fork of known frequency for comparison; and from this the velocity of sound in the gas can be determined using the relation

$$V = n\lambda.$$

FIG. 119.—Trace of Tuning-fork



If the velocity of sound in the gas is assumed to be known, the frequency of the note of the rod can be determined by this same equation.

Calculation of Young's Modulus for the Rod.—The rod vibrates with a node at its middle point and an antinode at each end; hence its length is equal to half the wave-length of the note in the material of the rod.




FIG. 120.—Kundt's Tube

The velocity of sound in the rod is $\sqrt{E/\rho}$, where ρ is the density of the



FIG. 121.—Antinodes in Kundt's Tube

rod and E the modulus of elasticity for longitudinal strain, so that E is Young's Modulus.

¹ By continued sounding it is possible, though difficult, to get the dust to settle in little heaps at the nodes.

If $V' =$ Velocity of sound in the rod
and $\lambda' =$ Wave-length of sound in the rod,

$$V' = n\lambda'.$$

Here n is known, λ' is equal to twice the length of the rod, which can be measured ; hence V' can be calculated.

The density of the rod is also known, and

$$V' = \sqrt{\frac{E}{\rho}},$$

hence we can find Young's Modulus for the material of the rod.

§ 2. BEATS

When two pure notes of nearly the same pitch are sounded together, periodic variations in the intensity of the sound are heard. These alterations of sound and comparative silence are termed **Beats**. They can be plainly recognised when two tuning-forks of nearly the same frequency are set in vibration together. If the forks have frequencies N_1 and N_2 respectively, the number of beats per second is the difference between these frequencies, $n = N_1 - N_2$. Here N_1 is supposed greater than N_2 .

This result can be explained by the principle of interference. The velocity of propagation is the same for the two notes, but the wave-lengths differ slightly. Where the waves agree in phase they will strengthen each other, but where they are opposed they will neutralise one another (Fig. 122). Let us take as starting-point an instant when




FIG. 122.—Variations of Amplitude in Beats

waves from the two sources reach the ear in the same phase. At the end of one second, the higher note has made N_1 complete vibrations, the lower note only N_2 , that is, the higher note has made $N_1 - N_2$ more vibrations than the lower. During the second, one system of waves has been falling behind the other, and the loss amounts to $N_1 - N_2$ wave-lengths. Hence there must have been $N_1 - N_2$ occasions in the course of the second when the two systems agreed in phase, and $N_1 - N_2$ occasions when the phases were opposed so that there was comparative silence. In other words, the number of beats in one second $n = N_1 - N_2$.

If two notes are nearly in unison, the beats are very slow and it is difficult to distinguish them. On the other hand, if the number of

beats is more than four per second it is difficult to count them. When the beats become so rapid that they cannot be separately perceived, a 'discord' or 'dissonance' is produced.



EXPT. 83. Beats between Tuning-forks.—Take two tuning-forks of nearly the same pitch mounted on resonance boxes. The frequency of one fork can be altered by means of a movable mass which can be clamped at any part of the prong (Fig. 123).

Fix the mass at a definite distance from the end of the prong, and count the number of beats made with the other fork in a measured interval of time.

The number of beats per second should be determined by counting as many beats as possible, taking the time with a stop-clock or stop-watch.

FIG. 123.—Loaded Tuning-fork

Repeat the observations with the mass at other points on the prong, and plot a curve showing the relation between the distance of the mass from the free end of the prong and the number of beats per second.

§ 3. COMPOSITION OF HARMONIC VIBRATIONS AT RIGHT ANGLES

When two Simple Harmonic Motions (Fig. 83, p. 123) in directions at right angles are superposed, the resulting motion may be found by using the respective circles of reference (auxiliary circles). The figures obtained are named after the French professor of physics, J. A. Lissajous, whose chief memoir was published in 1873. Typical illustrations are shown in Fig. 123A, in which the amplitudes of the rectangular vibrations are the same. The simplest figures are those in the upper row of the diagram and in these the two periods are the same. The resulting curve is then found to be an ellipse, which degenerates into a straight line if the initial phases coincide or differ by π . If, in addition, while the amplitudes of the components remain equal, the difference in phase is $\frac{1}{2}\pi$, the ellipse becomes a circle. Uniform circular motion may be regarded as the superposition of two simple harmonic motions at right angles, differing in phase by one quarter of a complete period.

The figures in the lower rows of the diagram correspond to component vibrations having periods in the ratio 1 : 2, 1 : 3, and 2 : 3. More complicated figures of this type are given in Barton's *Text-Book of Sound*, Fig. 18, p. 61.

The geometrical method of obtaining Lissajous' figures is illustrated in Fig. 123B. Several diagrams of this kind are given on a large scale in Alfred Daniell's *Text-Book of the Principles of Physics* (1884). In

the figure selected the vibrations are of unequal amplitude corresponding to AB and CD, and the periods are in the rates of 12 : 8 or 3 : 2.




FIG. 123A.—Lissajous Figures

Consequently the frequencies or pulsations (p. 124) are in the ratio 2 : 3.




FIG. 123B

Each reference circle is divided into equal arcs corresponding to equal intervals of time, so that any such arc is traversed in the same time. Only one half of the complete reference circle may be required for the construction. Through the selected points on the circles lines are drawn at right angles to the diameters AB and CD so as to form a rectangular network. If we start at a corner of any one of these rectangles (for instance the corner corresponding to A and C) and proceed diagonally, we pass through a succession of points (1I, 2II, etc.) separated by equal intervals of time, and these points lie on a curve which is one of Lissajous' figures. The resulting curve depends upon the phase difference between the two components, as already seen in Fig. 123A.

The student should practise using this geometrical method to obtain the more complicated curves when the amplitudes and phases as well as the periods are different. Greater accuracy is secured by using a considerable number of arcs.

BLACKBURN'S PENDULUM

Various experimental methods have been used for illustrating these results. A simple apparatus that is convenient for class demonstration is the pendulum devised by H. Blackburn, professor of mathematics in Glasgow, 1849-79. As we have seen (p. 126), the bob of a simple pendulum moves approximately with simple harmonic motion. By using a double suspension in the form of a letter Y, arranged as in Fig. 123c, the heavy bob of Blackburn's pendulum can oscillate in two directions at right angles. The bob BB is suspended by a double cord 2 or 3 metres in length from a fixed beam HK.




FIG. 123c

The adjustable clip A keeps the lower parts of the cord together and provides a means of altering the distance between A and the centre of gravity of the bob. The top of the cord above the beam is wound

round a peg D, which gives a further means of adjustment.

When the bob swings in the plane of the paper, the arrangement behaves like a pendulum of length AB, but when the bob swings in a

vertical plane at right angles to the plane of the figure, the length of the equivalent pendulum is EB. The bob is a ring of lead carrying a funnel C containing fine sand (or a coloured liquid). When in operation the jet of sand gives a record of the motion on a horizontal sheet of paper placed at a suitable distance below the bob.

A more complicated, but more efficient, device is the harmonograph, which consists of two massive rigid compound pendulums arranged so as to oscillate in planes at right angles. One pendulum carries a tracing point, the other a flat horizontal surface on which the trace is recorded.

The composition of vibrations at right angles is of great importance in studying the oscillations produced in thermionic valves, and the cathode ray oscillograph (p. 509) provides a striking illustration of the application of the results as well as furnishing a visual record of Lissajous' figures.

CHAPTER III

TRANSVERSE VIBRATIONS OF A STRETCHED STRING

§ 1. PROPAGATION OF TRANSVERSE WAVES ALONG A STRETCHED STRING

THE expression for the velocity of a transverse wave along a string under tension, can be shown to be

$$V = \sqrt{\frac{T}{m}},$$

where T is the force or tension exerted on the string, and m is the mass of unit length of the string.

If T is measured in *pounds* and m in pounds per foot of length, the velocity is given in feet per second; with T in *dynes* and m in gm. per cm. length, the velocity is obtained in centimetres per second.

EXPT. 84. Determination of the Velocity of a Wave along a String.—Set up a cord several metres in length, fixed at one end and with the other passing over a pulley and carrying a scale-pan. Stretch the cord by various weights placed in the scale-pan. Pluck the cord at one end, and find the time taken for the disturbance to travel, say 10 or 15 times, from end to end of the string. This can be done easily, for the motion of the disturbance is plainly visible and the time taken can be noted with a stop-watch.

Calculate the tension of the string in dynes from the known mass M grams hanging from the end,

$$T = Mg \text{ dynes.}$$

M here includes the mass of the scale-pan.

Determine the mass of 1 cm. of the cord by weighing a known length of a similar cord.

From the observations of the motion of the disturbance, calculate the velocity of the wave along the string, and show that the observed velocity is equal to $\sqrt{T/m}$ cm. per sec.

EXPT. 85. Determination of an Unknown Mass from Observations on the Velocity of a Wave.—Hang an unknown mass M on the string used in the last experiment, and observe the velocity of the wave disturbance as before. Calculate the mass of the suspended body from the equations

$$M (\text{unknown}) = \frac{T}{g},$$

and

$$T = V^2 m.$$

Verify your result by actual observation of M , using a balance.

§ 2. STATIONARY VIBRATIONS OF A STRETCHED STRING

If a string is stretched between two points A and B (Fig. 124), and a disturbance is created at any point on the string, the disturbance travels to one end, and is there reflected *reversed* to the other




FIG. 124.—Reflection of Disturbance from Ends of Stretched String

end. Here it is again reflected, but now in the same form as the original disturbance, so that the string is in exactly the same condition as at first, after the disturbance has travelled *twice* along its length; or when the disturbance has travelled *once along and once back*, the vibration of the string has completed one *cycle*.

Now the velocity of propagation is $\sqrt{T/m}$, and the distance travelled by the wave in a complete cycle is $2l$. Hence the period of vibration is

$$t = \frac{2l}{\sqrt{T/m}},$$

or the vibration frequency

$$n = \frac{1}{t} = \frac{1}{2l} \sqrt{\frac{T}{m}}.$$

This expression enables us to calculate the frequency of a string if the various quantities l , T , and m are known.

THE SONOMETER OR MONOCHORD

A sonometer consists of a firm frame carrying two fixed bridges over which one or more strings or wires can be stretched. Usually one string is fixed permanently to the apparatus, and its pitch is varied by 'keying up', wrench keys or other means being supplied whereby the tension can be adjusted as desired. Another string is also used, one end being fixed over one of the fixed bridges, while the other end, passing over the other bridge, carries a scale-pan. The tension in this second string is adjusted by suspending masses in the scale-pan hanging from it, and for this reason the sonometer is best supported in a vertical position. If a horizontal position be used, the string has to pass over a pulley so that the weights can hang downwards. There is usually considerable friction at the pulley, so that the tension on the string is not necessarily the same as the weight hanging from the end. A pair of movable bridges is also supplied, one for each

string; by moving these bridges along the strings, the *sounding length* can be altered at will, and the pitch of either string changed as a result of the altered length.

EXPT. 86. Determination of the Variation of Pitch with Length.—The sonometer is set up and the tension of the keyed wire adjusted so that a musical tone is emitted on plucking the wire. Several forks of known frequency are supplied, and the length of the keyed wire is altered by shifting the movable bridge, so as to give unison with each fork in turn, the tension of the wire being kept constant throughout. See the notes on tuning on p. 185.

The lengths l_1, l_2 , etc., corresponding with the frequencies n_1, n_2 , etc., of the forks (and of the tuned wire), are determined.

It will be found that $n_1 l_1 = n_2 l_2 = n_3 l_3$, showing that the frequency of the wire under constant tension is inversely proportional to its length. Draw a graph connecting n and $1/l$.

Use this result to find the pitch of an unmarked tuning-fork, tuning the wire first to unison with a known fork, and afterwards tuning to the unknown fork.

$$\frac{n_1}{n_2} = \frac{l_2}{l_1},$$

$$\text{or} \quad n_1 \text{ (unknown)} = n_2 \frac{l_2}{l_1} \text{ (all known).}$$

To determine the way in which the frequency of a wire of constant length varies with tension, etc., is a matter of some difficulty, requiring the use of a large number of tuning-forks of known pitch. In the following experiments an indirect method is used, the wire being tuned by altering the length as well as the tension, the effect of the alteration of length being allowed for by a simple calculation involving the result obtained in the experiment just described.




FIG. 125.—Vertical Sonometer

EXPT. 87. Determination of the Variation of Pitch with Tension.—Apply different tensions to the second wire of the sonometer and find the lengths of this wire which vibrate in unison with a certain length of the fixed wire, the fixed wire being kept under constant tension. Let the tensions be T_1, T_2, T_3 , etc., and the attuned lengths be l_1, l_2, l_3 , etc.

In order to find how the pitch of a *constant* length of the wire varies with the tension acting in the wire, we apply the result obtained in Experiment 86 in the following manner.

Let the pitch of the length l_1 , when pulled with a tension T_1 , be n_1 . A length l_2 of the same wire had the same frequency n_1 when pulled with a force T_2 . If we had used the same *length* of wire as at first (l_1), the pitch under tension T_2 would have been

$$n_2 = n_1 \frac{l_2}{l_1},$$

and we can therefore *calculate* the pitch n_2 of a length of wire l_1 when under a tension T_2 .

Similarly the length l_1 would have had a vibration frequency $n_3 = n_1 \frac{l_3}{l_1}$, if it had been sounding under a tension T_3 .

Calculate n_2 , n_3 , etc., and show that n is proportional to \sqrt{T} .

Arrange the results of the observations as in the table :—

Frequency of note of fixed string = n_1 .

Tension of Weighted Wire in Gm.-wt. T	Length giving Note of Frequency n_1 l	Calculated Frequency for a Length l_1 $n = n_1 \frac{l_2}{l_1}$, etc.	$\frac{\sqrt{T}}{n}$
$T_1 =$	$l_1 =$	$n_1 =$	$\frac{\sqrt{T_1}}{n_1}$
$T_2 =$	$l_2 =$	$n_2 = \frac{l_2}{l_1} n_1 =$	$\frac{\sqrt{T_2}}{n_2}$
$T_3 =$	$l_3 =$	$n_3 = \frac{l_3}{l_1} n_1 =$	$\frac{\sqrt{T_3}}{n_3}$

The last column of the table will be found to be constant, showing that n is proportional to \sqrt{T} . Draw a graph.

EXPT. 88. Variation of Frequency with Mass per Unit Length.—Stretch a wire on the sonometer with a given load, and find what length of it vibrates in unison with the fixed wire.

Remove the wire, and replace it by a second wire stretched with the same load ; again find the length giving unison with the fixed wire.




FIG. 126.—Horizontal Sonometer

Repeat this for three or four different wires, using wires of different material, or different diameter, each time.

Weigh each wire or a portion of each wire, measuring the length of the part weighed : a considerable length should be used to obtain accuracy. Calculate the mass of 1 cm. of each of the wires used.

By the result obtained in Experiment 86 calculate what frequency each of the wires would have had, if each had been under the same tension but of length equal to the length of the first wire used.

This gives the value of n for each of the wires when equal lengths are vibrating under the same tension.

Show that $n\sqrt{m}$ is the same for each wire, or that n is proportional to $1/\sqrt{m}$.

Arrange the results as below :—

Frequency of fixed wire = n_1 .

Lengths of Wire vibrating in Unison with Fixed Wire l_1, l_2, l_3 , etc.	Mass of each Wire per cm. Length m_1, m_2, m_3 , etc.	Calculated Frequency of a Length l_1 of each Wire under the given Tension n_1, n_2, n_3	$n\sqrt{m}$
$l_1 =$	$m_1 =$	n_1 (as above) =	$n_1\sqrt{m_1}$
$l_2 =$	$m_2 =$	$n_2 = \frac{n_1 l_2}{l_1} =$	$n_2\sqrt{m_2}$
$l_3 =$	$m_3 =$	$n_3 = \frac{n_1 l_3}{l_1} =$	$n_3\sqrt{m_3}$

The last column of the table will be found to be constant, showing that n varies as $1/\sqrt{m}$.

EXPT. 89. Absolute Determination of Pitch with a Sonometer.—Stretch a wire with a known force T dynes. Find the length l cm. vibrating in unison with the fork whose frequency is to be determined.

Cut off a length of the wire, weigh it, and determine its mass per unit length, m gm. per cm.

Calculate the vibration frequency of the wire, which is the same as that of the fork with which it is in unison.

$$n = \frac{1}{2l} \sqrt{\frac{T}{m}}.$$

These results can be applied in various ways. The following exercises are suggested as corollaries on the vibration of strings :—

EXPT. 90. Determination of the Density of the Material of a Wire, using the Sonometer.—In this determination the wire must not be removed from the sonometer board. A fork of known pitch is supplied. Stretch the wire with a known force, and tune a length of it to unison with the given fork.

In the equation
$$n = \frac{1}{2l} \sqrt{\frac{T}{m}},$$

n is given, T is known, and l is measured. Hence m can be calculated.

Now m is the mass of a cylinder of metal 1 cm. long, and of diameter equal to that of the wire, so that

$$m = \pi r^2 \rho,$$

where r is the radius of the wire, and ρ its density. Hence ρ can be determined from the calculated value of m , if the radius of the wire is measured with a micrometer screw.

EXPT. 91. Determination of the Weight of a Given Load by the Sonometer.—Another useful exercise is to weigh a bag of weights by means of a sonometer. A fork of known pitch is supplied, and a length of wire l , when stretched with the bag of weights, is tuned to unison with the fork. The mass in grams of 1 cm. of the wire is determined by weighing a considerable length of the wire. Thus in the equation

$$n = \frac{1}{2l} \sqrt{\frac{T}{m}},$$

n , l , and m can all be determined, and hence T can be calculated in dynes. Now $T = Mg$ dynes, where M is the mass of the bag in grams. Hence $M = T/g$, and the mass of the bag can thus be found.

NOTE.—Avoid such ‘ formulae ’ as

$$n = \frac{1}{2lr} \sqrt{\frac{T}{\pi \rho}}, \quad \rho = \frac{T}{4l^2 r^2 n^2 \pi}, \text{ etc.}$$

These are quite true, but the results required can always be found from the fundamental equation (pp. 180-181)

$$n = \frac{1}{2l} \sqrt{\frac{T}{m}}$$

by an application of first principles.

Melde's Experiment.—In this experiment vibrations are maintained in a stretched string by using a driver of definite frequency. It was the custom to attach one end of the thread to a fixed point on the prong of a tuning-fork, and to produce stationary waves formed by the superposition of direct waves sent out by the fork and waves reflected from the fixed point at the far end of the thread. When an alternating current supply of definite frequency is available, the experiment may be greatly simplified. This method of experimenting will be described in the electrical section (Experiment 258C, p. 468).

§ 3. NOTES ON TUNING

In tuning a fork and a string, two strings, or any two notes to unison, there may be a difficulty if the student has no musical ‘ ear ’. Certain aids may be used to indicate when the tuning is correct. One of these is given by the phenomenon of *beats*. When tuning is close but not perfect, the two notes will ‘ beat ’, and the rapid variations in intensity of the sound will be observable even if there is no musical appreciation of approximate unison.

The notes will be in unison when the beats are so slow that they cannot be detected. In using the sonometer, adjust the string by *very small alterations in length* so that the beats get slower and slower. When they can no longer be distinguished, the notes may be considered as identical, *i.e.* the frequencies of the sounding bodies are equal.

Another method, when a horizontal string is used, is to place a small rider of paper on the middle of the string to be tuned. If the other string or the fork be sounded, the fork being allowed to rest on the sonometer board, the paper rider will *flutter* if tuning is close ; it will be thrown violently off the wire if the tuning is exact. Thus, by altering the length so as to increase the fluttering, the wire may be

tuned to the other string or fork. See the 'Principle of Resonance' (p. 165).

In plucking a string to excite its note, care should be taken to avoid touching the string with the finger-nail, as this may introduce over-tones; the string should be pulled aside between the thumb and finger.

When listening to the note of a string, a small plate of wood fitted with a wooden handle may be held to the ear, the end of the handle being placed in contact with the base-board of the sonometer.

PART II

ADDITIONAL EXERCISES IN SOUND

1. Having given two tubes arranged so that one can slide inside the other, measure the frequency of a fork by finding the position of resonance for the compound tube open at both ends.

2. Compare the frequencies of two tuning-forks by the dropping plate method.

3. Find the velocity of sound in the given glass rod. Clamp a stout glass rod about 6 feet long at its middle point and find (page 174) the frequency of the note produced when the rod is rubbed longitudinally by a cloth moistened with alcohol. Determine the density of the glass and deduce the value of Young's Modulus.

4. Find the mass of 1 cm. of the given cord by determining the velocity of a transverse wave along it under a known tension.

5. Compare the densities of the materials of two wires by means of the sonometer.

6. Compare the frequencies of two forks by means of the sonometer.

7. Compare the weights of two loaded bags by means of the sonometer.

8. Stretch a wire with different weights, and find what lengths of the wire are in unison with a fork of known frequency. Deduce the stretching force required to make a similar wire, 2 metres long, vibrate with a frequency of 50 vibrations per second.

9. Plot a curve showing the relation between the volume of the given resonator and the frequency of the resonant vibration. (The resonator in this experiment is an ordinary medicine bottle with a narrow neck. The volume may be altered by adding water.)

10. Find the frequency of a tuning-fork by attaching a bristle to one prong and producing a trace of the vibrating point on a smoked drum revolving at a measured speed.

11. Find the difference between the frequencies of two given tuning-forks by counting the beats between them. Determine which fork has the higher pitch and load it until the frequencies are the same. (An auxiliary fork of nearly the same pitch may be employed in this experiment.)

12. Employ Kundt's tube to determine the velocity of sound in (a) coal gas, (b) carbon dioxide.

13. Compare the velocity of sound in coal gas with the velocity in air by means of Kundt's tube.

14. Clamp a thin steel strip, about 50 cm. long and 2 cm. wide, in a vice, and find how the frequency of vibration depends on the length of the portion in vibration.

PART III

LIGHT

NOTES ON LIGHT

Light is essentially a *practical* subject, and every opportunity should be taken of making simple experiments with familiar objects such as polished metal surfaces to act as mirrors and spectacle lenses or magnifying glasses for producing images of various types. Although a ray of light is a conception akin to the mathematician's definition of a line as 'length without breadth', even the study of 'geometrical optics' is made clearer by picturing a ray as a line joining two pin-points, and by using methods, such as the optical disk or Robinson's ray track apparatus, by which fine pencils of light are obtained from suitable sources and traced after reflection or refraction. The use of diagrams as forming an important part of the experimental work must also be emphasised.

In the study of Light it is an undoubted advantage to be familiar with geometrical methods, and an elementary knowledge of trigonometry is required in dealing with refraction. Also the use of an *algebraic* formula connecting distances is frequently necessary. This introduces the vexed question of the *sign* to be given to any particular distance, and in the Supplement (pp. 545-549) three separate ways of making the choice are given, which we have called 'conventions A, B, and C.' For the student of mathematical physics, convention A has distinct advantages; for the student of medicine or the practical optician, convention C may be selected.

There has been much discussion as to the sign convention to be adopted in optical problems. In the present text the older convention A has been retained. This considers distances positive when measured towards the source of light (pp. 206 and 212). As an alternative, convention C may be preferred mainly because it results in making the focal length of a converging lens positive, thus agreeing with custom in the optical industry. Convention C, described in the Supplement (pp. 548-555), may be stated briefly by saying 'Real is Positive' and 'Virtual is Negative'. Whatever convention is adopted, two points may be stressed: (1) an optical formula is *algebraic*, and before substituting any quantity in the formula the value should be written down *with the sign attached*, (2) a diagram should be drawn showing the paths of selected rays so as to check the results of the calculation.

The subject of Photometry (pp. 247-253) is of increasing importance and the determination of the energy used for purposes of illumination is described later in connection with the efficiency of an electric lamp (p. 443). For further information on modern photometry reference may be made to *A Text-Book of Light*, by G. R. Noakes.

CHAPTER I

THE LAWS OF GEOMETRICAL OPTICS

§ 1. PARALLAX

LIGHT travels in straight lines so long as its path lies in a medium the properties of which are the same at all points and in all directions round each point. According to the **axiom** called the **Rectilinear Propagation of Light** a ray of light, or a beam of light of very small cross section, can be represented by a geometrical straight line.

The direction in which any object is seen depends on the direction of the ray entering the eye of the observer. The term **parallax**, originally used in connection with astronomical observations, means the apparent displacement of an object caused by an actual change in position of the observer ; if a difference is made in the position of the point of observation, there is a corresponding difference in the apparent position of the object. Thus, if two bodies are viewed from a certain point, their relative positions will be altered if the observer move to another position. To illustrate this, set up two retort stands on a table and view them from such a position that the more distant rod appears to be directly behind the nearer. If the observer now move to the right, the further rod will appear to the right of the nearer, as viewed from this new position. Similarly, if the observer move to the left, the more distant rod will appear to move to the left of the nearer. Thus, the object at a greater distance moves in the same direction as the observer, relatively to an object at a smaller distance.

When the rods are placed nearer together, the relative motion of the rods for a given displacement of the observer is reduced. If the rods are placed one in continuation of the other, they appear together from any position in which the observer places himself. The same principle applies in dealing with images formed by mirrors or lenses. When two bodies are coincident, or in continuation of each other, there is *no parallax* between them, and this test is frequently used to determine if two bodies or two images are coincident. If parallax is observed, the rule given above determines at once which of the two is more distant. This method of experimenting is termed the **method of parallax**. Interesting examples of parallax may be met with in everyday life, as in the case of objects seen from the windows of a rapidly moving conveyance.

§ 2. REFLECTION AT PLANE SURFACES

THE LAWS OF REFLECTION

When a ray of light falls upon a polished surface it is reflected in accordance with the following laws :—

Law I. The incident ray, the reflected ray, and the normal to the surface lie in one plane.

Law II. The angle between the incident ray and the normal (the angle of incidence) is equal to the angle between the reflected ray and the normal (the angle of reflection).

EXPT. 92. Verification of the Laws of Reflection.—These laws may be verified by means of a plane mirror and a number of pins in the following way :—

Attach a sheet of drawing-paper to a drawing-board, and on it place a strip of mirror with its plane vertical. The mirror can be supported by

a wooden block with a vertical groove. The mirror should be of good plate glass but quite *thin*. If possible, glass silvered on the *front* surface should be used.

Draw a line on the paper to mark the position of the *reflecting* surface. Fix two pins into the board at points such as P and Q (Fig. 127). On looking into the mirror the images of these pins will be seen. Move the head till these images appear in a straight line, and then fix two other pins, R and S, in line with the images. P and Q should be some distance apart, say 10 cm. or 15 cm. R and S should be at a similar




FIG. 127.—Laws of Reflection

distance apart. The line PQ is the trace of an incident ray, RS that of a reflected ray.

If the mirror is perpendicular to the drawing-board, the feet of the pins R and S should appear in an unbroken line with the feet of the pins P and Q. For in this case the normal to the mirror lies in the plane of the drawing-board, and according to the first law of reflection the incident ray, the reflected ray, and the normal to the mirror must lie in one plane.

Let the rays PQ and RS meet the mirror at the point L. Draw LN, the normal to the mirror at L. Measure the angles MLN and KLN with a protractor, and also measure equal distances LK, LM (say 10 cm.) along the two rays and join KM.

If KN and MN are equal, the triangles are equal in all respects, and the angles MLN and KLN are equal to each other. Measure the lengths of KN and MN and record the results.

In order to verify the second law of reflection, the determination must be repeated for *at least two* other directions of the incident ray. In each case the angle of incidence should be found approximately equal to the angle of reflection.

If the mirror is *thick*, PQ and RS will meet at a point behind the front surface about two-thirds of the way through the glass. The place where they intersect should be taken as the equivalent reflecting surface.

The image of any object formed by a plane mirror is at the same distance behind the mirror as the object is in front of it.

EXPT. 93. The Image formed by a Plane Mirror.—Fix a pin somewhere in front of a plane mirror and find by trial the position of the image. This can be done by viewing a second pin over the top of the mirror and moving it about till there is no parallax between the second pin and the image of the first, so that there is no relative motion between the image and the second pin on moving the head from side to side (see p. 191).

Measure the perpendicular distance from the first pin to the equivalent reflecting surface, and also from the image to the equivalent reflecting surface. Make a note of the distances which should be approximately equal and enter the results in your notebook.

Two mirrors inclined at an angle give rise to a series of images.

EXPT. 94. Inclined Mirrors.—Draw two lines at an angle with each other, say at 90° and again at 60° , on a horizontal sheet of paper. Set up two mirrors on these lines. Place a pin somewhere in the angle between the mirrors and find the positions of *all* the images produced by reflection in the mirrors in each case. Verify the fact that all the images lie on a circle whose centre is at the point of intersection of the two mirrors, and that the number of images formed is $\frac{360}{\theta} - 1$, where θ is the angle in degrees between the mirrors.

One image will be found in the angle behind both mirrors; trace the path of the rays of light from the pin to the eye of the observer by means of which this image is seen.

Each image should be labelled I_1, I_2, I_3, \dots , according as it is formed by single reflection in mirror 1, single reflection in mirror 2, double reflection first in mirror 1, then in mirror 2, etc.

ROTATION OF A MIRROR

When a mirror is rotated about an axis perpendicular to the plane of incidence, the reflected ray is turned through an angle twice as great as that through which the mirror turns.

Let AB (Fig. 128) be the original position of the mirror, ML the incident, LK the reflected ray, and LN the normal to the surface. Let the accented letters denote corresponding quantities after the mirror has turned through a certain angle. The student should deduce from the laws of reflection already investigated that $\angle K'LK$ — the angle through which the reflected ray turns — is twice $\angle N'LN$ — the angle through which the mirror turns.




FIG. 128.—Rotation of a Mirror

EXPT. 95. Reflection from a Mirror which is rotated.—The result that the reflected ray turns through twice the angle turned through by the

mirror, may be verified experimentally by tracing the rays by means of pins. Two pins are used to define the incident ray ML , and two to define the reflected ray LK . After the position of the reflecting surface has been marked, the mirror is turned through a certain angle and the new position of the reflected ray is determined by pins as before. The angle through which the mirror is turned and the angle through which the reflected ray is turned are measured with a protractor. The ratio of the second angle to the first is then calculated. The process is repeated for a number of different positions of the mirror, and the results are given in tabular form.

Show also that if the direction of the *reflected* ray is kept constant, the objects viewed when the mirror is used first in one position, then when rotated through an angle θ , are along directions which subtend an angle 2θ at the axis of rotation of the mirror.

THE SEXTANT

The **Sextant** is an instrument for measuring the angular separation between two distant objects; that is, the angle between the lines joining the eye of the observer to the two objects. It is used in navigation for measuring the altitude of the sun, or of a star.

EXPT. 96. Examination and Adjustment of the Sextant.—Examine the sextant, and notice that the instrument consists of a graduated arc AB , of about 60° , connected with two fixed radial arms CA and CB .




FIG. 129.—The Sextant

A third radial arm CD is movable about the centre C of the arc, and carries an index and vernier at D . A clamp fitted with a tangent screw is provided to give a slow motion of this arm. At C is a plane mirror, called the **index glass**, attached to the arm and turning with it; the plane of this mirror should be perpendicular to the plane of the arc. At E is fixed a piece of plate glass, whose lower half only is silvered. The plane of this glass also is perpendicular to the plane of the arc. It is called the **horizon glass**. T is a telescope pointing towards the horizon glass. Usually the instrument is provided with a number of coloured glasses for diminishing the intensity of the sun's light.

When the index glass is exactly parallel to the horizon glass, rays from a distant object can reach the telescope by separate paths. One set of rays passes through the unsilvered part of the horizon glass and enters the telescope without deviation. Another set of rays is reflected from the mirror to the silvered portion of the horizon glass, and enters the telescope in the same direction as the first set. The parallel rays are brought to a focus in the focal plane of the object glass, and give rise to a single image of the distant object. When this is the case the index arm D should be at the zero of the graduated arc. If it be not, the reading of D should be taken; it is called the **zero reading**. If now the arm D with its mirror be turned through a small angle, the rays reflected by the mirror will enter the telescope at a different angle, and the image formed by these rays will be displaced with regard to the image seen directly.

Suppose it is required to measure the angle between two objects in the directions EP and CR respectively. The sextant is supported so that the telescope is pointed directly towards the object in the direction EP, the rays passing through the unsilvered glass. The mirror C is turned till rays coming in the direction RC are reflected along CE, and fall on the silvered glass which reflects them into the telescope. Then the angle between the directions of the two objects is the angle RCQ which is twice the angle ACD, through which the arm CD has turned from the zero position. This follows from the foregoing experiment (95), the direction of the ray reflected from C being the same (CE) in each case.

To save calculation, the arc AB is usually graduated so that each degree is numbered as 2 degrees; and the required angle can therefore be read directly from the graduations. The difference between the present reading and the zero reading gives the angle RCQ required.

In order to obtain accurate results the following conditions must be satisfied:—

(1) The plane of the index glass must be perpendicular to the plane of the graduated arc.

(2) The axis of the telescope must be parallel to the plane of the arc.

(3) The zero reading must be taken for each pair of objects used; it varies if the distance of the objects from the sextant is altered.

Adjusting screws are provided for making the necessary adjustments, but we shall assume that the adjustments have already been made by the instrument-maker.

EXPT. 97. Measurement of Azimuth with the Sextant.—Use the sextant to measure the angle θ between two objects in the same horizontal plane. Two candles or two incandescent lamps may conveniently be employed. The sextant must be held in the same horizontal plane as the objects. Measure the distance to each object, and calculate the distance between the objects from these distances and the angle θ . Confirm the result by measuring the distance between the objects directly.

EXPT. 98. Measurement of Altitude with the Sextant.—Use the sextant to measure the angular elevation of a distant object. In this measurement the foot of the object should be on the same level as the sextant. Calculate its height from the angle measured and the horizontal distance from the foot of the object to the sextant. If possible, confirm the result by measuring the height. A better method of finding the altitude of a distant object is to measure the angle between the object seen directly and its image formed by a horizontal mirror, such as the surface of mercury. The angle thus measured is twice the required altitude.

The height of a distant object, say the top of a tower, may be determined by measuring the angular altitude θ_A and θ_B at two points A and B a known distance apart in the same horizontal straight line as the foot of the tower (assumed to be on the same level as the sextant). The method of calculation is left as an exercise for the student.

§ 3. REFRACTION AT PLANE SURFACES

THE LAWS OF REFRACTION

An isotropic medium is a substance which shows no differences of quality in different directions.

When a ray of light passes from one medium into a second, its

direction is in general changed, and the direction of the refracted ray is found to obey, for all isotropic media, the two laws of refraction here stated.

Law I. The incident ray, the normal to the surface, and the refracted ray lie in one plane.

Law II. The ratio of the sine of the angle of incidence to the sine of the angle of refraction is a constant for any two particular media and for light of a particular colour. This constant is called the **refractive index** (μ) in passing from the first medium into the second.




FIG. 130.—Law of Refraction

Thus if AB (Fig. 130) represent the surface of separation between the two media, SP a ray incident at the point P, and NPN' the normal to the surface, the refracted ray PR lies in the plane containing SP and NPN', and

$$\frac{\sin i}{\sin r} = \text{a constant} = {}_1\mu_2.$$

Here i is the angle of incidence, or the angle SPN between the incident ray and the normal, and r is the angle of refraction, or the angle RPN' between the refracted ray and the normal.

The refractive index from medium 1 into medium 2 is written with distinguishing suffixes as ${}_1\mu_2$.

The absolute refractive index of a substance is the value of the constant when a ray passes into the substance from a vacuum; this is nearly the same as the value obtained for a ray passing into the substance from air. This may be written as μ .

EXPT. 99. Verification of the Laws of Refraction.—Place a rectangular glass block on a large sheet of drawing-paper, and mark its position by drawing a fine pencil line round it. Then set up two pins on one side of the block, so that the line joining them may represent the direction of a ray incident obliquely on the glass face. The two pins should be *at least* 10 cm. apart. Look through the glass from the opposite side and move the head until both pins can be seen. Then, using one eye only, move the head until the two pins appear to be in one straight line. Set up two more pins between the block and the eye, so that these also appear in line with the two pins on the far side of the block. The second pair of pins should be *at least* 10 cm. apart. Note that when the eye is just on a level with the surface of the paper the points where the four pins pierce the paper appear to be in one straight line. Since the block is rectangular, the normal to the refracting surface lies in the plane of the paper, so that the first law of refraction is verified.

Mark the positions of the pins (C, D, E, F) and remove pins and block from the paper. Join CD and produce the line to meet the first

surface of the block at P. Join EF and produce the line to meet the second surface of the block at Q. CD is evidently the direction of the incident ray and EF that of the emerging ray; hence the ray entered the glass at P and emerged at Q. Join PQ; then PQ represents the direction of the ray of light through the glass. Verify that the emergent ray EF is parallel to the incident ray CD. Draw the normals at P and at Q.




FIG. 131.—Refraction through Glass Block

The angle of incidence at the first surface is SPN. Call this angle i .

The angle of refraction at the first surface is N'PQ. Denote this by r .

The corresponding angles, MQR and M'QR at the second surface, are denoted by i' and e respectively.

To find the ratio of $\sin i$ to $\sin r$ two methods may be employed :

(1) Measure the angles i and r with a protractor, and look up the values of the sines in the tables (p. 573). Calculate the value of $\frac{\sin i}{\sin r}$.

(2) **A Graphic Method.**—Describe a circle with P as centre and a radius of at least 10 cm. Find the point S where the incident ray cuts the circle, and also the point R where the refracted ray PQ (produced if necessary) cuts the circle. From S and R draw perpendiculars SN and RN' to the normal at P. Measure carefully the lengths of these perpendiculars.

$$\text{Then} \quad \frac{\sin i}{\sin r} = \frac{SN/SP}{RN'/RP} = \frac{SN}{RN'}$$

Calculate the value of $\frac{SN}{RN'}$.

In order to verify the second law of refraction the determination must be repeated for *at least two* other positions of the incident ray. The values of $\frac{\sin i}{\sin r}$ obtained for different values of i should be in close agree-

ment. The mean of these values may be taken to represent the refractive index of the glass.

A similar determination may be applied for the refraction at the second surface of the glass, showing $\frac{\sin i'}{\sin e}$ is a constant.

The first constant determined, $\left(\frac{\sin i}{\sin r}\right)$, is the refractive index from air to glass.

The second constant is the refractive index from glass to air.

They may be denoted by ${}_a\mu_g$ and ${}_g\mu_a$ respectively. It will be found that ${}_g\mu_a = 1/{}_a\mu_g$.

This can be deduced from the facts that the block of glass is parallel-sided and the emerging ray is parallel to the incident ray, or $i = e$ and $r = i'$.

$$\text{Hence } {}_a\mu_g = \frac{\sin i}{\sin r} :: \frac{\sin e}{\sin i'} \quad \frac{1}{{}_g\mu_a}$$

Since $i = e$, there is no *deviation* produced by refraction through a parallel-sided block of any medium, the deviation at the one surface being exactly reversed at the other.

REFRACTION THROUGH A PRISM

When a ray passes through a prism of glass, or of some optically dense medium, as in Fig. 132, the deviation at the first surface is usually




FIG. 132.—Refraction through a Prism

followed by a deviation *in the same direction* at the second surface. Even if this be not the case, there is *on the whole* a deviation produced when a ray of light passes through a prism, the ray being bent towards the base of the prism. The angle between the direction of the emergent ray QT, and the direction of the incident ray SP, is called the **angle of deviation**. It is the angle marked D in Fig. 132. The amount of deviation produced by a given prism varies with the angle of incidence. It can be shown both by theory and by experiment, that the angle of deviation is least when the ray passes through the prism symmetrically ;

that is, when the direction of the ray in the glass (PQ) makes equal angles with the sides of the prism. The prism is then said to be in the position of **minimum deviation**.

In this case it can be shown that if i and r are the angles of incidence and refraction, the deviation $D = 2i - 2r$, and the angle of the prism $A = 2r$.

This gives $i = \frac{1}{2}(A + D)$ and $r = \frac{1}{2}A$.

Consequently

$$\mu = \frac{\sin i}{\sin r} = \frac{\sin \frac{1}{2}(A + D)}{\sin \frac{1}{2}A}.$$

To find the refractive index of the glass of a prism we measure the refracting angle A of the prism, and the angle D of minimum deviation, and calculate μ from the formula

$$\mu = \frac{\sin \frac{1}{2}(A + D)}{\sin \frac{1}{2}A}.$$

EXPT. 100. Refraction through a Glass Prism, using Pins.—Place a large glass prism on a sheet of drawing-paper with its refracting edge vertical, marking its position with a fine pencil line. Place a pin very close to one face of the prism and another pin about 10 cm. away from the first. Look into the other side of the prism, moving the eye until the two pins when seen through the refracting angle of the prism appear to be one behind the other. Place two pins between the eye and the prism, in line with these first pins as viewed through the prism. Draw the incident and emerging rays, produce them until they meet, and find the resulting angle of deviation: find also the angle of emergence. Keep the first pin in the same position in contact with the prism side, but place the second pin so that the incident ray considered makes a different angle of incidence with the prism face; find the corresponding emerging ray and angle of deviation.

Repeat this for several angles of incidence, altering this by 5° at a time, and plot a curve showing the variation of the angle of deviation with different angles of incidence.

This curve will have a minimum value corresponding with a certain angle of incidence. Show that for this value the angle of incidence and the angle of emergence are equal.

EXPT. 101. Determination of the Angle of Minimum Deviation for a Prism (Pin Method).—Place the prism on the drawing-board as before, with a pin in contact with one of the sides including the refracting angle, and a second pin about 10 cm. from this.

Observe these pins by looking through the refracting angle from the other side of the prism, placing the eye so as to see the two pins, one behind the other. Rotate the prism about the pin in contact with the side, moving the eye so as to keep the pins one behind the other in all positions of the prism.

The prism when rotated in one direction will require the eye to move in the direction in which the refracting angle points; reversing the direction of rotation will require a motion of the eye in the opposite direction (Fig. 132). In the first case, the motion of the prism reduces the deviation of the light, and as this is what is desired, the prism must be rotated so that the eye, when sighted on the pins, moves in the direction in which the refracting angle points.

When the prism has been rotated through some angle in this manner, the pins will appear to be stationary for a little while, although the prism is being moved slowly all the time. A further rotation of the prism requires the eye to *reverse* its former motion. This means that the deviation is beginning to *increase* again. The prism must be rotated back again slightly until the eye is as near the dotted line GK as possible.

When the prism is in the position of minimum deviation, set up two pins to mark the direction of the emergent ray, and trace the outline of the prism on the paper marking the refracting angle A. The prism and the pins may now be removed, and the diagram completed by producing the incident and the emergent rays so as to show the angle of minimum deviation, D. As a check on the accuracy of the setting, notice whether the path of the ray through the glass makes equal angles with the faces of the prism.




FIG. 133.—Graphic Method for μ

prism coincides with the point of intersection of the incident and emergent rays at K. The angle of the prism is then marked on the paper by drawing a line along the second edge of the prism, as in Fig. 133. With K as centre and a radius of 10 or 15 cm. a circle is described, cutting the three lines in X, Y, and Z.

Then from the geometry of the figure

$$\frac{\sin \frac{1}{2}(A+D)}{\sin \frac{1}{2}A} = \frac{XY}{XZ},$$

and therefore

$$\mu = \frac{XY}{XZ}.$$

Measure the lengths of XY and XZ and calculate the value of μ .

TOTAL INTERNAL REFLECTION AND THE CRITICAL ANGLE

When a ray of light passes from a denser into a rarer medium, it is bent *away from* the normal, and $\frac{\sin i}{\sin r} < 1$.

Thus the angle of refraction increases more rapidly than the angle of incidence.

¹ For this method we are indebted to Dr. W. Wilson, our colleague at King's College, London.

For a certain particular angle of incidence when $i = C$ say, the emerging ray just grazes the surface, or is parallel to the surface, so that the angle of refraction r is 90° , and thus $\frac{\sin C}{\sin 90^\circ} =$ the refractive index from the denser to the rarer medium.

But $\sin 90^\circ = 1$; therefore this refractive index is equal to $\sin C$.

Light incident at an angle *greater than* this angle C cannot emerge, since the angle of emergence would require to have a sine greater than unity, which is impossible; the whole of the light in this case would be reflected *totally internally*.

This limiting angle C , which is the angle of incidence for grazing emergence, or which is the smallest angle of incidence for which **total internal reflection** occurs, is called the **critical angle** for this pair of media.

If the rarer medium is air, $\sin C$ is the reciprocal of the refractive index for the denser medium (p. 198), since it is the refractive index *from the dense medium into air*.




FIG. 134.—Determination of Critical Angle

EXPT. 102. Determination of the Critical Angle.—A thin film of air is enclosed between two parallel plates of plate glass which are kept separate by a thin india-rubber ring, or an annulus cut out of tinfoil. This apparatus is fixed to a vertical spindle parallel to the faces of the plates, so that the whole may be rotated about a vertical axis. The angle of rotation can be measured by means of a co-axial circular scale, AA' (Fig. 134).

The glass plates with the enclosed air film dip into the liquid of which the critical angle is to be determined. The liquid is contained in a cubical glass box BB' , the sides of which are of plate glass.

A beam of light is passed through the liquid in a direction at right angles to one pair of sides. In order to obtain a definite beam, two narrow slits S_1, S_2 are employed, so that the eye looking through one slit receives the beam from a source of light beyond the other slit.

When the air film is perpendicular to the path of the beam of light, the light passes through it. As the spindle is rotated, the angle of incidence of the light passing from the liquid to air increases until the critical angle is reached. If the spindle is rotated through a greater angle, total reflection occurs, and no light is transmitted. The position on the graduated circle at which this occurs is noted. The cell is then rotated back so that the light is transmitted again, the rotation being continued until the light is extinguished once more. The angle through which the cell has been turned is equal to twice the critical angle for the liquid.

The refractive index of the liquid is then obtained from the formula

$$\mu = \frac{1}{\sin C}$$

Determine in this way the critical angle and the refractive index for water.

The extinction takes place when the light is incident *in glass* to the air film between the glass plates, that is when the angle of incidence *in the glass* is the critical angle for glass. The critical angle obtained, however, is the critical angle for water. This is shown as follows:—

If the angle of incidence in the water is C , the critical angle for water, and the angle of incidence to the glass-air surface is C' , then

$$\frac{\sin C}{\sin C'} = \mu \text{ between water and glass} = \frac{\mu \text{ for glass}}{\mu \text{ for water}},$$

that is
$$\frac{\sin C}{\sin C'} = \frac{\mu_g}{\mu_w}.$$

Now
$$\sin C = \frac{1}{\mu_w}.$$

$$\therefore \sin C' = \frac{1}{\mu_g};$$




FIG. 135.—Critical Angle

or if the light is incident to the water-glass surface at the critical angle for water, the refracted light will strike the glass-air surface at the critical angle for glass. Thus total internal reflection will occur at the glass-air surface when the angle of incidence to the water-glass surface is the critical angle for water.

REFRACTIVE INDEX BY APPARENT THICKNESS

To an observer looking vertically into a pond the depth of the water appears less than it actually is. In the same way the thickness of a slab of glass appears smaller than its real thickness to an observer looking through it. This is a direct consequence of the bending or refraction of the light in passing from the water or the glass into the air.

Let P be a point from which rays of light pass to emerge at the surface SS' separating the two media (Fig. 136). Two rays PS , PS' equally inclined to the normal PO will be refracted in directions SQ , $S'Q'$ as shown. The directions of these refracted rays, if produced backwards, meet in a point P' . An observer looking into the optically denser medium and receiving these two rays would infer that the point P' represented the position of the object.

If μ be the refractive index in passing into the denser medium,

$$\begin{aligned} \mu &= \frac{\sin QSM}{\sin PSN} = \frac{\sin SP'O}{\sin SPO} \\ &= \frac{OS/SP'}{OS/SP} = \frac{SP}{SP'}. \end{aligned}$$

When the observer is looking normally into the slab, the angles

OPS and OP'S are very small, so that SP becomes practically the same as OP, and SP' as OP'.

Then
$$\mu = \frac{OP}{OP'} = \frac{\text{Real thickness}}{\text{Apparent thickness}}.$$

If then we measure the real thickness and also the apparent thickness we can determine at once the refractive index of the material.

EXPT. 103. Refractive Index for Water by Apparent Depth.—Place a small white object at the bottom of a can or beaker. A pointed piece of white paper weighted by a coin will serve admirably. The bottom of the can must be blackened, or the beaker must stand on black paper or a dark bench. Fill the vessel with water, and place it at such a height that the observer can look down into it. Then fix a second paper pointer in a stand so that its height above the surface of the water can be adjusted. On looking down into the water the first paper can be seen without difficulty, and a *reflected* image of the second paper formed by reflection at the water surface can also be distinguished, *provided the lower face of the second paper is well illuminated.* The height of the second paper must now be adjusted until there is no parallax between the two images in question. The reflected image and the refracted image are now coincident; but the image formed by reflection is at the same distance below the water surface as the paper pointer is above that surface. Consequently the apparent depth is equal to the distance of the second paper above the water surface. Measure the apparent depth and the real depth and calculate the refractive index.




FIG. 136.—Apparent Thickness

EXPT. 104. Refractive Index for Glass by Apparent Thickness.—Use a large rectangular block of glass placed on a sheet of white paper across which a straight line has been drawn. On looking down from above the whole of the line can be seen, but part of it is viewed through the glass, part of it through air alone. The part of the line seen through the glass is apparently raised. Its apparent position is determined by raising or lowering a horizontal pin placed parallel to the line, with its point in contact with the side of the block, and finding when there is no parallax between the point of the pin and the line seen through the glass. The pin for this purpose should be mounted in a stand capable of vertical adjustment.

Measure the distance from the point of the pin to the upper surface of the glass, and also the real thickness of the block of glass. Calculate the refractive index of the glass.

This method is suitable only for thick blocks of glass. For thin sheets (2 cm. thick or less) a vernier microscope with a vertical adjustment is often employed.

EXPT. 105. Refractive Index by using a Microscope.—The microscope is adjusted so as to be in focus (α) on the paper, or some other flat surface,

when there is no glass, (b) on the paper through the glass, and (c) on the upper surface of the glass, care being taken that there is no parallax between the image seen and the cross-hairs of the microscope in each case.

From the readings of the vernier scale in these positions both the real thickness and the apparent thickness of the glass plate are easily deduced. The refractive index is then calculated as before.

The method with the vernier microscope is also applicable in the case of liquids of which only small quantities are available. Focus the microscope on the base of the containing vessel when it is empty and also when it is full, and again on the upper surface of the liquid, on which a floating speck of lycopodium has been placed.

§ 4. CAUSTIC CURVES

In the elementary theory of reflection and refraction at plane and spherical surfaces, it is assumed that a pencil of rays proceeding from a given point will, after reflection or refraction, converge to or diverge from a second point—the




FIG. 137.—Caustic by Reflection

conjugate focus. In general, this is only approximately true. Two consecutive rays may intersect one another, but the point of intersection need not exactly coincide with the point of intersection of two neighbouring consecutive rays; all the rays touch a certain curve called the caustic curve.

As an example, consider reflection at a concave hemispherical mirror when the incident rays are all parallel to the principal axis. Fig. 137 shows that only rays near the axis pass through the principal focus half-way between C and A. The other reflected rays touch a caustic curve which is symmetrical about the axis and has a cusp at the point F which is the principal focus of the mirror.

EXPT. 106. Caustic by Reflection.—Make an accurate drawing to scale in the note-book showing the caustic curve when parallel rays fall on a hemispherical mirror.

Draw a semicircle to represent a section of the mirror. Then draw any ray parallel to the axis CA. The corresponding reflected ray may be found by a simple construction. Draw a circle with centre C so as to touch the incident ray. Draw another tangent to this circle from the point where the incident ray meets the mirror. This tangent represents the reflected ray. (Prove this.)

Repeat the construction for several rays parallel to the axis, and draw a curve to represent the locus of intersections of consecutive reflected rays. This curve is a section of the caustic by reflection at a concave hemispherical mirror for incident rays parallel to the axis.

The caustic curve formed by refraction through a glass block may be traced experimentally by means of pins.

EXPT. 107. Caustic by Refraction.—Lay the glass block on a sheet of drawing paper and fix a pin about 2 cm. from one corner on one of the longer sides as at A (Fig. 138). Mark off a number of points P_1, P_2, P_3, \dots on the opposite side of the block half a centimetre apart. Place a pin at one of these points, P_1 say, and determine where another pin P_1' must be placed, so that on looking through the block the three pins appear in a straight line. Repeat the observation for each point P. When all the points have been found, remove the glass block, the trace




FIG. 138.—Caustic by Refraction

of which should be marked on the paper. Join the points P_1, P_1' by a line and produce it in both directions. Join the points P_2, P_2' in the same way. These two lines will meet in a point which represents the virtual image of the pin A as seen by an eye near P_1' . Join the remaining pairs of points in the same way. If the work has been done carefully it will be found that all the lines touch a caustic curve having a well-defined cusp.

In order to obtain both branches of the caustic curve, it may be necessary to shift the glass block sideways to the position indicated by the dotted lines. To an eye looking normally through the block, the virtual image would appear at the cusp of the caustic. The diagram should accompany the student's notes or be reproduced in the note-book.

Next calculate the refractive index of the glass by the formula proved on p. 203.

$$\mu = \frac{\text{Real thickness of block}}{\text{Apparent thickness of block}}$$

The apparent thickness is the distance from the face of the block nearest the observer to the cusp of the caustic curve. The real thickness should be measured with a pair of callipers.

NOTE.—The position of the point of the cusp A' cannot be determined with great accuracy, and the value of μ obtained by this graphic construction is therefore not very exact.

CHAPTER II

SPHERICAL MIRRORS

§ 1. INTRODUCTORY THEORY

THE mirror usually considered in elementary work is a polished surface having the form of a portion of a sphere. The centre of the sphere of which the mirror forms a part is called the **centre of curvature** of the mirror. If the polished surface faces the centre of curvature the mirror is **concave**, if the polished surface faces away from the centre of curvature the mirror is **convex**. The centre of curvature must be distinguished from the centre of the face of the mirror, which is usually called the **pole**. The **axis** of the mirror is the line joining the centre of curvature to the pole. The angle subtended by the diameter of the face of the mirror at its centre of curvature may be called its **aperture**; the aperture of a mirror is usually small.

If a pencil of rays parallel to the axis fall on a spherical mirror, they will either converge to (in the case of a concave mirror) or diverge from (in the case of a convex mirror) a point on the axis, called the **principal focus** of the mirror.

The principal focus of a spherical mirror is situated half-way between the pole of the mirror and the centre of curvature.

If a point source of light be placed at the principal focus of a concave mirror, the emergent pencil will consist of rays parallel to the axis. If a convergent pencil be directed towards the principal focus of a convex mirror, the emergent rays will be parallel to the axis.

Definite conventions must be adopted with regard to the signs to be attached to distances measured on the axis of a mirror. The following are frequently employed and were used in earlier editions :—

- (1) All distances are to be measured *from the pole*.
- (2) Distances on one side of the mirror are considered positive, on the other side negative.
- (3) Distances are to be considered positive when measured in a direction towards the source of light.

With these conventions the radius of curvature and the focal length of a concave mirror are reckoned positive, while the radius of curvature and the focal length of a convex mirror are reckoned negative (Fig. 139).

Alternative systems of conventions are given on pp. 545-555.

Two points on the axis are said to be **conjugate foci** when a pencil of rays diverging from one point and reflected from the mirror either




Fig. 139.—Concave and Convex Mirrors

converge to or diverge from the second point. One point may be called the geometrical image of the other point.

In the case of a mirror, radius of curvature r , focal length f , the distance u of the object from the pole and the distance v of the image from the pole are connected by the formula

$$\frac{1}{v} + \frac{1}{u} = \frac{1}{f} = \frac{2}{r}.$$

The curvature of a spherical surface may be measured by the reciprocal of the radius of the sphere. It is easy to see that the surface of a sphere of large radius has small curvature, while the surface of a sphere of small radius has large curvature. Thus if r denote the radius of a sphere, the curvature of the surface may be denoted by R , where $R = 1/r$. Opticians use a special unit for measuring curvature, the **DIOPTRE**. This unit represents the curvature of a sphere having a radius of 1 metre.

Hence the curvature in dioptres

$$= \frac{1}{r \text{ (metres)}} = \frac{100}{r \text{ (cm.)}} = \frac{39.37}{r \text{ (in.)}}.$$

The following table should be studied in order to form definite ideas as to curvatures expressed in this way :—

Curvature in dioptres	1	2	2.5	3	4	5	10	20	25	50	100
Radius of curvature in cm.	100	50	40	33.3	25	20	10	5	4	2	1

The Curvature of a Small Circular Arc is Proportional to the Sagitta of the Arc.

—If AMB be the chord of an arc APB, the distance PM on the diameter bisecting the chord at right angles is called the **sagitta** or **sag** of the arc.




Fig. 140.—Curvature of an Arc

Relation between Curvature and Sagitta of Arc.—In Fig. 140 PQ and AB are two chords intersecting at M.

$$\text{Hence} \quad \text{PM} \cdot \text{MQ} = \text{MA}^2,$$

$$\text{so that} \quad \text{PM} = \frac{\text{MA}^2}{\text{MQ}},$$

$$\text{or approximately} \quad \text{PM} = \frac{\text{MA}^2}{2r} = \frac{\text{MA}^2}{2} \times \text{R.}$$

Thus in the case of a number of small circular arcs having the same chord, the curvature of any arc is proportional to the sagitta. The sagitta is the distance measured by an ordinary spherometer, and it is possible to construct a spherometer which shall determine the curvature of a surface directly in dioptries. Simple instruments based on the same principle are used by opticians for measuring the curvature of the surface of a spectacle lens.

§ 2. FORMATION OF A REAL IMAGE BY A CONCAVE MIRROR

Image and Object Coincident.—If a small bright source of light be placed at the centre of curvature of a concave mirror, all the rays of light will fall on the face of the mirror normally. Consequently each ray will be reflected back along its original path, and all the reflected rays will pass through the centre of curvature. Thus an image of the source will be formed at the point of intersection of the rays at the centre of the sphere. Hence image and object coincide in position when the object is at the centre of curvature, and an *inverted* image will be formed.

EXPT. 108. Determination of the Radius of Curvature of a Concave Mirror.—The position of the centre of curvature can be found readily by setting up a small object such as a pin, and finding, by the method of parallax, the position in which the object and the image coincide. The mirror may be fixed with its face vertical, in which case it should be set up on a table, or it may be fixed with its face horizontal, in which case it should be placed on a stool of convenient height so that the observer can look down into it from above. On looking into the mirror the observer will see the reflection of his own face. Using one eye only, the head should be moved until the reflection of the open eye is seen in the middle of the mirror. Then the eye and its image are in the axis of the mirror.

Support a pin in a suitable stand and place it so that the point of the pin lies on the axis of the mirror. When this is the case the point of the




FIG. 141.—Coincidence of Pin Point and its Image

pin will appear to overlap the image of the eye seen in the mirror. If this adjustment is correct an image of the pin should be seen in the mirror, and, provided the pin is not too near the mirror, the image should be inverted. The important point to be observed for success, in practically

all optical experiments using pins, is that the observer should get as far away as convenient from the mirror or lens, and the object-pin should also be at a considerable distance.

The adjustment so far made secures that the point of the pin lies on the axis of the mirror, but the object and image do not necessarily coincide. The pin must be moved so that, to the eye looking along the axis, the point of the pin and the point of the image coincide. To test for such coincidence the method of parallax is employed (see p. 191).

When no parallax can be detected the point of the pin is at the centre of curvature of the mirror. Measure the radius of curvature, that is the distance from the pole of the mirror to the point of the pin.

Calculate the curvature of the surface in dioptries.

To check the result, the radius of curvature may be measured by means of the spherometer, but it must be remembered that in this case it is the front surface of the mirror that is employed, while in the optical measurement it is usually the back surface that is made use of. Many so-called concave mirrors are actually converging lenses mounted with a plane mirror behind them, or they may be lenses silvered on the back surface of the lens.

Conjugate Foci.—When an object is placed between the principal focus and the centre of curvature of a concave mirror, a real, inverted image is formed at a distance from the mirror greater than the radius of curvature. Such an image can be received upon a screen, as the rays forming the image actually intersect.

EXPT. 109. Determination of the Positions of Conjugate Foci of a Concave Mirror, and Deduction of the Focal Length.—Determine the radius of curvature of the mirror by the method described in Expt. 108. The principal focus is midway between the centre of curvature and the pole of the mirror. Place the pin, with its point still on the axis of the mirror, between the centre of curvature and the principal focus but not far from the centre of curvature *at first*. For this position of the pin an image will be formed real, inverted, and magnified, at a distance from the mirror greater than the radius of curvature.

To find the image, the observer should get at a considerable distance from the mirror, with his eye on the axis of the mirror (see p. 208). An inverted image of the pin will then be seen. For convenience, the object-pin may be provided with a small flag of paper to facilitate the recognition of its image.

Now take a second pin and set it up with its point along the axis of the mirror and adjust it by the parallax method, until it is in the continuation of the image of the first pin. Having found the correct position for the second pin, measure, as accurately as possible, the distance from the pole of the mirror to the point of the first pin (u), and the distance from the pole of the mirror to the image, that is to the point of the second pin (v).

Repeat the experiment for three or four positions of the object, moving the object nearer to the principal focus for each successive experiment. Note that the image moves further from the mirror as the object approaches the mirror.

The focal length of the concave mirror is now calculated in each case from the formula

$$\frac{1}{v} + \frac{1}{u} = \frac{1}{f}.$$

Great care must be taken in applying this *algebraic* formula. See the important note at the top of p. 210.

Signs in Optical Formulae.—In using any formula for mirrors or for lenses, the signs in the formula must never be altered. The values of the various quantities observed, u , v , etc., should be written down at the side, with the proper sign (+ or -) prefixed according to the conventions on p. 206. They should then be substituted in the formula, and no 'rectification' of signs should be made until the actual numerical values have been substituted in this manner. Failure to observe this rule is certain to lead to errors, especially in the more complicated expressions which are used in dealing with lenses.

§ 3. FORMATION OF A VIRTUAL IMAGE BY A SPHERICAL MIRROR

When a real object is placed in front of a convex mirror, or between the pole and the principal focus of a concave mirror, the image formed is **virtual**. The directions of the reflected rays, but not the rays themselves, intersect; consequently such an image cannot be received upon a screen.

EXPT. 110. Determination of the Focal Length of a Convex Mirror by the Pin Method.

METHOD I.—Place a pin in front of a convex mirror. The image is always behind the mirror, but its position can be found if a large pin is placed behind the mirror, and adjusted until its head, as viewed over the top of the mirror, gives no parallax with the virtual image of the first pin as seen in the mirror. Owing to spherical aberration, the adjustment cannot be carried out very accurately if the aperture of the mirror is large. Sometimes a small area of the silvering is removed from the centre of the mirror and the pin behind the mirror is viewed through the transparent hole left.

Observe the position of the reflected image for several positions of the object; note that as the object approaches the mirror the image also is brought nearer to the mirror. Measure u and v in each case.

Calculate the focal length of the mirror for each pair of distances obtained, taking special precautions as to the signs of these quantities (see note above).

For other methods of finding the radius of curvature suitable for use with a convex mirror see pp. 217-219.

EXPT. 111. Determination of the Focal Length of a Concave Mirror by means of a Virtual Image.—Carry out a similar experiment with a *concave* mirror, placing the object-pin between the principal focus and the pole of the mirror, and locating the virtual image either by looking over the top of the mirror, or through a hole in the middle.

CHAPTER III

LENSES

§ 1. INTRODUCTORY THEORY

THE lens considered in elementary work is bounded by two surfaces each of which forms a portion of a sphere. The lens is supposed to be *thin*, that is, the distance between the two surfaces is small compared




FIG. 142.—Converging (convex) and Diverging (concave) Lenses

with the radius of curvature of either surface. Since there are two surfaces there must be **two centres of curvature** and **two radii of curvature**. If one surface of the lens is plane the corresponding radius of curvature is infinite. The line joining the two centres of curvature is called the **axis** of the lens.

Lenses may be divided into two classes, **converging** and **diverging**.

A **converging lens** is thicker in the middle than it is at the edges. This is often called a **convex lens**.

A **diverging lens** is thinner in the middle than it is at the edges. This is often called a **concave lens**.

Lenses (unlike mirrors) possess **two principal foci** and **two focal lengths**, which are, however, equal to one another numerically. The focal length is the distance from the lens to a principal focus.

The **first principal focus** is the position of the object (point) for which the image is at infinity. It is the point corresponding to parallel emergent rays or the point for which the **out-rays** are parallel.

The **second principal focus** is the position of the image (point) when the object is at infinity. It is the point corresponding to parallel

incident rays or the point for which the in-rays are parallel. It is sometimes called the **solar focus**.

A plane drawn perpendicular to the axis through the point where the axis meets the lens is called the **principal plane** of the lens; planes drawn perpendicular to the axis through the focal points are termed the **focal planes**. The **optic centre** of a *thin* lens is the point where the axis meets the lens.

The angle subtended by the diameter of the lens at a principal focus may be called the **aperture** of a lens; the aperture of a simple lens is usually small.

As in the case of mirrors, definite conventions must be used with regard to the **signs** of all distances measured along the axis. The older conventions, used in this chapter, are as follows :—

- (1) All distances are to be measured *from the centre* of the lens.
- (2) Distances on one side of the lens are considered positive, on the other side negative.

- (3) Distances are to be considered positive when measured in a direction towards the source of light.

Alternative systems of conventions are given on pp. 545-555.

In speaking of the focal length of a lens, it is customary to consider the distance from the lens to the *second* principal focus as the **focal length**. With the conventions adopted, it follows that the focal length of a *convex* lens is to be reckoned *negative*, and the focal length of a *concave* lens *positive*.

In the case of a lens of focal length f , the distance u of the object from the lens and the distance v of the image from the lens are connected by the formula

$$\frac{1}{v} - \frac{1}{u} = \frac{1}{f}.$$

If we put $\frac{1}{v} = V$, $\frac{1}{u} = U$, and $\frac{1}{f} = F$, the formula may be written

$$V - U = F.$$

In this equation U measures the curvature of the incident wave-front, V the curvature of the wave-front after passing through the lens.

The quantity F , which is the reciprocal of the focal length of the lens, is called the **focal power** of the lens.

From the point of view of the Wave Theory of Light, this formula expresses the fact that the change produced in the curvature of the wave-front by the lens is equal to the focal power of the lens. These curvatures, and also the focal power of the lens, are measured in **dioptries** (p. 207). The focal power of a lens is 1 dioptry when its focal length is 1 metre.

Spectacle-makers call the focal power of a convex lens positive, and that of a concave lens negative. This convention is the opposite of that adopted above.

§ 2. SIMPLE EXPERIMENTS WITH LENSES

EXPT. 112. Determination of the Character of a Lens.—A simple, yet delicate, test for distinguishing between a convex and a concave lens is to hold the lens just in front of the eye, and to move it from side to side while viewing a distant object through it. If the object appear to move in the *opposite* direction to the lens, the lens is *convex*; if the object appear to move in the *same* direction as the lens, the lens is *concave*.

Test a number of thin lenses in this way, and separate the converging from the diverging lenses. Then combine the lenses in pairs and determine whether the combination is converging or diverging.

Examine the image formed by a convex lens of focal length 20 or 30 cm. When the lens is close to the eye, the image is erect and magnified. If the object is distant the image seen will be blurred, but objects at a smaller distance will give distinct virtual images. If, when viewing a distant object, the lens is moved away from the eye, the image becomes more and more blurred, until at a certain distance it is impossible to distinguish the character of the object at all. If, however, the lens is moved still further from the eye an inverted image will be seen. This is a real image formed between the lens and the eye.

Examine, in a similar way, the image formed by a concave lens. The image is always erect, diminished and virtual.

METHODS OF DETERMINING THE FOCAL LENGTH OF A CONVERGING (CONVEX) LENS

METHOD I. By finding the Image of a Distant Object.—If rays from a very distant source of light fall on a convex lens, they are rendered convergent and brought to a focus at the principal focus of the lens. The distance from the lens to this point is the focal length of the lens.

EXPT. 113. Determination of the Focal Length of a Convex Lens. I.—A simple method of finding the principal focus of a convex lens consists in forming a real image of a distant object on a screen by means of the lens. If direct light from the sun cannot be used, employ a distant lamp or window as the object. Adjust the lens so that a sharp image is focused on the screen, and measure the distance from lens to screen. This is approximately the focal length. It is essential that the distance of the object should be great compared with the focal length of the lens under test.

METHOD II. By using a Combination of Plane Mirror and Lens.—If a point source of light be placed at the principal focus of a convex lens the rays emerging from the lens will be parallel to one another. If now a plane mirror be placed at right angles to the emergent rays, they will be reflected back along their original path and after passing through the lens will form a real image at the point from which they started.

This fact may be made the basis of a simple method of finding the position of the principal focus of a convex lens or of any converging system of lenses.

EXPT. 114. Determination of the Focal Length of a Convex Lens. II.—Place a piece of plane mirror face upwards on a table; on it place the lens to be tested. Support a pin in a stand so that its point is vertically above the centre of the face of the lens. A paper flag attached to the pin may be used with advantage in finding the *real inverted image*.

[When the pin is at a sufficient distance from the lens the image is real and inverted. If the pin is lowered the image becomes blurred, and if it is lowered still further the image is virtual and erect. The action of the combination of lens and mirror is similar to that of a concave mirror.]

The observer must get as far away from the lens as convenient (see the caution on p. 208).

The pin must now be adjusted till the point of the pin and the point of this real image coincide, that is until there is no parallax between them. The method of adjustment is exactly the same as that already described in the process of finding the radius of curvature of a concave mirror (p. 208). When this position has been found, measure the distance from the upper surface of the lens to the pin, and also the distance from the lower surface of the lens (that is the surface of the mirror) to the pin. The mean of these distances gives the focal length of the lens.

The same method may be applied when the lens and mirror are supported with their faces vertical instead of horizontal.

METHOD III. By finding the Positions of Conjugate Foci.—In this method a pin is set up on one side of the lens so as to give a real image on the other




FIG. 143.—Conjugate Foci

side of the lens, and a second pin is adjusted so as to coincide in position with this real image.

For this to be possible two conditions must be satisfied. The object must be at a distance from the lens greater than the focal length. The distance between the two pins must be not less than four times the focal length.

EXPT. 115. Determination of the Focal Length of a Convex Lens.

III.—The adjustment presents no difficulty if the pin be placed some considerable distance from the lens, and the observer place his eye along the axis of the lens, on the side remote from the pin, and at a considerable distance from the lens. The object-pin should be supplied with a small flag as before. When the inverted image of pin No. 1 is seen, set up a second pin (pin No. 2 in Fig. 143) and adjust it till its point coincides in position with the point of the image, using the method of parallax.

Measure as accurately as possible the distance from the lens to the object (u) and the distance from the lens to the image (v) and calculate the focal length by means of the formula

$$\frac{1}{v} - \frac{1}{u} = \frac{1}{f}.$$

Remember to take into account the proper signs for u and v when substituting the numerical values in the formula (see note on p. 210).

Repeat the observations for two other positions of the object-pin, and take the mean of the values obtained for f to represent the focal length. Calculate also the focal power of the lens in dioptries.

METHODS OF DETERMINING THE FOCAL LENGTH OF A DIVERGING (CONCAVE) LENS

METHOD I. By Use of a Distant Object.—If rays from a very distant source of light fall on a concave lens, they are rendered divergent and appear to proceed from the principal focus of the lens.

EXPT. 116. Determination of the Focal Length of a Concave Lens.
I.—Set up a retort stand at a well-lighted window and at a distance of several metres from the concave lens. Place the lens vertically in a holder, and view the retort stand through the lens. An erect virtual image of the retort stand will be seen, this image being on the side of the lens remote from the observer. By placing a pin on the same side as the retort stand, but close up to the lens, the position of this image can be found. The pin is adjusted until, as viewed over the top of the lens, there is no parallax between it and the image of the retort stand viewed through the lens. The distance from the lens to the pin is the focal length of the lens when this condition is satisfied.

METHOD II. By Determination of Conjugate Foci.—In the case of a concave lens a real object gives rise to a virtual image on the same side of the lens as the object.

EXPT. 117. Determination of the Focal Length of a Concave Lens.
II.—Set up a pin at a distance of about 1 metre from the lens and adjust a second pin to coincide with the image of the first pin formed by the lens, in the same way as described in Method I for a distant object. Measure the distances of the object and image from the lens.

Repeat the experiment for several positions of the object and calculate the focal length of the lens from the formula

$$\frac{1}{v} - \frac{1}{u} = \frac{1}{f},$$

taking due note of the signs of the quantities involved.

NOTE.—The image seen through the lens will be distorted in consequence of spherical aberration, and the adjustment of the pin seen over the top, to the position where there is no parallax, is only approximate.

METHOD III. By combining with it a Suitable Convex Lens.—When two thin lenses are placed in contact the focal power of the combination is equal to the algebraic sum of the focal powers of the two component lenses. That is

$$F = F_1 + F_2,$$

or, since the focal power is inversely proportional to the focal length,

$$\frac{1}{f} = \frac{1}{f_1} + \frac{1}{f_2}.$$

In these formulæ F, f refer to the combination, F_1, f_1 to the first component, F_2, f_2 to the second component.

EXPT. 118. Determination of the Focal Length of a Concave Lens.
III.—If with the given concave lens a convex lens of sufficient power (or

of shorter focal length) is combined, a combination is obtained which acts like a convex lens. The focal length of this combination may be measured by any of the methods already given for a convex lens. The focal length of the single convex lens may be measured in a similar way. The focal length of the concave lens may then be calculated by substituting the values obtained in the formula above.

Care must be taken with regard to signs. According to the conventions adopted, the focal length of a convex lens or of a converging combination of lenses is to be considered negative.

CHAPTER IV

FURTHER EXPERIMENTS WITH MIRRORS AND LENSES

§ 1. RADIUS OF CURVATURE OF A SPHERICAL MIRROR

SOME simple methods of finding the radius of curvature of a spherical mirror have been described in Chapter II. When the image formed is real, its position may be found accurately by the method of parallax. When the image is virtual, the results obtained by this method are less accurate.

RADIUS OF CURVATURE OF A CONVEX MIRROR

METHOD I. See p. 210.

METHOD II. By using a Plane Mirror.—When an object is placed in front of a convex mirror, the image formed is necessarily virtual and lies between




FIG. 144.—Convex Mirror and Plane Mirror

the principal focus and the pole of the mirror. The following method, which is more generally applicable than the pin method already described, may be used to find the position of the virtual image.

EXPT. 119. Radius of Curvature of a Convex Mirror. II.—Set up a pin some distance in front of the convex mirror. On looking into the mirror from a position behind the pin the virtual diminished image can be seen easily. Now set up a piece of plane mirror between the pin and the convex mirror, so that its upper edge is on a level with the centre of the face of the convex mirror whilst its plane is perpendicular to the axis. Then on looking into the mirror as before from a position behind the pin, only the upper half of the convex mirror will be seen, the lower half being covered by the plane mirror. Two images of the pin will be seen, one in the convex mirror, the other in the plane mirror, the former being smaller than the latter, as shown on the right of Fig. 144. The

plane mirror must now be adjusted until there is no parallax between these two images; that is, until the image in the convex mirror appears to be a continuation of that in the plane mirror when the eye is moved into different positions from side to side. The image in the convex mirror should remain accurately in the *centre* of the plane-mirror image; when this is the case, the image Q formed of the pin P by the convex mirror at A coincides in position with the image of P formed by the plane mirror M. Measure the distances AP, AM, and MP. (Verify the accuracy of the measurements by seeing that $AP = AM + MP$.) Since M is a plane mirror we know that $MP = MQ$.

Hence find AQ which is the difference between MQ and AM, that is between MP and AM. We now know the *numerical* values of u , the distance of the




FIG. 145.—Convex Mirror and Lens

object from the pole, and of v , the distance of the image from the pole. We can therefore determine the radius of curvature r , or the focal length f , by means of the formula

$$\frac{1}{v} + \frac{1}{u} = \frac{2}{r} = \frac{1}{f}.$$

Pay special attention to the signs of the quantities considered. Several different determinations should be made, varying the positions of the plane mirror and of the pin.

METHOD III. By using a Convex Lens.—When a suitable convex lens is placed between a pin and a convex mirror, it is possible to adjust the lens and the pin so that a real image of the pin is formed in coincidence with the pin itself.

When the point of the pin coincides with its image, rays starting from the pin must retrace their original path after falling on the convex mirror. The condition necessary is that all the rays should fall on the mirror normally, or, in other words, that the rays after passing through the lens should be directed towards the centre of curvature of the mirror (Fig. 145). If then we can find the point to which the rays of light converge after passing through the lens we can find the centre of curvature of the mirror.

EXPT. 120. Radius of Curvature of a Convex Mirror. III.—Set up a pin some distance in front of the convex mirror. Between the pin and the mirror set up a convex lens so that its axis coincides in direction with the axis of the mirror. By properly adjusting the lens and (if necessary) the pin, a *real inverted* image of the pin can be formed and made to coincide in position with the pin itself. This coincidence can be tested by the method of parallax. Measure the distance LA between the mirror and the lens.

Remove the mirror altogether, *but be careful not to alter the position of the lens and the pin*. Then set up another pin so that its point may coincide in position with the image of the first pin formed by the lens. Test the coincidence by the method of parallax. Measure the distance LC between the lens and the second pin. Since the pin is now in the position that was occupied by the centre of curvature of the mirror, the radius of curvature is found at once by subtracting the first measurement from the second :

$$r = LC - LA.$$

NOTE.—A lens of suitable focal length should be chosen. The distance LC must be greater than the focal length of the lens, and the distance PC must be at least four times the focal length.

The results of all these experiments may be checked by measuring the radius of curvature with the spherometer, but it must be noted that the spherometer gives the radius of the front surface while the optical method gives the apparent radius of the back surface in the case of a glass mirror.

Calculate also the curvature of the surface in dioptries.

EXPT. 121. The Radius of Curvature of a Concave or Convex Mirror by means of a Turn-table.—A convenient method of determining the radius of curvature is by the use of a turn-table, consisting of a flat table which can turn about a vertical axis. The mirror is mounted on the table so that its axis is parallel to the table. A low-power telescope is used to view an ink-spot or a speck of lycopodium at the pole of the mirror, and the position of the mirror on the table is adjusted till no motion of this spot is observed when the table is rotated. This point must then lie on the axis about which the table is rotated.

The telescope is now used to view the reflection of some distant object in the mirror, and the mirror is adjusted again on the turn-table till no motion of this reflected image can be observed when the table is rotated. This will be the case when the centre of curvature of the mirror lies on the axis of rotation of the turn-table; for then the result of rotation is merely to substitute one portion of the spherical surface of the mirror for another, so that no displacement of the reflected image takes place.

The distance between the two positions of the mirror on the table is equal to its radius of curvature.

§ 2. FOCAL LENGTH OF A LENS

THE TELESCOPE OR RANGE-FINDER METHOD OF TESTING LENSES

By the following method very accurate determinations of the focal length of a lens can be made. The method is particularly interesting, as the actual position of the principal focus is determined both for a convex and a concave lens.

Light diverging from the first principal focus of a convex lens emerges from the lens as a parallel beam (Fig. 142).

If a parallel beam fall upon a concave lens it is rendered divergent and appears to proceed from a point which is the principal focus of the lens (Fig. 142).

In the case of thin lenses the distance between the lens and the principal focus is called the focal length of the lens.

The apparatus required consists of a needle with a sharp point mounted in a stand and a telescope with an eye-piece of high magnification.

necessary is provided with cross-wires, first focus the eye-piece till the cross-wires are seen distinctly, and then focus on a very distant object (seen through an open window) so that there is no parallax between the image on the cross-wire and the cross-wire. When once this adjustment has been made it must not be altered during the course of the experiment.

Set up the telescope on the table with the axis horizontal, and place the convex lens, the focal length of which is to be measured, in front of the object glass, taking care that the centre of the lens is on the axis of the telescope. Mount the needle so that its point is at the same height as the centre of the lens and move it about in front of the lens till an image is seen in the field of the telescope.

Adjust the position of the needle carefully so as to give the sharpest possible image with the point of the needle in the centre of the field of view. There must be no parallax between the cross-wire and the image of the pin as seen through the telescope. The point must then be at the principal focus of the lens. For as the telescope is adjusted for parallel light, the light falling on the object glass must form a parallel beam in order to give a clear image. Hence the light must diverge from F , the principal focus of the lens. Measure the distance AF , the focal length of the convex lens.

EXPT. 123. Determination of the Focal Length of a Concave Lens.—The focal length of the concave lens must be less than that of the convex lens just found for the following method to be applicable. First find




FIG. 146.—Focal Lengths by Telescope

the principal focus F of the convex lens A as in the previous experiment. Then place the concave lens C between A and F , and move it about until objects at a great distance are focused clearly. When this is the case F must also be the principal focus of the concave lens. The path of the rays is shown in Fig. 146. Parallel light from a distant object falling on the concave lens is rendered divergent and appears to come from the principal focus of the lens. This divergent light is rendered parallel by the convex lens. Hence the principal focus of the convex lens must coincide with the principal focus of the concave lens. Measure the distance CF , which is the focal length of the concave lens.

In finding the position of the point F in this case we may dispense with the needle point and move the concave lens till a point on its surface is

focused sharply. This point will be at F, and the focal length is the distance CF between the two positions of the lens.

A pair of lenses suitable for this experiment may be selected without difficulty; they will form a diverging combination when placed in contact.

§ 3. DETERMINATION OF REFRACTIVE INDICES

EXPT. 124. Determination of the Refractive Index of a Liquid, using a Concave Mirror.—Place the mirror with its face horizontal at a convenient level, so that the observer can look down into it from above.

Adjust a pin so that the image of its point coincides in position with the point itself as tested by the method of parallax. The process of adjustment has been described already on p. 208, where it was shown that the point must be at the centre of curvature of the mirror. Measure the distance from the pole of the mirror to the centre of curvature.

Place a small quantity of the liquid, the refractive index of which is sought, on the face of the mirror so as to form a shallow pool from 5 to 10 cm. in diameter. Again adjust the pin so that its point coincides in position with the real image formed by reflection in the mirror, and measure the distance from the pole of the mirror to the point. Then the refractive index of the liquid is found by dividing the first distance (the radius of curvature of the mirror) by the second.




FIG. 147.—Refractive Index of a Liquid using a Concave Mirror

The truth of this statement can be verified by drawing a figure showing the path of a ray from the point to the mirror in the second case (Fig. 147).

Let C be the position of the pin in the first experiment, P that in the second. Then C is the centre of curvature of the mirror. The ray PO, starting from the point P, is refracted on striking the surface of the water at O. The refracted ray after striking the surface of the mirror at R must retrace its original path in order that it may return to the point P. The condition for this is that the ray OR in the water should strike the mirror at right angles. Hence OR being a normal to the mirror must pass through the centre of curvature C.

The angle of incidence i is the angle PON, which is equal to the angle OPA. The angle of refraction r is the angle RON', which is equal to the angle OCA.

Thus

$$\begin{aligned}\mu &= \frac{\sin i}{\sin r} = \frac{\sin \text{OPA}}{\sin \text{OCA}} \\ &= \frac{\text{OB/OP}}{\text{OB/OC}} = \frac{\text{OC}}{\text{OP}}.\end{aligned}$$

When the angle of incidence is very small, this becomes approximately AC/AP, which proves the statement made above.

REFRACTIVE INDEX OF THE MATERIAL OF A LENS

The focal length (f) of a lens depends upon the refractive index (μ) of the material, and upon the radii of curvature r and s of the two surfaces, the formula connecting these quantities being

$$\frac{1}{f} = (\mu - 1) \left(\frac{1}{r} - \frac{1}{s} \right).$$

If by experiment the values of f , r , and s are determined the value of μ can be deduced. The quantity $\mu - 1$ which appears on the right hand side of the formula is called the **refractivity** of the material. It is assumed that the refractive index of air is equal to 1.

EXPT. 125. Determination of the Refractive Index of the Material of a Lens.—The focal length of the lens may be found by any of the methods already described, but for the present determination, if a convex lens be used, it may be found by the pin method No. III on p. 214.

The values of r and s might be found by an optical method regarding the surfaces of the lens as portions of spherical mirrors (see pp. 208 and 217). It is, however, sometimes convenient to determine these quantities by means of the spherometer as described on p. 37. It is important that attention should be paid to the conventions as to signs when substituting the numerical values for f , r , and s in the above formula (see note on p. 210).




FIG. 148.—Refraction Index of a Liquid, using a Lens and a Plane Mirror

The refractive index of a liquid, when only a small quantity is available, may be found by using the liquid to form a lens the focal length of which is then measured.

EXPT. 126. Determination of the Refractive Index of a Liquid, using a Lens and a Plane Mirror.—Select a convex lens having a focal length between 10 and 15 cm. Lay the lens on a plane horizontal mirror, and find the position of a pin point on the axis such that the point and its real image coincide. The distance from the centre of the lens to the pin is then equal to the focal length of the lens (Method II, p. 213). Now place a little of the liquid between the lower surface of the lens and the plane mirror. This will form a plano-concave lens of the liquid, the radius of curvature (r) of the upper surface of the liquid being the same as that of the lower surface of the glass lens.

If the focal length of this liquid lens be f_a ,

$$\frac{1}{f_a} = (\mu_a - 1) \frac{1}{r},$$

where μ_a is the refractive index of the liquid.

Now determine by the pin method the focal length of the compound lens of glass and liquid. Let this be f_s .

Then

$$\frac{1}{f_s} = \frac{1}{f} + \frac{1}{f_a} \quad \text{or} \quad \frac{1}{f_a} = \frac{1}{f_s} - \frac{1}{f}.$$

By means of this formula, f_a may be calculated, and the value thus found may be used in the previous formula in order to determine μ_a . The value of r may be found by using the spherometer.

The foregoing method may be used to *compare* the refractive indices of two liquids, *without requiring a knowledge of the radius of curvature r* . If a second liquid, of refractive index μ_b , be substituted for the first, the corresponding equations will be

$$\frac{1}{f_i} = (\mu_b - 1) \frac{1}{r}, \quad \text{and} \quad \frac{1}{f_b} = \frac{1}{f}.$$

Hence

$$\begin{aligned} \frac{\mu_a - 1}{\mu_b - 1} &= \frac{1/f_a}{1/f_b} \\ &= \frac{1/f_a - 1/f}{1/f_b - 1/f}. \end{aligned}$$

Consequently if f, f_a, f_b be measured by the method described, we can compare the *refractivities* of the two liquids. If the refractive index of one liquid be known, then that of the second can be calculated.

EXPT. 127. Comparison of the Refractive Indices of Two Liquids, using a Lens and a Plane Mirror.—It is convenient to use water ($\mu = 1.333$) as one of the liquids. Glycerin or anilin may be used as the other liquid. Measure the focal lengths f, f_a, f_b by the method of Expt. 126, calculate $1/f_a, 1/f_b$, and the refractive index of the liquid employed.

THE OPTICAL BENCH

§ 1. CONSTRUCTION OF THE OPTICAL BENCH

THE optical bench (Fig. 149) is used for carrying out accurate measurements in connection with mirrors and lenses or other optical apparatus. It consists of a long beam with guides like a lathe-bed, on which can slide a number of carriages to support the optical fittings. In this way the distance apart of the fittings can be varied without any transverse




FIG. 149.—Optical Bench

motion taking place. In some cases provision is made for a transverse motion also. In order to measure the distance between two particular fittings (say between the pole of a mirror and the screen used to receive the image) the bench is generally fitted with a graduated scale. The determination of the distance must be made by using a measuring rod or *distance-piece* of known length mounted on a carriage on the optical bench. The measuring rod is adjusted till one end of it (A) touches the mirror, and the position of its carriage on the bench is read. Then the carriage is moved till the other end (B) touches the screen, and the position of the carriage is again read. The difference between the two readings gives the distance through which the carriage has been moved. The distance to be found is equal to this distance plus the length of the measuring rod.

In some cases it is more convenient to make one end (A) of the rod touch the two fittings in succession. Then the distance between the fittings is simply the distance through which the carriage has been moved.

In experiments with mirrors and lenses on the optical bench, a real image of some object is formed usually on a white screen. The object may consist of a piece of wire gauze or two wires stretched at right angles across an aperture. The object should be illuminated by a source of light placed behind it. The flame of an oil or gas lamp may be used for this purpose; it is better to employ a small electric lamp (say 6 volts) mounted behind a short-focus lens at a distance equal to the focal length of the lens so as to throw a nearly parallel beam of light along the optical bench.

An alternative plan is to illuminate a ground-glass screen by the electric lamp, using a pin point mounted in an adjustable stand as the object. The pin should stand out clearly against the brightly illuminated background. A second pin is used in place of the screen on the optical bench, and is adjusted as in Fig. 143, Expt. 115, so as to coincide with the real image. This method will give accurate results, and may be used to supplement observations made with a screen. See p. 556.

It is important in all experiments with the optical bench that *all the lenses and mirrors used should lie on the same axis, which must be parallel to the bench itself.*

§ 2. EXPERIMENTS WITH THE OPTICAL BENCH

EXPT. 128. Optical Bench: Determination of the Focal Length and Radius of Curvature of a Concave Mirror.—Set up the mirror in its holder on the optical bench so that it faces a wire gauze which is illuminated by a lamp. Use a screen with a small hole at its centre placed between the gauze and the mirror. Adjust the gauze and screen so that the light passing through the gauze goes through the hole in the screen and falls on the mirror. For this adjustment it is necessary that the source of light, the centre of the gauze, the centre of the hole, and the pole of the mirror should be in a straight line.

By altering the position of the mirror it can be made to throw a distinct image on the screen close to the hole.

When the image is focused sharply on the screen, measure by means of the measuring rod the distance from the mirror to the object, u , and the distance from the mirror to the image, v . Write down the values of u and v with the proper signs affixed, and calculate the values of r and f by means of the formula

$$\frac{1}{v} + \frac{1}{u} = \frac{2}{r} = \frac{1}{f}.$$

Repeat the determination, using at least three different positions for the screen.

Lastly, adjust the mirror so that it throws on the screen a distinct image of a wire stretched across the hole in the screen. The mirror must be rotated slightly about a vertical axis, so that this image may be as close to the hole as possible. In this case $u=v$, and therefore $r=u$ or $f=r/2$. Tabulate the results obtained from u , v , r , and f .

Plot on squared paper the curve showing the relation between u as abscissa and v as ordinate.

Draw a diagram showing the paths of rays of light by which a real image is formed by a concave mirror.

EXPT. 129. Optical Bench : Determination of the Focal Length of a Convex Lens.—Set up the lens in its holder on the optical bench between the illuminated object and an adjustable screen. Adjust the height of the lens so that its axis passes through the centre of the object. A blurred image of the gauze will probably be seen on the screen. The position of the lens and the screen must now be altered until a sharp well-defined image is formed on the screen.

In carrying out the adjustment two points should be borne in mind :—

1. In order that the image formed by the lens should be real and not virtual, the distance from the lens to the object must be greater than the focal length; the lens must therefore be put some distance from the illuminated gauze.

2. In order that the real image should be formed on the screen, the distance between the object and the screen must be at least equal to four times the focal length. The screen should be put far enough away and gradually brought nearer until the image is focused sharply.

METHOD I.—Let

u = distance from the lens to the object,

v = distance from the lens to the image,

f = focal length of the lens.

Then (p. 212) $\frac{1}{v} - \frac{1}{u} = \frac{1}{f}$ or $V - U = F$.

Hence if u and v are measured, F and f may be calculated.

Measure the distances u and v by using the measuring rod fixed on a sliding carriage, and calculate the value of F and that of f , being careful to attach the proper signs to the numerical quantities.

Repeat the observations, using at least three different positions, and tabulate the results obtained.

It is instructive to draw a graph showing the relation between the values of u and v .

u	v	U	V	F	f

The mean value of f should be calculated, and the focal power expressed in dioptries.

Draw a diagram showing the paths of rays by which the real image is formed by a convex lens.

A Graphic Construction.—An interesting graphic construction for determining the value of the focal length is associated with the name of Sir Howard Grubb. Two axes at right angles to one another are taken, and the values of u are marked off along one axis, the corresponding values of v being marked off along the other axis. In the present case, since the

values of v are negative the corresponding axis is drawn downwards. Corresponding points on the axes are then joined by straight lines, and if the construction is carried out accurately all such lines should intersect in a single point. The distance of this point from each of the axes is equal to f , so that OM and MF in Fig. 150 are each equal to the focal length f .




FIG. 150.—Graphic Construction for Focal Length

METHOD II.—When a convex lens is used to form a real image of an object on a screen, there are in general *two* positions of the lens corresponding with a given distance between the object and the screen. In one of these positions the lens gives a magnified, in the other a diminished image. The distance from the lens to the object in the first case is equal to the distance from the lens to the screen in the second case.

Let d be the distance between the object and the screen, and a the distance between the two positions of the lens. Then

$$u = -\frac{d-a}{2}, \quad v = -\frac{d+a}{2},$$

and on substituting in the formula

$$\frac{1}{v} - \frac{1}{u} = \frac{1}{f}$$

we obtain

$$f = -\frac{d^2 - a^2}{4d}.$$

Set up the lens between the object and the screen so that a real image is formed on the screen. Keeping the object and the screen fixed, move the lens so as to find the second position in which it can form a real image. Measure the distance through which the lens has been moved, and also the distance between the object and the screen, and calculate the focal length.

As a particular case of the above, find by trial the position for which $a = 0$. In this case d has its minimum value and

$$f = -\frac{d}{4}.$$

EXPT. 130. Optical Bench : Determination of the Focal Length of a Concave Lens.—Since it is impossible to obtain a real image using a single concave lens, it is necessary to combine a convex lens of suitable focal length with the given concave lens in order to carry out the foregoing methods. The combination consisting of the convex and concave lenses should act like a convex lens, and the focal length of the combination (f) may be found as in Expt. 129. The focal length (f_1) of the single convex lens employed may be found by the same method. Then the focal length of the concave lens (f_2) may be calculated by means of the formula

$$\frac{1}{f} = \frac{1}{f_1} + \frac{1}{f_2}.$$

Care must be taken to give the proper signs to each quantity in the formula.

EXPT. 131. Measurement of the Radii of Curvature of the Surfaces of a Double Convex Lens.—First find the focal length of the lens by one




FIG. 151.—Reflection from the Second Face of a Lens

of the methods already described. Next find the distance from the lens at which an object must be placed so that it may coincide in position with the image formed by reflection from the *second* face of the lens.

The way in which this image is formed is shown in Fig. 151. A ray starting from P and refracted by the first surface of the lens will retrace its original path after reflection from the second surface provided it meet that surface at right angles. Consequently the refracted ray QR must pass through C, the centre of curvature of the second surface. Some of the light is transmitted through this surface as shown by the dotted lines on the right. Thus C is the virtual image of P formed by rays passing *through* the lens. If $OP = d$ and $OC = s$, then in the equation

$$\frac{1}{v} - \frac{1}{u} = \frac{1}{f}, \quad u = d, v = s.$$

Hence

so that
$$s = \frac{df}{d+f}.$$

In this formula f is to be considered as having its *algebraic* value.

The experimental determination of d may be carried out by using the method of parallax with a pin as the object, but as the image formed by reflection is faint it is easier to carry out the measurement on the

optical bench, using a screen with a circular aperture crossed by wires at right angles to receive the image of the illuminated aperture. Since object and image are then at the same distance from the lens, the distance from the lens to the screen is equal to d .

In a dark room the experiment can be done with a pin fitted with a small well-illuminated flag, or in the laboratory the lens may be floated on mercury to intensify the reflection.

The radius of curvature r , of the other face of the lens, may be found by the same method after reversing the lens in its holder.

Knowing the values of f , r , and s , the refractive index of the lens can be found from the formula

$$\frac{1}{f} = (\mu - 1) \left(\frac{1}{r} - \frac{1}{s} \right).$$

The quantities f , r , and s must all be prefixed with their proper signs. To do this for the two radii, the lens may be imagined to be set up for use ; one side is considered as the *incident* side, and all distances measured on this side are positive. Thus, if either surface of the lens is *convex* in this direction, its radius of curvature is negative since its radius would be measured in the opposite direction, and so on.

CHAPTER VI

OPTICAL INSTRUMENTS

§ 1. MAGNIFYING POWER OF A SIMPLE LENS

THE apparent size of an object depends on the angle which the object subtends at the observer's eye, that is, it depends on the linear dimen-




FIG. 152.—Magnifying Power of Lens

sions of the object and on its distance from the eye. By bringing the object nearer to the eye its apparent size is increased, but when it is brought too close it cannot be seen distinctly. The least distance of distinct vision for a normal eye is taken usually as 25 cm.

When a single lens is used as a simple microscope, it is placed close to the eye, and the distance of the object is adjusted so that a virtual image is formed about 25 cm. away. Thus, if AB is an object at a distance from the convex lens less than its focal length, a virtual image is formed at *ab* which should be 25 cm. from the eye (Fig. 152).

The **magnifying power** of a lens or microscope¹ is defined as the ratio of the angle subtended at the eye by the virtual image to the angle which would be subtended at the eye by the object *when placed 25 cm. away*. That is

Magnifying power, $M = \frac{\text{Angle subtended at the eye by } ab \text{ at } 25 \text{ cm.}}{\text{Angle subtended at the eye by } AB \text{ at } 25 \text{ cm.}}$

¹ In speaking of a telescope the expression 'magnifying power' is used in a different sense (p. 235).

When the angles are small and the eye is almost touching the lens, we have

$$\text{Magnifying power, } M = \frac{ab/25}{AB/25} = \frac{ab}{AB}.$$

Consequently the magnifying power is equal to the linear magnification.

Relation of Magnifying Power to Focal Length of Lens.—Let the focal length of the lens be f cm. Let the distance of AB from the lens be u cm.

$$\text{Then} \quad \frac{1}{25} - \frac{1}{u} = \frac{1}{f};$$

$$\therefore \frac{1}{u} = \frac{1}{25} - \frac{1}{f}.$$

$$\text{But the magnifying power } M = \frac{ab}{AB} = \frac{25}{u} = 1 - \frac{25}{f}.$$

Hence, if f be known, the magnifying power can be calculated. Here f has its algebraic value; for a convex lens it is negative.

EXPT. 132. Determination of Magnifying Power of a Simple Lens.

METHOD I.—Measure the focal length of the lens by placing it between two pins, and adjusting the distances of the pins so that the image of one coincides with the other. Measure the distances (u and v) of the pins from the lens, and substitute in the formula

$$\frac{1}{v} - \frac{1}{u} = \frac{1}{f}.$$

Remember that distances are positive only when measured opposite to the direction in which the light is travelling. Knowing the focal length, the magnifying power is given by

$$M = 1 - \frac{25}{f}.$$

METHOD II.—Place a millimetre scale on the table, and support another scale about 20 cm. above it, and parallel to it. View the upper scale with the lens, and arrange so that the lower scale can be seen directly at the same time with the other eye. Adjust the lens and scales so that both scales can be seen distinctly, the upper through the lens and the lower directly. Then count the number of millimetres on the lower scale which appear equal to two or to three millimetres on the upper scale. Let N_1 mm. on the upper scale equal N_2 on the lower scale.

$$\text{Then} \quad M = \frac{N_2}{N_1}.$$

§ 2. THE MICROSCOPE

CONSTRUCTION AND MAGNIFYING POWER OF A MICROSCOPE

The essential parts of a compound microscope are two convex lenses of short focal length :

- (1) The object-glass or objective.
- (2) The eye-piece or eye-lens.

The distance between the object and the objective is a little greater than the focal length of the objective. Consequently a real inverted magnified image is produced on the other side of the lens. In Fig. 153 AB is the object, A'B' is the real magnified inverted image formed by the object-glass at O. This real image is then viewed through the eye-lens, which acts in exactly the same way as a magnifying glass.¹

The distance between the real image and the eye-lens is less than the focal length of the lens; consequently a magnified virtual image is produced. The lens is adjusted so that this virtual image is formed at the




Fig. 153.—Magnifying Power of Microscope

least distance of distinct vision, usually taken as 25 cm. from the eye. A'B' is the real image formed by the objective, A''B'' is the virtual image formed by the eye-piece E.

The magnifying power of the instrument is defined as the ratio of the angle subtended at the eye by the image A''B'' to the angle subtended at the eye by the object when placed at the least distance of distinct vision.

Hence the magnifying power

$$\begin{aligned}
 &= \frac{\text{Angle subtended at E by } A''B''}{\text{Angle subtended at E by object at 25 cm.}} \\
 &= \frac{\text{Angle subtended at E by } A''B''}{\text{Angle subtended at E by } ab} \quad (\text{where } ab = AB), \\
 &= \frac{A''B''}{ab}, \text{ approximately.}
 \end{aligned}$$

EXPT. 133. Construction of a Microscope.—1. It may be convenient to set up the microscope on an optical bench with its axis horizontal. Here the axis is taken to be vertical. As the object use a small piece of squared paper, or a short clearly marked millimetre scale, placed on the horizontal base of a retort stand.

2. Find approximately the focal length of the short-focus lens² to be used as objective, and support the lens above the squared paper at a distance a little greater than this.

3. Above the lens place a small horizontal platform with a circular hole in it, and arrange matters so that the axis of the lens passes through the centre of the hole. A second piece of squared paper is fixed on the platform.

¹ If the experiment on the determination of the magnifying power of a simple lens has not been done, it should be worked through before going further with the compound microscope.

² The focal length should be less than 5 cm., preferably about 2 or 3 cm.

4. Above the platform arrange on the retort stand a metal ring carrying cross-wires. On looking down from above, the real magnified image $A'B'$ will be seen. Adjust the height of the cross-wires so that there is no parallax between them and the lines of the image. When this is the case the cross-wires must be in the same horizontal plane as the image formed by the object-glass.

5. Place the eye-piece¹ in position so as to magnify the image formed by the object-glass.

6. The image which the eye-piece forms of the object-glass is called the **eye-ring** or **Ramsden circle**. Through it passes all the light which traverses the instrument. When the eye is at the **eye-point** (the centre of this circle), the field of the eye-lens should appear filled with the magnified image of the squared paper. Mark the position by a metal ring.

7. Adjust the platform till it is 25 cm. from the eye-ring.

EXPT. 134. Magnifying Power of a Microscope.

METHOD I.—Observe the squared paper on the platform directly with one eye while looking through the microscope at the magnified image of the first paper with the other eye. With practice it is possible (assuming the vision of both eyes to be normal) to see the two images at the same time with the magnified squares overlapping those seen directly. If any difficulty is found in seeing the two images together, try opening and shutting the eyes alternately for a time so as to see separate images, and then open both eyes at once to get the superposed images. Observe the number n of divisions seen directly which correspond with a number m seen through the microscope. Then the magnification is n/m , for in this case $A''B''/ab = n/m$.

In this determination the eye should be placed at the eye-ring.

METHOD II.—Determine separately the magnification M_o , produced by the objective, and M_e , that produced by the eye-lens; then the magnifying power of the microscope is $M = M_o \times M_e$.

Determination of M_o .—Place a small piece of squared paper on the ring supporting the cross-wires and arrange it so that the divisions are alongside the divisions of the real image $A'B'$. Find the number n' of divisions on this small piece of paper which correspond with a number m' of the image $A'B'$.

Then

$$M_o = \frac{n'}{m'}$$

Determination of M_e .—To find the magnifying power of the eye-piece, place a small piece of squared paper on the ring supporting the cross-wires and arrange it so that it covers over the real image $A'B'$. Then place the eye at the eye-ring and compare the divisions on this piece of paper with the divisions on the squared paper on the platform seen with the other eye. The process is exactly that employed in finding the magnifying power of a simple lens. Note the value of M_e thus found and calculate

$$M = M_o \times M_e.$$

METHOD III.—Determine M_o and M_e separately by calculation, and calculate $M = M_o \times M_e$.

To calculate M_o :—

$$\begin{aligned} M_o &= \frac{\text{Size of image } A'B'}{\text{Size of object } AB} \\ &= \frac{\text{Distance of image } A'B' \text{ from O}}{\text{Distance of object from O}}. \end{aligned}$$

¹ The focal length of the lens for the eye-piece should be less than 7 cm., preferably about 4 or 5 cm.

Measure these distances and calculate M_o . Note that the distance of the object AB from O is very nearly equal to the focal length of the object-glass, while the distance of the image A'B' from O is about the length of the microscope tube.

To calculate M_e :—

Assuming the eye-ring to be very near the eye-lens the magnifying power of the eye-lens is given by the formula

$$M_e = 1 - \frac{25}{f},$$

where f stands for the algebraic value of the focal length of the eye-lens. Find f , and calculate M_e , and hence determine

$$M = M_o \times M_e.$$

If the distance between the eye-ring and the eye-lens is not small, let it be denoted by e . The virtual image is formed at 25 cm. from the eye-ring, not from the eye-lens. The magnifying power is now

$$M_e = 1 - \frac{25 - e}{f}.$$

Since e is nearly equal to f this gives as an approximate formula

$$M_e = - \frac{25}{f}.$$

§ 3. THE TELESCOPE

CONSTRUCTION AND MAGNIFYING POWER OF A TELESCOPE

The essential parts of a refracting astronomical telescope are two convex lenses :

- (1) The object-glass or objective of long focal length.
- (2) The eye-piece or eye-lens of short focal length.

The lens of long focal length forms a real inverted image of a distant object. If the object be *very* distant, as may be assumed for the astronomical telescope, this image is formed in the focal plane of the lens.

In Fig. 154, rays coming from a point of the distant object in a direction parallel to the axis are brought to a focus at F, the principal focus of the object-glass O. A pencil of parallel rays coming from some other point of the distant object in a direction parallel to AO is brought to a focus at A', a point in the focal plane of the object-glass.

The real inverted image thus formed is then magnified by the eye-lens, which forms a virtual image on the same side of the eye-lens as this real image.

When the telescope is in normal adjustment, the eye-lens is placed at a distance equal to its focal length beyond the real image formed by the object-glass. Consequently, in this case the rays emerging from the eye-piece are parallel, the final virtual image being formed at an

infinite distance from the eye. The direction of the parallel rays is found by joining A' to E , the centre of the eye-lens.

If the eye, accommodated for distant vision, be placed behind the eye-lens, the parallel rays will be brought to a focus on the retina and a magnified image will be seen.

The **magnifying power** of an optical instrument is defined as the ratio of the angle subtended at the eye by the image to the angle subtended by the object.

In order to make this definition complete, it is necessary to specify the exact position of the image and also that of the object. In dealing




FIG. 154.—Telescope in Normal Adjustment

with the magnifying glass or the microscope, it is usual to assume that, in making the comparison, both the image and the object are placed at the least distance of distinct vision, that is about 25 cm. from the eye.

In the case of the astronomical telescope such an assumption would obviously be absurd, and instead we assume both image and object are at an infinite distance from the eye.

Thus for a telescope in normal adjustment the magnifying power

$$\begin{aligned}
 &= \frac{\text{Angle subtended by image}}{\text{Angle subtended by object}} \\
 &= \frac{A'EB}{AOB} = \frac{A'EF}{A'OF} \\
 &= \frac{A'F/EF}{A'F/OF} \quad \begin{array}{l} \text{regarding the circular measure} \\ \text{as equal to the tangent of the} \\ \text{small angle;} \end{array} \\
 &= \frac{\text{Focal length of object-glass}}{\text{Focal length of eye-lens}}
 \end{aligned}$$

The simple telescope is often used to view terrestrial objects the distance of which may be considerable but still far from infinite. In

such a case the telescope is not in normal adjustment, and the final image may be formed at any distance convenient to the observer. Thus, the observer may adjust the eye-lens so that the final image is at the same distance from the eye as the object, or he may prefer to have the final image at the least distance of distinct vision.




FIG. 155.—Telescope not in Normal Adjustment

The magnifying power can then be calculated as follows :—

$$\begin{aligned}\text{Magnifying power} &= \frac{\text{Angle subtended by image}}{\text{Angle subtended by object}} \\ &= \frac{A'EB''}{AOB} = \frac{A'EB'}{A'OB'}, \\ &= \frac{OB'}{EB'}, \text{ approximately.}\end{aligned}$$

Thus the magnifying power

$$= \frac{\text{Distance of real image from object-glass}}{\text{Distance of real image from eye-lens}}.$$

This expression holds good whether the telescope is or is not in normal adjustment, and whatever be the distance of the final virtual image from the eye.

EXPT. 135. Construction of a Simple Telescope.—Set up a graduated scale at a considerable distance to serve as the object. In default of a scale, a brick wall forms a convenient object on which to make observations. Choose two convex lenses, one having as long, the other as short, a focal length as possible. Set up the long focus lens to serve as the object-glass so as to produce a real image of the distant scale. This real image can be seen by an eye placed at a sufficient distance behind it. Set up a pin so that it coincides in position with the real image of one of the divisions of the scale. This will be the case when there is no parallax between the pin and the image.

Then arrange the short focus lens as an eye-piece to magnify the real image, so that the divisions of the scale are clearly visible.

EXPT. 136. Magnifying Power of a Telescope.—With one eye look through the telescope, with the other look at the scale directly. The two eyes are thus being used independently at the same time, and this fact may cause difficulty on a first trial. The difficulty is reduced by arranging the eye-lens so that the *accommodation* is the same for both eyes, and then the final virtual image is formed at the same distance from the observer as the scale itself. Focus the telescope by moving the eye-lens, with the idea clearly in mind that the image is situated at the actual distance of the scale. If the adjustment is correct, and both

eyes are made use of, a slight movement of the head should not cause relative movement of the two images.

Fix the attention on a certain definite number m of divisions seen through the telescope, and notice the number n seen *directly*, which correspond with these. Then the magnifying power $= n/m$.

Verify this by measuring the distance from the object-glass to the pin, and dividing it by the distance from the eye-lens to the pin.

Also determine the focal lengths of the two lenses and calculate the ratio of the focal length of the object-glass to that of the eye-lens. This gives the value of the magnifying power for the telescope in normal adjustment.

§ 4. THE OPTICAL LANTERN

The optical lantern is used for projecting a magnified image of an object — usually a photographic transparency — on a distant screen. It comprises two lenses, or lens systems, the projection lens (or objective),




FIG. 156.—Diagram showing Construction of Optical Lantern

and the condenser. The former is a corrected achromatic system which gives a real, magnified image ab of an object AB placed at a point somewhat beyond the first principal focus. The condenser usually consists of two plano-convex lenses mounted near together and forming a converging system. Its object is to concentrate the divergent light from the source, so that as much light as possible may pass through the middle of the projection lens. This causes the image to be distorted as little as possible and also gives the largest field.

The **linear magnification** produced by the projection lens is the ratio of the linear dimensions of the image to the corresponding linear dimensions of the object. This ratio is considered positive for an erect, negative for an inverted, image. The general formula for the linear magnification m is

$$m = \frac{v}{u},$$

for the length of the image is to that of the object as the distance v of the image from the lens is to the distance u of the object from the lens.

But $\frac{1}{v} - \frac{1}{u} = \frac{1}{f}$ for a lens of focal length f .

Hence $1 - \frac{v}{u} = \frac{v}{f}$ or $1 - m = \frac{v}{f}$.

Thus the focal length $f = \frac{v}{1 - m}$

EXPT. 137. Construction of an Optical Lantern.—To illustrate the action of the optical lantern select two lenses of large aperture, one having a focal length of about 25 cm., the other about 15 cm. A source of light of small dimensions is required. This may be secured by placing the flame of a candle or lamp behind a hole of about 0.5 cm. diameter in a metal screen. As object a metal arrow, or a scale ruled on glass, may be employed. If an attempt is made to obtain a magnified image on a distant screen, using the lens of longer focal length as the projection lens, it will be found that the image is very faint, and that only the central portions appear at all. Now place the lens of shorter focal length behind the object, and adjust the screen with the hole in it so as to form an image of the hole at the place occupied by the projection lens. This means that the hole and the projection lens are at conjugate foci with regard to the condenser or short focus lens. For example, the apparatus may be adjusted so that the distance between the hole and the projection lens is a minimum (p. 227) and equal to four times the focal length of the condenser. The conjugate foci in this case are said to be the *symmetric points* of the lens.

If the object is just in front of the condenser, the image on the screen should now be uniformly illuminated and all parts of the object (assumed smaller than the aperture of the condenser) should be represented on the screen. Examine the effect of moving the position of the screen with the hole in it, and notice that there is only one position which gives uniform illumination.

EXPT. 138. Measurement of the Magnification and Determination of the Focal Length of the Projection Lens.—Measure the distance between two well-defined points on the object, and the corresponding distance between the image points. Calculate the linear magnification, which in this case is considered negative as the image is inverted.

Measure the distance from the lens to the screen and deduce the value of the focal length f from the formula

$$f = \frac{v}{1 - m},$$

being careful to give the proper signs to v and to m .

SPECTRA AND THE SPECTROMETER

§ 1. FORMATION OF THE SPECTRUM

WHEN white light is passed through a prism, as in the celebrated experiment of Sir Isaac Newton, the light is dispersed giving rise to a coloured band known as the **spectrum**. To produce a pure spectrum, in which there is no overlapping of the images of different colours, it is necessary to use a very narrow slit, and also to pass parallel rays through the prism when the latter is in the position of minimum deviation.

EXPT. 139. Projection of a Spectrum on a Screen.—A powerful source of white light is required, such as lime light or the electric arc, but in a perfectly dark room a gas or oil lamp may be used. The light of the source should be brought to a focus on a narrow vertical slit in a metal plate by a converging or convex lens used as a **condenser**.

A second convex lens is placed on the other side of the slit, and is adjusted till a sharp image of the slit is formed on a white screen.

The prism is then placed, with its refracting edge vertical, in the path of the light issuing from the lens. On placing a sheet of white paper in the path of the emergent rays, a coloured band will be seen, and the screen will, in general, require to be moved from its first position, so that this band of colour may fall upon it. Rotate the prism about a vertical axis, and note whether the coloured image moves towards or away from the original undeviated image. Turn the prism until the position of minimum deviation is reached, so that the spectrum is formed as near as possible to the undeviated image. It will probably be necessary to focus the image of the slit on the screen again, after the position of minimum deviation has been found. This may be done by placing a small piece of plane mirror in the path of the light issuing from the lens, turning the mirror till a white image of the slit is formed on the screen close to the spectrum, and then moving the lens till this image is in sharp focus. In this way a moderately pure spectrum is projected upon the screen.




FIG. 157.—Projection of Spectrum

Since the rays passing through the prism belong to a converging beam the spectrum produced is not strictly a pure spectrum. To satisfy the condition that monochromatic rays should be parallel, when passing through

the prism, the distance between the lens and the slit must be equal to the focal length of the lens. An eye placed to receive the beam emerging from the prism would then see a virtual pure spectrum. In order to project the pure spectrum on a screen, a second convex lens must be placed in




FIG. 158.—Projection of Pure Spectrum

the path of the light, so that its distance from the screen is equal to its focal length. This arrangement for projecting a pure spectrum is sometimes useful, as, for example, when it is desired to photograph the spectrum by replacing the screen by a photographic plate. The same principle is employed in the construction of the spectrometer.

§ 2. THE SPECTROMETER

The **spectroscope** is an instrument for producing dispersion of rays of light so as to form a spectrum, and for observing the spectrum so formed.




FIG. 159.—Spectrometer

The **spectrometer** is a similar instrument provided with suitable arrangements for *measuring* the deviation of the dispersed rays.

The essential parts of such an instrument are :—

- (1) The **collimator**, which is an apparatus for securing a pencil of parallel rays.
- (2) The **prism** (or diffraction grating), for dispersing the rays, mounted on a revolving table.
- (3) The **telescope**, for viewing the spectrum.

The spectrometer is also provided with graduated circles (with verniers) for determining accurately the positions of the prism and




FIG. 160.—Plan of Spectrometer

the telescope. Figs. 159 and 160 show the most important features of the instrument.

The **collimator** is a tube which carries at one end a narrow adjustable slit S, and at the other an achromatic convex lens L. The slit is illuminated by the source of light the spectrum of which is to be examined. For many purposes a flame impregnated with a salt of sodium, and showing a characteristic yellow coloration, is a convenient source, since the light is approximately monochromatic. The distance between the slit and the lens can be adjusted so that the slit is at the focus of the lens and the light emerges from the lens as a parallel beam.

The **prism** ABC rests on a circular table D, which is capable of rotation about a vertical axis. The table is provided usually with a clamp so that it may be fixed in any desired position, and sometimes with a tangent screw to give it a slow motion.

Parallel light emerging from the prism falls on the lens M, and is thereby brought to a focus at F, the principal focus of the lens, so that a real image of the slit is formed in the focal plane. Another lens E (or more commonly a compound eye-piece) is used to give a magnified virtual image of this real image. The two lenses M and E, mounted in a tube, together constitute a **telescope**. The telescope can be rotated about the same vertical axis as the prism table, and, like the latter, is usually provided with a clamp and a tangent screw.

Great care must be taken in the use of an angular scale and vernier, such as that shown in Fig. 5, to make quite sure of the least angle that can be determined by means of the vernier provided. All readings should be checked before the clamp is released.

EXPT. 140. Adjustments of a Spectrometer.—The exact adjustment of a spectrometer is a process which requires considerable care. It may

be assumed that the mechanical adjustments have been made by the instrument-maker, and only the principal optical adjustments will be described.

The Telescope.—The eye-piece of the telescope is used to give a magnified image of an object placed at a certain small distance from the field-lens. It is made to slide in and out of the telescope tube. Turn the telescope towards a uniformly illuminated surface, such as a light wall, and slide the eyepiece in and out of the tube until the spider-line or cross-wires fixed in the tube can be seen distinctly. The eye-piece is now said to be **in focus on the cross-wires**. In consequence of the power of accommodation of the eye there is, however, a certain amount of latitude in this adjustment. It is next necessary to focus the telescope for parallel rays, *i.e.* to make the distance of the object-glass from the cross-wires equal to the focal length of the lens. The simplest way of making this adjustment is to focus the telescope on a very distant object.

When the adjustment has been made, the observer looking through the telescope should be able to see clearly both the distant object and the cross-wires without altering the accommodation of the eye. To test the accuracy of the adjustment the method of no parallax should be used, that is, the eye should be moved from side to side *behind the eye-piece* and any relative motion of the spider-line and the distant object should be noted. The adjustment is correct when no such motion can be observed.

The Collimator.—Set up a sodium flame (p. 241) so that the brightest part of the flame is opposite the slit of the collimator, and turn the telescope so that the axes of the tubes are in the same straight line.

On looking through the telescope the yellow light passing through the slit should be seen, but the image of the slit will, as a rule, be badly defined. Now *focus the collimator* by altering the distance between the slit and the lens until the image of the slit is seen with clear and well-defined edges.

When the adjustment is correct there should be no parallax between the cross-wires and the edges of the slit. Since the telescope already has been adjusted for parallel light, the collimator must now be giving parallel light from the slit.

EXPT. 141. Measurement of the Angle of the Prism of the Spectrometer.—Open the slit fairly wide so as to allow plenty of light to pass through the collimator. Place the prism on the table of the spectrometer with the angle to be measured turned towards the lens of the collimator. Parallel light from this lens will now fall on both the faces AB, AC of the prism, which contain the angle to be measured. Some of the light falling on each face will be reflected as shown by the continuous lines, and it is easy to prove that the angle between the two reflected beams is equal to twice the angle of the prism. By moving the eye in the horizontal plane of the axis of the collimator, and looking at one face AB of the prism, the direction of the reflected beam can be found. Turn the telescope to point in this direction; then on looking through it the image of the slit should be seen. *When the slit has been brought into the field of view, the width of the slit must be made very small* and the telescope turned till the intersection of the cross-wires coincides with the image of the narrow slit.

Read the position of the telescope by the vernier or verniers provided. To do this it may be necessary to reflect the light of a gas or electric lamp upon the verniers by means of a small mirror. Without moving the prism or the table, turn the telescope to view the image formed by reflection from the second face AC of the prism, and again

read the position of the telescope. Find the angle between the two positions of the telescope, and deduce the angle of the prism, A.

It often happens that *four* slit images can be seen as the telescope is moved round in a horizontal plane. Two of these are reflection images, the two of which the positions are required; the other two are images formed by *refraction* through the back surface of the prism, and care must be taken to use neither of these by mistake. This can be avoided readily if




FIG. 161.—Measurement of Angle of Prism

the images are first obtained by the unaided eye, and the telescope brought into position without moving the eye, it being easy to see from which surface the light is coming.

The bogus images correspond with the refracted rays shown dotted in Fig. 161. This trouble can be avoided entirely if the back surface BC is covered with paper, or if a prism with a *matte* face is used.

Sometimes the reflected images can be seen plainly with the unaided eye, but cannot be seen in the telescope. This is due to the table of the spectrometer not being properly levelled, the light being reflected either upwards or downwards so that it strikes the inside of the telescope tube. It will be observed in such a case that when the telescope is swung into position after finding the images with the eye unaided, the eye-piece of the telescope is not level with the eye. The table must be levelled with the screws fitted to it until the eye when viewing the reflected images unaided is on the same level as the eye-piece. Then finally adjust the level till the image of the slit occupies the same position in the telescope field when viewed by reflection in either face, and also when viewed directly with the telescope and collimator in line, and no prism on the table.

EXPT. 142. Measurement of the Angle of Minimum Deviation.—Place the prism on the table of the spectrometer so that the angle A already measured may serve as the refracting angle. Then the light from the collimator should be incident on the face AB and emerge from the face AC to enter the telescope. The positions of the different parts of the apparatus when light is refracted through the prism are shown in plan in Fig. 160. *In setting up the prism be careful to place it in such a position that the maximum amount of light available from the collimator may be utilised and enter the telescope.* This is best achieved if the refracting edge of the prism is placed over the centre of the table.

In order to find the direction in which the telescope must point, turn it to one side, and, using one eye only, look into the face AC of the prism,

moving the eye until an image of the slit formed by refraction through the prism is found. Have the slit wide open in looking for this image. When the proper direction has been found, turn the telescope to point in this direction without moving the head. On looking through the telescope the image of the slit should now be within the field of view.

The light has been deviated in passing through the prism ; the angle of deviation being the *acute* angle between the direction of the collimator and that of the telescope. This angle is a minimum when the light passes through the prism symmetrically.

To find the position of minimum deviation, look through the telescope and rotate the table carrying the prism so that the image of the slit moves towards the axis of the collimator produced. It may be necessary to move the telescope so as to keep the image within the field of view. A position will be found in which the image of the slit is as near as it can possibly be to the axis of the collimator. This is the position of minimum deviation.

The telescope is adjusted until the slit is approximately in the centre of the field of view when the prism is in this position, and the telescope must then be clamped. The slit is now made as narrow as possible, and the prism is rotated slowly backwards and forwards through the minimum position several times. The telescope is moved by the slow motion screw until, as the prism is rotated, the slit moves up from one side until it is bisected by the vertical cross-wire, and then moves away again to *the same side* without ever passing beyond this position. The position of the telescope must now be read by means of the verniers and the graduated circle.

Now remove the prism from the table of the spectrometer, and turn the telescope to point directly towards the collimator, so that the undeviated rays may enter the object-glass and form an image of the slit on the cross-wires. Clamp the telescope in this position and make the final adjustment with the slow-movement screw. Again read the position of the telescope by means of the verniers and the graduated circle.

The difference between the reading in this position and that already obtained in the position of minimum deviation gives the angle of minimum deviation D .

The refractive index of the material of the prism may now be calculated by means of the formula

$$\sin \frac{A+D}{2}$$

\sin

The refractive index of a liquid may be determined by the same method, using a hollow prism with *parallel* worked glass faces to contain the liquid.

ADJUSTMENT OF A SPECTROMETER BY SCHUSTER'S METHOD

An accurate method of adjusting a spectrometer, due to Sir Arthur Schuster, has the advantage that it is not necessary to focus the telescope on a very distant object and so does not involve removing either the telescope or the prism from the instrument. It is possible to focus both telescope and collimator in a small room without windows.

EXPT. 142A. To Adjust a Spectrometer by Schuster's Method.—The steps in the process of adjustment are as follows:—

1. Having placed the prism on the table of the instrument as in Fig. 160, illuminate the slit of the collimator with light from a sodium flame and find the position of minimum deviation as in Expt. 141. Use a fairly wide slit and focus the eye-piece on the cross-wires of the telescope. Notice that the angle of deviation is the *acute* angle between the axis of the collimator and the axis of the telescope.

2. Turn the telescope so as to *increase* the deviation, which means making the axis of the telescope more nearly at right angles to the axis of the collimator. Clamp the telescope when the image of the slit is near the edge of the field of view.

3. Turn the prism table in the *same* direction as in 2, so as to get the image of the slit in the centre of the field of view. This position of the prism may be called the 'slanting' position.

4. Focus the telescope carefully while the prism is in this 'slanting' position.

5. Next, turn the prism table in the *opposite* direction, until the image of the slit is again in the centre of the field. The new position of the prism may be called the 'normal' position.

6. Focus the collimator carefully while the prism is in the 'normal' position.

7. Repeat these processes several times, being careful to focus the telescope in the slanting position, and the collimator in the normal position. The adjustment is complete when the slit is clearly in focus in *both* positions. In practice it is usually not necessary to repeat processes 4 and 6 more than three times.

MAPPING SPECTRA

The position of a line in the spectrum may be determined by finding the position of the telescope when the line is on the cross-wires, or by finding the reading of the line on a scale which is reflected into the field of the telescope from the second face of the prism. In either case the prism is supposed to be kept fixed. In some instruments, known as **Constant Deviation Spectrometers**, the telescope is kept fixed, and the prism is rotated so as to bring one line after another upon the cross-wires. The angle through which the prism is turned then serves to fix the position of a particular line.

If a curve be plotted showing the relation between the wave-length of the lines and their position as defined above, the graph is called a **map** of the spectrum, or a **calibration curve** of the spectrometer. Such a map may be used to find the wave-length of any line of which the position can be determined.

Wave-lengths are usually expressed in Angstrom Units (A.U.) or Tenth Metres (10^{-10} metre or 10^{-8} cm.). Occasionally, however, they are expressed in terms of a unit ten times larger, viz. the micromillimetre ($1\text{m}\mu = 10^{-6}$ mm. = 10^{-7} cm.). This unit was formerly called $1\mu\mu$.

The wave-lengths of some important lines are recorded in the Appendix (p. 563).

EXPT. 143. Mapping Spectra.—Adjust the spectrometer as in Expt. 140, and using a sodium flame as the source of light, arrange that the prism may be in the position of minimum deviation as in Expt. 142. Clamp the prism in this position.

When a photographic scale fixed in a separate collimator tube is used to determine the position of the lines, this must be set up so that the scale, illuminated by a small lamp, gives rise to an image in the focal plane of the telescope, by reflection from the face of the prism. When this method is not employed, the position of the telescope must be determined by reading the vernier attached to it.

The position of the sodium line should be taken as a standard (wave-length 5893 A.U.), and the position of other lines determined with reference to it. The sodium line, when examined by a spectroscope of sufficient resolving power, is found to consist of two lines close together, known as the D lines.

Determine the position of a number of lines in the flame spectra of metallic salts, the spectra being produced by volatilising salts of the metals in a Bunsen flame. Introduce the salts into the flame on a platinum wire fused into a glass tube as a handle, cleaning the wire between each experiment by immersing it, while incandescent, in hydrochloric acid. Suitable salts for this purpose are lithium chloride, thallium chloride, potassium chloride. (See Appendix, p. 563.) In the case of the potassium salt two lines can be found, one in the red, the other in the extreme violet. The latter can only be found by turning the telescope far enough into the violet, and observing *immediately* after the salt is introduced into the flame. Two experimenters are required, one to introduce the salt into the flame, the other to observe the line in the telescope. Nitre (potassium nitrate) may be used for this line. Strontium chloride gives a strong line in the blue at 4607 A.U. Barium and calcium chloride give a number of lines which can be identified *after* the calibration curve has been drawn.

Spark spectra may be observed by passing the discharge of an induction coil (see Expt. 249 in Electricity) between terminals of the metal to be examined. The inner and outer coats of an insulated Leyden jar should be connected to the terminals of the spark-gap.

The spectra of gases may be observed by passing the discharge of an induction coil through 'vacuum tubes' containing the rarefied gases. Electric lamps are now available for use on the mains, containing the vapour of mercury or of sodium, or the inert gas neon. These are very convenient since they give bright spectra.

Absorption spectra may be observed by illuminating the slit with white light, and introducing the absorbing substance in the path of the rays travelling towards the slit. Observe in this way the characteristic spectrum due to a dilute solution of blood, and the spectrum due to an alcoholic solution of chlorophyll. The vapour of iodine, obtained by heating a few crystals in a glass tube in front of the slit, gives rise to fine dark absorption lines.

By reflecting sunlight into the collimator, the dark Fraunhofer lines, due to absorption in the atmospheres of the sun and the earth, may be observed.

Plot a curve on squared paper, on a large scale, showing the relation between the scale-reading and the wave-length corresponding with certain suitable lines. This curve is an *Interpolation Curve* for the particular prism used. From this curve may be determined the wave-lengths of bright lines or the limits of absorption bands.

NOTE.—Attention is directed to Schuster's method of adjusting a spectrometer described on p. 244.

The use of a diffraction grating is described later (pp. 257-259).

CHAPTER VIII

PHOTOMETRY

§ 1. GENERAL PRINCIPLES

Photometry means literally 'measurement of light'. In early days the term Photometry was used especially of the measurement of what was called the **illuminating power** or **light-giving power of a source of light**. This is now usually called the **luminous intensity of the source**, and the estimation is made by comparison with a standard source of reference. The **candle-power** is taken as the unit of illuminating power; and the luminous intensity of any source is expressed in terms of the number of **standard candles** which would give out the same quantity of light.

Attention may be drawn to the fact that this use of the word 'power' is in harmony with the modern use of 'power' or 'activity' to denote *rate of production or expenditure of energy*. This is brought out by the mention of the rate at which the candle or oil is burnt or electrical energy is spent.

The standard candle is defined as a sperm candle $\frac{7}{8}$ inch in diameter, weighing six to the pound, and burning at the rate of 120 grains an hour. It is an unsatisfactory standard, and usually some other standardised source, such as a Pentane lamp, is used. The most convenient standard is perhaps an incandescent electric lamp, working at a certain constant voltage. The unit of luminous intensity based on such standards is called the International Candle.

The **illumination of a surface**, as the **intensity of illumination of a surface** is usually called, is measured in terms of a unit called the **lux**. The illumination on a surface is 1 lux when the surface is illuminated normally by a point source of unit intensity at a distance of 1 metre.

In Great Britain the **foot-candle** is commonly used as the unit of intensity of illumination. It is the illumination on a surface illuminated normally by one standard candle at the distance of one foot.

The term **luminous flux** is used in photometry to denote the emission of light *per unit time*. The unit of light flux is the flux emitted per unit solid angle from a source of unit intensity; this is called 1 **lumen**. The total luminous flux from an ideal point source of one candle-power radiating uniformly in all directions is 4π lumens.

Unit solid angle is the angle subtended at the centre of a sphere of unit radius by unit area of the spherical surface. The total solid angle for the whole spherical surface is 4π .

The eye is unable to make direct estimate of luminous intensity with any approach to accuracy, on account of the variation of the diameter of the iris, and also for other reasons, mainly physiological and psychological. To compare luminous intensities, therefore, some form of apparatus is used to assist the eye. Any such apparatus is called a Photometer.

The use of a photometer depends on the adjustment of two surfaces to have equal intensity of illumination, this equality being judged by the eye of the observer. With lights of the same *colour* the adjustment can be made with practice to about 0.5 per cent; but if the surfaces are illuminated by lights of different colours the accuracy is not nearly so great. In this case it will be found much easier to make the comparison between the two surfaces if the eyes are half-closed. It is impossible to retain any accurate idea of the intensity of illumination of a surface even for so short a time as a second, and therefore the two surfaces to be compared must be viewed simultaneously or interchanged rapidly as in the Flicker Photometer.¹ If the surfaces are separated by a band whose intensity of illumination is different from that of the surfaces to be compared, the estimation is rendered much less accurate, and therefore the surfaces must really be *contiguous* parts of the *same* surface illuminated simultaneously.

The illumination of a surface due to a small source of light varies *inversely as the square of the distance* of the surface from the source. If, therefore, a source of luminosity of candle-power, I , is placed d cm. from a surface, the intensity of illumination is measured by I/d^2 .

If two sources of candle-powers, I_1 and I_2 respectively, illuminate two parts of a surface equally, when at distances d_1 and d_2 cm., their intensities are related by the equation

$$\frac{I_1}{d_1^2} = \frac{I_2}{d_2^2};$$

so that if I_2 is known and d_1 and d_2 are measured, I_1 can be calculated, for

$$I_1 = I_2 \frac{d_1^2}{d_2^2}.$$

§ 2. PHOTOMETRIC MEASUREMENTS

In Great Britain since 1920 gas lighting by means of a naked flame has been superseded through the introduction of incandescent mantles. The illuminating power of the gas is no longer of consequence and it

¹ The Flicker Photometer used in 'heterochromatic photometry' is described in more advanced text-books.

is the fuel value that is important. For some experiments small oil lamps may be used, but electric lamps possess the great advantage that the candle power may readily be controlled by means of a regulating resistance as in Expt. 247.

Most experiments in photometry must be made in a dark room with blackened walls and ceiling, but this is less important in using Rumford's photometer.

RUMFORD'S PHOTOMETER OR THE SHADOW PHOTOMETER

In this apparatus the surface illuminated may be either a white opaque sheet of paper viewed from the same side as the two sources of light, or it may be a translucent screen viewed from the side remote from the sources. In either case, one part of the surface is screened from one of the sources by a rod placed between the screen and the source, the rod being so situated that shadows of the rod, one thrown by each source, lie side by side on the screen. The shadows must neither overlap nor should they be separated by a bright band illuminated by both sources. In Fig. 162 the shadows are separated to simplify the diagram.

The shadow thrown by each source is of course illuminated by light from the other, and when the shadows are equally intense, the intensities of illumination due to the two sources are equal.

EXPT. 144. *Rumford's Photometer.*—Set up in a dark room a vertical rod in front of the screen of the photometer. Compare the luminosity




FIG. 162.—Rumford's Photometer

of a gas (or electric) light with that of a wax candle by adjusting the distances of the sources from the screen, until the shadows are of the same intensity. Care must be taken that the lines joining the sources to the rod are equally inclined to the screen, so that the angles θ and ϕ in Fig. 162 must be approximately equal. Measure the distances, d_1 , d_2 , from the sources to the screen, and calculate the candle-power of the source under test. Repeat the determination several times with the sources at different distances from the screen, and take the mean of the results obtained.

BUNSEN'S GREASE-SPOT PHOTOMETER

In this form of photometer, an opaque white screen (of paper) is rendered translucent over a portion of its surface by means of a spot of




FIG. 163.—Bunsen's Photometer

clean white paraffin wax.¹ It is illuminated from one side by the standard source, and from the other by the source of which the luminous intensity is to be measured.

The opaque portions of the screen are assumed to *reflect* the whole of the incident light, while the translucent portions reflect a definite fraction, say $1/n$, of the light falling on them, transmitting the remainder. If the intensity of illumination from one side is I_1/d_1^2 and from the other side is I_2/d_2^2 , the grease-spot will appear to be of the same brightness as the rest of the screen, when

$$\frac{I_1}{d_1^2} = \frac{1}{n} \frac{I_1}{d_1^2} + \left(1 - \frac{1}{n}\right) \frac{I_2}{d_2^2}, \quad \text{that is when} \quad \frac{I_1}{d_1^2} = \frac{I_2}{d_2^2}.$$

According to this simplified description the grease-spot should disappear when viewed from either side. There is, however, a certain fraction of the light *absorbed* in passing through the translucent grease-spot, and although it may be possible to make the spot almost invisible when viewed from one side, the appearance on the other side is always quite different. In practice, the adjustment should be made until the grease-spot appears *the same amount darker* than the rest of the screen on *both* sides.




FIG. 164.—Bunsen's Photometer Head

Two plane mirrors are usually attached to the screen so as to make an angle of about 60° with it on either side. By means of these mirrors both surfaces of the screen may be viewed at the same time.

An alternative method is to adjust the 'unknown' source until the grease-spot is invisible when viewed from the *standard* side, and to observe the value of d_1 , which gives this result; then to readjust the position until the grease-spot is invisible when viewed from the *unknown* side, keeping the standard source and the screen fixed, that is d_2 being kept constant.

¹ 'A piece of good homogeneous paper is uniformly warmed on a plate. In the centre of this a small circlet or annulus is described with a little melted stearin on a fine brush. This ring is allowed to cool; there is a free unwaxed spot within the boundary thus made, which must now be filled with melted wax, well pressed into the paper. The previously formed boundary secures a well-defined spot.'—Sheppard, *Photo-chemistry*, p. 31.

If these distances are d_1 and d_1' their mean may be taken as the true value of d_1 , or the expression

$$I_1 = I_2 \frac{d_1^2 + d_1'^2}{2d_2^2}$$

may be used to calculate I_1 .

This second method is easier to use, there being no trouble such as is involved in the first method in estimating when the grease-spot is the same amount darker than the rest on both sides.

EXPT. 145. Bunsen's Photometer.—Use the photometer for comparing the illuminating power of an electric lamp with that of a candle, and that of a luminous gas flame (or small oil lamp) with that of a candle. Check the results of the observations by comparing the gas flame and the electric light directly.

If possible use a stand on which three candles can be mounted close together and make the comparisons with one, two, and three candles, estimating the percentage error.

JOLY'S PHOTOMETER

Two rectangular blocks of paraffin, about $5 \times 2 \times 1$ cm., are placed together, with two of the larger faces separated by a sheet of tinfoil. The blocks are placed between the two sources of light to be compared, so that one block is illuminated by one source and the second block by the other source. The observer views the blocks from the side (Fig. 165), and adjusts the position until the two faces separated by the tinfoil as dividing line appear equally bright. The eyes of the observer should be protected by suitable screens from the direct rays of the lights used.




FIG. 165.—Joly's Paraffin Wax Photometer

EXPT. 146. Joly's Photometer.—Set up the photometer on a long optical bench and use it to compare the candle-power of an incandescent gas lamp with that of an electric lamp. When the correct positions have been found, measure the distances from the photometer to the two sources and calculate the ratio of the illuminating powers. Repeat the observation several times for different positions of the sources, and take the mean of the results. Make an estimate of the percentage error possible in the measurement.

LUMMER-BRODHUN PHOTOMETER

The essential part of this instrument is the same as that in Swan's prism photometer¹ (1859). The two sources send beams of light to two

¹ William Swan, professor of natural philosophy in St. Andrews, 1859-1890.

mirrors at $22\frac{1}{2}^\circ$ to the paths of the beams, and at 45° to each other. After a second reflection the beams strike a block of glass consisting of two right-angled prisms cemented together at the middle parts of their faces with Canada balsam, but separated by an air film at their edges (Fig. 166).




FIG. 166.—Lummer-Brodhun Photometer

The observer views the base of one of the prisms through a telescope at C. The light from the source A is transmitted by the balsam, but is totally reflected by the air film. The light from B is totally reflected by the air film so that it enters the telescope parallel to the transmitted light from A. Thus the telescope receives a composite beam of light, the edges being composed of light from B, and the centre of light from A. The apparatus is usually arranged to give a somewhat elaborate 'field pattern'.

By using a balsam of the same refractive index as that of the two prisms, there is no reflection at the inter-face and no absorption of the transmitted light, so that the trouble which arose in Bunsen's photometer is entirely obviated. Very great accuracy can be secured by this form of apparatus, and it is very largely used in photometric laboratories.

Expt. 147. Lummer-Brodhun Photometer.—Set up the Lummer-Brodhun photometer on the optical bench, and use it to find the candle-power of a gas flame and of an electric lamp. Confirm the results by comparing directly the gas flame and the electric lamp. Estimate the percentage error possible in the measurement.

§ 3. MEASUREMENT OF ILLUMINATION

The illumination of a surface can be measured by means of an illumination photometer. This is a portable instrument provided with a screen which may be placed in the position where the illumination is to be measured. A neighbouring surface, viewed at the same time, is

illuminated only by a standardised source, usually a small electric lamp supplied by an accumulator. The illumination of this surface can be varied until equality of illumination is secured by various methods, for example by tilting the surface. The scale of such an instrument must be calibrated empirically.

Photo-electric Photometers.—A direct measurement of illumination can be obtained by using a photo-electric cell. When a metal plate is exposed to ultra-violet light, electrons (p. 450) are emitted and this 'electronic current' is proportional to the light energy absorbed. While most metals require ultra-violet light to show the photo-electric effect, the alkali metals respond to wave-lengths in the visible spectrum and can be used in photometry. In one form of photo-electric cell a thin layer of cuprous oxide on a copper plate is covered with a transparent film of metal. When illuminated this gives an electromotive force between its plates. Such a 'photo-voltaic' cell may be connected to a sensitive moving-coil indicator having a scale calibrated in foot-candles. The instrument is very compact and simple in use. Experiments may be made in the laboratory to compare the illumination (*a*) at different places, (*b*) due to different sources, or (assuming the calibration to be correct) to test the law of the inverse square of the distance.

Instruments of this type are used for the determination of photographic exposures. Adjustable scales are provided so as to read directly the exposure required for any emulsion at various lens apertures.

MEASUREMENT OF WAVE-LENGTH

§ 1. THE UNDULATORY OR WAVE THEORY OF LIGHT

ROBERT HOOKE (1665) regarded light as 'a quick and short vibratory motion, propagated in every way through a homogeneous highly elastic medium, in straight lines like rays from the centre of a sphere'. The true founder of the wave theory was Christian Huygens, whose *Treatise on Light* was published in 1690. Although Sir Isaac Newton was prepared to recognise the existence of a *periodic* character in light he did not view this theory with favour, and his name is usually associated with the emission or corpuscular theory. The undulatory theory was developed by Young and by Fresnel at the beginning of the nineteenth century. Measurements of the wave-length, λ , of light in the visible part of the spectrum were made with continually increasing accuracy. The product of wave-length and frequency, f , is equal to the velocity of wave motion. About 1868 Clerk Maxwell pointed out the correspondence between the velocity of light, c , and that of electromagnetic waves, and advanced the theory that these waves are identical in their properties.

According to Einstein (1905) the energy of all forms of radiation is concentrated in certain bundles or units, and the energy of each *light quantum* or *photon* is definite for light of a given colour, being equal to the product hf , where h is Planck's radiation constant. This hypothesis was used in explaining the photo-electric effect (p. 253). On this view the propagation of light resembles in many respects the transmission of the 'corpuscles' of Newton. These apparently conflicting pictures of the nature of light are now regarded as complementary and not contradictory, and the same attitude is adopted as to the nature of elementary particles such as *protons* and *electrons* (pp. 362, 450).

§ 2. COLOURS OF THIN FILMS

When a thin film of a transparent material is exposed to an extended source of light colours may frequently be seen both by reflected and by transmitted light. Illustrations are found in the colours of a soap film, or a thin film of oil spread over water. Films of solid material such as celluloid, or the transparent wrapping called cellophane, show the same appearance. The phenomenon is due to succes-

sive reflections and refractions taking place from the two surfaces of the film, the wave-fronts produced being eventually superposed. For generality multiple beams undergoing a number of reflections and refractions must be taken into account, but for simplicity only double beams will be considered. Let an air film between two parallel surfaces of glass be separated by a distance t . Interference will take place between light reflected from the first surface and light reflected from the second when

$$2t \cos \theta = n\lambda,$$

and the illumination will then be a minimum. In this equation θ is the angle of refraction *in the air* and n is an integer. The equation takes into account the fact that one reflection may be called 'external' and the other 'internal', and that in consequence a retardation is introduced corresponding to one-half of a wave-length measured in air. This retardation explains why a very thin film ($t \rightarrow 0$) appears black by reflected light. When the light falls on the film at nearly normal incidence $\theta = 0$ and $\cos \theta = 1$, so that the condition for minimum illumination is

$$2t = n\lambda.$$

Newton's Rings.—When a plano-convex lens of long focal length is placed with its curved surface in contact with a glass plate, there is an air film between the surfaces. At points such as A and B, Fig. 166A, the




FIG. 166A.

faces of the film may be supposed approximately parallel and separated by a distance t , equal to MP the sagitta of the arc (compare Fig. 140). Consequently for light incident normally illumination is a minimum at

points C and D provided $2t = n\lambda$, and as the figure is symmetrical about MP a dark ring is formed of radius ρ , equal to MA or MB. But, as on p. 208, the sagitta MP is $\frac{1}{2} MA^2/s$ approximately. Here s is the radius of curvature of the *second* face of the lens in accordance with the notation adopted for a thin lens on p. 228. Accordingly the condition for a dark ring may be written

$$2MP = n\lambda, \text{ or } \frac{MA^2}{s} = n\lambda, \text{ or } \rho^2 = s \times n\lambda.$$

In practice the diameter δ of the dark ring is measured, and we may write $\delta^2 = 4s \times n\lambda$, where n is an integer.

EXPT. 147A. Measurement of the Wave-Length of Sodium Light.—

The surfaces of the glass plates P and R and of the plano-convex lens must be cleaned carefully. Place the plate P on a plane horizontal black surface, and rest the lens upon P with the convex surface of the lens in contact with the plate. Set up the reflecting plate R in a stand so that it may be turned about a horizontal axis at right angles to the diagram. A very bright sodium flame must be used as a source, and it is convenient to introduce a converging lens F, of focal length 15 or 20 cm., to give an approximately parallel beam. The light is reflected downwards by the plate R and falls normally on the plate P. A travelling microscope T with its axis vertical is used to measure the rings. Focus the eyepiece of the microscope on the cross-wires, and to begin with focus the microscope on the edge of the lens L. Move the lens until its centre is approximately on the axis of the microscope. Rotate the plate R until the field is brightly illuminated. The microscope is then moved in the vertical direction until the rings are visible. One of the cross-wires of the microscope should be parallel to the direction of travel and pass through the centre of the system of rings.

The central spot should be dark but usually it is not well defined. Instead of attempting to measure the *radius* ρ of a dark ring, measure the *diameter* δ . When moving the microscope across the rings, it should always travel in the same direction between the settings. This is to avoid errors due to 'backlash', for the carriage of the microscope is usually kept in contact with the end of the screw by means of springs. In order to measure from, say, the 25th dark ring, set the microscope on a dark ring a few rings beyond this and then move the microscope towards the centre till the cross-wire lies over the centre of the 25th ring. Take the reading of the carriage, and continue to make settings and take readings for every fifth ring, proceeding towards the centre and continuing onwards on the other side until the 25th ring is again reached.

From these readings find the values of the diameters δ_n for corresponding values of the integer n .

$$\begin{aligned} \text{For a dark ring } n \quad \delta_n^2 &= 4s \times n\lambda; \\ \text{and for a ring } (n+5) \quad \delta_{(n+5)}^2 &= 4s \times (n+5)\lambda. \\ \text{By subtraction} \quad \delta_{(n+5)}^2 - \delta_n^2 &= 4s \times 5\lambda. \end{aligned}$$

Measure s the radius of curvature of the *second* (or curved) surface of the plano-convex lens by the method of Expt. 131, p. 228.

Calculate the wave-length of sodium light from the above relation. Repeat the calculation for other sets of rings.

It is instructive to plot a graph showing the relation between δ^2 (as ordinate) and n as abscissa. What information does it give?

The wave-length of the mercury green line may be measured if a mercury vapour lamp and filter for isolating green light are available.

§ 3. DIFFRACTION GRATING

Diffraction is the breaking up of a beam of light into a series of light and dark spaces or bands; this occurs at the edge of an opaque body or through a narrow aperture. When the incident beam is of white light, coloured bands are observed; with monochromatic light there is an alternating variation in brightness near the position corresponding to rectilinear propagation. The resulting bands are known as **diffraction fringes**.

The existence of diffraction bands when observing even the most sharply defined shadows, indicates that the propagation of light is only approximately rectilinear. The bands are attributed to the superposition of *secondary wavelets* which are regarded as diverging from all points of the wave front.

For simplicity the incident light is here assumed to be parallel, or to have a plane wave front. This condition may be realised by using a collimator as in the spectrometer (p. 241). Further the diffraction of parallel light in some particular direction may be studied, and for this purpose an observing telescope adjusted for a parallel beam and pointing in the desired direction is employed. In practice, then, an ordinary spectrometer may be used, and in place of a prism a straight edge, a narrow wire, or a slit may be set up on the table of the instrument. With white light coloured diffraction fringes may then be studied for the various obstacles or apertures employed. Or, alternatively, the slit of the collimator may be illuminated with sodium light.

The original **diffraction grating** was an arrangement of parallel wires equally spaced so as to provide a number of parallel equidistant slits. A modern grating is formed by ruling with a diamond point a series of equidistant parallel lines on glass or on a polished surface of speculum metal (an alloy of copper and tin). Replicas may be obtained made by photography or casting in celluloid (Thorp gratings). A diffraction grating should be handled by its edge, and ON NO ACCOUNT SHOULD THE FACE OF THE GRATING BE TOUCHED.

In a prismatic spectrum there is no simple relation between wave-length and angular deviation, but in the spectrum formed by a grating the angular separation is related to the wave-length by a very simple law. Only a **transmission grating**, with parallel light falling normally upon it, will be considered here. Let a be the width of each clear space or aperture, and b the width of each opaque part. Put the sum $a+b$ equal to e , the so-called **grating space**. If these distances are in cm. the value of $1/e$ determines the number of lines per cm. for the grating. When a parallel beam of light falls normally on the grating, the light emerging normally from the grating will be brought to a focus by the telescope, giving rise to a bright image of the slit of the collimator. This we call the central line of the grating. Now let the

telescope be turned through an angle θ , on either side of this central position. By considering wavelets starting from corresponding points of the apertures it is not difficult to show that reinforcement will take place when the path retardation, $e \sin \theta$, is equal to an integral number of wave-lengths. This means that there will be *maximum illumination* when

$$e \sin \theta = n\lambda,$$

where n is an integer, 0, 1, 2, 3

When $n=0$, we must have $\sin \theta=0$, and the central image will correspond to $\theta=0$ for all wave-lengths. For $n=1, 2, 3$. . . the value of $\sin \theta$ is proportional to the wave-length, and with white light there will be, in general, a series of spectra, called spectra of the first, second, third, . . . order.

Notice that in any spectrum formed by a grating the *red* end, corresponding to long wave-lengths, is *most deviated*; in the spectrum formed by a prism the violet end is most refracted.

By using a diffraction grating and determining the angle θ for a given value of n , the wave-length of monochromatic light may be found by using the formula $\lambda = e \sin \theta / n$, where e is the grating space or the distance between *corresponding* points of the grating elements.

EXPT. 147B. Measurement of the Wave-length of Sodium Light by means of a Transmission Grating.—Since *accurate* readings of the angles are needed, the vernier scales of the spectrometer should be examined carefully so that the readings may be correctly interpreted. Place a lamp with a switch in a convenient position for taking readings.

Use a bright sodium flame as the source, arranging suitable screens to cut off stray light. Adjust the spectrometer as in Expt. 140, using Schuster's method for making the optical adjustments. It is to be noted that the eye-piece and the cross-wires must be adjusted to suit the individual observer.

Remove the prism and set the telescope in line with the collimator so that a direct image of the slit coincides with the cross-wires. Take the reading of the vernier attached to the telescope, and then turn the telescope through 90° so that its axis is at right angles to the rays of light from the collimator. Place the grating on the table of the spectrometer without touching either face of the grating. Arrange it so that the ruled face is approximately over the centre and parallel to the line joining *two* of the levelling screws. Turn the table carrying the grating until light from the collimator is *reflected* from one face of the grating into the telescope. Now adjust one or other of these two levelling screws until the reflected image occupies the same position in the field of the telescope as the direct image previously occupied. This adjustment ensures that the vertical axis of rotation is parallel to the face of the grating. Read the vernier attached to the table.

The plane of the grating now makes an angle of 45° with the ray of light from the collimator. Since we wish the plane of the grating to be perpendicular to the incident light, the table which carries the grating must now be turned through 45° in the proper direction.

Restore the telescope to the position in which it is in line with the collimator, and check the position of the central image formed by light passing through the grating. Next turn the telescope to view one of

the diffracted images of the first order, and if necessary adjust the *third* levelling screw so as to bring the diffracted image into the centre of the field. This is done to ensure that the rulings of the grating are parallel to the axis of rotation.

Now find the readings of the telescope vernier for settings on the various diffracted images on each side of the central image, and obtain the corresponding values of the angle θ . Take the mean of the two angles for a given order n , and calculate the wave-length from the formula $\lambda = e \sin \theta / n$.

If the number of lines per cm. of the grating is not known it may be determined by using light of known wave-length, and calculating the value of $1/e$ from the formula. For example the wave-length of the green line of mercury is very nearly 5461 A.U. (angstrom units) or 0.0005461 cm.

PART III

ADDITIONAL EXERCISES IN LIGHT

1. When a pin is fixed between two parallel mirrors a number of images can be seen. Trace the path of the rays by which the third image in one mirror is seen.

2. Set up two plane mirrors so that the angle between them is 72° . Find the positions of the images of a pin placed in the angle between the mirrors.

3. Plot a curve showing how the lateral displacement of a ray of light passing obliquely through a plate of glass depends upon the angle of incidence.

4. A cubical glass tank is filled with water, and a vertical pin is placed inside it. Plot a caustic curve for the rays refracted into the air through one side of the tank.

5. Plot the caustic curve formed by rays reflected from a cylindrical mirror, using a pin as the object and two other pins to determine the reflected rays. Do this both for convex and concave mirrors.

6. Plot the caustic curve formed by rays refracted into air from a cylindrical beaker containing water, using a pin inside the beaker as the object and two other pins to determine the refracted rays.

7. Plot the caustic curve formed when parallel rays are refracted through a cylindrical lens. (One-half of a lantern condenser may be used instead of a cylindrical lens.)

8. A pin is fixed in a vertical position inside a cylindrical beaker of water. Trace the paths of rays from the pin into the air. Deduce the position of the image seen by an eye viewing the pin from the side of the vessel nearest to the pin.

9. Trace the paths of parallel rays of light through a convex lens, and deduce the focal length.

10. Trace the paths of parallel rays of light through a concave lens, and deduce the focal length.

11. Find the focal length of the given convex lens in three different ways.

12. Place the given convex lens so as to form on a screen an image three times the size of the object. Measure the distance from the object to the screen, and deduce the focal length of the lens.

13. Plot a curve showing how the distance of the image from the given convex lens depends upon the distance of the object, using pin-sights and the method of parallax.

14. Find the shortest distance between an object and its image formed by the given convex lens. Deduce the focal length of the lens.

15. The given lens is fixed at a distance of 40 cm. from a screen. Find at what distance from the lens an object must be placed to give a sharply defined image on the screen. Determine the linear magnification of the image.

16. Find the focal length of the lens formed by filling a watch-glass with the given liquid.

17. Set up the two given convex lenses so that parallel rays passing through the first meet again at the principal focus of the second.

18. Measure the focal length of the combination formed by two given lenses, (a) in contact, (b) separated by a distance of 2 cm.

19. Determine the radii of curvature of the surfaces of the given concave lens.

20. Determine the radii of curvature of the surfaces of the given convex lens.

21. Set up a convex lens to form a real image on a screen. Between the lens and the screen introduce a concave lens with a plane mirror behind it. Adjust the position of this lens so that an image is formed coincident with the object. Deduce the focal length of the concave lens.

22. Find the centre of curvature of a concave mirror. Set up a concave lens between the mirror and its centre of curvature. Adjust the position of a pin so that it may coincide with its reflection formed by rays passing through the lens. Deduce the focal length of the lens. In what case does this method fail? Is the method applicable for a convex lens?

23. Arrange a slit, prism, and lenses to project a pure spectrum on a screen.

24. Adjust a prism on the table of a spectrometer to be in the position of minimum deviation. Measure the angle at which light is incident on the prism by finding the direction of the rays reflected from the first face.

25. Plot a curve showing how the angle of deviation for the given prism varies with the angle of incidence.

26. Measure the angle of the prism of a spectrometer, *keeping the telescope fixed*, and turning the prism so that the image of the slit is observed by reflection first from one face, and secondly from the other face. (The angle so measured is the supplement of the angle of the prism.)

27. Compare the refractive indices of two liquids, using a spectrometer and a hollow prism of small angle.

28. Map the flame spectra of calcium, strontium, and barium.

29. Focus a spectrometer by employing Schuster's method (p. 244).

This method has advantages as it does not require a distant object, and does not involve removing either the telescope or the prism from the instrument.

PART IV

HEAT

NOTES ON HEAT

The idea of warmth or heat is derived from our sense-perception, and the term 'temperature' was introduced to express the 'degree of hotness' of a body. Early in the seventeenth century the thermometer was constructed for the *measurement* of such 'degrees'. When a hot body is placed in contact with a cold body, the resulting temperature is usually intermediate in value. To explain this fact it is said that 'heat' passes from the hot to the cold body. At first 'heat' was regarded as a fluid, to which the name of 'caloric' was given. One of the great achievements of the nineteenth century was the development by Mayer and Joule of the theory that heat may be regarded as a form of *energy*. After a century of exact investigation the value of the 'mechanical equivalent of heat' accepted in 1941 is 4.185 joules per gram calorie at 15° C. The importance of using the 'joule' (which should rhyme with 'cool'), as the unit of heat is stressed in the present text-book. One joule (10⁷ ergs) is the unit of energy in the M.K.S. system of units, and one joule per second, or one 'watt', is the unit of power or activity.

The subject of heat provides many examples of the necessity of developing a sense of proportion in making physical measurements. Although Joule claimed that constant practice had enabled him to read his thermometers to a high degree of accuracy, an ordinary laboratory thermometer cannot usually give greater accuracy than one part in a hundred. The student should always attempt to estimate the reading of a thermometer to one-tenth of a degree centigrade, but if the rise of temperature to be measured is small (say 5° C.) the error may be much larger than 2 per cent. It follows that it is useless, in an elementary experiment on heat, to make observations on length, or volume, or mass to a greater degree of accuracy than say 1 per cent.

CHAPTER I

THERMOMETRY

§ 1. INTRODUCTORY

To define a scale of temperature we may use any property of a body which varies continuously with temperature. If this property have values X_0 at the Ice Point or Freezing Point, and X_{100} at the Steam Point or Boiling Point of water under standard pressure, we define one centigrade degree as that change in temperature which causes a change $(X_{100} - X_0)/100$ in this property.

If the value of the property be X_t when the body is in certain surroundings, the temperature of its surroundings is given by

$$t^{\circ} \text{C.} = \frac{X_t - X_0}{X_{100} - X_0} \times 100$$

on the particular scale which depends on this property X .

For most practical purposes we take as our scale the scale depending on the position of the top of a thread of mercury in a glass tube. Its position is observed at the Freezing Point and again at the Boiling Point; and the thermometer stem between these points is divided into 100 equal divisions, each being one centigrade degree. Two mercury-in-glass thermometers will agree only if similar kinds of glass are used and the bore of each is quite regular.

Mercury-in-glass thermometers are used chiefly on account of their convenience. The standard thermometer for scientific purposes is a constant volume thermometer (p. 282) filled with hydrogen gas.

The efficiency of a laboratory depends on the care taken of apparatus *when in use*, and the student should use all reasonable precautions in the handling of fragile apparatus such as thermometers. A thermometer should never be raised to a higher temperature than that for which it is constructed, and the thermometer should be returned to its case when finished with.

In reading a thermometer any error due to parallax must be avoided: that is, the line joining the eye to the top of the mercury thread must be at right angles to the stem of the instrument, so that the divisions of the scale may not be displaced relatively to the top of the thread. The student should practise estimating the reading of the thermometer to the tenth part of a centigrade degree.

It must not be forgotten that a thermometer registers its *own* temperature ; and therefore in using it to determine the temperature of any substance it must be brought into intimate contact with that substance and must be left there a sufficient length of time to acquire its temperature.

EXPT. 148. Effect of Stem Exposure.—Place a thermometer in a hypsometer (p. 267) so that the whole stem is enclosed in the steam up to the 100° C. mark. Note the reading of the thermometer when the water is boiling gently. Raise the thermometer until the stem is exposed from the 70° mark upwards, leave it for a few minutes and take the reading again, the water being kept boiling gently the whole time. Repeat the observations with the stem exposed from 40° C. upwards, and again from 10° C. upwards, and note the effect the exposure of the stem produces on the *reading*, although the temperature of the bulb is maintained the same throughout.

Bear this in mind in all thermometric measurements.

§ 2. FIXED POINTS OF A THERMOMETER

Two fixed points are necessary in order to define a scale of temperature.

The **lower fixed point** is defined as the temperature of fusion of ice from pure distilled water ; that is, it is the temperature at which ice and water can exist together in equilibrium. This is called the **Ice Point** or the **Freezing Point** and is marked 0° on the centigrade scale. The effect of pressure on the melting point of a substance is so small that it can be disregarded, for all practical purposes, in defining the freezing point.

The **upper fixed point** is defined as the temperature of steam rising from pure distilled water boiling under normal atmospheric pressure. This pressure corresponds to a barometric height of 760 mm. of mercury. The upper fixed point is called the **Steam Point** or the **Boiling Point** and is marked 100° . Thus, on the centigrade scale, the interval between the freezing point and the boiling point is divided into one hundred

The temperature of steam from boiling water is independent of the nature of the vessel in which the water is boiled, and of the impurities in the water, but varies with the atmospheric pressure. The variation of the boiling point with the pressure was carefully studied by Regnault, who found that in the neighbourhood of 760 mm. an increase of pressure of 26.8 mm. produced an elevation in the boiling point of 1° C. For small variations the change in boiling point may be taken proportional to the difference in pressure. The graph (Fig. 168) is drawn on this assumption. This should be copied in the student's note-book.

It is found that the glass of the thermometer changes gradually

with time producing small changes in the fixed points. It is therefore necessary to redetermine these from time to time, so that corrections may be applied for the errors. In this country it is usual to mark the lower fixed point first.

EXPR. 149. Determination of the Fixed Points of a Thermometer.—

(i) **Freezing Point.**—Fill a suitable vessel nearly to the top with ice in small lumps, and allow the spaces between the lumps to become filled with ice-cold water. It is better not to drain away the water from the melting ice, but too much water must not be allowed to accumulate. The whole must be kept well stirred.

Place the thermometer carefully in the ice so that the bulb is in the centre of the vessel, and the zero point is just above the surface of the ice. Read the lowest point reached by the top of the mercury column (estimating to one-tenth of a degree) while the mercury column is still surrounded by the ice. If the reading be above zero, the error is called positive; if below, negative. If the error be positive, the correction to be applied to the reading, to give the true temperature, is negative.

(ii) **Boiling Point.**—To determine the boiling point the thermometer is placed in a metal vessel called a **hypsometer**. This is a boiler fitted with a double-walled steam jacket above it. The thermometer is supported by a cork fitted into the top of the hypsometer in such a way that the upper fixed point is just visible above the cork. Care must be taken that the thermometer does not fall into the hypsometer, as this would probably result in breakage of the bulb. A loop of wire through the hole at the top of the stem will prevent such an accident. The thermometer should remain in the steam about ten minutes before the reading is taken. The water must not be made to boil too violently or the pressure of the steam in the hypsometer will exceed the atmospheric pressure. Read the top of the mercury column to a tenth of a degree.

Correction for Pressure.—Read the height of the barometer in millimetres and determine from the graph (Fig. 168) the boiling point corresponding to the observed atmospheric pressure.

Enter in the note-book this, the true boiling point, and also the boiling point recorded by the thermometer under test. Calculate the error of the thermometer at the boiling point.




FIG. 167.—Hypsometer

In order to determine the correction required at any temperature between the freezing point and the boiling point, use a graphic method. Take intervals along a horizontal axis to represent intervals on the thermometer scale, and distances along a perpendicular axis to represent the correction required. In the diagram (Fig. 169) the correction at the freezing point is supposed to be $+0.2^{\circ}\text{C}$. and the correction at the boiling point $+0.8^{\circ}\text{C}$.

The correction is the amount that has to be *added* to the reading to give the true temperature.




FIG. 168.—Variation of Boiling Point with Pressure

for

0.4




FIG. 169.—Correction for Thermometer

§ 3. CALIBRATION AND GRADUATION OF A THERMOMETER

To obtain equal values for the temperature differences indicated by equal movements of the mercury along the tube, it is essential that the bore should be uniform : this is rarely or never found to be the case.

Similarly at about 30° the correction is $3(9.995) - (9.82 + 10.08 + 10.06) = +0.025^\circ \text{C.}$; and so on. Thus we get

$\delta_{10} = +0.175$	$\delta_{80} = -0.03$
$\delta_{20} = +0.09$	$\delta_{70} = +0.015$
$\delta_{30} = +0.025$	$\delta_{60} = +0.01$
$\delta_{40} = -0.2$	$\delta_{50} = -0.135$
$\delta_{50} = +0.095$	$\delta_{100} = 0.00$

The last value must be zero, of course.

From these observations a correction curve can be drawn, giving the amount that has to be added at each point in the scale to correct for unevenness of bore and scale.

NOTE.—Thermometers for accurate work may be submitted to a standardising laboratory for comparison with a standard thermometer.

GRADUATION OF A THERMOMETER WITH AN ARBITRARY SCALE

In some cases the scale engraved on the stem of a thermometer may be entirely arbitrary, so that the readings are not obtained directly in degrees centigrade. For example, the stem might be marked with a scale of millimetres, yet such a thermometer can be used to find the temperature on the centigrade scale. For this purpose the thermometer must first be standardised by finding the two fixed points by the methods described in the previous section. Thus it might be found that at the freezing point the mercury stands at a point 24 mm. from the bottom of the scale, while at the boiling point the mercury stands at a point 184 mm. from the bottom of the scale. If the reading of the barometer at the time of the determination were 733 mm. the boiling point would be 99°C. instead of 100°C. Consequently the point 24 mm. from the bottom of the scale corresponds to 0°C. , and the point 184 mm. from the bottom corresponds to 99°C. Thus a distance of 160 mm. on the scale corresponds to an interval of 99°C. centigrade degrees. It is then easy to calculate the interval on the centigrade scale for 1 mm. on the thermometer; in this case $99/160$ degrees correspond to 1 mm.

Suppose this thermometer is employed for finding the temperature of a liquid in a calorimeter (p. 287), and that the mercury stands at 64 mm. from the bottom of the scale. Then the mercury stands at 40 mm. above the freezing point, and the corresponding temperature on the centigrade

scale is $40 \times \frac{99}{160} = 24.75^\circ \text{C.}$

The relation between the scale of the given thermometer and the centigrade scale can be shown graphically, taking the readings of the thermometer as abscissae and the readings of the centigrade scale as ordinates.

EXPT. 151. Graduation of a Thermometer with an Arbitrary Scale.—Standardise a thermometer provided with an arbitrary scale, in the manner described, and use it to determine the temperature of the room, and also the temperature of the water supply.

§ 4. MELTING POINTS AND BOILING POINTS

EXPT. 152. Determination of the Melting Point of a Solid.—To determine the melting point of a solid such as paraffin wax, draw out a piece of glass tube in the flame of a blowpipe so as to form a thin-walled

capillary tube. Cut off with a file, or glass-cutter's knife, a piece of this tube a few centimetres long. The tube must now be filled with the material under investigation by dipping one end into the liquid formed by heating a small quantity of the solid in a suitable vessel. In most cases the liquid will be drawn into the tube by capillary action. The tube must be sealed off at the bottom after filling, otherwise the sub-




FIG. 170.—Melting Point of a Solid




FIG. 171.—Boiling Point of a Liquid

stance will run out when melted, or the water will rise up the tube and the solidifying point cannot be observed.

The tube containing the solid substance is now attached to the bulb of a thermometer by elastic bands or fine threads, and the bulb is heated carefully in a water bath (Fig. 170). The reading of the thermometer is noted at the instant when the solid in the small tube assumes the liquid state, and another reading may be taken by allowing the water-bath to cool and noting when the solid reforms. The temperature taken for the *melting* will be somewhat above the true melting point, and the temperature for the *solidification* will be too low. The mean must be taken as the true melting point. There is, however, a possibility of *super-cooling* the liquid and in such an event the true melting point is not obtained by this type of experiment.

In some cases the capillary tube may be dispensed with and a thin

film of the solid may be formed round the bulb of the thermometer, which is then heated carefully as before.

See also the experiment on the curve of cooling when a liquid solidifies, p. 299.

EXPT. 153. Determination of the Boiling Point of a Liquid.—For this determination, place the liquid in a test-tube fitted with a cork provided with two holes. A thermometer passes through one hole and a glass tube to carry off the vapour through the other. The test-tube is heated carefully by a small flame or a water-bath till the boiling point of the liquid is reached. In order to prevent *boiling with bumping*, a few glass beads, or short pieces of thin walled capillary tubing (made by drawing out a glass tube in the flame of the blowpipe), should be placed in the liquid. The position of the thermometer in the test-tube will depend on the liquid under test.

(a) In the case of a pure liquid, the thermometer is used to register the temperature of the vapour only, and the bulb of the thermometer should not dip into the liquid (Fig. 171).

(b) In the case of a solution, the temperature of the liquid differs appreciably from that of the pure solvent. In order to determine the boiling point of the *solution*, the bulb of the thermometer must be immersed in the liquid. Notice the difference between the readings when the thermometer bulb is in the solution, and when it is in the vapour above the liquid. The solution must be boiling *very gently* to avoid superheating.

NOTE.—Great care must be taken in handling and using sensitive thermometers, which must not be over-heated. It is sometimes convenient to protect the bulb with a cap of thin metal, but the water equivalent of the cap must be taken into account in calorimetry.

COEFFICIENTS OF EXPANSION

§ 1. THE COEFFICIENT OF LINEAR EXPANSION

THE increase in length of a rod produced by raising its temperature one degree is small compared with the length of the rod, and is found to be nearly constant for different temperatures.

The **coefficient of linear expansion** of a solid may be defined as the ratio of the increase in length to the original length for a rise in temperature of one degree.

Thus, if the original length of the bar is l_0 and its length becomes l_1 when its temperature is raised 1° , the coefficient of linear expansion α is given by

$$\alpha = \frac{l_1 - l_0}{l_0}.$$

If the length of the bar becomes l when its temperature is raised t° we may write

$$\alpha = \frac{l - l_0}{l_0 t}. \quad (1)$$

Hence

$$l - l_0 = l_0 \alpha t$$

or

$$l = l_0(1 + \alpha t). \quad (2)$$

It is sometimes convenient to take the original temperature of the bar as 0°C. ; then l_0 represents the length at 0°C. and t represents the temperature of the bar in degrees centigrade corresponding to the length l .

Since the change in length actually observed is small, it is in practice convenient to assume that the original temperature is that of the room, and that l_0 represents the length of the bar at that temperature. In this case it must be noted that t represents the *rise* of temperature; that is, the difference between the final temperature and that of the room.

NOTE.—In any determination of the coefficient it is essential that sufficient time should be allowed for the temperature of the bar to become uniform throughout its volume. The coefficient is here expressed in $(^\circ\text{C.})^{-1}$.

We see from equation (1) that a determination of the coefficient of linear expansion involves the measurement of three quantities, the original

length, the rise of temperature, and the *increase in length*. The only measurement presenting any difficulty is the last. Since the probable error in this measurement is large, it is useless attempting great accuracy in the measurement of the other two quantities. (See p. 5.) The original length of the bar should first be determined to within 1 part in 1000, and the temperature at which the measurement is made be noted. To measure the small increase in length when the bar is heated to a known temperature several methods may be employed:—

1. The increase in length may be magnified by means of a mechanical, or an optical, lever (Lavoisier and Laplace) in a known proportion. The magnification factor requires careful determination.

2. The increase in length may be measured directly by means of a micrometer screw. An ordinary spherometer can be employed.

3. The increase in length may be measured directly by adjusting one micrometer or vernier microscope in focus on the first end of the bar under test, and a second microscope on the other end.

This method has the advantage over the other two in the fact that observations are made on both ends of the bar, and no assumption is made that one end of the bar remains fixed throughout the experiment. This is essentially the method of Roy and Ramsden.

Strictly speaking all three methods give the difference between the expansion of *two* bodies. Care must be taken to avoid error due to assuming that one does not expand.

Methods depending on optical interference are not included here.

EXPT. 154A. Determination of the Coefficient of Linear Expansion.—

The following apparatus is an example of the second method. The bar to be experimented upon is placed inside a steam jacket consisting of a hollow metal (or glass) tube through which a current of steam can be passed. The ends of the bar project slightly beyond the ends of the jacket, the joints being made steam-tight by cork or rubber tubing. A thermometer is provided to measure the temperature at each end of the bar. One end of the bar remains in contact with a fixed metal stud; the other end is free to expand. A micrometer screw with a divided head (spherometer) is arranged at this end so that the axis of the screw coincides in direction with that of the bar. Contact between the end of the screw and the end of the bar may be detected by the sense of touch, or a *ratchet* micrometer may be used, so as to slip as soon as contact takes place, but it is preferable to use a simple electrical device to indicate the position of contact.

One pole of a voltaic cell is put in connection with the micrometer screw; the other pole is connected through a simple galvanometer with the stud against which the fixed end of the bar rests. As soon as the point of the micrometer screw touches the end of the bar, the circuit is completed and the galvanometer needle is deflected.

Set up the apparatus and determine at the ordinary temperature the reading of the micrometer screw when contact takes place with the end of the bar. This adjustment should be repeated several times.

Now turn the micrometer screw back several turns to allow for expansion. Heat the bar by passing a current of steam from a boiler through the jacket, and wait until the bar has had time to acquire a steady temperature. Note the readings of both thermometers. Again adjust the micrometer screw to give contact, and take the reading. The reading should be repeated several times. The difference between this and the former reading gives the increase in length of the bar.

Calculate from the observations the coefficient of linear expansion of the bar.

EXPT. 154B. An alternative plan, using an ordinary micrometer screw gauge, is to clamp one end of a horizontal metal tube firmly, and to allow the other end to slide easily through an aperture in a fixed block.¹ A block of about the same size is clamped on the tube near the place where it passes through this aperture. Each block has a vertical projection serving as an index for measurement. The distance between the outside faces of these projections is measured by the screw gauge when the tube is cold and again after it has been heated by a current of steam to 100° C. The difference between the readings gives the increase in length due to expansion. Calculate the coefficient of expansion.

The third method may be employed to find the coefficient of expansion of a metal tube.

EXPT. 155. Determination of the Coefficient of Linear Expansion of a Metal Tube.—Make two transverse scratches, one near each end of a metal tube about one metre long. Measure the distance between them at the temperature of the room by setting up two travelling microscopes as in the comparison of the Yard and the Metre, Expt. 4. It is desirable to set up the microscope stands on a slab of slate, so that the distance between them may not be affected when the tube is heated. Focus the microscopes on the scratches. Pass a current of steam through the tube. Adjust the tube so that the scratch at one end coincides with the cross hair of the first microscope, and measure the distance through which the second microscope must be moved to give coincidence at that end of the tube. This gives the increase in the length of the tube. Calculate the coefficient of linear expansion on the assumption that the tube is heated to 100° C.

§ 2. THE COEFFICIENT OF EXPANSION (DILATATION) OF A LIQUID

The coefficient of expansion of a liquid may be defined in two distinct ways :—

I. The Zero Coefficient of Expansion.—The coefficient of expansion of a liquid is the ratio of the increase in volume to the volume at 0° C. produced by a rise of temperature of 1° C.

Thus, if V_1 be the volume at 1° C., V_0 the volume at 0° C., and α the coefficient of expansion,

$$\alpha = \frac{V_1 - V_0}{V_0}.$$

If we assume that the substance expands uniformly with rise of temperature ; that is, that equal changes of volume correspond to equal changes of temperature, the volume V_t at any temperature t is given by

$$V_t = V_0$$

or

$$V_t = V_0 (1 + \alpha t).$$

II. The Mean Coefficient of Expansion between two Temperatures.—The mean coefficient of expansion between any two temperatures is

¹ Allen and Maxwell, *A Text-Book of Heat*, Part I, p. 78, Fig. 29

the ratio of the increase in volume to the original volume per degree rise of temperature. Thus, if a rise of temperature of t° change the volume from V to V' the mean coefficient of expansion is

$$\frac{V' - V}{Vt}.$$

Note that no reference is made here to the original temperature being 0°C .

In the case of a substance like water, which does not expand uniformly, this definition is necessary.

EFFECT OF A CHANGE OF TEMPERATURE ON THE DENSITY OF A LIQUID

Let V_0, ρ_0 , denote the volume and density of a given mass of liquid at 0°C . Then the mass of the liquid is $V_0 \rho_0$.

Let V, ρ , denote the volume and density at any other temperature $t^\circ \text{C}$. Then the mass of the liquid is $V\rho$. But the mass is the same at both temperatures.

Hence

$$V\rho = V_0\rho_0,$$

or

$$\frac{V}{V_0} = \frac{\rho_0}{\rho}.$$

But

$$\frac{V}{V_0} = 1 + \alpha t,$$

so it follows that

$$\frac{\rho_0}{\rho} = 1 + \alpha t,$$

or

$$\rho_0 = \rho (1 + \alpha t).$$

The difference should be noticed between this equation and that containing V . The effect of a rise in temperature is, in general, to increase the volume but to diminish the density.

The coefficient of expansion is given by

$$\alpha = \frac{\rho_0 - \rho}{\rho t}.$$

This expression is *exact*, and not a mere approximation.

In the same way, the *mean* coefficient of expansion between two temperatures t_1 and t_2 may be shown to be

$$\alpha = \frac{\rho_1 - \rho_2}{\rho_2(t_2 - t_1)},$$

where ρ_1 is the density at t_1 , and ρ_2 is the density at t_2 .

COEFFICIENT OF EXPANSION OF WATER OVER VARIOUS RANGES OF TEMPERATURE

In the case of a liquid, it is much easier to determine the variation in *density* than to determine the variation in the volume of a given mass of liquid. The method usually adopted is to fill a specific gravity bottle up to the mark with liquid at various temperatures, and to weigh the quantity of liquid present.

EXPT. 156. Expansion of Water by Specific Gravity Bottle Method.—

In this case the density of the liquid is proportional to the weight of liquid filling the bottle. Dry and weigh a specific gravity bottle of about 100 c.c. capacity. Fill the bottle to the mark with water at a temperature between 2° C. and 7° C. Weigh the bottle and water.

Empty the bottle, place it in a bath of water and raise the temperature to about 20° C. Fill the bottle with water from the bath, adjusting the level of the water to the mark on the neck, while the bottle is still in the bath. Take the temperature of the bath. Remove the bottle and water from the bath, carefully dry the outside of the bottle, and weigh it.

Repeat the experiment, adjusting the temperature of the water bath to about 40° C., 60° C., and 80° C., and filling the bottle to the mark at each of these temperatures. In weighing, the bottle and water will cool considerably and the liquid surface will fall below the mark in the neck. No notice need be taken of this. The liquid in the bottle is the amount of liquid which filled the bottle to the mark at the temperature of the bath, its *mass* is not altered by its contraction.

It is necessary, however, at the high temperatures to weigh as quickly as possible to avoid evaporation. There may also be an error due to the upward convection current past the hot bottle, and it is therefore advisable to cool the bottle rapidly under the cold-water tap before weighing.

The mass in gm. of the water filling the bottle at the first temperature t_1 (between 2° C. and 7° C.), may be taken as numerically equal to the volume of the vessel V_1 at that temperature, the density of the water being one gram per c.c. within the limits of accuracy of experiment over this range of temperature.

Calculate the capacity of the vessel V at each of the other temperatures taken, using the expression

$$V = V_1(1 + \beta(t - t_1)),$$

β being the coefficient of cubical expansion of glass: β is approximately 0.000025 per 1° C.

Find the density of the water at each temperature by dividing the mass of water in the bottle by the volume of the bottle at that temperature as calculated above. Tabulate the quantities: temperature, mass of liquid in bottle, volume of bottle (calculated), and density of liquid.

From the densities at 20° and t_1 ° C. calculate the mean coefficient of expansion of the water between these two temperatures—

$$\text{Mean } \alpha (t_1 \text{ to } 20^\circ) = \frac{\rho_1 - \rho_{20}}{\rho_{20}(20 - t_1)}.$$

Calculate also the mean coefficients of expansion from 20° C. to 40° C., 40° C. to 60° C., and 60° C. to 80° C., by a similar method.

Plot a curve showing the variation of density with temperature and also showing the variation of the coefficient of expansion with temperature.

The mean coefficient of expansion from 20° C. to 40° C. is practically the same as the coefficient of expansion at 30° C., and so on.

DENSITY OF WATER AT VARIOUS TEMPERATURES BY MEANS OF A GLASS SINKER

The variation of the density of water with the temperature may be found by observing the weight of a glass sinker in water at different temperatures.

Let V_0 denote the volume of the glass bulb at 0° C., and β the coefficient of cubical expansion of glass. Then the volume of the bulb at any temperature t° C. will be $V = V_0(1 + \beta t)$. The value of β for ordinary glass is about 0.000025 per 1° C.

If ρ_t denote the density of water at t° C., the weight of water displaced by the sinker when completely immersed is $V\rho_t = V_0(1 + \beta t)\rho_t$. But this is equal, in accordance with the principle of Archimedes, to the loss of weight in water = W , say.

Thus

$$V_0(1 + \beta t)\rho_t = W$$

and

$$\rho_t = \frac{W}{V_0(1 + \beta t)}$$

The value of V_0 may be determined indirectly by finding the loss of weight when the sinker is immersed in water the temperature of which is approximately 4° C. For temperatures not far from 4° C. the density of water may be considered as 1 gm. per c.c., so that the volume of the sinker at this temperature is found readily.

EXPT. 157. Determination of the Density of Water at various Temperatures by Means of a Glass Sinker.—A convenient form of sinker consists of a glass bulb containing lead shot. The quantity of shot must be adjusted before the bulb is sealed finally so that the sinker is sufficiently heavy to sink in water. The bulb is suspended by a fine wire from one arm of a sensitive balance. If a chemical balance with a closed case is employed, a small hole must be provided in the floor of the balance-case through which the wire can pass. Another hole must be made in the shelf on which the balance-case rests so that the wire passes freely through the two holes. The sinker is attached to the lower end of the wire, and can be immersed completely in a large vessel of water which can be heated to any desired temperature. To diminish the effects of surface tension at the point where the wire passes through the surface of the water, the diameter of the wire should not exceed 0.1 mm.

The sinker is first counterpoised in air, then it is immersed completely in the water in the vessel and weighed again. The difference between the two weighings gives the loss of weight in water. The first observation may be made when the water is cooled to a temperature of about 4° C. Then heat the bath to 70° or 80° C. and allow it to cool slowly. It is easier to regulate the temperature when the bath is cooling, and to maintain it at a steady value while the process of weighing is being carried on. The flame of a Bunsen burner should be regulated carefully by altering its size or its distance below the bath so as to keep the temperature steady during the observation. Care must be taken to stir the water thoroughly between the observations, so that the temperature is uniform throughout the mass. Observations of the loss of weight and of the temperature, should be made at intervals of 10° or 15° C.

A table should be drawn up giving the density of water at different temperatures, and the results should be plotted on squared paper.

Calculate the mean coefficients of expansion of water between the consecutive pairs of temperatures taken.

THE WEIGHT THERMOMETER

The **Weight Thermometer** is a cylindrical glass bulb, with a neck drawn down into a fine tube. This tube is bent round so that its open end may dip into a vessel of liquid. The apparatus is used for finding the coefficient of expansion of a liquid. It is simplest to regard it as an instrument for comparing the densities of the liquid at two specified temperatures.

Let V_0 = volume of the thermometer at 0°C. ,
 m_0 = mass of liquid filling it at 0°C. ,
 ρ_0 = density of liquid at 0°C.

Let V_t , m_t , ρ_t denote the corresponding quantities at $t^\circ \text{C.}$

Then, if β is the coefficient of cubical expansion of glass,

$$V_t = V_0(1 + \beta t).$$

From the definition of density it follows that

$$m_0 = V_0 \rho_0 \text{ and } m_t = V_t \rho_t.$$

Hence

$$\frac{V_0 \rho_0}{V_t \rho_t} = \frac{m_0}{m_t},$$

or

$$\begin{aligned} \frac{\rho_0}{\rho_t} &= \frac{m_0}{m_t} \times \frac{V_t}{V_0} \\ &= \frac{m_0}{m_t} (1 + \beta t) \end{aligned}$$

But it has been proved (p. 276) that

$$\frac{\rho_0}{\rho_t} = 1 + \alpha t,$$

where α is the coefficient of absolute expansion of the liquid.

$$\text{Hence } 1 + \alpha t = \frac{m_0}{m_t} (1 + \beta t).$$

Solving this equation for α , it is found that

$$\alpha = \frac{m_0 - m_t}{m_t t} + \beta \frac{m_0}{m_t}.$$

Notice that no approximations whatever have been made in obtaining this result.

If the expansion of the thermometer bulb be ignored, $\beta = 0$, and the coefficient of apparent expansion of the liquid is

$$\frac{m_0 - m_t}{m_t t}.$$

EXPT. 158. Determination of the Coefficient of Expansion of Glycerin by the Weight Thermometer.—Find the mass of the empty thermometer.

Fill the thermometer with glycerin by heating the bulb cautiously with a Bunsen flame, and letting the nozzle dip into a vessel containing some warm glycerin. As the bulb cools, glycerin will be drawn into it. By repeated heating and cooling the bulb should be filled completely with glycerin. When the bulb has cooled to the temperature of the room, surround it with a vessel containing crushed ice, still keeping the nozzle in the glycerin. While the bulb is cooling to 0°C ., weigh a small cup or crucible. Remove the thermometer from the ice, placing the cup so as to catch the liquid that escapes. Weigh the thermometer and the cup together, and determine the mass of glycerin filling the thermometer at 0°C .

Next place the thermometer in a beaker of water and heat to the boiling point, allowing the glycerin that is forced out to escape. Remove the thermometer, and let it cool to the temperature of the room. The liquid will contract, but the mass is still the mass of liquid filling the thermometer at 100°C . Weigh the thermometer again, and determine the mass of glycerin.

Calculate the coefficient of apparent expansion of glycerin. Calculate also the coefficient of absolute expansion, assuming the coefficient of expansion of glass to be known.

The coefficient of expansion of fused silica or quartz is so small that the expansion of a vessel made of this material may be neglected.

THE VOLUME DILATOMETER

The **Dilatometer** consists of a cylindrical bulb to which is attached a straight graduated tube. If the volume of the bulb up to the first division on the stem is known, and also the volume corresponding to a division of the tube, the apparatus may be used to determine the coefficient of apparent expansion of a liquid.

EXPT. 159. Determination of the Coefficient of Apparent Expansion of a Liquid by Means of the Dilatometer.—First weigh the empty dilatometer. Then fill it to the first division on the stem with a liquid of known density, and weigh again. From the mass of liquid thus found, calculate the volume of the bulb. Fill the dilatometer to a mark near the top of the stem and weigh again. Find the mass of liquid filling a definite length of the stem, and calculate the volume of this length of the stem. Deduce the volume corresponding with one scale division.

To find the coefficient of apparent expansion of a liquid, fill the bulb and part of the stem with the liquid, and cool the whole to 0°C . by immersing in ice. Read the position of the liquid in the stem. Then heat to a known temperature in a water bath, and again read the position of the liquid in the stem. Calculate the volumes corresponding to these readings. Calculate the coefficient of apparent expansion from the formula $V_t = V_0(1 + \alpha t)$.

§ 3. EXPANSION OF GASES

THE EXPANSION OF AIR AT CONSTANT PRESSURE

When a given mass of a gas expands under a constant pressure, in consequence of a rise of temperature, the relation between the volume and the temperature is expressed by the equation

$$V_t = V_0(1 + \alpha t),$$

where V_t represents the volume of the gas at $t^\circ \text{C.}$, V_0 the volume at 0°C. , and α is called the coefficient of expansion, or the coefficient of increase of volume at constant pressure, its value being very nearly the same for all gases.

The equation expresses in symbolic form the Law of Charles which states that when a fixed mass of gas expands under constant pressure, the volume increases by a definite fraction of the volume at 0°C. for each degree rise of temperature.

EXPT. 160. Determination of the Coefficient of Expansion of Air at Constant Pressure.—A flask of 300 or 400 c.c. capacity is provided with a well-fitting rubber stopper through which passes a short length of glass tubing. The lower end of the tube should be flush with the bottom of the stopper and the upper end should not project more than 2 or 3 cm. above the stopper. A piece of rubber tubing about 5 cm. long is fitted to the projecting glass tube.

The flask, stopper and tube must be dried thoroughly. This drying may be done by washing out with methylated spirit, and blowing a current of air through the apparatus. The weight W_1 of the dry flask is next found.

The flask, with the stopper inserted, is then placed in a can of water which is heated gradually to the boiling point. If the can be fitted with a wire handle, the latter will serve to hold the flask immersed in the water (Fig. 172). The flask must be left in the water for at least five minutes after the boiling point has been reached, so that the air inside may reach the temperature of the boiling water, which we shall assume to be 100°C. The rubber tubing is then pinched firmly between the thumb and finger, and the flask is *quickly* lifted out of the can and turned upside down in a large vessel containing cold water (Fig. 173). As soon as the stopper is under the surface of the cold water, the rubber tube may be released so that cold water may enter the flask. The flask must be immersed completely for several minutes, neck downwards, so that the contents may come to the temperature of the water. Let this temperature be $t^\circ \text{C.}$ The flask is then raised till the level of the water inside the flask is the same as the level outside, and then the pressure of the air inside is the same as the atmospheric pressure. The rubber tubing is pinched while this condition is satisfied and the flask is lifted out of the water, turned right way up, dried on the outside




FIG. 172.—Flask heated to the Boiling Point




FIG. 173.—Flask in Cold Water

and weighed. Let the weight be W_2 .

Then the flask is filled completely with cold water, the stopper is inserted so that the water fills the glass tube, and the weight W_3 is found.

The weight of water filling the whole flask is $W_3 - W_1$ gm. But 1 gm. of water occupies 1 c.c. So the volume of the flask is $W_3 - W_1$ c.c. Now

when the flask was in the boiling water, the air inside it occupied the whole volume and the pressure was atmospheric. Let this volume be V_{100} , then

$$V_{100} = W_3 - W_1 \text{ c.c.}$$

When the flask was placed in the cold water at $t^\circ \text{C.}$, the volume of the air diminished till it became V_t ; and a little consideration will show that

$$V_t = W_3 - W_2 \text{ c.c.}$$

This is the case because the air at this lower temperature occupied the volume *not* occupied by the water sucked into the flask.¹ Thus we find both V_{100} and V_t .

But it is necessary to refer the volumes to the volume at 0°C. in order to calculate the coefficient of expansion. That is, we have two equations

$$\begin{aligned} V_{100} &= V_0 (1 + 100\alpha), \\ V_t &= V_0 (1 + \alpha t), \end{aligned}$$

with two unknown quantities.

Divide the first by the second, then

$$\frac{V_{100}}{V_t} = \frac{1 + 100\alpha}{1 + \alpha t},$$

which gives

$$\alpha = \frac{V_{100} - V_t}{100V_t - tV_{100}},$$

from which the value of α may be calculated.

THE CONSTANT VOLUME AIR THERMOMETER

When a definite mass of gas is enclosed in a vessel the volume of which remains unchanged, the pressure exerted by the gas on the walls of the vessel increases as the temperature is raised. The relation between the pressure and the temperature of the gas may be examined by means of the apparatus known as the **constant volume gas thermometer** due to Jolly (1874).

The gas is contained in a glass globe A (Fig. 174) which may be heated to any desired temperature by the bath of water, or oil, in which it is placed. The globe is connected by a glass tube of small bore with a mercury manometer for measuring the pressure. The manometer consists of two fairly wide glass tubes BD and EC connected by a length of rubber tubing. It contains sufficient mercury to fill the rubber tube and some part of the wide glass tubes. The level of the mercury in BD can be adjusted by raising or lowering the glass tube EC until the meniscus just touches the tip of a little glass index fixed inside B near the junction of the wide and narrow tubes.

In using the apparatus, the mercury meniscus in BD must occupy this definite position, in order that the volume of the gas enclosed in the globe A and the narrow tube may remain constant. The pressure exerted by the gas is equal to that at the level of the mercury surface at B. This

¹ Strictly speaking, there is an error due to the saturated water vapour in the flask.

pressure is found by measuring the difference in level between the surface of the mercury at B and that of the mercury in EC, and taking into account the pressure of the atmosphere on the mercury at E. The atmospheric pressure at the time when the observations are made, must be found by reading the height of the barometer.

Three points in connection with the use of the apparatus require to be emphasised :—

I. In order to determine the difference in level of the mercury surfaces accurately, the apparatus must be so arranged that the tubes C and D are quite close to the scale used in measuring the level.

II. The determination of the pressure must be made while the temperature of the gas is constant. *Great care must be taken to keep the bath in which A is immersed at a steady temperature* while EC is being adjusted, and the reading of the difference of level of the mercury surfaces is being made. This can be done more easily when the temperature is falling than when it is rising, so that it is advisable to heat the bath to the highest temperature to be used in the experiments and then allow the bath to cool slowly. As, however, this takes a considerable time, the bath may be heated to one or two degrees above any desired temperature and then the heater removed. The water is now stirred thoroughly until it has cooled to the temperature desired. The adjustments are made *approximately* while the water is cooling, are brought rapidly to their exact value, and the reading is taken when this temperature has been reached. The whole bath is then heated rapidly to a little above the next temperature desired, when the same process is repeated.

The success of the experiment depends on the temperature of the gas inside the bulb being exactly the same as the temperature of the bath outside, and upon this temperature being determined accurately.

III. When the bath is allowed to cool, *great care must be taken that the mercury in BD is not drawn over into the bulb A* in consequence of the reduction of the pressure of the gas. To prevent this, lower the tube EC so that the mercury in BD may be well below the top of the tube. *When the experiment is completed the tube EC must always be lowered in this way.*




FIG. 174.—Jolly's Constant Volume Gas Thermometer

EXPT. 161. Variation of the Pressure of a fixed Mass of Air with the Temperature as shown by a Mercury Thermometer when the Volume is kept constant.—Use a water bath to heat the bulb of the air thermometer, and a mercury thermometer to take the temperature of the water bath. Heat the water to the boiling point, and when the temperature has become steady, read the thermometer, adjust the mercury in the manometer, and read the level of B and E. Then lower the tube EC as described above and allow the temperature to fall about 20° , and again take readings of temperature and pressure. Take a series of readings in this way, allowing the temperature to fall about 20° between consecutive

readings. Or the adjustments to the different temperatures may be made while raising the temperature, if the precautions mentioned in II are taken, the final temperature being 100°C .

Record the results as follows :—

Height of Barometer = . . .
Level of Index Mark at B = . . .

Temperature	Level of E	Difference of Level, E - B	Pressure A
-------------	------------	-------------------------------	------------

The relation between the pressure of the air and its temperature must now be represented graphically, taking the pressure as the ordinate and the temperature as the abscissa. The points so obtained should fall nearly on a straight line. Draw a straight line passing through the points so that there are about as many points above the line as below it. Find from this line, which may be taken to represent an average of the experimental results, the pressures corresponding to two chosen temperatures t_1 and t_2 . Let these pressures be p_1 and p_2 .

Then, if α denote the coefficient of increase of pressure of a gas with temperature, we may write

$$p_1 = p_0(1 + \alpha t_1),$$

$$p_2 = p_0(1 + \alpha t_2).$$

We can eliminate p_0 by dividing one equation by the other, and so obtain

$$\frac{p_1}{p_2} = \frac{1 + \alpha t_1}{1 + \alpha t_2}.$$

Solving for α we get

$$\alpha = \frac{p_2 - p_1}{p_1 t_2 - p_2 t_1}.$$

Calculate the value of α by means of this equation.

We may, if we please, select as the chosen temperatures $t_1 = 0^{\circ}\text{C}$. and $t_2 = 100^{\circ}\text{C}$. Find from the graph the corresponding pressures p_0 and p_{100} , and calculate α from the equation

$$p_{100} = p_0(1 + \alpha 100).$$

To do this the graph must be extended beyond the lowest temperature used, the pressure p_0 being obtained by *extrapolation*.

EXPT. 162. Determination of the Temperature of the Melting Point of a Substance by means of the Constant Volume Air Thermometer.—In this experiment no mercury thermometer is to be used, but the scale of temperature defined by the constant volume air thermometer is to be employed. First determine the 'fixed points' of the thermometer. Determine the lower fixed point by observing the pressure of the air in the bulb when the surrounding bath contains melting ice. Let this pressure be p_0 . Determine the upper fixed point by observing the pressure of the air in the bulb when at the boiling point. Strictly speaking, it would be necessary to surround the bulb with steam from pure water boiling under standard pressure to obtain this point accurately. For the present purpose it will suffice to surround the bulb with boiling water in the water bath. Let the corresponding pressure be p_{100} .

Then

$$p_{100} = p_0(1 + \alpha 100).$$

The value of α can thus be found by direct experiment.

Now adjust the temperature of the water in the water bath till it is equal to that of the melting point of the solid. For this purpose a small quantity of the solid may be placed in a thin-walled test-tube, which may be immersed in the water bath. Read the pressure p corresponding with this temperature.

Then on the scale of the constant volume air thermometer we have

$$p = p_0(1 + \alpha t),$$

where t is the temperature to be determined, and α has the value already found experimentally.

Calculate the temperature t from this equation.

A process is said to be **isothermal**, when it takes place at *constant* temperature.

The results of experiments on gases expressed in the laws of Boyle and of Charles may be combined in the single expression

$$PV = RT,$$

where P denotes the pressure, V the volume of a given mass of gas, and T is the absolute temperature, or the temperature reckoned from 273°C. below the freezing point on the centigrade scale.

The temperature of the ice point on the absolute or Kelvin scale is 273°K. or more accurately 273.16°K.

R is a constant generally known as the **gas constant**.

This expression should be employed in dealing with calculations with regard to gases, except when the gas coefficient α has to be determined from experimental observations.

If unit mass of gas be considered, $V = 1/\rho$, where ρ is the density of the gas, and the gas equation may be written

$$P/\rho = RT.$$

In this equation R is the gas constant reckoned for 1 gm. of gas.

The **gram-molecule** (or the **mole**) of any substance is a mass of that substance containing as many grams as there are units in the molecular weight of the substance. The volume of one gram-molecule of gas at normal temperature and pressure is 22415 c.c. The atmospheric pressure corresponding to 760 mm. of mercury at 0°C. , lat. 45° , and sea level is 1,013,200 dynes per sq. cm. Hence the gas constant for 1 mole or 1 gram-molecule is

$$\begin{aligned} R &= \frac{P_0 V_0}{T_0} \\ &= \frac{1013200 \times 22415}{273.16} \\ &= 8.314 \times 10^7 \text{ erg. deg.}^{-1} \text{ gm.-mol.}^{-1} \\ &= 1.987 \text{ cal. deg.}^{-1} \text{ gm.-mol.}^{-1} \end{aligned}$$

To find R for 1 gram of a gas, this figure must be divided by the molecular weight of the gas.

CHAPTER III

CALORIMETRY

§ 1. MEASUREMENT OF QUANTITIES OF HEAT

THE subject of calorimetry deals with the measurement of quantities of heat. The unit quantity of heat is that quantity which is required to raise the temperature of unit mass of water one degree. The unit generally employed in scientific work is the *calorie*, which may be defined as the quantity of heat required to raise the temperature of 1 gm. of water 1° C. at some specified temperature. This quantity is nearly, but not exactly, the same at different temperatures, between 0° C. and 100° C., for example the 15° calorie is about 1 part in 1000 greater than the 20° calorie. In what follows these small variations will be ignored. The number of calories required to raise the temperature of m gm. of water from t_1° C. to t_2° C. will then be

$$H = m(t_2 - t_1).$$

A certain quantity of heat is required to raise the temperature of a body 1° C. — this quantity is called the **thermal capacity of the body**. The quantity of water which requires the same amount of heat as a certain body to raise its temperature 1° C. is called the **water equivalent of the body**. The water equivalent in *grams* is numerically equal to the thermal capacity in *calories per $^{\circ}$ C.*

If the water equivalent of a body be w gm., then the heat required to raise the temperature of the body from t_1° C. to t_2° C. is

$$H = w(t_2 - t_1).$$

The thermal capacity of unit mass, or the **specific heat**, of a substance is the number of calories required to raise the temperature of 1 gm. of the substance 1° C. If the specific heat of a substance be denoted by s calories per gram per $^{\circ}$ C., or s cal. gm. $^{-1}$ ($^{\circ}$ C) $^{-1}$, the heat required to raise the temperature of m gm. from t_1° C. to t_2° C. is

$$H = ms(t_2 - t_1).$$

This is the fundamental equation in connection with the measurement of quantities of heat.

Comparing this with the preceding equation, we see that the water equivalent $w = ms$. Hence the water equivalent of a body can be

calculated as the product of the mass of the body and the specific heat of the substance.

In some branches of science it is convenient to use the kilogram as the unit of mass and the corresponding thermal unit, the **large calorie**, or **kilogram calorie**, which is 1000 times as large as the gram calorie.

In the measurement of quantities of heat by making observations of changes of temperature, that is in **thermometric calorimetry**, a principle of "conservation" is employed. This may be expressed in the statement :

HEAT LOST by hot bodies = HEAT GAINED by colder bodies.

This principle, must, however, be applied with care, as in dealing with so-called Latent Heat, and the production of heat by mechanical processes.

CALORIMETERS

A vessel adapted for the measurement of quantities of heat is termed a **calorimeter**. It should be arranged so as to avoid, as far as possible, transference of heat to or from external bodies. Such transference can take place by conduction, convection, or radiation. To avoid conduction of heat, the calorimeter is supported by some bad conductor of heat, such as felt, cotton wool, cork, or ebonite. To avoid convection currents, the vessel is sometimes packed in cotton wool or surrounded by a vacuum jacket. To prevent transference of heat by radiation, usually the calorimeter is supported in an outer vessel, the outside of the inner vessel being brightly polished to diminish the emissivity, and the inside of the outer vessel being polished brightly to increase the reflecting power.

A Dewar's vacuum vessel (thermos flask) is a convenient calorimeter for some experiments, but as the glass does not all acquire the same temperature, there is some difficulty in deciding what value to take as its thermal capacity. See, however, p. 296.

§ 2. DETERMINATION OF THE SPECIFIC HEAT OF A SOLID

EXPT. 163. Simple Methods of determining the Specific Heat of a Solid.—A known mass of the solid is heated to a definite temperature and then placed in a known mass of water at the temperature of the room. The solid and the water finally attain a common temperature, which is observed. The specific heat of the solid can then be calculated.

The solid should be weighed first of all, so that the other weighings can be carried out while the solid is being heated. If the solid is a lump of metal, attach to it a fine thread or wire, and lower it into a can of water which can be heated to the boiling point.¹ If the solid is in fragments (e.g. lead shot or brass filings) place the fragments in a test-tube of glass or thin metal plugged with cotton-wool and heat this in the boiling water. The solid must be heated for a sufficient time to reach a steady temperature.

While the solid is being heated, weigh a calorimeter (with its stirrer) and weigh it again when about half full of water. Observe and record the temperature of the water to 0.1° C.

¹ Simple forms of heater are now available which avoid contact between the solid and boiling water or steam.

When the temperature of the solid has reached that of the boiling water, transfer it as quickly as possible to the calorimeter. In the case of the fragments, the test-tube is lifted by a suitable handle and tilted so that the fragments fall into the calorimeter. Stir the water in the calorimeter and observe carefully the highest temperature recorded by the thermometer. In the case of the solid lump, a small quantity of water is unavoidably transferred to the calorimeter when the lump is lifted by the thread and placed in the latter vessel; and this introduces a serious error.

The following example (in which simple numbers have been chosen) illustrates the method of entering the observations and calculating the result :—

Example.—Determination of the specific heat of lead shot.

Mass of lead shot	= 200 gm.
Mass of calorimeter and stirrer	= 40.0 gm.
Mass of calorimeter, stirrer, and water	= 252.2 gm.
Mass of water	= 212.2 gm.
Initial temperature of shot	= 100° C.
Initial temperature of water, t_1	= 15.0° C.
Final temperature of water and shot, t_2	= 17.3° C.

We assume that the heat given out by the solid in cooling from 100° C. to the final temperature t_2 is exactly equal to the heat taken in by the water and the calorimeter when their temperature rises from t_1 to t_2 .

If s is the specific heat of the solid, the heat it gives out is

$$200 \times s \times (100 - t_2) \text{ calories.}$$

The 'water equivalent' of the calorimeter is equal to its mass multiplied by the specific heat of the material (0.095 say)

$$= 40 \times 0.095 = 3.8 \text{ gm.}$$

The total water equivalent (including both calorimeter and water)

$$\begin{aligned} &= 212.2 + 3.8 \text{ gm.} \\ &= 216 \text{ gm.} \end{aligned}$$

The heat taken in by the water and the calorimeter

$$\begin{aligned} &= 216 \times (17.3 - 15) \\ &= 496.8 \text{ calories.} \end{aligned}$$

We next write down an equation expressing the fact that the heat given out by the solid is equal to the heat taken in by the water and the calorimeter.

$$\begin{aligned} 200 \times s \times (100 - 17.3) &= 496.8 \\ s &= 0.03 \text{ calories per gm. per } 1^\circ \text{ C.} \end{aligned}$$

REGNAULT'S APPARATUS

For the accurate determination of the specific heat of a solid an apparatus of the type designed by Regnault may be employed. The chief points kept in view in the design of this apparatus were the heating of the solid to a fixed temperature without contact with moisture, the rapidity of transference from the heating chamber to the calorimeter, and the protection of the calorimeter from the heating chamber during the other parts of the experiment.

The solid at A (Fig. 175) is heated inside a double-walled steam jacket, through which a current of steam is passed from a boiler. The boiler and the outlet pipe must be arranged so as not to radiate heat to the calorimeter C, which is shielded from the steam heater by a sliding wooden shutter D. While the solid is being heated the upper end of the chamber is closed by a cork through which passes a thermometer reading to 100° C., and the lower end is closed by part of the wooden platform E. The solid,

which should be placed in contact with the bulb of the thermometer, is suspended by a fine thread held in position by the cork. In the case of a metal it is convenient to use a wire bent into the form of a helix.

EXPT. 164. Regnault's Apparatus for the Specific Heat of a Solid.—

As it requires a long time for the solid to attain a steady temperature, the first operation, after arranging for a supply of steam, should be to weigh the solid and to suspend it in the heating chamber. Then the inner vessel of the calorimeter should be weighed, and filled about three parts full of water, after which it is weighed again to determine the mass of the water. It is then placed in position in the outer metal vessel, which is further protected by the wooden box. A sensitive thermometer is used to determine the temperature of the water in the calorimeter as accurately as possible. The solid should be allowed to remain in the heating chamber for at least five minutes *after the temperature shown by the thermometer in the chamber has become steady.* The whole process of heating the solid will take probably from twenty to thirty minutes after steam has commenced to pass.



When this steady temperature has been recorded, the heating chamber is swung round till it comes above the hole in the platform E. The shutter D is raised, and the box F containing the calori-




Fig. 175.—Regnault's Apparatus

meter is pushed into position so that the inner vessel of the calorimeter is exactly underneath the hole in the platform. The solid is lowered quickly into the calorimeter without splashing, the box F is withdrawn, and the shutter is lowered. The temperature of the calorimeter is observed carefully and the highest temperature reached recorded. In an accurate determination a cooling curve would be plotted in order to determine the correction necessary to allow for loss of heat by radiation (p. 291).

From the observations the specific heat can be calculated exactly as in the simpler experiment on p. 288.

- Let m = the mass of the solid.
 s = the unknown specific heat.
 c = the mass of the calorimeter.
 M = the mass of water in the calorimeter.
 s_1 = the specific heat of the material of the calorimeter.
 t = the temperature of the hot solid.
 t_1 = the initial temperature of the calorimeter.
 t_2 = the final temperature of the calorimeter.

Then the heat given out by the solid in cooling from t to t_2

$$= ms(t - t_2).$$

The heat taken in by the water and the calorimeter in changing in temperature from t_1 to t_2

$$= (M + cs_1)(t_2 - t_1).$$

Assuming these quantities of heat to be equal,

$$ms(t - t_2) = (M + cs_1)(t_2 - t_1),$$

an equation from which the value of s can be determined.

The student should not attempt to remember an equation of this kind, but should obtain the result in any particular case from first principles.

§ 3. DETERMINATION OF THE SPECIFIC HEAT OF LIQUIDS

The specific heat of a liquid may be determined by the method of mixtures in several ways.

EXPT. 165. Determination of the Specific Heat of a Liquid, using a Solid of known Specific Heat.—The solid must have no chemical action on the liquid.

This determination is carried out in exactly the same manner as that of the specific heat of a solid (Expts. 163 and 164), using the given liquid in place of water in the calorimeter.

Let s_2 denote the specific heat of the liquid, M its mass, then

$$ms(t - t_2) = (Ms_2 + cs_1)(t_2 - t_1),$$

where the other symbols have the meaning previously assigned to them.

EXPT. 166. Determination of the Specific Heat of a Liquid by Regnault's Method.—The specific heat is determined by running the hot liquid into a thin-walled metal vessel placed in the water in the calorimeter, or conversely by running hot water into a thin-walled metal vessel placed in the given liquid in the calorimeter. Since the mixture of two liquids at the same temperature often results in the evolution of heat through chemical action, the two liquids should not, as a rule, be brought into direct contact.

EXPT. 167. Determination of the Specific Heat of a Liquid by the Method of Mixtures.—A more convenient method is to heat the liquid in a small thin-walled glass bottle, or metal cylinder,¹ closed by a cork through which passes a thermometer. The heated bottle, after its temperature has been determined, is transferred to the calorimeter. The bottle, held by the stem of the thermometer, may be used as a stirrer. A second thermometer is used to determine the temperature of the water in the calorimeter. The final temperature is taken as the mean of the readings of the two thermometers when they differ by only one degree or less. The water equivalent of the vessel containing the liquid must of course be taken into account, as well as the water equivalent of the calorimeter.

EXPT. 168. Determination of the Specific Heat of a Liquid by means of the Calorifer.—The calorifer resembles a mercury thermometer with a large bulb. There are, however, only two marks on the stem. By heating the calorifer in boiling water the mercury rises above the upper mark. The calorifer is removed from the boiling water, dried, and placed in a weighed quantity of liquid in the calorimeter at the instant when

¹ Thin-walled aluminium cylinders are obtainable which are suitable for this purpose.

the mercury reaches the upper mark. It is left in the calorimeter till the mercury sinks to the lower mark, when it is at once removed. The rise of temperature of the liquid in the calorimeter is measured by a sensitive thermometer. The same operation is then repeated, using a known weight of water in the calorimeter. Since exactly the same quantity of heat is transferred by the calorifer to the calorimeter in the two experiments, it is easy to calculate the specific heat of the liquid. The method of calculation is left as an exercise for the student.

A description of the determination of the specific heat of a liquid by the method of cooling will be found on p. 300.

§ 4. METHOD OF CORRECTING CALORIMETRIC OBSERVATIONS FOR RADIATION

For accurate calorimetry, the calorimeter should be enclosed in a double-walled metal vessel, between the walls of which water is placed. By this means, the calorimeter is enclosed in constant temperature surroundings, and the radiation may be assumed to be proportional to the difference between the temperature of the calorimeter, and the temperature of the surrounding enclosure.

The temperature of the calorimeter is taken every 30 seconds before and after the experiment as well as during the experiment itself, and a curve showing the temperature variation with time is plotted.

At the highest temperature reached, the rate of fall of temperature is determined from the curve; let this be x degrees per minute, the highest temperature being t degrees above the surroundings.

Divide the curve into one-minute intervals, starting from the instant when the hot body was dropped into the calorimeter, and take the temperature at the middle of each of these intervals as the mean temperature during that minute. Let these temperatures be respectively t_1, t_2, t_3 degrees above the temperature of the enclosing




FIG. 176.—Correction Curve

During the first minute, heat was lost corresponding with a mean temperature excess of t_1 degrees. If this heat had been retained, the temperature at the end of the first minute would have been higher than the temperature actually reached by an amount $x_1 = \frac{x}{t} t_1$.

During the second minute the heat lost would correspond with a loss of temperature $x_2 = \frac{x}{t_2}$, and so on.

The temperature at the end of the first minute is x_1 degrees too low, during the second minute there is a further loss of x_2 degrees, so that the temperature at the end of the second minute is $x_1 + x_2$ degrees too low, due to the cooling in the *two* minutes which have elapsed since the hot body was introduced.

Similarly, the correction to be added at the end of the third minute is $x_1 + x_2 + x_3$, and so on. By adding on these corrections to the curve plotted, a new curve will be obtained, giving the temperatures that would have been reached if there had been no radiation losses; this curve will be horizontal at the end of the experiment, the ordinate of the horizontal portion being the corrected temperature.

If desired, *half*-minute intervals may be taken, the correction being added on every half-minute instead of every minute as described.

§ 5. LATENT HEATS

DETERMINATION OF THE LATENT HEAT OF WATER

Latent Heat of Fusion of Ice.—The quantity of heat required to change one gram of ice from the solid to the liquid form without change of temperature is called the latent heat of water, or the latent heat of fusion of ice.

When small lumps of dry ice are added to a known mass of water in a calorimeter the ice is melted, becoming water at 0°C. , and the ice-cold water abstracts heat from the warm water and calorimeter, until an equilibrium temperature is reached.

If the calorimeter at the commencement of the experiment is at the temperature of the room, it will be cooled below that temperature by the addition of ice, and so will be gaining heat by radiation throughout the experiment.

To avoid error due to this cause, it is advisable to warm the calorimeter and the contained water to about 5° above the temperature of the room, and to add sufficient ice to cool it through the same number of degrees below the temperature of room. The loss of heat during the first half of the experiment will then about balance the gain during the second half, provided the second half of the experiment does not require much longer time than the first half.¹

EXPT. 169. Determination of the Latent Heat of Fusion of Ice.—First weigh the calorimeter with the stirrer. Introduce from 100 c.c. to 200 c.c. of water and weigh again.

The difference between these two weighings gives the mass of water in the calorimeter.

Warm the calorimeter to about 5° above the temperature of the room, by placing it in a vessel of hot water.

¹ This method of avoiding error cannot be applied satisfactorily if the temperature of the room is very low, or if, as sometimes happens in tropical countries, the cooling would result in the temperature being reduced much below the dew point. In such cases it would be preferable to start with the temperature above that of the room, and finish when the temperature is about the same as that of the room, applying a correction for the heat lost by radiation by the method on p. 291.

DETERMINATION OF THE LATENT HEAT OF STEAM

Latent Heat of Steam.—The latent heat of steam, or the latent heat of vaporisation of water, is the amount of heat required to convert 1 gm. of water into steam without change of temperature under a specified pressure.

When steam from a boiler is passed through a known mass of water in a calorimeter, some of the steam is condensed and the final tempera-




FIG. 177.—Latent Heat of Steam

ture of the water is raised above its initial temperature. From the observed rise of temperature and the mass of steam condensed, the latent heat of steam can be calculated. *The particular temperature concerned should be stated.*

If the water in the calorimeter is at the temperature of the room at the beginning of the experiment, it will lose heat by radiation as soon as its temperature is raised above that of surrounding objects. This would tend to give too small a value for the latent heat.

The error due to this cause may be reduced by commencing the experiment with the tempera-

ture of the water as much below the temperature of the room as it is above the temperature of the room at the end of the experiment. The error may also be diminished by making the duration of the heating as short as possible. For this purpose the steam should be made to issue from the nozzle in a rapid stream. A screen may be placed between the boiler and the calorimeter to prevent radiation of heat (Fig. 177).

To obtain an accurate result the steam must be dry, that is, free from condensed water. A well-designed water trap may be used to remove as much of the condensed water as possible. The rubber tube connecting the boiler to the water trap should be short: it may be lagged with cotton wool.

The importance of having the steam dry will be realised from the fact that carrying over 1 gm. of water with the steam introduces an error equivalent to about 500 calories.

Expt. 170. Determination of the Latent Heat of Steam.—First see that the boiler contains a sufficient quantity of water, then begin to heat it by means of a gas-burner.

The calorimeter is made in two parts, an inner and an outer vessel. Weigh the inner vessel, and fill it about two-thirds full with water.

Add small pieces of ice till the temperature of the water has fallen to about 5° C. Then weigh the inner vessel with its contents accurately.

Note the temperature of the room and again read the thermometer in the calorimeter. Estimate the temperature at which the experiment

ought to be finished. For example, if the temperature of the room is 15°C ., the final temperature should be about 25°C .

In this experiment the nozzle must not be immersed in the water: it should be placed with its end only the slightest amount below the surface, so that the water surface is blown away from the end of the nozzle and the steam merely plays on the water surface. If the nozzle is put right down into the water the steam may condense too rapidly, when the water will be sucked up into the steam trap and the whole experiment spoiled. No error is introduced by escaping steam; the steam which escapes does not condense in the water, so that its latent heat is not given up, nor is its mass included in the mass of steam condensed.

Remove any water drops adhering to the nozzle of the delivery tube after the flow of steam has commenced. Pass a rapid current of steam, at the same time thoroughly stirring the water so as to ensure uniformity of temperature. When the temperature has risen to the desired point, remove the calorimeter as quickly as possible from the neighbourhood of the boiler, and observe the highest temperature recorded by the thermometer.

Weigh the calorimeter again in order to determine the amount of steam condensed.

Read the height of the barometer.

For the standard pressure 760 mm. the temperature of steam is 100°C . Near this pressure an increase of pressure corresponding to 26.8 mm. of mercury raises the boiling point one degree C ., and for small changes the rise in the boiling point is proportional to the change in pressure. Hence the temperature of steam corresponding to the observed pressure may be calculated. As, however, the temperature thus found differs but little from 100°C ., the error introduced by taking the temperature of the steam as 100°C . is inappreciable compared with other unavoidable experimental errors.

Enter the results as follows :—

Mass of calorimeter	= 160.0 gm.
„ calorimeter and water	= 684.2 gm.
„ water	= 524.2 gm.
„ calorimeter and water and steam	= 704.4 gm.
„ steam condensed	= 20.2 gm.
Initial temperature of water $t_1^{\circ}\text{C}$.	= 6.2°C .
Final temperature of water $t_2^{\circ}\text{C}$.	= 28.6°C .
Barometric height	= 758 mm.
Temperature of steam $T^{\circ}\text{C}$.	= 100°C .

Calculate the 'water equivalent' of the calorimeter. The total water equivalent is obtained by adding the mass of water in the calorimeter to the water equivalent of the calorimeter. If this is multiplied by the rise of temperature, $t_2^{\circ} - t_1^{\circ}$, we obtain the amount of heat absorbed by the calorimeter and the water in it. This is expressed in calories.

Now consider the heat given out in condensing the steam and in lowering the temperature of the resulting water.

Heat given out in condensing the steam

$$\begin{aligned}
 &= \text{mass of steam condensed} \times L \\
 &= \text{mass of condensed water} \times L \\
 &= 20.2 \text{ gm.} \times L.
 \end{aligned}$$

Heat given out in lowering the temperature of the resulting water from T° to t_2°

$$\begin{aligned}
 &= \text{mass of steam} \times (T - t_2) \\
 &= 20.2(100 - 28.6) \text{ calories.}
 \end{aligned}$$

Assuming that there is no loss or gain of heat by radiation, the sum of these two quantities must equal the heat absorbed by the calorimeter and the water in it.

This gives a simple equation from which L may be determined.

WATER EQUIVALENT OF A DEWAR FLASK

This method of finding the water equivalent of a Dewar flask is due to Dr. L. F. Richardson. The directions apply to a pint size (half-litre) flask. Take the temperature (t_1) of a known quantity (about 50 c.c.) of cold water. Fill the flask about three-quarters full with hot water and close with a well-fitting cork through which a thermometer passes. Turn the flask upside down and roll the water round inside it to ensure uniform temperature throughout the interior. Accurate results depend on the care with which this is done. Note the temperature t_2 . Pour away the hot water and quickly pour in the known quantity of cold water. Replace the cork, and, after again shaking, observe the resulting temperature t_3 . From the above data the water equivalent of the flask can be calculated. The flask may be used for determining the latent heat of water or that of steam.

CHAPTER IV

COOLING

§ 1. THE LAW OF COOLING

WHEN a hot body is placed in an enclosure kept at a constant temperature, the temperature of the hot body will fall till at length it becomes equal to that of the enclosure. If the body be supported in such a way that the transference of heat by conduction can be neglected, the cooling process will be due partly to radiation and partly to convection. If the effect of convection currents be eliminated, as by carrying out experiments in a vacuum, the total radiation emitted per second is found to be proportional to the fourth power of the absolute temperature. This is known as Stefan's Law.

It must be remembered that the enclosure is also emitting radiation at a rate proportional to the fourth power of its own absolute temperature.

In the ordinary case in which a hot body cools in air at atmospheric pressure, the rate of cooling is found to be proportional to the difference between the temperature of the body and that of its surroundings. This is known as Newton's Law of Cooling. Recent experiments have shown that the law is approximately true within fairly wide limits of temperature, when the cooling takes place both by convection and by radiation.

EXPT. 171. Determination of the Rate of Cooling at different Temperatures.—To illustrate Newton's law of cooling, support a small thin-walled metal vessel inside a larger one,¹ in such a way as to reduce as far as possible transference of heat by conduction. Nearly fill the small vessel with hot water at a temperature of about 80° C. Take readings of the temperature of the water at intervals of half a minute until the temperature has fallen to within about ten degrees of the constant temperature of the surroundings. Plot a graph with the temperature as ordinate and the time as abscissa, taking care that the curve is drawn *smoothly* through the observed points (Fig. 178). This cooling curve will be steep at first, but will become less steep as the temperature approaches that of the room. Draw a horizontal line on the squared paper to represent the temperature of the room (here assumed constant), or of the enclosure.

To find the rate of cooling, or the rate of change of temperature, at any particular temperature corresponding to a point P on the graph,

¹ As the temperature of the room may vary, it is advisable to enclose this in another still larger and fill the space between with water. The small vessel containing the hot water should be closed (Fig. 180).

draw a tangent to the curve at this point. Draw this line very carefully so that its direction may represent as accurately as possible the direction of the curve at the point.

Let the tangent meet the vertical axis at A and the horizontal line representing the temperature of the room at B. Then the rate of change




FIG. 178.—Rate of Cooling

of temperature is given by the slope of this line, that is, the tangent of the angle ABC or θ . Measure the lengths AC and CB, and calculate $\tan \theta$, which is equal to AC/BC. The difference between the temperature of the body and that of the room is represented by PN. Determine this difference of temperature.

Then according to Newton's law of cooling, $\tan \theta$, the rate of cooling, should be proportional to PN, the difference of temperature. That is, since $\tan \theta \propto PN$, $\tan \theta = kPN$, or $\tan \theta / PN = k$, a constant. This assumes the temperature of the room or enclosure constant.

Determine this quantity for at least three points on the graph, selecting the points so as to repre-

sent fairly different portions of the complete curve, and notice whether the result is constant.¹

Find the difference between the greatest and the least value of the results obtained, and calculate the percentage difference.

When one quantity varies with another in such a way that the rate of change of the first quantity with regard to the second is proportional to the first quantity, then the variation is said to obey the logarithmic, or exponential, law.

This is the case when a sum of money accumulates at compound interest, but then the quantity is continually increasing while in the question now under consideration the temperature of the hot body is continually diminishing. If we plot the logarithm of the excess of temperature (above the room temperature) against the time, the result should be a straight line. Students who have an elementary knowledge of the differential calculus may then verify Newton's law as follows. If the graph in question is a straight line

$$\log E - \log e = at,$$

where e is the excess at time t , E is the initial excess when $t = 0$, and a is a constant.

Differentiating,

$$-\frac{1}{e} \frac{de}{dt} = a \quad \text{or} \quad -\frac{de}{dt} = ae,$$

that is, the rate of fall at time t is proportional to the excess at this time t .

§ 2. CURVE OF COOLING WHEN A LIQUID SOLIDIFIES

In the last experiment, Newton's Law of Cooling was illustrated by the cooling of a thin-walled metal vessel containing hot water. The

¹ Since $\tan \theta = PN/NB$, $\tan \theta / PN = 1/NB$.

Hence if $\tan \theta / PN$ is a constant, NB must be a constant.

This gives a simple graphical method of testing the truth of the law. Measure the length of the line NB for the different points considered, and notice whether this length is approximately constant.

results obtained in such an experiment are modified in a characteristic way when the liquid in the vessel passes through the temperature at which solidification occurs.

In the present experiment, a substance may be used having a melting point above the ordinary atmospheric temperature, but below 100°C . For instance, naphthalene, stearin, or paraffin wax of good quality may be employed. If the substance at the beginning of the experiment is in the liquid state, and the vessel is allowed to cool, the




FIG. 179.—Cooling Curve showing Melting Point of Naphthalene

temperature falls regularly until the point of solidification of the liquid is reached. Then, as each successive portion solidifies, it gives up its latent heat, and so prevents the temperature from falling. The temperature therefore remains approximately constant till the whole of the substance has solidified. From this time the temperature again diminishes regularly, till at length the solid reaches the temperature of the room (Fig. 179).

EXPT. 172. Determination of the Melting Point by a Cooling Curve.—

The small metal vessel containing the substance to be examined is heated carefully by plunging it in a vessel of hot water, till the whole of the wax has melted and reached a temperature of not more than 80°C . or 90°C .

The small vessel is then supported inside a larger, and readings of the temperature are taken at half-minute intervals. When the substance begins to solidify, it becomes necessary to leave the thermometer at rest in the centre of the solidifying mass, so that it is better *not* to stir in this

experiment. Continue reading the temperature till it has fallen 10° or 15° below the melting point of the substance.

Plot a curve with the times as abscissae and the temperatures as ordinates. Be careful so to choose the scale that the curve covers practically the whole of the sheet of paper. From the curve determine the melting point of the substance, that is the temperature at which the curve first shows a horizontal portion.

When the substance is a mixture, there may be several different melting points indicated, or no sharp change may be observed. The cheaper kinds of paraffin wax are mixtures of various members of the paraffin series which melt at different temperatures: the various constituents dissolve each other to a slight extent, and there may be no definite melting point.

Super-cooling.—An interesting case of cooling is offered by sodium thio-sulphate, better known as ordinary photographic 'hypo'. If this is melted and a cooling curve taken in the usual way, the temperature will fall quite steadily for a considerable time, obeying Newton's law of cooling. Suddenly solidification will commence and immediately a considerable *rise* of temperature will take place, the temperature rising to, and remaining steady at, the true melting point, until all the 'hypo' has solidified. It will then commence to fall again according to the ordinary law of cooling. The student should endeavour to formulate some theory as to the cause of the *rise* of temperature when solidification begins.

It may sometimes be observed that the temperature has fallen to only a few degrees above atmospheric temperature and yet solidification has not taken place. If the temperature falls to below 25° C. without solidification occurring, a crystal of solid 'hypo' should be dropped into the molten mass, the temperature being carefully observed the while.

§ 3. SPECIFIC HEAT OF A LIQUID BY METHOD OF COOLING

The quantity of heat lost per second by a substance in given surroundings depends on the temperature of the cooling body, on the area it exposes, and on the nature of the surface exposed. The fall of temperature per second is equal to the heat lost per second divided by the thermal capacity of the body.

When a quantity of liquid heated to some fairly high temperature is allowed to cool in a calorimeter placed in a constant temperature enclosure, a cooling curve can be plotted from observations of the temperature of the liquid taken at half-minute or minute intervals. The liquid can then be replaced by water, and a similar experiment carried out for the water.

If we take *identical ranges of temperature* in the two cases, the average rates of loss of heat will be identical, though the average rates of fall of temperature will not. If the rates of fall of temperature are found from the curves in the two cases, then we can find expressions for the rates of loss of heat, and by equating these we can determine the specific heat of the liquid.

Let M = mass of liquid used and S its specific heat,
 W = mass of water,
 m = mass of calorimeter, s its specific heat.

Then suppose that the temperature falls from θ_1 to θ_2 in each case, the times taken for this to take place being t_1 , when the liquid is used, and t_2 with water.

The average rate of loss of heat in the first case is

$$\frac{(MS+ms)(\theta_1 - \theta_2)}{t_1},$$

and in the second case is

$$\frac{(W+ms)(\theta_1 - \theta_2)}{t_2}.$$

These rates are equal, hence

$$\frac{MS+ms}{t_1} = \frac{W+ms}{t_2}.$$

From this equation S can be calculated.

EXPT. 173. Determination of the Specific Heat of a Liquid by the Method of Cooling. I.—A double-walled vessel with water *between* the




FIG. 180.—Specific Heat of a Liquid

walls is useful as a constant temperature enclosure. Paraffin oil is a suitable liquid to employ in this determination. A small calorimeter of metal, with a lid pierced for a thermometer and a stirrer, is used to contain the liquid. It is important that the outer surface of the calorimeter should be in the same condition in the two parts of the experiment. It may either be highly polished or coated with dead-black varnish.

Weigh the calorimeter. Heat some paraffin in another vessel to about 75°C . by dipping the vessel in hot water, and pour the hot paraffin into the calorimeter. Cover the calorimeter and place it in position in the enclosure, supporting it by a non-conductor of heat so that it does not come into contact with the surrounding vessel (Fig. 180). Read the thermometer at intervals of 1 minute as the temperature falls from 70° to 30°C ., keeping the liquid gently stirred. The calorimeter must be removed and weighed at the end of the observations to determine the mass of paraffin. The same procedure must then be followed, using water

instead of paraffin, taking care not to alter the radiating surface in any way.

Plot the two cooling curves on squared paper, taking temperatures as ordinates, times as abscissae. From the curves determine the number of seconds required for the paraffin and for the water to cool through *the same range* of temperature (say from 65° to 30° C.). Calculate the specific heat of the paraffin from the formula given on p. 301.

Sometimes two calorimeters are used, one containing water and the other the liquid (paraffin). If this is done, they must be of the same metal (aluminium), have identical dimensions and be polished carefully; they are suspended at a little distance apart in the same enclosure. Except for the saving of time in taking the cooling curves simultaneously, this method is not to be recommended, as it is impossible to ensure that the cooling surfaces, even if equal in area, shall be identical in polish. The calorimeters used are small, and it is assumed that the temperature shown by the thermometer represents the temperature of the liquid *without stirring*.

Let m_1 denote the mass of the first, m_2 the mass of the second calorimeter.

Then $\frac{(MS + m_1s)(\theta_1 - \theta_2)}{t_1}$ is equal to $\frac{(W + m_2s)(\theta_1 - \theta_2)}{t_2}$.

Hence $\frac{MS + m_1s}{t_1} = \frac{W + m_2s}{t_2}$.

From this equation S can be calculated.

EXPT. 174. Determination of the Specific Heat of a Liquid by the Method of Cooling. II.—Fill the space between the inner chamber B




FIG. 181.—Specific Heat of a Liquid

and the outer chamber C with cold water, so that the inner chamber may form a constant temperature enclosure. No water is put into the inside of B as cooling from the two calorimeters A is to take place by radiation and convection in air. A vessel of hot water will be required for heating the two calorimeters. While this is being prepared weigh the empty calorimeters. Fill one calorimeter about two-thirds full with paraffin and the other with water. Support the calorimeters from the lid of the

enclosure by passing thermometers through rubber stoppers as in Fig. 181. Heat the calorimeters with the contained liquid to about 75°C. by immersing them in the vessel of hot water. Place the lid, with the calorimeters attached, on the enclosure, taking care that the calorimeters do not touch the metal vessel B. When the lid is in position, commence taking reading of the thermometers.

A convenient plan is to take the reading of the first thermometer when the seconds hand of a watch is at 60, and the reading of the second thermometer when the seconds hand is at 30. Readings should not be commenced unless the two thermometers indicate approximately the same temperature (between 60° and 70°C.). Continue the readings till the temperature falls below 30°C. in each case. The paraffin cools more rapidly, and therefore the paraffin will reach this temperature first. When this is the case, the readings of the paraffin thermometer can be discontinued, but the water thermometer must still be read. It is the time to cool through equal ranges of temperature which is required, not the temperature change in equal times.

At the end of these observations, remove and weigh the calorimeters to determine the mass of liquid in each. Plot two curves on a sheet of squared paper to show the cooling of the two calorimeters, taking temperatures as ordinates, times as abscissae. From the curves determine the number of seconds required in each case in cooling from θ_1 (about 60°C.) to θ_2 (about 30°C.). Calculate the specific heat of the liquid from the formula on p. 302.

Instead of paraffin oil, olive oil, glycerine, or strong salt solution may be used in the previous experiments.

THE COEFFICIENT OF THERMAL CONDUCTIVITY

§ 1. DEFINITIONS

WHEN the temperature at one point of a body is higher than the temperature at a neighbouring point, heat tends to flow from the first point to the second. If the temperature at the two points be T_1 and T_2 , and d be the distance between them, the quantity $(T_1 - T_2)/d$ is called the **temperature slope** or **temperature gradient**, G . This important magnitude G may be expressed in degrees per centimetre.




FIG. 182.—Slab with Parallel Faces

In the notation of the differential calculus the temperature gradient G may be written $\frac{dT}{dx}$, if x be taken to represent distance.

When a slab of any material, of thickness d , with parallel faces, has one face maintained at a temperature T_1 and the other face at a temperature T_2 , a steady flow of heat will eventually take place in straight lines perpendicular to the faces of the slab, and the temperature slope will be uniform and equal to $(T_1 - T_2)/d$.

The quantity of heat Q , flowing in time t through an area A measured on one face of the slab, will be proportional to the time, to the area, and to the temperature slope. It will also depend on the material of which the slab is composed. Hence we may write—

$$Q = KA \frac{T_1 - T_2}{d} \quad \text{or} \quad Q = KAGt,$$

where K is a quantity depending on the material of the slab. This equation may be regarded as defining the meaning of K , the **coefficient of thermal conductivity** of the material. Solving the equation for K we find

$$K = \frac{Q/t}{A \cdot (T_1 - T_2)/d}, \quad \text{or} \quad K = \frac{Q/t}{AG}.$$

The numerator Q/t measures the rate of flow of heat through the slab. This may be expressed in calories per second.

Hence the **coefficient of thermal conductivity** may be defined briefly

as the rate of flow of heat per unit area per unit temperature gradient. The coefficient will be expressed in calories per second, per square centimetre, per unit temperature gradient.

The measurement of a coefficient of thermal conductivity consequently involves the determination, after a steady state has been reached, of the three quantities : rate of flow of heat, area through which the heat flows, and temperature gradient.

In the notation of the differential calculus the equation may be written—

$$K = \frac{dQ/dt}{AdT/dx}.$$

§ 2. EXPERIMENTAL DETERMINATIONS

COEFFICIENT OF THERMAL CONDUCTIVITY OF A METAL BAR

The metal, of which the coefficient of thermal conductivity is to be found, is in the form of a cylindrical bar (Fig. 183). One end of the bar




FIG. 183.—Thermal Conductivity of Metal Bar

is heated by passing a current of steam through a steam chamber B, the other end is cooled by passing a current of water through a spiral tube encircling the bar at C. The temperature at two points, D and E, along the length of the bar is determined by thermometers T_1 and T_2 . The temperature in the water is determined at the point F, where it leaves the coil, by the thermometer T_3 , and at the point G, where it enters the coil, by the thermometer T_4 .

EXPT. 175. Determination of the Coefficient of Thermal Conductivity of a Metal Bar.—In carrying out the experiment a steady current of steam from a boiler must be passed through the steam chamber, and a steady current of water must be passed through the coil. The bar is

packed round with a bad conductor of heat, such as felt, and is left until a steady state is reached. This may take from twenty minutes to half an hour. The four thermometers are read from time to time in order to see whether the temperatures recorded are steady. The final temperatures recorded will depend on the rate at which water is flowing through the coil. To secure a reasonably large difference between the temperatures T_3 and T_4 it is best to have a rather slow stream; in fact little more than a trickle of water should issue from the coil. The quantity of water flowing through the coil per second must be determined by collecting the water that issues in a given time (two or three minutes), and either weighing it or measuring the volume in a graduated vessel. In this way is found the number of grams, m , of water passing through the coil in t seconds. The temperature of this mass of water has been raised from T_4 to T_3 , so that the water must have absorbed $m(T_3 - T_4)$ units of heat from the bar. Assuming that no heat has been lost from the sides of the bar, we may write for Q/t in the definition of the coefficient of thermal conductivity $m(T_3 - T_4)/t$.

The area of cross-section of the bar can be found by measuring the diameter with the vernier callipers, and taking $A = \pi r^2$ where r is the radius of the circular cross-section. The temperature slope can be found from the temperatures T_1 and T_2 , and the distance d between the two points D and E. Thus all the quantities necessary for the determination of K can be found.

COEFFICIENT OF THERMAL CONDUCTIVITY OF A BAD CONDUCTOR IN THE FORM OF A PLATE

In the case of a bad conductor of heat, the thickness of the slab of material to be examined must be small. The apparatus described below is similar in principle to that used in the researches of Professor C. H. Lees, but, for convenience in manipulation, his apparatus, which was suspended by strings in an enclosure, has been inverted.

The determination of K comprises two distinct parts: (I) finding the temperature gradient, G , through the plate; (II) finding Q/t the rate of flow of heat through the material. In the following description, Expt. 176, it is assumed that the temperature of the room remains approximately constant. It is advisable to record the temperature in the neighbourhood of the apparatus, by means of a separate thermometer, at the beginning and at the end of each part of the experiment. Find the *mean* temperature for each part. If these means are approximately equal, no difficulty arises. Even when the means are not the same, as may happen if there is some interval of time between Parts I and II, the observed results may be used to find the actual rate of cooling in Part I by applying Newton's law of cooling (pp. 297–298).

EXPT. 176. Determination of the Coefficient of Thermal Conductivity of a Bad Conductor such as Cardboard.—The material is in the form of a thin circular plate, of which the thickness and diameter must be measured.

PART I. TO FIND G . One face of the plate is heated by being placed in contact with a metal chamber B (Fig. 184), through which a current of steam is passed. The other face of the plate is in contact with a circular disk C of metal. All the metal surfaces are nickel-plated. Thermometers D and E are inserted in holes in the chamber B and the disk C.

The apparatus is left until a steady state is attained, and then the readings of the thermometers are recorded.

The temperature of the air in the room should also be observed.

It is assumed that the temperatures T_1 and T_2 indicated by the thermometers represent the temperatures of the two faces of the cardboard plate. The thickness of the cardboard being known, the temperature slope can then be calculated. The area through which the heat flows is taken to be the area of the face of the card, which can be calculated from the diameter of the circle.

PART II. TO DETERMINE

Q/t , the rate of flow of heat through the card. For this a separate experiment is necessary. When the steady state is reached in the first experiment the rate of flow of heat through the card must be exactly equal to the rate at which heat is lost from the surface of the disk C by convection and radiation. For when the temperature has become stationary there can be no accumulation of heat going on in the disk, and the heat gained by the disk must be equal to the heat lost. Consequently, if we can determine the rate at which heat is lost, we know the rate at which heat is flowing through the card.

The heating chamber B is removed, and the disk C, with the cardboard in contact with one face, is supported so that transference of heat by conduction is a minimum. This is sometimes done by suspending the disk by strings, but it may be more convenient to place the cardboard on a support, such as a block of wood, which is a bad conductor of heat.

The disk is then heated by the flame of a Bunsen burner till its temperature is 5 or 6 degrees higher than the steady temperature T_2 . It is then allowed to cool until its temperature has fallen from this temperature, T_3 , to a temperature T_4 , the same number of degrees below T_2 , and the time t taken in cooling is noted carefully.

The heat lost in cooling is $MS(T_3 - T_4)$, when M is the mass of the disk and S the specific heat of the metal. Consequently the rate at which heat is lost is $MS(T_3 - T_4)/t$. Assuming¹ that this is equal to Q/t in the formula for thermal conductivity, we have all the data necessary for the calculation of the latter quantity.




FIG. 184.—Thermal Conductivity of Cardboard

COEFFICIENT OF THERMAL CONDUCTIVITY OF A BAD CONDUCTOR IN THE FORM OF A TUBE

The Coefficient of Thermal Conductivity of a bad conductor of heat in the shape of a tube can be determined by passing a current of steam through the tube, or through a jacket surrounding the tube, and measuring the quantity of heat transmitted through the walls of the tube by the ordinary methods of calorimetry.

First Form of Apparatus.—Steam is passed *through* the tube. The tube may be immersed in a known mass of water in a calorimeter and the rise of temperature of the water in a certain time may be observed.

¹ This assumption is not strictly accurate, for when the heater is removed some heat is lost from the disk by conduction through the cardboard. It would be more correct to determine the rate of loss of heat from the disk when the heater is in position, but at the same temperature as the disk, so that there is no slope of temperature in the cardboard. It is not difficult to realise this condition in practice, at least in an approximate fashion.

EXPT. 177. Determination of the Coefficient of Thermal Conductivity of a Poor Conductor in the Form of a Tube.—In the case of a rubber tube select a calorimeter of fairly large capacity (500 or 600 c.c.) so as to allow a considerable length of the tubing to be coiled up inside it. Weigh the inner vessel of the calorimeter and fill it about two-thirds full of water. Weigh the vessel thus filled in order to find the weight of the water. Take the temperature, T_2 , of the water, which may conveniently be below that of the room to start with. Coil up the rubber tube in the water, allowing both ends to project some distance out of the calorimeter.

The rubber tube must then be connected to the nozzle of a steam generator, so that a steady current of steam can be passed through it. The other end may dip into a tin can to catch any drippings from the condensed steam.

Allow the steam to pass through the tube for an observed time, until the temperature of the water has risen 15° or 20° C. Note the time during which the steam has passed, and also the final temperature, T_3 , of the water.

The length of tube immersed in the water must be measured, and for this purpose it is convenient to have two marks made on the tube at the points where it enters and leaves the water in the calorimeter. Let the length immersed be l cm. Measure also the internal and the external radius of the tube. Let these be r_1 and r_2 cm. respectively. Then the thickness of the wall of the tube is $r_2 - r_1$ cm. If we imagine the tube slit open by a cut parallel to its axis (Fig. 185), it will approximately correspond to a slab of material of thickness $r_2 - r_1$.

The area through which the heat flows may be taken approximately as the *mean* of the areas of the two faces of the slab, that is

$$A = \frac{1}{2}(2\pi r_1 l + 2\pi r_2 l) = 2\pi \bar{r} l,$$

where $\bar{r} = \frac{1}{2}(r_1 + r_2)$ is the *mean* radius of the tube.

The temperature on the outside of the tube is not constant, but we take the mean of the initial and final temperatures in calculating the temperature gradient. The temperature of the inside of the tube may be taken as $T_1 = 100^\circ$ C. Thus the temperature gradient is

$$\frac{T_1 - \bar{T}}{r_2 - r_1},$$

where $\bar{T} = \frac{1}{2}(T_2 + T_3)$ is the *mean* temperature outside the tube.

The only other quantity required is the quantity of heat flowing through the wall of the tube in time t . As the heat goes to raise the temperature of the calorimeter and its contents from T_2 to T_3 it can be calculated easily. Thus all the quantities required for the determination of the coefficient of thermal conductivity can be obtained, and the coefficient can be calculated from the equation¹ deduced from the definition on p. 304.

$$K = \frac{Q/t}{2\pi \bar{r} l \left(\frac{T_1 - \bar{T}}{r_2 - r_1} \right)};$$

¹ A more accurate formula, obtained by considering the flow of heat through the wall of a hollow cylinder, gives

$$K = \frac{Q/t}{2\pi l \left(T_1 - \frac{1}{2}(T_2 + T_3) \right) \log_e r_2/r_1}$$

When the tube is thin, so that $r_2 - r_1$ is small compared with r_1 or r_2 , this reduces to the form above.

Second Form of Apparatus.—If the tube is not flexible, as in the case of a glass tube, its thermal conductivity may be determined in the following manner:—A slow stream of water is passed through the tube, the stream being maintained steady by use of a Mariotte's Bottle. The tube is inclined slightly so that it is always full of water while the experiment is in progress; it is enclosed in a steam jacket through which steam is passing (Fig. 186).

EXPT. 178. Determination of the Coefficient of Thermal Conductivity of a Poor Conductor in the Form of a Tube.—As the water enters the tube its *inflow* temperature T_1 is taken. As the water flows through the tube, it receives heat by conduction through the tube walls, its temperature rising to T_2 , by the time it has flowed through the jacketed part of the tube. This *outflow* temperature is taken, and the emerging water is collected in a measuring cylinder. The mass of water flowing through the tube in a certain time is noted; this interval of time should be such




FIG. 186.—Thermal Conductivity of Glass Tube

that at least 300 c.c. of water are collected in a measuring glass, the mass being calculated on the assumption that the density is unity. If the mass of water flowing through the tube in t seconds be M gm., the quantity of heat Q conducted through the walls of the tube in this time is $M(T_2 - T_1)$ calories.

The length of the tube between the ends of the steam jacket is measured, and also the internal and external radii of the tube. Let these be l , r_1 , and r_2 respectively.

Then the average area through which the heat flows is $2\pi\bar{r}l$, where $\bar{r} = (r_1 + r_2)/2$.

The average temperature slope through the tube is

$$\frac{100 - \bar{T}}{r_2 - r_1}, \text{ where } \bar{T} = \frac{T_1 + T_2}{2}.$$

Hence¹

$$M(T_2 - T_1) = K 2\pi\bar{r}l \left[\frac{100 - \bar{T}}{r_2 - r_1} \right] t.$$

All these quantities can be measured or observed except K , hence K can be calculated.

¹ If the more accurate equation is used

$$M(T_2 - T_1) = \frac{K 2\pi l (100 - \bar{T}) t}{\log_e r_2 / r_1}$$

THE MECHANICAL EQUIVALENT OF HEAT

§ 1. DEFINITION AND DETERMINATION OF THE MECHANICAL EQUIVALENT OF HEAT

It was proved by Dr. J. P. Joule (1818–1889) that when heat was produced by the expenditure of mechanical energy, for every unit of heat produced a definite number of units of work had to be done. There is a *constant* transformation ratio between W the work expended and H the heat produced. This ratio W/H or J is called the **mechanical equivalent of heat**. Thus, in order to produce one calorie (gram-degree centigrade), 4.2×10^7 ergs or 4.2 joules of work are required. In C.G.S. units, using the centigrade scale of temperature, the mechanical equivalent of heat is 4.2×10^7 ergs per calorie, or, more exactly, 4.185×10^7 ergs per 15° calorie.

EXPT. 179. Determination of the Mechanical Equivalent of Heat by the Fall of Mercury in a Tube.—A wide glass tube about a metre in length and 3 to 4 cm. in diameter is sealed at one end and provided at the other with a well-fitting rubber cork through which passes a sensitive thermometer. About 50 c.c. of mercury is introduced into the tube and the cork is fixed securely in position. The tube is grasped firmly at its centre and held vertically so that the lower end rests level with a table. The tube is then inverted quickly so that the upper end now occupies the position formerly occupied by the lower end. This means that the tube must be rotated about a horizontal axis through the middle of its length. During the rotation the mercury remains at the end of the tube, but when the tube becomes vertical the mercury falls from one end of the tube to the other.

The work done in lifting the mercury is converted into kinetic energy during the fall, and this is converted into heat when the mercury comes to rest at the bottom of the tube. In order to secure an appreciable rise of temperature, the operation must be repeated about 50 times.

Let m = mass of mercury in the tube,
 s = specific heat of mercury,
 t_1 = final temperature,
 t_2 = initial temperature.

Then assuming that no heat is lost, the total amount of heat produced $H = ms(t_1 - t_2)$.

Let h = the vertical distance through which the centre of gravity of the mercury falls when the tube is inverted (note that this is *not* the length of the glass tube), n = the number of times the operation is carried out.

Then the mechanical energy E which disappears = $nmg h$.

$$\text{So we have } J = \frac{E}{H} = \frac{nmg h}{ms(t_1 - t_2)} = \frac{ng h}{s(t_1 - t_2)}.$$

From this result Joule's equivalent can be calculated.

Note that the value of J is independent of the mass of mercury used. In an actual experiment a very small quantity of mercury must not be used, otherwise the heat used in warming the tube would be appreciable in comparison with that used in warming the mercury. A less accurate method, attended with less risk of breaking the thermometer, is to use a solid cork, and to take the temperature of the mercury in a small beaker before and after the operations.

PRODUCTION OF HEAT BY FRICTION BETWEEN METAL CONES

The following method of determining the mechanical equivalent of heat by the friction between two metal cones is an adaptation of one employed by Joule.

Two metal cones, D and E (Fig. 187), are provided which fit closely




FIG. 187.—Mechanical Equivalent of Heat

one within the other. The outer cone is forced to rotate by attaching it to a vertical spindle driven by a flywheel turned by hand. The inner cone is prevented from rotating. Consequently friction takes place between the surfaces in contact, and the heat produced goes to heat the cones and any liquid (usually water, sometimes mercury) that may be placed in the inner cone.

The amount of heat produced is determined from a knowledge of the total water equivalent and the rise of temperature.

The amount of mechanical work expended can be estimated by applying a measurable torque to the inner cone in order to prevent it from rotating, and by counting the number of revolutions made by the outer cone. A circular wooden disk (A in Fig. 187) rests upon the inner cone, to which it is attached by two steady-pins. A leaden weight B is placed on the top of it to hold it in position. A string attached to the circumference of the disk passes over a pulley and is kept stretched with tension T dynes by a

known load M (100 to 200 gm.) fastened to its other end. When the outer cone is rotated the inner cone tends to move with it, but it is prevented by the moment of the force due to the tension T in the string.

The string must always be tangential to the circumference of the wooden disk when the apparatus is in use.

Let R be the radius of the disk, and r the mean radius of the surface of contact of the cones. Then if F represent a mean value of the friction between the cones,

$$\begin{aligned} Fr &= TR \\ &= MgR, \end{aligned}$$

where M is the mass of the suspended load.

The work done in *one* revolution of the outer cone, when the inner cone is at rest, is $F2\pi r$. Consequently W the work done in n revolutions $= 2\pi nFr$.

Although the values of F and r separately cannot be determined accurately, the value of Fr can be found from the equation above. Substituting this value we find for the work done in n revolutions

$$W = 2\pi nMgR.$$

Consequently the mechanical work can be calculated in ergs.

EXPT. 180. Determination of the Mechanical Equivalent of Heat by the Friction between two Metal Cones.—In carrying out the experiment, it is essential that the friction between the cones should be suitable in amount. Otherwise it will be impossible to keep the load at a fixed level. A single drop of lubricating oil is usually sufficient to place between the inner and the outer cone. If the cones are not lubricated the surfaces in contact will 'seize'.

The adjustment of the amount of lubricant should be made before beginning the actual experiment, the apparatus being tested by turning the driving wheel so as to see whether the load can be maintained approximately at a fixed level, whilst turning at a fair speed.

Weigh the two cones together when empty, and also when the inner cone is about two-thirds full of water. Then replace the cones in the apparatus and introduce a sensitive thermometer to determine the temperature. If care be taken, the thermometer itself may be used as a stirrer. Sometimes the thermometer is held in a stand and a separate stirrer is employed.

It is important to allow for any loss or gain of heat due to radiation. In order to do this, readings of the temperature should be taken at intervals of 1 minute for 5 minutes before the actual experiment commences. Then the flywheel should be set in rotation and the required number of revolutions made. The number is indicated by the counting mechanism C geared to the rotating spindle. To obtain a rise of temperature that can be measured with reasonable accuracy a large number of revolutions must be made: 500 or 1000 revolutions may be necessary. The time this takes must be noted. When this operation is completed, the temperature must be read, and readings of the thermometer taken again at intervals of 1 minute for 5 minutes. From the readings before and after the *mean rate of change of temperature* can be found, and knowing the time the experiment lasted, the actual change during this period can be calculated. This change must be taken into account in estimating the rise of temperature produced by the friction between the cones.

Calculate the number of calories of heat produced, from the water equivalent and the rise of temperature. Measure the diameter of the wooden disk with a large pair of callipers, and calculate the work done from the expression $W = 2\pi nMgR$. The mechanical equivalent should be expressed both in ergs per calorie and also in joules per calorie.

CALENDAR'S APPARATUS FOR THE MECHANICAL EQUIVALENT OF HEAT

In this form of apparatus (Fig. 188), the water is contained in a hollow drum which is rotated by an electro-motor or by hand. Over the drum passes a brake-band of silk,¹ consisting of three ribbons. The two outer ribbons are wound once round the drum and at one end carry a mass A (Fig. 189), of several (3 to 5) kgm. The other




FIG. 188.—Callendar's Apparatus
(Cambridge Scientific Instrument Co.)




FIG. 189.—Dynamometer
used in Callendar's Ap-
paratus

ends of these ribbons are fastened to an ivory or vulcanite bar, to which the middle ribbon is also attached. This ribbon also passes over the drum, lying between the other ribbons and in continuation of them. It carries a yoke S at its other end, and from this yoke is suspended a small mass B, about 200 to 400 gm. From the lower end of the yoke passes a spring-balance which hangs from the frame of the apparatus at C; this spring acts upwards on the mass B and supports B to some extent during the experiment: its action is to steady the working of the apparatus.

Suppose the drum to be rotating in the direction of the arrow: A is raised by the friction of the band, and B is depressed. The difference in tension between the ends of the band is equal to the force of

¹ The silk belt must be kept clean and dry, and be put away in a paper wrapper when the apparatus is not in use. In later models the belt is of velvet.

friction between the band and the drum. Now the force of friction round a drum or fixed pulley depends on the tension T_0 at the free end (see p. 74); if the weight of B were adjusted carefully, it would be possible for B to keep A balanced exactly when the drum was rotating at a certain speed. If, however, B were not adjusted exactly to this value, the band would move slowly either in the same direction as the drum or against the motion of the drum, according as B were greater or less than this special value. The slightest alteration of the coefficient of friction, due to rise of temperature, alteration of speed,¹ or any other cause, would require a readjustment of B, or if the angle of contact between the brake-band and the drum were altered through slight oscillation of either end, the band would begin to move in one direction or the other.

The adjustment of B would be troublesome if the spring-balance were not used, and readjustment would be necessary at frequent intervals in the experiment. The spring avoids all this troublesome adjustment in the following way: If at any moment the force of friction is too large, B begins to move downwards, its weight is thus thrown on the spring to some extent, and the cord, being released from this part of the weight of B, exerts a smaller frictional force on the drum and the downward motion of B is arrested. Diminution in the force of friction causes B to rise; its weight is then taken by the cord more completely and the friction increases accordingly, the motion of the cord being again stopped. The arrangement of a brake-band round a drum is called a **Dynamometer**.

The force of friction is equal to $T - T_0$, where T is the weight of A, and T_0 is the difference between the weight of B and the force exerted by the spring: all these forces are measured in dynes.

The **work done** is equal to the product of the frictional couple exerted on the drum, and the angle in radians through which the drum revolves: thus in n revolutions the work done is $2\pi n(T - T_0) R$, where R is the radius of the drum. W is measured in ergs.

The number of revolutions is determined by means of a revolution counter mounted on the axle of the drum.

The **heat generated** in any given number of revolutions is determined by the rise of temperature of the water, multiplied by the thermal equivalent of the drum and contents. To avoid loss of heat from the drum by conduction, and also to give a definite value to the thermal equivalent of the drum, it is mounted at six points on its circumference on ivory or vulcanite studs, by means of which it is attached to the driving disk and spindle. The drum has a hole in the centre of its end plate, into which the thermometer is inserted and through which the

¹ The force of friction between solid surfaces is nearly, but not quite, independent of their relative velocity.

water is introduced. The drum is half-filled with water before the experiment, the mass of water used, w gm., being determined before introducing it into the drum. As the drum revolves, the water gradually acquires a motion of rotation and rotates with the drum, being prevented from escaping from the drum by centripetal force, which keeps it in contact with the rim.

The thermometer is of a special design, being bent so that its bulb lies near the rim of the drum and inside the drum, while the graduated stem projects from the hole at the centre, and is clamped as shown in Fig. 188. The water swirls past the bulb, and its temperature is registered on the thermometer, the rotary motion ensuring thorough mixing and consequent uniformity of temperature throughout the liquid. The thermometer, being fixed, enables temperatures to be taken at any instant during the experiment, and it is possible therefore to plot a temperature-time curve if desired, and to correct the final temperature for radiation losses by means of this curve (p. 291). The water equivalent of the drum can be determined from its mass m and its specific heat s .

From the work done and the heat generated, the mechanical equivalent of heat J is determined by the equation

$$W = JH.$$

W is the work done and is given by $2\pi n (T - T_0) R$.

H is the heat generated and is equal to $(w + ms) (\theta_2 - \theta_1)$, θ_1 being the initial and θ_2 the final temperature of the water in the drum.

EXPT. 181. Determination of the Mechanical Equivalent of Heat by Callendar's Apparatus.—The apparatus is set up to be driven either by hand or by motor. Polish the drum *very carefully* by applying a liquid metal polish on a soft rag to the revolving surface. Adjust the brake-bands over the drum as shown diagrammatically in Fig. 189, placing a five-kilogram weight on the end A and a mass of 400 gm. on B, the spring-balance being fixed to the frame of the apparatus at C.

Measure an amount of water sufficient to fill the drum nearly up to the hole at the centre — between 300 and 500 c.c. will be required ; let the mass of this be w gm. Introduce the water into the drum.

Place the thermometer bulb in the interior of the drum, clamping the thermometer in the clamp provided on the apparatus so that the stem projects along the axis of the drum. Care must be used in inserting the bulb, as the thermometer is fractured easily at the bends.

Start the motor and adjust its speed or the masses of A or B until the band is stationary when the drum rotates. Care must be taken that the yoke is not touching the frame of the instrument, and that the index of the spring-balance is well away from both ends of the scale. When these adjustments have been made the motor is stopped and the water allowed to come to rest. Take readings of the water temperature θ_1 , and of the revolution counter.

To carry out the experiment proper, start the motor and read the temperature of the water every fifty or one hundred revolutions of the drum. Read the tension of the spring-balance between every pair of temperature readings so as to get the mean force exerted by the spring

during that part of the rise of temperature. Note also the time occupied by the experiment.

After 1000 revolutions (or some other convenient number) stop the motor and take the temperature θ_2 when the water has come to rest. The apparatus is then left for the same length of time as that taken for the experiment, and the fall of temperature during this period is noted; let this be $\delta\theta$.

The mean excess of temperature over the surroundings during the experiment is half the final excess, and therefore the mean rate of loss of




FIG. 190.—Callendar's Apparatus driven by Motor
(Cambridge Scientific Instrument Co.)

heat during the experiment would be half the rate at the end of the experiment. The correction for radiation during the experiment is therefore made by adding $\delta\theta/2$ to the observed rise of temperature, and we have

$$H = (w + ms) \left(\theta_2 - \theta_1 + \frac{\delta\theta}{2} \right),$$

where H is the Heat generated during the experiment.

In this expression m is the mass of the drum in grams, and s the specific heat of the material of the drum (usually brass): m is usually stamped on the end of the drum by the maker.

To calculate the work done it is necessary to measure the radius of the drum; let this be R cm. Then the force of friction is given by the difference in tension between the ends of the cord. Let the mean reading of the spring-balance be C gm., then the tension T_0 at the end of the band carrying the weight B is $(B - C)$ gm. weight.

At the other end the tension T is equal to A gm. weight, and the friction force is given by

$$F = (T - T_0) \text{ dynes} = \{A - (B - C)\}g \text{ dynes.}$$

This force is exerted round the periphery of the drum, and the couple due to friction is

$$FR \text{ dyne-cm.,}$$

the work done in n revolutions being equal to

$$W = 2\pi n FR \text{ ergs.}$$

Calculate the heat generated H gram calories and W ergs the work done in the number of revolutions taken, and calculate the mechanical equivalent of heat J from the equation

$$W = JH.$$

The value of J should also be given in joules per gram calorie.

NOTE.—The satisfactory use of Callendar's apparatus depends very largely on obtaining a good polish on the surface of the drum. This may require considerable time and care, particularly when the apparatus has not been in use for a long period.

In later models some modifications have been made in the design of Callendar's apparatus and the brake-band is now made of velvet instead of silk.

Experiments on the heating effect of an electric current are described on pp. 440-443.

NOTE ON THE MECHANICAL EQUIVALENT OF HEAT

The principle of **equivalence** established by J. P. Joule may be stated by saying that when exchange occurs between work and heat, the **ratio of the exchange** is fixed. Joule's **equivalent** states this constant transformation ratio as the quantity of mechanical work equivalent to one thermal unit. The numerical value of J depends on the units chosen for measuring work and heat. Provided the unit of mass selected is the same for work as for heat, the value of J does not depend on the mass unit, but it does depend on the temperature scale chosen.

CHAPTER VII

HYGROMETRY

§ 1. DEFINITIONS

THE Hygrometric State or Relative Humidity of the air can be defined as the percentage or fractional saturation of the air. At any temperature t a certain maximum amount of aqueous vapour can exist in the air; this corresponds with the Saturation Vapour Pressure, F , of water vapour at that temperature.

The actual quantity of vapour present is rarely equal to this maximum, the aqueous vapour actually present corresponding with a saturation pressure f which is usually considerably less than F . The mass of aqueous vapour present is proportional to f , and consequently the fractional saturation can be expressed as f/F or as a percentage by $f/F \times 100$.

The aqueous vapour present in the air would be sufficient to saturate the air at a certain temperature t_1 . If the air is cooled down *locally* to this temperature t_1 , dew will be deposited on any flat surface exposed to this cooled air: the temperature t_1 is called the dew point.

To a very close degree of approximation, the saturation vapour pressure (S.V.P.) at the dew point may be taken as equal to the pressure of the vapour actually present in the air. Thus if we can determine the dew point, we can obtain the hygrometric state of the air, for the saturation vapour pressure of water vapour at any temperature can be obtained from tables (Appendix, p. 563), and the

$$\text{Hygrometric state} = \frac{f}{F} = \frac{\text{S.V.P. at the dew point}}{\text{S.V.P. at the air temperature}}.$$

§ 2. METHODS OF DETERMINING THE DEW POINT. HYGROMETERS

The method of cooling the air locally is to cool down a bright metallic surface. When dew is deposited on this, its bright surface assumes a dull appearance, and with practice a very slight trace of dew can be detected. If the temperature of the surface is then taken, this temperature will be the dew point. Any apparatus designed for measuring the relative humidity of air or gas is called a **Hygrometer**, the Dew Point Hygrometer being a particular form.

DANIELL'S HYGROMETER

Daniell's Hygrometer is shown in Fig. 191. In this form the metallic surface is a gold band fused round the lower glass bulb A. Inside this bulb is a thermometer the stem of which passes up the tube connecting this bulb with the second bulb B on the other side of the stand. The two bulbs and the connecting tube contain ether and ether vapour only.

By pouring ether on the cloth surrounding the upper bulb, and causing it to evaporate rapidly, this bulb is cooled. The ether vapour inside the bulb B is condensed, and its place is taken by more vapour which passes over from the other bulb A. Condensation is continued in the upper bulb, and vapour passes over from A to B to replace the condensed vapour, so that continuous evaporation goes on in the lower bulb so long as the upper is being cooled.

The evaporation inside the lower bulb causes a steady fall of temperature in it, and the gold band finally cools to the dew point. When the first trace of dew is noticed, the temperature of the thermometer inside the apparatus is taken and also the temperature of the air of the room. Usually a second thermometer is mounted on the stand of the instrument for this latter purpose.




FIG. 191.—Daniell's Hygrometer

The first of these temperatures is taken as the dew point, and the hygrometric state is calculated from these observations.

The apparatus is not a good one. The thermometer inside the apparatus is separated from the gold band by a mass of liquid at least 1 cm. thick, and then by a layer of glass of from 1 to 2 mm. thickness. The liquid is practically *still*, and there may be considerable variations of temperature in the liquid itself; the glass too is a bad conductor of heat, and consequently the temperature of the thermometer may be from 1°C. to 2°C. below the temperature of the gold band, the value obtained for the dew point being wrong to the same extent.

There are other objections to this form of instrument; the air all round it is charged with ether vapour and also the rate of cooling cannot be regulated, being determined by the rate of evaporation of the ether on the cloth.

EXPT. 182. Determination of the Dew Point by means of Daniell's Hygrometer.—Read the temperature of the air in the room as given by the thermometer mounted on the stand of the instrument. Pour some ether on the muslin surrounding the upper bulb, and watch the gold band for the first trace of a deposit of dew. If the surface is touched from time to time with the end of a long paper spill or a feather, the presence of dew may be detected more easily. Immediately the deposit is noticed read the temperature of the thermometer inside the apparatus.

Find from the table (p. 563) the saturation vapour pressure corresponding with these two temperatures, and calculate the relative humidity.

REGNAULT'S HYGROMETER

The form of hygrometer designed by Regnault, when constructed and used properly, avoids the disadvantages of Daniell's Hygrometer. An *open* glass tube A is fitted at its lower end with a silver cap B (Fig. 192). In this is placed sufficient ether to fill the silvered cap, and a thermometer

dips into the ether. Tubes CD and EF are fitted as shown, and the latter is attached by the side tube G to an aspirator. When the aspirator is in action, a current of air passes in the direction of the arrows and bubbles through the ether in the lower part of AB. The air becomes charged with ether vapour as it bubbles through, and the rapid evaporation lowers the temperature of the liquid. This is in immediate contact with the

silver cap and with the thermometer, and is well stirred by the bubbling air, consequently the thermometer, the liquid, and the silver cap will all be at the same temperature.

Dew forms on the silver cap as soon as the temperature of the dew point is reached, and the dew point can therefore be determined very accurately by taking the temperature of the thermometer when dew is first observed on the cap.




FIG. 192.—Regnault's Hygrometer

EXPT. 183. Determination of the Dew Point by means of Regnault's Hygrometer.

—Connect the short glass tube to the aspirator, which should be at least 2 metres from the hygrometer. The dew point should first be determined approximately by using a rapid current of air. This causes rapid cooling, and the dew will not be noticed until the temperature is slightly below the true dew point. If now the current of air is stopped, the whole apparatus will warm up *slowly* and the dew will disappear. The temperature at which the dew disappears should be noted; this will be much nearer the true dew point than the value previously taken, but will be somewhat too high.

The aspirator is now set working again so as to aspirate a very slow current of air through the apparatus. By this means the temperature will be lowered again but very slowly, and the appearance of dew will be noticed very soon after the dew point is reached; a more accurate value of the dew point will thus be obtained.

By alternately cooling the bulb and allowing it to warm up again in the manner described, temperatures will finally be obtained for the appearance and disappearance, which will not differ by more than 0.2 of a degree. When this is the case the mean of these may be taken as the dew point. The thermometer in the tube K gives the temperature of the room.

Find from the table (p. 563) the saturation vapour pressure corresponding with the dew point, and also with the temperature of the room, and deduce the relative humidity.

NOTE.—In order to detect the smallest trace of dew it is convenient to use a long dry quill, or a spill of paper formed by rolling up a half sheet of note-paper. This should be held at one end, and the silver cap gently stroked at one point with the other end of the paper or quill. Any deposition of dew can be detected in this way, as the moistened surface of the silver shows a higher polish where the paper has been stroked along it. The hand must not approach within 20 cm. of the silver cap, and the apparatus should be watched through a large pane of glass; the experiment should not be carried out near any place where a large surface of water is exposed.

Some instrument makers supply a complete glass test-tube with a silver cap slipped on the end as a Regnault's Hygrometer. The use of such an apparatus reintroduces one of the main errors which Regnault's apparatus was designed to avoid, by placing a badly conducting medium between the silver cap and the thermometer.

The end of the test-tube must be cut off with a file and the silver cap cemented to the tube so as to have the tube closed with a silver cap in immediate contact with the ether.

WET AND DRY BULB HYGROMETER

Two thermometers are arranged on a stand; one is exposed to the air, and the bulb of the other is wrapped round with a cloth that is kept moist by dipping at its lower end into a small vessel of water (Fig. 193). The drier the air, the more rapidly will evaporation take place from the wet bulb and the lower will be its temperature. By reading the two temperatures an estimate may be made of the hygrometric state, tables for the reduction of the readings having been found by trial, using a Regnault's hygrometer for comparison. Such a table is given below and is explained on p. 322.

TABLE FOR WET AND DRY BULB HYGROMETER

The first vertical column gives the temperature of the dry bulb thermometer. The first horizontal line gives the difference between the two thermometers. The remaining figures give the actual vapour pressure in mm. at the time of observation. When the air is saturated the difference between the thermometers is zero, and the second vertical column gives the saturated vapour pressure.




FIG. 193.—Wet and Dry Bulb Thermometers

° C.	0	1	2	3	4	5	6	7	8	9	10
0	4.6	3.7	2.9	2.1	1.3						
1	4.9	4.0	3.2	2.4	1.6	0.8					
2	5.3	4.4	3.4	2.7	1.9	1.0					
3	5.7	4.7	3.7	2.8	2.2	1.3					
4	6.1	5.1	4.1	3.2	2.4	1.6	0.8				
5	6.5	5.5	4.5	3.5	2.6	1.8	1.0				
6	7.0	5.9	4.9	3.9	2.9	2.0	1.1				
7	7.5	6.4	5.3	4.3	3.3	2.3	1.4	0.4			
8	8.0	6.9	5.8	4.7	3.7	2.7	1.7	0.8			
9	8.6	7.4	6.3	5.2	4.1	3.1	2.1	1.1	0.2		
10	9.2	8.0	6.8	5.7	4.6	3.5	2.5	1.5	0.5		
11	9.8	8.6	7.4	6.2	5.1	4.0	2.9	1.9	0.9		
12	10.5	9.2	8.0	6.8	5.6	4.5	3.4	2.3	1.3		
13	11.2	9.8	8.6	7.3	6.2	5.0	3.9	2.8	1.7		
14	12.0	10.6	9.2	8.0	6.7	5.6	4.4	3.3	2.2	1.1	
15	12.8	11.3	9.9	8.6	7.4	6.1	5.0	3.8	2.7	1.6	0.5
16	13.6	12.1	10.7	9.3	8.0	6.8	5.5	4.3	3.2	2.1	1.0
17	14.5	13.0	11.5	10.1	8.7	7.4	6.2	4.9	3.7	2.6	1.5
18	15.5	13.8	12.3	10.9	9.5	8.1	6.8	5.5	4.3	3.1	2.0
19	16.5	14.7	13.2	11.7	10.3	8.9	7.5	6.2	4.9	3.7	2.5
20	17.5	15.7	14.1	12.6	11.1	9.7	8.3	6.9	5.6	4.3	3.1

The instrument, though used extensively by meteorologists and in industry, is not very accurate and does not give a direct estimate.

As an alternative the thermometers are fixed to a rod and whirled round, or air is drawn past them by using an electric motor. These instruments (psychrometers) give more reliable results than the stationary form.

In making a determination the sling psychrometer should be whirled rapidly in the air for about half a minute, stopped and quickly read—the wet bulb first. With an instrument of ordinary size the revolutions should be not less than 120 per minute, corresponding to an air speed past the wet bulb of about 15 feet per second.

Reference may be made to the *Meteorological Observers' Handbook*.

CALCULATION OF THE MASS OF AQUEOUS VAPOUR PER LITRE OF THE ATMOSPHERE

The gas laws connecting the pressure, volume and temperature of a gas such as oxygen or hydrogen have been given on p. 285. The experiments of Regnault showed that these laws may be applied over a fairly wide range to unsaturated water vapour. He found that the density of water vapour compared with that of *dry* air at N.T.P. was approximately 0.62 or about 5/8. It is worth noting that the mass of any volume of aqueous vapour is nearly *five-eighths* that of the same volume of dry air at the same temperature and pressure.

It is sometimes more convenient to make a comparison between water vapour and pure hydrogen.

A litre of hydrogen at 0° C. and pressure 760 mm. Hg. weighs 0.09 gm. At a pressure f mm. Hg. and a temperature t_1 ° C., its mass would be

$$0.09 \times \frac{f}{760} \times \frac{273}{273+t_1} \text{ gm.}$$

Now we have aqueous vapour at a pressure f mm. Hg. when measured at a temperature t_1 ° C. (the dew point). Aqueous vapour (H_2O) is nine times as dense as hydrogen (H_2) under similar conditions. Hence the mass of aqueous vapour present per litre is

$$0.81 \times \frac{f}{760} \times \frac{273}{273+t_1} \text{ gm.}$$

It is contended sometimes that the aqueous vapour is present at a pressure f mm. at the temperature of the air, in which case t_1 in the above expression should be replaced by t the air temperature. Either method may be adopted for the calculation, the percentage error, if any, due to using either expression being much less than the percentage error of experiment in determining f .

The mass of aqueous vapour per litre can be determined also by chemical means, by aspirating a known volume of air through weighed drying tubes and finding the mass of aqueous vapour absorbed by these.

PART IV

ADDITIONAL EXERCISES IN HEAT

1. Determine the fixed points of the thermometer provided, and use it to find the melting point of the given solid.

2. Determine the temperature of the room by means of an ungraduated thermometer, ice and steam.

3. Standardise the given thermometer and use it to find at what temperature the given substance coagulates when heated.

4. Find the mean coefficient of expansion of the given liquid between 20°C . and 30°C ., and also between 30°C . and 40°C .

5. Find the boiling point of a liquid, and determine the change in the boiling point produced by adding 10 per cent by weight of a solid.

6. Find the density of water at 20°C ., 40°C ., and 60°C ., being given the coefficient of cubical expansion of glass.

7. Find the density of the given liquid at 20°C ., 40°C ., and 60°C . by means of a hydrostatic balance. Determine whether the coefficient of expansion between 20°C . and 40°C . is the same as that between 40°C . and 60°C .

8. Find the coefficient of apparent expansion of the given liquid, using a bulb of known volume to which is attached a tube of known diameter.

9. Find the temperature coefficient of increase of pressure of air at constant volume between the melting point and the boiling point of water.

10. Plot a graph showing how the pressure of the given volume of air varies with the temperature as indicated by a mercury thermometer.

11. Find the water equivalent of the given calorimeter.

12. Find the thermal capacity of the given mass of metal.

13. Find what would be the water equivalent of a calorimeter, weighing 150 grams, made of the given metal.

14. Find the specific heat of a liquid, being given that of a solid which has no chemical action upon it.

15. Find the specific heat of paraffin oil by adding ice.

16. Find the specific heat of the given liquid by condensing steam in it. Latent heat of steam = 540 calories per gram. Neglect heat of dilution.

17. Having been given a known weight of water in a calorimeter of known weight, condense steam in it, and find from thermometric observations the weight of steam condensed, assuming the latent heat of steam to be 539 calories per gram.

18. Heat the given vessel of water over a Bunsen burner and find the time taken for the temperature to rise from 40°C . to 80°C . Now boil the water for a measured time, and deduce an approximate value for the latent heat of steam.

19. Compare the rates of cooling at a given temperature of the blackened and silvered test-tubes when filled with warm water.

20. Plot a cooling curve for a calorimeter containing a known amount of water. Calculate the number of calories lost per second when the temperature of the calorimeter is 20° above that of its surroundings.

21. Find the mass of aqueous vapour in 1 litre of air in the room.

22. Determine the dew point by two different methods.

23. Being given the coefficient of thermal conductivity of the metal bar, determine the temperature at the marked point without using a thermometer at that point.

24. Determine the coefficient of thermal conductivity of a sheet of ebonite.

25. Compare the coefficients of thermal conductivity of ebonite and cardboard.

26. Find the coefficient of thermal conductivity of porcelain in the form of a tube.

PART V

MAGNETISM

NOTES ON MAGNETISM

An ideal or simple magnet would have only two magnetic poles of opposite polarity (N and S) situated at mathematical points. An ordinary bar magnet possesses certain polar *regions* which do not satisfy this condition, but an approach to the ideal may be realised by means of Robison's ball-ended magnets, carefully constructed and properly magnetised.

Magnetite or lodestone is an oxide of iron (Fe_3O_4) which is strongly magnetic, while other oxides of iron are only feebly magnetic. Soft iron may be magnetised temporarily by placing it in a magnetic field, but hard iron and steel become permanently magnetised by the field. Bars of nickel, cobalt and Heusler alloy (composed of copper, aluminium and manganese) are ferromagnetic, like iron. Vibration or shock may demagnetise hard iron, but make it easier for soft iron to become magnetic. Loss of magnetic properties occurs when a magnet is heated to a certain critical temperature. By combining steel with other elements, such as cobalt and chromium, great improvements have been made in the construction of strong magnets, and these are very convenient for many magnetic experiments.

Special attention is directed to the NOTES ON THE CARE OF MAGNETS on p. 336.

The best way of remagnetising a bar magnet is by placing it along the axis of a solenoid (p. 373) of thick insulated wire, through which a strong electric current (several amperes) can be passed for a few seconds. It is necessary that the length of the solenoid should be much greater than the length of the magnet. This is specially important in remagnetising ball-ended magnets.

It is now generally accepted that magnetic poles have never been separated from one another so as to exist independently, and a bar magnet may be looked upon as an assembly of an immense number of small magnets. Ewing constructed models in support of this view, and these are still of service in illustrating modern theories which attribute magnetism to the spin or orbital motion of certain elementary particles, notably electrons, which constitute matter.

FUNDAMENTAL PROPERTIES AND LAWS

§ 1. FUNDAMENTAL PROPERTIES AND DEFINITIONS

MAGNETS are characterised by their power of attracting small particles of iron, and by the property of setting in a definite direction when suspended so as to be able to turn freely. When a magnet can turn about a vertical axis, a certain direction fixed with regard to it becomes parallel to a direction fixed with regard to the earth. The first direction is that of the **Magnetic Axis** of the magnet, the second that of the **Magnetic Meridian**. A magnet of any shape usually behaves as though forces of attraction or repulsion originated from two points or regions in its substance, which may be termed its **poles**. The pole which points towards the north is called the **North** (or north-seeking) **Pole**, the other the **South** (or south-seeking) **Pole** of the magnet. North polarity is usually taken as **positive**, South polarity as **negative**. Unlike poles (poles of opposite sign) attract, like poles (poles of the same sign) repel one another.




FIG. 194.—Magnetic Needle




FIG. 195.—Bar Magnet and Ball-ended Magnet

Definition of Unit Pole.—The unit magnetic pole is that pole which repels an equal and similar pole at a distance of 1 cm. from it, in air, with a force of 1 dyne.

The strength of the magnetic field or field-strength at any point is determined by the force in dynes acting on a unit north pole placed at that point. This is sometimes called the **magnetic force**¹ or the **magnetic intensity** at the point. The latter expression must not be confused with intensity of magnetisation. Magnetic force is a Vector quantity (p. 51).

¹ Some writers object to the term 'magnetic force', as there is a risk of its being confused with ordinary mechanical force. It has, however, the sanction of Maxwell's classical treatise, and is less cumbersome than 'strength of magnetic field'. If regarded as a compound expression, magnetic force, it is easy to distinguish it from a mechanical force.

Magnetic force is a quantity of a different kind from a mechanical force; it is measured, not in dynes, but in **dynes per unit pole**.¹

The **magnetic moment** M of a magnet is the moment of the couple required to hold the magnet with its axis at right angles to a magnetic field of unit intensity. The magnetic moment of a *simple* magnet is equal to the product of the pole strength m and the distance between the poles.

Assuming ideal point-poles at N and S we find $M = m \times NS$.

§ 2. PLOTTING MAGNETIC FIELDS

A **line of magnetic force** is a line drawn in a magnetic field, such that its direction at any point of its length is the direction of the resultant magnetic force at that point, or the tangent to the curve points in the direction in which a *small* magnet would set itself if placed at that point. The *positive* direction of a line of force is the direction in which a *north* pole would be urged. Lines of magnetic force may be regarded as starting from north magnetic poles and as ending at south magnetic poles. Lines passing completely through the substance of the magnet so as to form closed curves are known as **lines of magnetic induction**.

Lines of magnetic force in air may be traced experimentally either by means of iron filings or by means of a compass needle.

EXPT. 184. Plotting Magnetic Fields with Iron Filings.—A sheet of glass is supported in a horizontal position on two strips of wood placed on the table, and one or more magnets are arranged below it. A sheet of paper is then placed on the glass, and fine iron filings are dusted on to the paper through a piece of muslin. If the glass is tapped gently, the filings will arrange themselves in the direction of the lines of force. Examine in this way the field of (a) one pole of a long ball-ended magnet, (b) a strong bar magnet, (c) two bar magnets placed in various positions.

If a permanent record of the lines is desired, it can be secured by using a piece of paper which has been soaked in paraffin wax. On gently warming the glass plate the filings adhere to the paraffin. Another method is to obtain a photograph of the filings, using a camera pointing vertically downwards; or a print on 'blue' paper can be obtained easily by using a sensitised paper to receive the filings and afterwards exposing and developing in the usual way.

PLOTTING LINES OF MAGNETIC FORCE WITH A COMPASS NEEDLE

It is most instructive to plot the lines of magnetic force in various cases, using a small compass needle. The 'charm' compasses, in which both the top and bottom face are of glass, are most convenient for this

¹ This unit of field strength was formerly called the **gauss**, but later the name **oersted** was approved.

purpose. Such compasses should be handled by the rim and not by the glass faces.

Fix a large sheet of drawing paper to a drawing board, and place the latter so that one edge coincides with the edge of the table. The board may then be replaced in the same position if it should be moved accidentally in the course of the experiment.

Place the compass on the paper, and when it has come to rest make a dot with a pencil opposite each end of the needle. Then shift the compass so that the S. pole lies just above the dot which was near the N. pole, and make another dot near the new position of the N. pole. Repeat this process, so that a row of dots is marked on the paper. Draw a freehand line passing through the row of dots. This will represent one line of magnetic force. Repeat the process about 2 cm. from this line and obtain a second line. In the same way draw a third line of magnetic force about 2 cm. from the second. If the magnetic field is due to the earth alone, the three lines thus obtained should be approximately straight and parallel to one another, since, in the comparatively small space occupied by the drawing board, the earth's field may be considered uniform.

If the field is plotted in the vicinity of any magnetic material or near to a conductor carrying a current, the field obtained is more complex in character than that just described. The lines of force obtained will represent the resultant field due to the superposition of the field of the earth and the field of the magnetic material or of the current. The lines of force will be curved in various ways, depending on the nature of the fields and on the manner in which they are superposed.

Lines of force starting close together will diverge considerably at points along their lengths, and may converge again where they re-enter the magnetic material. As the lines diverge the field is weakened, and some idea can be obtained of the relative intensity of the field at various points by noting the extent to which two lines, originally close together, have diverged by the time they have reached the points in question.

It is important to remember that **lines of magnetic force cannot cross one another**; for, if they did, the magnetic force at the point of intersection would be in two different directions at the same time. In general, there will be a line of force passing through any point chosen; there are, however, exceptional cases in which the lines of force seem to avoid certain points, and no line will be found to pass through these points. If there is no line of force passing through a point, the magnetic force at that point is zero. Such a point in a magnetic field is called a **neutral** or a **null point**.

In the neighbourhood of such a point the magnetic field is extremely

weak, and it is therefore difficult to determine the direction in which the compass needle tends to point. Accordingly when a neutral point is suspected, the lines of force should first of all be plotted at some




FIG. 196.—Neutral Point

distance from it, where the field is stronger, and afterwards the lines plotted should approach nearer and nearer to the neutral point. *It is impossible to find the neutral point by finding the place where the needle will point in any direction.*

A neutral point is enclosed generally by four sets of lines of force, forming a curvilinear quadrilateral. By continually diminishing the size of the quadrilateral the position of the neutral point N can be found with considerable accuracy. It will be shown later how information of importance can be obtained by finding the position of such a point in certain particular cases.

EXPT. 185. Plotting the Lines of Magnetic Force due to the Earth's Field.—To find the character of the lines of magnetic force due to the earth's field, select a position at a distance from iron girders, pipes, or stoves, and remove all magnets, or masses of iron, from the neighbourhood. Starting from one edge of the paper, obtain a row of dots as described above. In the absence of disturbing magnets these dots should lie nearly on a straight line. Starting again about 2 cm. from this line, repeat the process and obtain a second line of force. Draw about half a dozen lines in this way, and verify the fact that the field is approximately uniform by showing that the lines are nearly straight and parallel. The direction thus obtained is the direction of the magnetic meridian at the place where the experiment is carried out.

EXPT. 186. Plotting the Lines of Magnetic Force due to a Bar Magnet and the Earth together.—Place a magnet in any position on a drawing board covered with paper, and plot round it the field due to the magnet and the earth's magnetism together. Before beginning to trace the lines of force, mark the position of the magnet on the paper so that it can be put back in its proper position if accidentally displaced. Some judgment is required in choosing the starting-points for the separate lines so that they may be neither too widely separated nor too closely packed together. Wherever two lines are converging at a small angle to a pair of points close together, it is unnecessary to plot a third line between them in view of the fact that lines of force cannot cross.

In general, *two* neutral points will be found in the field near to a bar magnet, for there are two points at which the magnetic field due to the magnet exactly counterbalances the earth's field. The position of these two points relative to the magnet depends on the position of the magnet relative to the earth's field, and if possible the field of the *same* magnet should be plotted with the magnet in various positions. Special interest arises when the magnet occupies a symmetrical position with regard to the magnetic meridian, being either perpendicular or parallel to the lines of force due to the earth's field. It is suggested that the field should be plotted in each of these positions, and also in one or two positions where the magnet lies unsymmetrically across the earth's lines of force.

FIELD DUE TO A SINGLE POLE IN THE EARTH'S FIELD

The strength of the magnetic field at a distance r cm. from an ideal point pole m is m/r^2 , and varies inversely as the square of the distance from the pole.

In experimenting with a single magnetic pole it is convenient to make use of a very long (50 to 100 cm.) ball-ended magnet, so that the second pole may be placed so far away from the place where the test is being made that its effect may be neglected.

EXPT. 187. Field due to a Single Pole in the Earth's Field.—For the present experiment, support the magnet in a stand of wood with its axis vertical. Let the lower pole rest on a sheet of drawing paper fixed to a horizontal drawing board. Plot the lines of force due to the combined action of this pole and the horizontal component of the earth's magnetic field. Determine carefully the position of the neutral point, and measure the distance (r cm.) between this point and the pole.

At this point the magnetic force due to the pole of strength m is m/r^2 . But at the neutral point this is equal to H , the horizontal component of the earth's field. Thus $m/r^2 = H$, or $m = Hr^2$. Assuming H to be known, m can be calculated. A typical value is $H = 0.18$ dyne per unit pole.

FIELD DUE TO A BAR MAGNET IN THE EARTH'S FIELD

Position I.—The magnet is placed on a horizontal surface with its axis in the magnetic meridian and its *north* pole pointing to the *north*. In this position there is a *neutral point* on either side of the magnetic axis, where the horizontal component due to the earth's magnetism is balanced exactly by the magnetic force of the magnet.

If the bar is magnetised uniformly its poles will be equidistant from the centre. The poles of a bar magnet are not at the extreme ends of the bar. Their positions must be found experimentally by drawing the lines of force near the ends of the bar and determining the points where the directions of the lines *approximately* meet (Fig. 197).




FIG. 197.—Poles of Bar Magnet

The neutral points will lie in a line drawn through the centre, midway between the two poles at right angles to the length.

Let P represent the position of a neutral point at a distance d cm. from either pole of an ideal or simple magnet ¹ (Fig. 198).

The magnetic force at P, due to a pole m at N, is equal to m/d^2 along NP. The magnetic force due to a pole $-m$ at S is equal to m/d^2 along PS.




FIG. 198.—Neutral Point in the Earth's Field

The resultant of these two equal forces bisects the angle 2θ between them, and is evidently perpendicular to OP. Its magnitude is

$$F = 2 \frac{m}{d^2} \cos \theta = 2 \frac{m l}{d^3} = \frac{M}{d^3},$$

since M , the magnetic moment = $2ml$. The formula for F is *exact* provided d is measured from the *poles*.

But P is a 'neutral point'; therefore at P the field $F = H$, the horizontal intensity of the earth's field;

$$\therefore \frac{M}{d^3} = H,$$

or

$$M = Hd^3.$$

EXPT. 188. Determination of the Magnetic Moment of a Bar Magnet, Neutral Point Method I.—Plot the lines of force due to a bar magnet by means of a small compass, when the magnet is placed in the magnetic meridian with its N. pole pointing towards the north. Determine the positions of the neutral points as accurately as possible, and measure the distances from the poles. Calculate the magnetic moment of the magnet from the equation

$$M = Hd^3.$$

As a typical value H may be taken as 0.18 dyne per unit pole, but if possible use the local value; d must be in centimetres.

Measure the distance between the two poles, and deduce the pole strength m of the magnet.

Position II.—The magnet is placed in the magnetic meridian with its N. pole pointing towards the south. Two neutral points will be somewhere on the axis of the magnet produced. If the mean distance of a neutral point from the centre of the magnet be r , the

¹ A ball-ended magnet, when carefully magnetised, gives a closer approximation to the ideal magnetic dipole.

magnetic force due to the magnet is in this case $F = \frac{2M}{r^3}$, approximately (p. 343). Consequently at a neutral point

$$\frac{2M}{r^3} = H, \text{ approximately,}$$

and therefore $M = \frac{Hr^3}{2}$, approximately.

EXPT. 189. Determination of the Magnetic Moment of a Bar Magnet, Neutral Point Method II.—Place a bar magnet with its axis in the magnetic meridian, and its N. pole pointing towards the south. Plot the lines of magnetic force, using a small compass, and find the positions of the neutral points. Measure the distance from each neutral point to the centre of the magnet, and deduce the value of the magnetic moment.

Position III.—The magnet is placed in any position in the magnetic field of the earth. Two neutral points will be found symmetrically situated with regard to the centre of the magnet. The resultant magnetic field may be regarded as due to three forces: one due to the earth, which is supposed known in direction and magnitude, and two due to the magnetic poles in the direction of the lines joining the point to the poles. If the point in question is a neutral point, these three forces must be in equilibrium. By resolving the forces in a direction parallel to the earth's field we can obtain an expression for the strength of a magnetic pole in terms of distances and angles which can all be measured from the diagram.




FIG. 199.—Neutral Points in the Earth's Field

If the magnet lies in some such position as is shown in Fig. 199 (the axis east and west is convenient), the neutral points will be found as at A and B.

Draw a line through A pointing towards the magnetic north. Join AS(r_1) and AN(r_2). If the angles made by AS and AN with the magnetic meridian at A are θ_1 and θ_2 respectively, and m is the pole strength—

$$F = \frac{m}{r_1^2} \cos \theta_1 - \frac{m}{r_2^2} \cos \theta_2,$$

and $F = H = 0.18$ (say) dyne per unit pole.

By measuring r_1 and r_2 , θ_1 and θ_2 , m can be calculated.

The proof of this expression is left as an exercise for the student.

EXPT. 190. Determination of the Magnetic Moment of a Bar Magnet, Neutral Point Method III.—Place a bar magnet with its axis east and west. Plot the lines of magnetic force, and find the positions of the

neutral points as accurately as possible. Measure r_1 and r_2 , θ_1 and θ_2 , for *each* neutral point, and deduce the value of m , the pole strength in each case.

§ 3. MAGNETIC AXIS AND MAGNETIC MERIDIAN

When a magnet is suspended so that it can turn freely about a vertical axis, a certain direction fixed with regard to the magnet tends to become parallel to a certain direction fixed with regard to the earth. The direction fixed relatively to the magnet is the direction of the **magnetic axis of the magnet**; the direction fixed relatively to the earth is the direction of the **magnetic meridian**. In the case of a long, thin magnet, the magnetic axis may be taken to correspond with the direction of the length of the magnet, but in the case of a broader magnet—an ordinary *bar* magnet—it is not allowable to assume that the direction of the magnetic axis coincides with the direction of symmetry. The following experiment illustrates the method used in magnetic observatories for determining the magnetic axis of a magnet and the magnetic meridian.

In order to take an extreme case, we construct a magnetised disk whose magnetic axis is quite unknown. To do this, a light bar magnet is enclosed in a flat circular wooden box, so that its position is concealed entirely. A reference line is traced on each flat face of the box, joining two points, A and B, at opposite ends of a diameter (Fig. 200). The problem is to find the angle between the axis of the concealed magnet (or of the whole disk) and this reference line.




FIG. 200.—Magnetised Disk

EXPT. 191. Determination of the Magnetic Axis of a Magnet and the Magnetic Meridian at any Place.—The magnetised disk is suspended from the centre of one face by a fine thread, which should be as free from torsion as possible. If the thread is not torsionless there will be a couple acting on the disk due to the torsion of the suspension, and the position of rest of the disk will be determined by the action of this couple in

addition to the magnetic couple due to the earth's field. A sheet of paper is *fixed* horizontally, immediately below but not in contact with the disk. The position of the reference line when the disk has come to rest must be marked on the paper. It is not necessary, however, to wait till the plate comes to rest of its own accord. Notice the positions of the extremities of its swings, and then gently check the motion halfway between these two positions. In order to mark the position of rest of the reference line accurately on the paper, it is convenient to have a metal pointer fixed to the circumference of the plate at each end of the line. A line such as A'B' is thus obtained on the paper.

The plate should then be turned upside down and suspended from the opposite face, and the new position of the reference line determined; let this be A''B'' (Fig. 201).

No lines should be drawn on the plate itself.

In this way two lines, $A'B'$, $A''B''$, are obtained on the paper, these lines being inclined to one another at a definite angle. A little consideration will show that the direction of the magnetic axis must bisect the angle between the two lines, for the magnetic axis coincides with the fixed meridian, and the reference line must be at the same angle with the meridian on one side in the first case, as it is on the other side in the second case.

As there are two bisectors between the lines AA' and BB' it is necessary to determine which of the two coincides with the meridian.

The points A' and A'' were made by the same pointer A , one for each position of the plate. Similarly B' and B'' were both made by the pointer at B on the plate. Thus in reversing the plate and allowing it to take up its second position of equilibrium, it has virtually been rotated about the diameter passing midway A' and A'' , and B' and B'' . Hence the line marked NS in the diagram bisecting $A'OA''$ and $B'OB''$ is the magnetic axis of the plate and the magnetic meridian.




Fig. 201.—Magnetic Meridian

Measure with a protractor the angle between the line on the paper representing the magnetic axis (or the magnetic meridian) and the reference line $A'B'$.

Measure also the angle between the magnetic meridian and some line fixed in the room such as the edge of a laboratory table.

§ 4. TRACTIVE FORCE FOR A BAR MAGNET

Measurements of the tractive force at different points in the length of a magnet were made by Coulomb. He observed the weights of iron which could be supported at the points. His results may be represented by a curve of the form shown in Fig. 202, in which the ordinates are proportional to the force at different points in the length. If the distribution of magnetism is uniform the curve is symmetrical about C , the centre of the magnet.

EXPT. 192. Determination of the Distribution of Tractive Force along a Bar Magnet.—Mark off the magnet into, say, 10 equal parts, and place

B

it on a levelling table beneath the scale-pan of a 'hydrostatic' balance. From the hook of the scale-pan suspend a small iron ball. Adjust the levelling table so that the pointer of the balance is near the middle of the scale when the ball is in contact with the magnet, and then find the weight that must be placed in the other scale-pan in order to separate the ball from the magnet. Repeat the observation with

Fig. 202.—Tractive Force of Bar Magnet

the ball at different points marked in the length of the magnet.

The attraction depends largely on the closeness of contact between the ball and the magnet; any grease or dirt between them may diminish the force by several grams-weight. The ball may be rubbed slightly across the breadth of the magnet in putting it into position, thus removing any dirt and ensuring greater consistency in the observations.

In order to prevent injury to the balance when the iron ball leaves the magnet, the weights must be added very carefully, and wooden blocks must be placed under the scale-pan containing them, so as to limit the movement of the balance.

Determine the weight of the ball when the magnet is not near it.




FIG. 203.—Determination of Tractive Force

This weight must be subtracted from the weights observed in the previous observations, so as to give the force due to the attraction of the magnet.

Plot a curve showing the attraction at different points in the length of the magnet.

Instead of using a hydrostatic balance in this experiment, a spring balance may be employed. In this case the levelling table may be lowered, or, keeping the magnet fixed, the spring balance may be raised gently till the ball leaves the magnet. The reading of the spring balance must be taken just as the separation occurs.

CARE OF MAGNETS

General weakening or demagnetisation of magnets can be produced by mechanical shocks or rough treatment of any kind, also by heating or by placing magnets close together without due regard to their polarity. **Consequent poles** can be produced by bringing a strong magnet close to the side of a weaker magnet. When not in use bar magnets should be kept in pairs in suitable boxes, with *opposite* poles adjacent and with 'keepers' bridging the poles at each end; horse-shoe magnets should also be provided with keepers. The keepers should be applied gently and not allowed to 'snap' into position against the poles. Ball-ended magnets may be kept in pairs with *opposite* poles in contact.

MAGNETOMETRY

§ 1. THE DEFLECTION MAGNETOMETER

In its simplest form the **magnetometer** consists of a pivoted or suspended magnetic needle, free to turn about a vertical axis, and provided with a circular graduated scale for measuring deflection. The needle




FIG. 204.—Deflection Magnetometer

and circular scale are contained usually in a case of wood or of brass, provided with a glass top, through which the reading can be taken. A long, light pointer pp' is fitted to the needle, so that the movement of the needle may be measured over a circle of large diameter although the needle itself is small: the circle is usually large enough to give readings accurate to about 1° of angle. In order to avoid parallax in reading the position of the pointer, the base of the magnetometer is provided generally with a plane mirror. In taking a reading, the eye of the observer must be placed in such a position that the reflection of the pointer is hidden by the pointer itself; the observer will then be looking straight down on the scale, and the true reading will be obtained.

For very accurate work a **mirror magnetometer** is used in conjunction with a lamp and scale. In this form there is a mirror fixed to the needle, a beam of light from the lamp strikes this mirror, and the motion of the reflected beam over the scale is used to measure the deflection of the needle. The beam of light serves as a long weightless pointer, the angle it turns through being *twice* the deflection of the needle (p. 193).

The magnetometer is usually set up so that the zero reading is obtained when the needle is under the influence only of the horizontal component H of the earth's magnetic field. A second field of strength F , in a direction at right angles to H , is then applied to the needle, say by means of a magnet placed in the neighbourhood of the instrument. The pointer is thus deflected through an angle θ . By measuring this angle we can determine the relation between F and H . For this purpose the following important theorem is required :—




FIG. 205.—Proof that $F = H \tan \theta$

When a magnet is placed in a magnetic field due to the superposition of two mutually perpendicular magnetic fields both of which are uniform, its position is determined by the relation

$$\frac{F}{H} = \tan \theta,$$

where F and H are the strengths of the magnetic fields and θ is the angle between the axis of the magnet and the direction of the field H .

Let NS (Fig. 205) represent the magnet, whose pole strength is m . The N pole is under the action of two forces, viz. mH dynes parallel to H , and mF dynes parallel to F . The S pole is under the action of equal forces in the contrary sense. These forces constitute couples which keep the magnet in a position of equilibrium.

Taking moments about the centre O of the magnet we get

$$mF \times OA = mH \times OB,$$

$$\begin{aligned} \text{or} \quad \frac{F}{H} &= \frac{OB}{OA} = \frac{AN}{OA} \\ &= \tan \theta, \end{aligned}$$

and consequently

$$F = H \tan \theta.$$

Thus if we know the ratio of F to H , we can calculate the angle θ ; and if we know the strength of the field H and can observe the angle θ , we can determine the strength of the field F .

In most experiments of this kind the field F is only approximately uniform. For this reason it is important that the needle of the magneto-

meter should not be too long. If the needle is short only a small error is introduced by treating the field F as uniform.

§ 2. COMPARISON OF MAGNETIC FIELDS BY THE MAGNETOMETER

EXPT. 193A. Field due to a Single Pole of a Vertical Magnet.—In this experiment the long ball-ended magnet described previously (p. 331) should be used. As the intention is to examine the effect of one pole only, the second pole must be placed in such a position that it will have no effect on the reading of the magnetometer. This can be done by supporting the magnet vertically in a wooden stand.

Find the magnetic meridian by means of the magnetometer needle. Place a metre scale on the table at right angles to the meridian, and put the magnetometer box on the scale so that the centre of the box is directly above the central division of the scale. Carefully adjust the box and the metre scale so that the pointer is at the zero division, and the scale points exactly east and west (magnetically). In some forms of magnetometer the metre scale is fitted permanently (AB, Fig. 204).

The upper pole of the magnet is at a considerable distance (approximately 1 metre) from the magnetometer, while the lower pole is at a much smaller distance. If, for instance, the lower pole is 20 cm. from the magnetometer, the magnetic force due to the upper pole is not greater than 4 per cent of the force due to the lower pole. By placing the magnet vertically, the horizontal component of the force due to the upper pole at the magnetometer is reduced to about $\frac{1}{10}$ th of the total force due to it when the distance of the magnetometer is greatest.

The extreme value of the horizontal force due to the upper pole is thus reduced to less than 1 per cent of the force due to the lower pole, an error which is much below the probable errors of reading.

EXPT. 193B. Field due to a Single Pole of a Tilted Magnet.—If the magnet is tilted somewhat so as to bring the upper pole over the middle of the magnetometer (Fig. 206), any horizontal force due to it may be quite eliminated. If the magnet is long enough this is not absolutely necessary, as will be seen from the above. For a shorter magnet the method of tilting should be used.

The first pole of the magnet must be on the metre scale, so that its field at the magnetometer lies east and west. In this position it will produce a magnetic force $F = m/r^2$ at the centre of the magnetometer, if m is the strength of the pole and r its distance from that centre (p. 331). Consequently a deflection θ will be produced, given by $F = H \tan \theta$, or $m/r^2 = H \tan \theta$. Hence $r^2 \tan \theta = m/H = \text{a constant for the particular strength of pole under test in a given field.}$

Consequently, if we take a series of readings of r and θ , reading both ends of the pointer, we should find that $r^2 \tan \theta$ is constant.

Tabulate the results under the headings: r , θ , $\tan \theta$, $r^2 \tan \theta$.

If the numbers in the last column of the table are approximately constant, the result may be regarded as a verification of the law that the magnetic force due to a single pole varies inversely as the square of the distance from the pole.




FIG. 206.—Field due to Single Pole

Assuming this inverse square law to be true, it is possible to calculate the strength of the field due to a bar magnet (pp. 343-344), but we shall in the first place employ an *experimental* treatment for a *short* magnet.

EXPT. 194A. Field due to a Short Bar Magnet end-on.—Place the magnet, which should be strongly magnetised, on the metre scale with its axis pointing east and west (Fig. 207). In this 'end-on' position it will produce a magnetic field at the magnetometer pointing east and west, and of the approximate strength $F = 2M/r^3$, where M is its magnetic moment and r is the distance from the centre of the magnetometer to the centre of the magnet. *This is only true provided the length of the magnet is small in comparison with the distance r .*

The magnetometer needle will be deflected through an angle θ given by $F = H \tan \theta$, so that $2M/r^3 = H \tan \theta$. Hence $r^3 \tan \theta = 2M/H = a$ constant for the particular magnet under test.

Note the distance r and read the deflection θ for both ends of the pointer. Now turn the magnet end for end, keeping its centre at the same point, and take two more readings. Take the mean of these readings as the true deflection. Tabulate the results under the headings: r , θ , $\tan \theta$, $r^3 \tan \theta$. The values obtained in the last column will be approximately constant.

This shows that the strength of the field along the axis of a short bar magnet varies inversely as the cube of the distance from the centre of the magnet.

EXPT. 194B. Field due to short Bar Magnet broadside-on.—This experiment is similar to the previous one, but the magnet is placed in the broadside-on position (Fig. 209). In this position $F = M/r^3$ for a short bar magnet.

§ 3. COMPARISON OF MAGNETIC MOMENTS BY THE MAGNETOMETER. ELEMENTARY TREATMENT

When a magnet is placed in a uniform field of strength H , its axis being at right angles to the field, it experiences a mechanical couple proportional to H . The ratio of this couple to the strength of the




FIG. 207.—'End-on' Position. Method of Tangents

field is the magnetic moment M or the turning moment of the magnet.

In the first instance an elementary discussion of the comparison of magnetic moments is given, on the assumption that the lengths of the magnets compared are small enough to be neglected in comparison with the distance from a magnet to the magnetometer.

EXPT. 195. Comparison of Magnetic Moments, using the 'End-on' (or A) Position.—Place the magnetometer box on a metre scale laid flat on the table, so that the centre of the box coincides with the centre of the scale, the zero line of the magnetometer pointing exactly along the length of the scale. Turn the scale round till it points east and west, as judged by the magnetometer needle (Fig. 207).

(i) **Method of Tangents, or Method of Equal Distances.**—Place the first magnet (magnetic moment M_1) with its centre at a definite division on the metre scale and with its axis pointing east and west. The distance from the magnetometer must be large compared with the length of the magnet, but must not be so large as to give a very small deflection of the needle. A deflection anywhere between 15° and 55° would be suitable. Take readings of both ends of the needle, taking care to avoid errors due to parallax. Reverse the magnet, end for end, keeping its centre at the same graduation as before, and again read the position of the needle.

Now repeat the observations with the magnet on the other side of the magnetometer at the same distance from it. Let the mean of all the readings be θ_1 .

Take readings in exactly the same way with the second magnet (magnetic moment M_2), placing the centre of the magnet in the positions occupied by the centre of the first magnet. Let the mean of all these readings be θ_2 .

$$\text{Now } F_1 = \frac{2M_1}{r_1^3}, \quad F_2 = \frac{2M_2}{r_2^3}, \quad \text{and } F_1 = H \tan \theta_1, \quad \text{and } F_2 = H \tan \theta_2.$$

$$\text{Then, approximately,} \quad \frac{M_1}{M_2} = \frac{\tan \theta_1}{\tan \theta_2}.$$

(ii) **Method of no Deflection.**—In this method the two magnets are used at the same time, one to the east, the other to the west of the magnetometer, and their distances from the magnetometer are adjusted




FIG. 208.—'End-on' Position. Method of no Deflection

till there is no deflection of the needle. Measure the distances r_1 , r_2 , from the centre of the magnetometer to the centres of the magnets. Reverse the magnets, keeping r_1 unaltered, and readjust the second magnet till no deflection is given: r_2 may now have a slightly different value. Take the mean of the two values of r_2 .

$$\text{Now } F_1 = \frac{2M_1}{r_1^3}, \quad F_2 = \frac{2M_2}{r_2^3}, \quad \text{and since the deflection is zero } F_1 = F_2.$$

$$\text{Then, approximately,} \quad \frac{M_1}{M_2} = \frac{r_2^3}{r_1^3}.$$

EXPT. 196. Comparison of Magnetic Moments, using the 'Broadside-on' (or B) Position.—Turn the metre scale till it lies in the magnetic

meridian, the magnetometer box being still at the centre of the scale. In order that the pointer may still point to the zero of the circular scale the box also must be turned through a right angle on the metre scale.

(i) **Method of Tangents, or Method of Equal Distances.**—Place the first magnet on the metre scale with its axis pointing east and west, and read the position of the pointer. Reverse the magnet end for end and again take readings (Fig. 209).

Repeat the observations with the magnet on the other side of the magnetometer at the same distance from it. Let the mean of all the readings be θ_1 .

Take readings in the same way with the second magnet at the same distance from the magnetometer, and let the mean be θ_2 .




FIG. 209.—'Broadside-on' Position.
Method of Tangents




FIG. 210.—'Broadside-on' Position.
Method of no Deflection

Now $F_1 = \frac{M_1}{r^3}$, and $F_2 = \frac{M_2}{r^3}$, and $F_1 = H \tan \theta_1$, and $F_2 = H \tan \theta_2$.

Then, approximately, $\frac{M_1}{M_2} = \frac{\tan \theta_1}{\tan \theta_2}$.

(ii) **Method of no Deflection.**—One magnet is placed to the north, the other to the south of the magnetometer, and their distances, r_1 , r_2 , from the magnetometer are adjusted till there is no deflection of the needle (Fig. 210). Reverse the magnets, keeping r_1 constant, and take the mean of the values of r_2 . Both magnets must be pointing east and west.

Now F_1 and F_2 are equal, and

$$F_1 = \frac{M_1}{r_1^3}, F_2 = \frac{M_2}{r_2^3}.$$

Then, approximately,

$$\frac{M_1}{r_1^3} = \frac{M_2}{r_2^3}.$$

Thus there are in all four different methods of making the comparison, two in the 'end-on', two in the 'broadside-on' position. In all cases the axes of the magnets under examination point east and west.

§ 4. COMPARISON OF MAGNETIC MOMENTS BY THE MAGNETOMETER. MORE ADVANCED TREATMENT

A. Magnetic Force at a Point on the Axis of the Magnet — 'End-on' Position.—The magnetic moment M of a magnet length $2l$, poles $+m$




FIG. 211.—'End-on' Position

and $-m$, is $2lm$. The force on unit north magnetic pole at P is

$$\frac{m}{NP^2} = \frac{m}{(r-l)^2},$$

repulsion from N ,

$$\text{and} \quad \frac{m}{SP^2} = \frac{m}{(r+l)^2},$$

attraction towards S .

The resultant magnetic force at P is in the direction, OP , and

$$\begin{aligned} &= \frac{m}{(r-l)^2} - \frac{m}{(r+l)^2} \\ &= \frac{m}{(r^2-l^2)^2} \{ (r+l)^2 - (r-l)^2 \} \\ &= \frac{m4rl}{(r^2-l^2)^2} = \frac{2Mr}{(r^2-l^2)^2}. \end{aligned}$$

When r is large compared with l the term in l^2 may be neglected, and the expression becomes

$$F = \frac{2M}{r^3} \text{ (approximately).}$$

B. Magnetic Force at a Point in the Equatorial Plane of the Magnet — 'Broadside-on' Position.—In this case the point P is in a line bisecting the magnet at right angles (Fig. 212). The components of the magnetic force at P are m/NP^2 along NP and m/SP^2 along PS .

Each of these components, which are equal in magnitude, may be resolved into forces along and perpendicular to OP. The forces in the direction OP balance one another. The forces at right angles to OP give

$$F = \frac{m}{NP^2} \cos PNO + \frac{m}{SP^2} \cos PSO = \frac{2m}{NP^2} \frac{ON}{NP} = \frac{2ml}{NP^3} = \frac{M}{(r^2 + l^2)^{\frac{3}{2}}},$$

or

$$F = \frac{M}{r^3}$$

approximately,¹ when r is large compared with l .

We compare the magnetic force F due to the magnet with the horizontal force H of the earth by the expression $F = H \tan \theta$ (p. 338). We assume that the needle of the magnetometer is so small that the field near it may be considered uniform.

The foregoing results provide four different methods for comparing the magnetic moments of two magnets by means of the magnetometer. For further experimental details see p. 341.




FIG. 212.—'Broadside-on' Position

EXPT. 197. Comparison of Magnetic Moments, using the 'End-on' Position (corresponding with Expt. 195).

(i) **Method of Tangents, or Method of Equal Distances.**

—Place each magnet in turn at the same distance r from the magnetometer, arranging the magnet so that its axis passes through the centre of the needle, and is at right angles to the magnetic meridian. The deflecting magnet must be placed with its axis pointing east and west. When the latter adjustment is secured the magnet produces the maximum deflection of the needle.

Observe the two deflections θ_1 and θ_2 of the pointer.

Then $F_1 = \frac{2M_1 r_1}{(r_1^2 - l_1^2)^{\frac{3}{2}}}$, and $F_2 = \frac{2M_2 r_2}{(r_2^2 - l_2^2)^{\frac{3}{2}}}$, and in this case $r_1 = r_2 = r$ (say).

Hence $\frac{F_1}{F_2} = \frac{2M_1 r / (r^2 - l_1^2)^{\frac{3}{2}}}{2M_2 r / (r^2 - l_2^2)^{\frac{3}{2}}} = \frac{H \tan \theta_1}{H \tan \theta_2}$,

$$\frac{M_1}{M_2} = \frac{(r^2 - l_1^2)^{\frac{3}{2}}}{(r^2 - l_2^2)^{\frac{3}{2}}} \times \frac{\tan \theta_1}{\tan \theta_2}.$$

If the magnets are of approximately the same length, then

$$\frac{M_1}{M_2} = \frac{\tan \theta_1}{\tan \theta_2}.$$

Note that r is the distance from the centre of the deflecting magnet to the centre of the magnetometer needle.

(ii) **Method of no Deflection.**—Arrange the magnets in positions similar to the above, but one on either side of the needle. Adjust their distances till there is no deflection of the magnetometer needle.

¹ If $NP = SP = d$, we see that $r^2 + l^2 = d^2$, and $F = M/d^3$ exactly.

If r_1 and r_2 are the distances, we have made $F_1 = F_2$,

$$\therefore \frac{2M_1 r_1}{(r_1^2 - l_1^2)^{\frac{3}{2}}} = \frac{2M_2 r_2}{r_2^3} \quad \frac{M_1}{M_2} = \frac{(r_1^2 - l_1^2)^{\frac{3}{2}}}{r_2^3} r_2$$

If r_1^2 and r_2^2 are both large compared with l^2 this reduces to

$$\frac{M_1}{M_2} = \frac{r_1^3}{r_2^3}.$$

EXPT. 198. Comparison of Magnetic Moments using the ' Broadside-on ' Position (corresponding with Expt. 196).

(i) **Method of Tangents, or Method of Equal Distances.**—Place each magnet in turn at the same distance r from the centre of the needle and observe the deflection produced in each case. Note again that the deflecting magnets must be placed with their axes pointing east and west.

Then, generally,

$$F_1 = \frac{M_1}{(r_1^2 + l_1^2)^{\frac{3}{2}}} \text{ and } F_2 = \frac{M_2}{(r_2^2 + l_2^2)^{\frac{3}{2}}}$$

In this case $r_1 = r_2 = r$ (say).

$$\frac{F_1}{F_2} = \frac{M_1 / (r^2 + l_1^2)^{\frac{3}{2}}}{M_2 / (r^2 + l_2^2)^{\frac{3}{2}}} = \frac{H \tan \theta_1}{H \tan \theta_2},$$

$$\frac{M_1}{M_2} = \frac{(r^2 + l_1^2)^{\frac{3}{2}} \tan \theta_1}{(r^2 + l_2^2)^{\frac{3}{2}} \tan \theta_2}.$$

If the magnets are of approximately the same length,

$$\frac{M_1}{M_2} = \frac{\tan \theta_1}{\tan \theta_2}.$$

(ii) **Method of no Deflection.**—Place the magnets one on either side of the needle with their centres north and south of it, and adjust their distances until the magnetometer needle remains in the magnetic meridian.

If r_1 and r_2 are the distances of the magnets from the needle,

$$\frac{M_1}{M_2} = \frac{(r_1^2 + l_1^2)^{\frac{3}{2}}}{(r_2^2 + l_2^2)^{\frac{3}{2}}}.$$

If l_1 and l_2 are both small in comparison with r , this reduces to

$$\frac{M_1}{M_2} = \frac{r_1^3}{r_2^3}.$$

Note on making Observations of θ and of r .—If the deflecting magnet is not magnetised uniformly, its magnetic equator is nearer to one end than the other. The true distance r is therefore not the distance from the centre of the needle to the centre of the bar. Again, if the pivot of the needle is not exactly in the centre of the magnetometer box, the value taken for r will be wrong on this account also. To avoid errors due to these two causes, the deflection should be taken first with the magnet one way round, then with the magnet reversed. After this the magnet should be placed on the other side of the magnetometer at an equal distance r , and the needle deflection determined again for both positions of the magnet on this side. Each time the two ends of the pointer must be read so that eight readings of θ are taken; the mean of these is taken as the true deflection θ .

In the method of no deflection one magnet must always be taken at the same distance r_1 . After taking r_2 to correspond with r_1 , both magnets must be reversed, when a new value of the second distance r_2 may be found to be necessary in order to get zero deflection. The magnets are then

placed on the other sides of the magnetometer, and two more values of r_2 are found to give zero deflection when the first magnet is at a distance r_1 . The mean of the four values of r_2 is used in the calculations.

HIBBERT'S MAGNETIC BALANCE

Coulomb investigated the law of force between magnetic poles by means of a *torsion* balance. A century later Hibbert designed an apparatus (Fig. 212A) which is a *gravity* balance, the force between




FIG. 212A.—Hibbert's Magnetic Balance

two adjacent poles being balanced by the weight of an adjustable rider or sliding mass on the beam. Two magnets (preferably ball-ended) are used. The first or 'swinging' magnet, N_1S_1 , serves as the balance beam, and it is held in a central block provided with steel pivots working in agate supports. More accurate results can be obtained if the block carries a pointer which moves over a graduated arc. The second or 'stationary' magnet, N_2S_2 , is held horizontally in a frame which can slide on a vertical centimetre scale and is capable of fine adjustment. If the magnets are of sufficient length, the forces due to the poles S_1 and S_2 can be neglected.

The rider is placed on the beam at some point P and the 'stationary' magnet is adjusted until the pointer oscillates about the centre of the arc. In equilibrium the moment of the force (F dynes) between the poles N_1, N_2 balances the moment of the weight ($w = mg$ dynes) of the rider. Hence $F \times ON_1 = w \times OP$. From this equation the force F in dynes can be found and the value of $F r^2$ calculated. If it is true that $F = \frac{m_1 m_2}{r^2}$, the product $F r^2$ should be constant for a given pair of poles.

The comparison of the pole strength of a number of magnets can be made by using Hibbert's balance.

THE OSCILLATIONS OF A MAGNET IN A
MAGNETIC FIELD

§ 1. COMPARISON OF MAGNETIC FIELDS BY OSCILLATIONS

WHEN a magnet is suspended so that it can oscillate about an axis of symmetry in a uniform magnetic field, the motion is very nearly Simple Harmonic provided the angular swings are small. The time of one complete vibration is given by the formula (deduced on the assumption that the motion is approximately Simple Harmonic Motion, p. 128),

$$T = 2\pi \sqrt{\frac{I}{MH}},$$

where T is the periodic time,

I is the moment of inertia about the chosen axis,

M is the magnetic moment,

H is the strength of the magnetic field.

If the *same* magnet be set in oscillation at various points of a magnetic field, I and M remain constant, but T and H vary. The formula shows that

$$\begin{aligned} HT^2 &= \frac{4\pi^2 I}{M} \\ &= C \text{ (where } C \text{ is a constant).} \end{aligned}$$

Thus if the value of the constant C be determined once for all by making the magnet oscillate in a magnetic field of *known* strength, the strength of any other field may be found by finding the value of T in that field.

EXPT. 199. Determination of the Strength of the Field at any Point assuming the Earth's Field known.—The oscillating needle used in this experiment is a small steel magnet only about 2 cm. in length mounted horizontally in a small brass stem suspended by a single silk fibre. A heavy short piece of 'rat-tail' file is suitable as the needle. A light aluminium pointer may be attached to the stem in order to make it easier to observe the oscillations. The apparatus should be protected from air currents by a glass shade. Place the apparatus on a table remote from masses of iron such as iron pipes, stoves, etc. Remove all other magnets, including knives and keys, from the neighbourhood. Set the needle oscillating by bringing a magnet momentarily near to it, but do not allow the amplitude of the oscillations to exceed a few degrees,

as the motion approximates to Simple Harmonic Motion only when the amplitude is small. Observe the time taken for the needle to complete a number of complete oscillations (40 or 50 should be observed if possible), and calculate the time T_0 for one complete oscillation.

Assuming H_0 , the horizontal component of the earth's magnetic field, to be known, find the value of the constant C by means of the equation

$$H_0 T_0^2 = C.$$

The object of the experiment is to determine H , the horizontal field at some other place. Move the apparatus to the spot where the strength of the field is to be measured, and again observe the time T of an oscilla-




FIG. 213.—Searle's Oscillating Needle

tion. Using the value of C just found, determine the value of H from $HT^2 = C$. In this way a magnetic survey of the laboratory can be carried out.

ELIMINATION OF THE EFFECT OF THE EARTH'S FIELD

It is frequently necessary to compare two fields neither of which is known. This could be done as already described if the two fields could be isolated, but in general this cannot be done, and the needle would have to oscillate in a field compounded of the earth's field and one or other of the fields to be compared.

If one of the fields (F) is arranged *parallel* to the earth's field (H_0) the resultant field (H) will be either the sum or the difference of F and H_0 : the needle can now be allowed to oscillate in this compound field and its period of swing (T) determined. It is important to note that greater accuracy is obtained if the composite field is made the *sum* of F and H_0 . If possible, therefore, the field F should be arranged

so as to assist the earth's field, so that the needle oscillates more rapidly than in the earth's field alone, *and still points in the same direction as when in the earth's field.*

If T_0 , the period of swing in the earth's field, be known, we have, from the fundamental equation,

$$H_0 = \frac{C}{T_0^2},$$

and
$$H = \frac{C}{T^2}.$$

But
$$H = H_0 + F,$$

or
$$F = H - H_0.$$

Therefore
$$F = \frac{C}{T^2} - \frac{C}{T_0^2},$$

or
$$F = C \left\{ \frac{1}{T^2} - \frac{1}{T_0^2} \right\}.$$

When two fields F_1 and F_2 are to be compared they must be combined separately with the earth's horizontal field H_0 in such a way as to assist it. The periods of swing of the needle are determined in the two compound fields, and the ratio of F_1 to F_2 is given by

$$\frac{F_1}{F_2} = \frac{\left\{ \frac{1}{T_1^2} - \frac{1}{T_0^2} \right\}}{\left\{ \frac{1}{T_2^2} - \frac{1}{T_0^2} \right\}}.$$

The student is required to deduce this expression from the discussion detailed above.

EXPT. 200. Verification of the Law of Force for a Single Magnetic Pole.—Observe the time taken for the oscillating needle to execute fifty complete swings when all other magnets are removed from its neighbourhood. The needle should be protected from draughts, and the amplitude of the oscillations should not exceed a few degrees.

Let the time of vibration in this case be T_0 , the strength of the field H_0 being due to the earth's magnetism.

Then $H_0 T_0^2 = C$ (C being a constant).

If H_0 is known the value of C could be calculated from this equation, but as it cancels out in the working of the results it is unnecessary to do this.

We have then the relation that

$$H_0 = \frac{C}{T_0^2}.$$

Next take one of the very long ball-ended magnets already referred to, and support it vertically in a wooden stand. Place the lower pole somewhere along a line passing through the centre of the needle, and directed north and south (magnetic).

The needle now swings either more or less rapidly than before, or it may perhaps try to turn round end for end; this depends on the nature of the pole and the position in which it is placed.

It is important to note that the pole should be placed in such a position that the oscillating needle points in the same direction as when in the earth's field alone, and *has a shorter period of swing* than before.

Since the period of oscillation is smaller, the field H in which the magnet oscillates is stronger than before. This combined field is equal to the sum of the field F due to the pole of the magnet, and H_0 due to the earth.

Then

$$H = H_0 + F.$$

Place the lower pole of the magnet at various distances r_1, r_2, r_3 , etc., from the oscillating needle, the pole of the magnet being always on the same side of the needle, and in the meridian line passing through the needle. Take the different distances r_1, r_2 , etc., ranging from about 5 cm. to 20 cm. Find the times of swing T_1, T_2, T_3 of the needle for the various distances of the pole.

We wish to show by this experiment that the field of a single pole varies inversely as the square of the distance from the pole, that is we wish to show that F is proportional to $1/r^2$.

We can show this if we prove that

$$F_1 r_1^2 = F_2 r_2^2 = F_3 r_3^2, \text{ etc.}$$

Now

$$F_1 = C \left\{ \frac{1}{T_1^2} - \frac{1}{T_0^2} \right\} \quad (\text{p. 349}),$$

$$F_2 = C \left\{ \frac{1}{T_2^2} - \frac{1}{T_0^2} \right\}, \text{ etc.}$$

Thus we shall show all that we wish if we prove that

$$C \left\{ \frac{1}{T_1^2} - \frac{1}{T_0^2} \right\} r_1^2 = C \left\{ \frac{1}{T_2^2} - \frac{1}{T_0^2} \right\} r_2^2 = C \left\{ \frac{1}{T_3^2} - \frac{1}{T_0^2} \right\} r_3^2 = \text{etc.}$$

The constant C occurs in each of these, and therefore can be cancelled throughout without affecting the equality, so that if we can show

$$r_1^2 \left\{ \frac{1}{T_1^2} - \frac{1}{T_0^2} \right\} = r_2^2 \left\{ \frac{1}{T_2^2} - \frac{1}{T_0^2} \right\} = r_3^2 \left\{ \frac{1}{T_3^2} - \frac{1}{T_0^2} \right\} = \text{etc.},$$

we shall have proved that

$$F_1 r_1^2 = F_2 r_2^2 = F_3 r_3^2 = \text{etc.}$$

or that F is proportional to $\frac{1}{r^2}$.

Arrange the observations as follows :—

Distance of Pole r (cm.)	Period of Swing T	$\frac{1}{T^2}$	$\frac{1}{T^2} - \frac{1}{T_0^2}$	$r^2 \left\{ \frac{1}{T^2} - \frac{1}{T_0^2} \right\}$
5	$T_0 =$			
6				
7				
8				
10				
12				
15				
20				
Infinity				

The period when the pole is at infinity is evidently the period of swing in the earth's field alone.

The last column will prove to be approximately constant, thereby showing that the force varies inversely as the square of the distance from a single pole.

The effect of the upper end of the magnet is negligible throughout these observations, as is shown in an earlier experiment (Field of Single Pole by Magnetometer, p. 339).

§ 2. COMPARISON OF MAGNETIC MOMENTS BY OSCILLATIONS

When a magnet is suspended by a fine fibre so that its axis hangs in a horizontal position, in a magnetic field of strength H , the axis will assume a certain equilibrium direction. If the magnet be disturbed slightly from this equilibrium position it will execute vibrations about it.

If the oscillations are small the time of each oscillation is the same—the vibrations are isochronous. The time depends on the form and mass of the magnet, and on the couple tending to bring it back to its equilibrium position.

The time of a complete vibration (backwards and forwards) is given by

$$T = 2\pi \sqrt{\frac{I}{MH}}.$$

Hence if I and H are kept constant, the square of the time of vibration is inversely proportional to the magnetic moment of the suspended system.

$$T^2 = \frac{4\pi^2 I}{MH} = \frac{4\pi^2 I/H}{M} = \frac{K}{M},$$

where K is a constant having the value $= \frac{4\pi^2 I}{H}$.

If I is not constant, T^2 is proportional to $\frac{I}{M}$, when the same field is used.

EXPT. 201. Comparison of the Magnetic Moments of Two Magnets by oscillating them separately.—Suspend one of the magnets from a fine thread, so that it can oscillate in a horizontal plane. Note its time of oscillation by taking 50 complete oscillations when under the action of the earth's field alone. Let this time be T_1 .

Remove this magnet and replace it by the second, allowing this to swing as nearly as possible in the same position as the first. Take its time of oscillation as before: let this be T_2 .

In making these oscillation experiments the twist in the thread must be taken out first by allowing it to untwist under a weight equal to the weight of the magnet to be suspended. If this is not done the magnet will not oscillate about a north and south line: it will be deflected from that line by the couple due to the twist in the suspending thread. The magnets should oscillate in a closed box with glass sides so that the

oscillations can be observed, and yet the motion shall not be affected by draughts (Fig. 216).

The swings should be counted and timed as the magnet swings through its middle position, and the angle of swing should not exceed 5° on either side of this position.

Then

$$T_1 = 2\pi \sqrt{\frac{I_1}{M_1 H}}$$

and

$$T_2 = 2\pi \sqrt{\frac{I_2}{M_2 H}}$$


Thus

$$\begin{aligned} \frac{T_1^2}{T_2^2} &= \frac{I_1 M_2}{I_2 M_1}, \\ \frac{M_1}{M_2} &= \frac{I_1 T_2^2}{I_2 T_1^2}. \end{aligned}$$

Calculate I_1 and I_2 from the masses and dimensions of the magnets (see page 560 for the calculation of Moments of Inertia) and determine M_1/M_2 .

If the magnets are similar in size and shape, and of the same density, $I_1 = I_2$.

EXPT. 202. Determination of the Ratio of the Magnetic Moments of two Magnets by allowing them to oscillate together.—Place the two



magnets together in a suitable stirrup (Fig. 214) with their north poles pointing in one direction. Suspend them from a thread from which the twist has been removed (p. 351), and allow them to swing inside an oscillation box in the earth's field.

Observe the period of swing in the usual way. Let this be T_1 .

Take out one magnet (the weaker ¹), and replace it in the stirrup with its axis reversed. Again take the period of swing T_2 .

The Moment of Inertia of the suspended system is not altered by reversing one of the magnets, but the magnetic moment ² of the system is in the first case equal to $M_1 + M_2$ and in the second case $M_1 - M_2$, M_1 being the magnetic moment of the magnet which is reversed.

$$\begin{aligned} \therefore \frac{T_1^2}{T_2^2} &= \frac{M_1 - M_2}{M_1 + M_2}, \\ \frac{M_1}{M_2} &= \frac{T_1^2 + T_2^2}{T_2^2 - T_1^2}. \end{aligned}$$

and hence

The student should prove these results for himself.

¹ The 'weaker' magnet can be found before the experiment by any rough means such as bringing the magnets in turn near to a compass needle — that having the smaller effect at the same distance is evidently the weaker.

² There is a tacit assumption made here that the magnetic moments of the two magnets are unaltered by their mutual action when in close proximity. This is not strictly accurate.

THE EARTH'S MAGNETIC FIELD

§ 1. SPECIFICATION OF THE FIELD

Three quantities are necessary in order to specify completely the magnetic field at any point, for any vector quantity can be determined if we know its magnitude and direction, and in three dimensions two quantities are required to fix a definite direction. The three quantities usually employed in defining the earth's magnetic field at any point are :—

- (1) The **Horizontal Component** of the magnetic force.
- (2) The **Declination**, that is the angle between the magnetic meridian and the geographical meridian.
- (3) The **Dip**, that is the angle between the direction of the resultant magnetic force and the horizontal plane.

We consider here only the first and third, since the determination of the Declination requires astronomical observations in finding the geographical meridian. So far as the magnetic observations are concerned, the principle involved is exactly that in the experiment already described for finding the magnetic axis of a magnet and the magnetic meridian (p. 334).

§ 2. DETERMINATION OF THE HORIZONTAL COMPONENT OF THE EARTH'S FIELD

The method to be described, which is due to Gauss, is employed usually to determine the horizontal component of the earth's field. It can be applied, however, to the determination of any magnetic field which is uniform throughout a sufficiently large volume.

The method involves two separate experiments, which of course must be done at the same place. The first consists in finding the period of swing of a freely suspended magnet of known Moment of Inertia ; and the second in comparing by means of a magnetometer the field due to this magnet with the earth's field.

Before beginning the experiments remove all iron objects from the neighbourhood.

(A) **The Oscillation Experiment.**—If T is the time of one complete

swing of the magnet, when oscillating freely in the earth's horizontal field


$$T = 2\pi \sqrt{\frac{I}{MH}}, \quad (\text{p. 128})$$

where H = Horizontal Component of the Earth's Field,
 M = Magnetic Moment of the Magnet,
 I = Moment of Inertia of the Magnet.

Hence
$$MH = \frac{4\pi^2 I}{T^2},$$

and thus MH can be calculated in C.G.S. units if I is known.

The bar is a regular geometrical shape, and hence its Moment of Inertia I can be calculated from its mass and dimensions. If the bar be rectangular, as is usually the case,



$$= m \frac{a^2 + b^2}{3},$$

where m is the mass of the magnet, and a and b are the half-lengths of that face of the magnet which

FIG. 215.—Rectangular Bar Magnet

was horizontal during the oscillations (Fig. 215).

For a bar of any regular shape the required expression for I can be found from the Appendix (p. 560).

EXPT. 203. Determination of MH .

—Before suspending the magnet be sure that the suspending fibre is not twisted. To ensure this, suspend in the stirrup a brass bar of the same mass as the magnet, and wait for the fibre to untwist. The motion of the brass bar must be checked every few revolutions, otherwise, when the fibre is untwisted, the inertia of the rotating brass bar will cause it to twist up in the opposite direction. When the brass bar remains motionless when hanging freely from the fibre, it should be withdrawn from the stirrup and the magnet inserted without allowing the fibre to twist again. The magnet is then suspended from the fibre in a box with glass sides so that the vibrations can be counted and yet air currents will be excluded (Fig. 216).

The magnet must be allowed to swing through only a very small angle.

Determine the period of vibration of the magnet by observing the time taken to make fifty complete vibrations.




FIG. 216.—Oscillation Magnetometer

Weigh the magnet, determine its length and breadth, and calculate its Moment of Inertia I .

Calculate the value of MH from the formula

$$MH = \frac{4\pi^2 I}{T^2}.$$

(B) **The Deflection Experiment.**—In the second part of the determination, the deflection produced by the *same* magnet on the needle of a magnetometer is observed.

The 'end-on' position is used, placing the magnet with its axis east and west, pointing to the centre of the magnetometer.

Let

$2l$ = distance between poles of magnet,

r = distance between the centres of magnetometer and magnet.

The force on unit magnetic pole at P is in the direction OP (Fig. 211) and is equal to F . As is proved in the chapter on Magnetometry (p. 343).

$$F = \frac{2Mr}{(r^2 - l^2)^2}.$$

The magnetometer needle comes to rest under the action of the two mutually perpendicular fields, F and H , in a position making an angle θ with the meridian, given by

$$\frac{F}{H} = \tan \theta.$$

$$\text{So} \quad \frac{M}{H} \times \frac{2r}{(r^2 - l^2)^2} = \tan \theta,$$

$$\text{or} \quad \frac{M}{H} = \frac{(r^2 - l^2)^2}{2r} \tan \theta.$$

Expt. 204. Determination of M/H .—Set up a magnetometer and place the magnet in the 'end-on' position as in Expt. 195. Determine the values of r , l , and θ , and calculate the value of M/H .

Note that $2l$ is the distance between the poles of the magnet used, while $2a$ is the distance between its ends. The poles are not exactly at the ends, so that these distances are not exactly equal. We may assume that the distance between the poles is $\frac{2}{3}$ of the distance between the ends of a bar magnet.

We have now found MH and M/H .

$$\text{Let} \quad MH = A$$

$$\text{and} \quad M/H = B.$$

$$\text{Then} \quad M^2 = AB, \text{ or } M = \sqrt{(AB)}$$

$$H^2 = \frac{A}{B}, \text{ or } H = \sqrt{\left(\frac{A}{B}\right)}.$$

Calculate M and H in C.G.S. electromagnetic units.

Intensity of Magnetisation.—The two experiments just described serve to determine the *two* unknown quantities M , the magnetic

moment of the magnet employed, and H , the horizontal component of the earth's magnetic field. Knowing the value of M we can calculate the *average* value of an important quantity known as the **Intensity of Magnetisation**, I , of the material of which the magnet is composed. This is found by dividing the magnetic moment of the magnet by the volume of the bar (in c.c.). If we suppose the bar to be uniformly magnetised, the magnetic moment of each unit cube having one set of its edges parallel to the direction of magnetisation would be the same whatever part of the body is chosen. Another way of defining I is to say that it is the pole strength per unit area (1 sq. cm.), the area being taken at right angles to the direction of magnetisation.

Measure the size of the bar magnet used in Expts. 203 and 204, calculate its volume V in c.c. and determine I from the equation $I = M/V$.

§ 3. DETERMINATION OF DIP

THE DIP CIRCLE

The **Dip Circle** consists of a vertical circle graduated in degrees, carrying at its centre a long needle pivoted on a horizontal pivot, so that it moves over the graduations of the vertical circular scale.

The scale and needle are enclosed in a box with glass sides, so that the needle is not affected by draughts. The whole box can be rotated about a vertical axis, the position of the box being indicated by a graduated circle on the base of the instrument.

To use the instrument, first it is levelled carefully to ensure that the central axis is vertical. The box is then rotated about this axis until the needle stands vertical. The plane of rotation of the needle is now exactly at right angles to the magnetic meridian. To bring it into the meridian, the box is rotated about the vertical axis through 90° , this being measured on the horizontal circle on the base of the instrument. The needle is now free to move anywhere in the magnetic meridian, and if perfectly constructed, it will take up a position along the earth's lines of force, and its inclination to the horizontal will be the angle of dip.

EXPT. 205. Determination of the Angle of Dip.—Level the instrument. Rotate the box until the needle is vertical, and take the reading on the horizontal circle. Rotate the box again till the reading is increased (or decreased) by 90° . The needle now sets with its axis inclined to the horizontal.

On account of possible slight imperfections in the construction of the needle, the adjustment of the vertical scale of degrees and so on, the angle of dip cannot be relied upon to be equal to the inclination of the needle, and the following series of observations must be made:—

1. Having got the vertical circle into the meridian, read the positions of both ends of the needle. This gives two readings.

2. Rotate the whole box 180° about the vertical axis and again read both ends ; this gives two more readings.

3. Remove the needle and replace it on the knife-edges supporting the pivot, but with the needle reversed back to front, so that the pivot is reversed end for end. Repeat readings 1 and 2, that is to say, read both ends and again rotate the whole box 180° about the vertical axis and again read both ends. This gives four more readings altogether.




FIG. 217 — Dip Circle

4. Remove the needle and remagnetise it with the magnetism reversed, and start at 1 again, repeating observations as 1, 2, and 3. This gives eight more readings or sixteen readings in all.

The mean of all these sixteen readings should be taken ; this is accurately equal to the Dip at the place where the experiment is performed.

For the theory of this experiment and a discussion of the types of errors avoided or corrected for by taking this series of observations, the student is referred to a text-book of theoretical physics.

Precautions in Use.—The needle must not be touched with the fingers, nor should it be brought anywhere where moisture can condense on it when being handled. It should be handled with the forceps supplied.

In placing it on the supporting knife-edges it must be put down gently—the pivot is glass-hard steel and is very brittle indeed ; the knife-edges are also very brittle, being made of agate. If raising-clips are fitted (as in a balance) the pivot must be raised from the knife-edges by these before removal from the box, and must be placed back on these before finally lowering to the knife-edges.

Care must be taken that the magnet is inserted with the proper end

dipping (north end downwards in northern hemisphere), otherwise it may revolve several times and roll off the end of the knife-edges.

In remagnetising the reverse way round, the magnet must not be rubbed with a magnet. If magnets are used, the needle must be fitted in a grooved piece of wood and the magnet moved over the wood surface in the requisite direction. A solenoid carrying a current is preferable to all other means of remagnetising the bar. This method is described on p. 373. The current is arranged to flow in the required direction, and is switched on and off once or twice while the needle is held inside the solenoid. Considerable force will be exerted on the needle in this process, and it must be held tightly in the forceps while being remagnetised; otherwise it may be pulled out of the forceps and receive damage in falling.

Treat the instrument throughout with the same care as that demanded in the use of an accurate balance.

The angle of dip may also be found by means of an Earth Inductor (Expt. 251).

PART V

ADDITIONAL EXERCISES ON MAGNETISM

1. Find the direction of the magnetic axis of a circular steel plate magnetised parallel to a diameter.

2. Make a survey of the laboratory, using a compass needle to determine the presence of north or south magnetism in iron pipes, girders, radiators, stoves, etc.

3. Plot the lines of force around one pole of a long bar magnet. Do the same when a piece of soft iron is placed not far from the pole.

4. Plot the lines of force between the opposite poles of two fixed magnets. Do the same when a piece of soft iron is placed in the space between the poles.

5. Adjust the given magnet so that the field produced by it may exactly neutralise the horizontal component of the earth's field at a marked point.

6. Place two long bar magnets in the magnetic meridian, with their north poles pointing in opposite directions and 16 cm. apart. Find the neutral point between them. Hence, neglecting the earth's field, compare their pole strengths.

7. Place the given bar magnet with its north pole pointing north, and find the neutral points in its vicinity. Carefully reverse the magnet, and show by means of an oscillating needle that the field at these points, with the magnet in this position, is twice as strong as the earth's field alone.

8. Magnetise the two given rods by placing them at the same time in a solenoid and passing a current through the solenoid. Then compare their magnetic moments. Repeat the experiment after heating the rods to redness and plunging them into cold water.

9. Plot a curve showing how the magnetic moment of the given electromagnet varies with the current passing through the coil.

10. Plot a curve showing how the intensity of the field of a magnet varies with distance along its axis, using a tangent magnetometer. Find the magnetic moment of the magnet. $H = 0.185$ C.G.S. unit.

11. Find how the intensity of the field of a magnet varies with distance along the axis, using an oscillating needle, and find the magnetic moment of the magnet. $H = 0.185$ C.G.S. unit.

12. Find the ratio of the magnetic moments of the two given bar magnets without using a third magnet.

13. Compare the horizontal components of the magnetic field at two marked points in the laboratory by using a magnetometer and the same bar magnet in each position.

14. Find the magnetic moment of the given magnet.

15. Place a short bar magnet in an oil bath so that its temperature may be varied. By means of a deflection magnetometer obtain a curve showing the relation between the magnetic moment of the magnet and the temperature, both when the temperature is rising and when it is falling.

PART VI

ELECTRICITY

NOTES ON ELECTRICITY

So long ago as 1834 Michael Faraday in his *Experimental Researches* anticipated later theories of the nature of chemical action when he wrote : ' Or, if we adopt the atomic theory or phraseology, then the atoms of bodies which are equivalents to each other in their ordinary chemical action, have equal quantities of electricity naturally associated with them.' According to the modern view (Rutherford and Bohr) a chemical atom is pictured as an extremely minute positive nucleus together with a number of surrounding negative electrons. Thus the nucleus represents the ' sun ' of a ' planetary system ' formed by these distant electrons. The proton is the nucleus of a normal hydrogen atom, consisting of a single proton and a single electron. A simplified picture of any other atomic nucleus is obtained by regarding it as built up of positive protons and a certain number of neutrons. The neutron is an electrically neutral particle, having a mass very nearly the same as that of a proton. In a neutral atom the number of electrons is equal to the number of protons in the nucleus—this number is called the atomic number Z . The total number of particles in the nucleus is called the mass number, A , and this is, to a close approximation, the chemical atomic weight of the element. In the Appendix (pp. 566-567) are given values of the atomic number, and the mass number for the elements from hydrogen to uranium and the notable trans-uranic elements neptunium and plutonium. It will be noticed that the Table is complicated by the existence of ' isotopes ', atoms having the same atomic number but different mass numbers (depending on the number of neutrons in the nucleus).

As a deduction from his theory of relativity Einstein concluded that mass and energy are equivalent. Any change in mass is associated with change in energy, and the converse also holds. In ordinary chemical changes such as the combustion of fuel, the change in mass is so very minute as to be beyond the possibility of measurement in the laboratory. But in nuclear disintegration the order of magnitude of the change is very different, and the process of ' nuclear fission ' that may occur in certain radioactive atoms may produce enormous amounts of energy.

CHAPTER I

ELECTROSTATIC EXPERIMENTS

§ 1. INTRODUCTORY

AMBER (Greek, *ēlektron*) is a fossilised vegetable resin, usually yellow in colour and transparent. It becomes electrified by friction, its power of attracting light particles being recorded by the Greeks. From the coasts of the Baltic and North Sea it was carried to all parts of Europe, being highly prized in antiquity for personal ornaments.

Other materials when rubbed with flannel, or silk, acquire the power of attracting light bodies. In this condition they are said to be electrified, or to carry a charge of electricity.

The electrification produced by rubbing a glass rod with silk differs from that produced by similarly rubbing a rod of ebonite. There are two kinds of electrification, vitreous (or positive) and resinous (or negative). Bodies electrified in the same way repel each other, while bodies oppositely electrified attract each other.

If a brass rod is held in the hand and rubbed with flannel no electrical charge can be detected on the rod. If, however, the rod is supported by a glass handle it becomes electrified negatively and the charge can be detected. These results may be explained by saying that the metal and the human body conduct away the electric charge, which passes through the body into the earth. The glass rod, if dry, does not conduct away the electric charge. Bodies which conduct well are called **conductors**; those which conduct badly are called **non-conductors** or **insulators**. Metals are good conductors, whilst glass and ebonite are good insulators under suitable conditions.

In all electrostatic experiments surface films of moisture on all insulators must be carefully avoided since such films are conductors of electricity. Continuous exposure to light may seriously impair the insulating properties of ebonite in consequence of the formation of an acid film.

Large specimens of amber are scarce, but by the compression of small fragments a material is obtained which has a very high insulation resistance and is but little affected by light. Ebonite or vulcanite is a form of hard rubber which has been treated with sulphur at high temperature. It varies greatly in its electrical properties; when of

good quality and highly polished it is an excellent insulator. It should be shielded from light as far as possible. For simple electrostatic experiments sticks of the best banker's sealing wax are useful. Some forms of the commercial plastic 'bakelite' have good insulating properties, and are used in the construction of electrical apparatus. Vitreous or positive electrification may usually be obtained from glass, but clean dry fused quartz (silica) is the best insulator known and should be used if possible. In a damp atmosphere apparatus for electrostatic experiments should be dried carefully by being placed at some little distance from an electric radiator, or by using a small tinplate oven with a double bottom, heated by a rose burner.

Electric charges are now attributed to the addition or removal of very minute particles of negative electricity, called negative electrons. An electric current in a metal is regarded as a flow of these electrons through the conductor. We shall, however, frequently adopt the older convention which supposed the current to flow from the positive (red) terminal of a cell or battery through an external resistance to the negative terminal.

§ 2. EXPERIMENTS WITH THE GOLD-LEAF ELECTROSCOPE

The gold-leaf electroscope is a convenient apparatus for experiments in electrostatics. A simple form of electroscope consists of a glass vessel with a brass rod passing through the insulating stopper. The top of the rod is fitted with a brass ball or disk, and a pair of gold leaves are attached to the lower end. If the leaves are given a charge the leaves will repel each other and diverge. If the insulation were perfect there would be no loss of charge and the leaves would remain inclined at the same angle indefinitely.

In modern forms of the electroscope, a single gold leaf is used, attached to a stiff strip of brass or aluminium (Fig. 219). The deflection of the gold leaf may be measured by means of a scale fixed to a mirror (to avoid any error due to parallax), or by means of a micrometer microscope.

EXPT. 206. Illustration of the Laws of Electrostatics.—I. Touch the disk of the electroscope with the finger so as to remove any charge it may possess. Electrify an ebonite rod by friction and bring it near to the disk. The gold leaves should diverge (A, Fig. 218). The charge on the ebonite induces a charge of opposite sign on the disk, and a charge of the same sign as that on the ebonite is repelled into the gold leaves.

Try the same experiment with a glass rod.

II. To show that there are two kinds of electrification, bring up an electrified ebonite rod as in the first experiment, then bring up an electrified glass or quartz rod. The presence of the second charge should diminish the effect due to the first. By suitably adjusting their distances (B) the two may be made to nullify each other's action.¹

¹ A glass rod sometimes shows a *negative* charge when rubbed, especially when the rubbing is violent or the rod has been passed through a flame.

III. The electroscope may be charged by conduction. The electrified rod is brought into contact with the disk of the instrument (C) and shares part of its charge with the gold leaves. These remain apart after the rod has been removed (D).

IV. To charge the electroscope by induction, bring the electrified rod near the disk without touching, then touch the disk with the finger for a moment (E). Remove the finger and afterwards withdraw the rod (F). The electroscope now bears a charge of the opposite kind to that on the rod, for when the finger touches the disk the charge of the same kind as that on the rod is repelled through the body into the earth.

V. To test the sign of a charge, charge the electroscope by induction as in the last experiment, using an ebonite rod. Then bring up a glass rod carrying a positive charge, and notice that the gold leaves diverge farther.

Next bring up the vulcanite rod; the leaves will now collapse, the divergence diminishing more and more as the rod gets nearer.

If the rod gets very close, it *may* cause the leaves to collapse entirely and then to open out again. It is left to the student to advance an explanation of this redivergence.

Now bring up a *large* uncharged body supported on an insulating handle. Then bring up an earth-connected body (the hand of the experimenter is suitable). Note that in *both* these cases the divergence of the leaves is diminished slightly although the bodies are not charged before being brought near the electroscope.

It will be seen from this that although *increased* divergence indicates a charge on the body of the same sign as that on the electroscope, we cannot conclude *with certainty* that *diminished* divergence indicates a charge of the opposite sign.

To test the sign of a charge of any kind it is necessary to have two electroscopes charged oppositely. The body to be tested is brought up to each in turn. A positively charged body gives an increased divergence with the positively charged electroscope, but a diminished divergence with the electroscope negatively charged.




FIG. 218.—Experiments with Gold-Leaf Electroscope

A negatively charged body increases the divergence of the negatively charged electroscope, but causes a diminished divergence in the positively charged one. An uncharged body or an earth-connected body causes the divergence to be diminished in each case.

§ 3. SIMPLE ELECTROSTATIC APPARATUS

THE ELECTROPHORUS

The **Electrophorus** consists of a plate of ebonite (or resin) supported by a sole-plate of metal. On this plate of insulating material can be placed a metal disk provided with an insulating handle.

When this disk is removed, a negative charge is produced upon the surface of the ebonite by rubbing or flicking it with a dry catskin. The metal disk is then lifted by the insulating handle and placed on the electrified surface. Actual contact occurs at only a few points, while over the rest of the surface the negative electrification on the ebonite induces a positive charge on the opposed metal surface, and a negative charge is repelled to the upper surface of the disk. On touching the disk with the finger this negative charge escapes through the body to the earth, leaving the positive charge 'bound' under the attraction of the negative charge below it. If the disk is now lifted from the ebonite, it carries with it this positive charge, which may be afterwards shared with some other conductor. When the disk has been discharged by connecting it to some earthed conductor, it may be placed once more on the ebonite, and the process repeated. The charge on the ebonite is not diminished appreciably in the operations, and if the insulation were perfect the process of charging could be repeated indefinitely. The same principle is employed in the Influence Machines designed by Voss and by Wimshurst.

EXPT. 207. The Electrophorus.—Charge an electrophorus, and use it to obtain a charge on the disk. Test the sign of the charge on the disk by the method described above. Show that it is possible to obtain sparks from the disk to any earthed conductor (for example the knuckle of the experimenter) placed near it.

FARADAY'S ICE-PAIL EXPERIMENTS

For these experiments a metal can is provided, which can be insulated by placing it on a block of paraffin or ebonite. If the electroscope is provided with a suitable flat plate connected with the gold-leaf system, it is simpler to stand the 'ice-pail' on this plate. If the can is on a block of ebonite or paraffin, then it should be connected by means of copper wire to the disk of the electroscope.

EXPT. 208. Faraday's Ice-Pail.—Take a brass ball suspended by a silk ribbon, or fitted with an insulating handle, and charge it by means of an electrophorus or a small Wimshurst machine.

Lower it into the ice-pail and observe the deflection of the gold leaf. If the charged ball is well within the mouth of the vessel, the deflection will be the same whatever the position of the ball. Even if the ball is allowed to touch the inside of the can the deflection will be unaltered.

This agrees with the view that a definite quantity of electricity has been introduced into the vessel, and that the effect on the electroscope depends only on the *quantity* inside the vessel.

We may make use of the ice-pail to determine whether two bodies are equally charged, and may then add together their charges (by placing them inside a hollow conductor) so as to obtain a charge double the original charge. In the same way we can give to the hollow conductor a charge which is any number of times the charge of a given body.

EXPT. 209. The Induced Charges are equal and opposite to the Inducing Charge if this is entirely enclosed by the Conductor on which the Charges are induced.—Place the charged ball inside the ice-pail without allowing it to touch the sides, and observe the deflection. Touch the ice-pail with the finger; the gold leaves will collapse. Remove the ball, still carrying its charge, from the pail. The deflection should be equal to the original one. The two charges induced were equal and opposite to each other; one has been removed, and the other gives the observed deflection. *Discharge the can* and reintroduce the ball, allowing it to touch the bottom. On removal it is quite uncharged; it has given all its charge to the can. The deflection of the leaves of the electroscope is the same after the ball touches the bottom as before it touches, and is not altered when the ball is removed.




FIG. 219.—Ice-Pail on Electroscope

EXPT. 210. Equal and Opposite Quantities of Electricity are produced by Friction.—To show this the rubber and the body rubbed must both be insulated. Rub the two bodies together, holding them by the insulating handles, and test each one by introducing it into the ice-pail. Then place the two together in the ice-pail. If the charges are exactly equal and opposite, no deflection of the gold leaves should be observed when *both* are used, but each *alone* gives a deflection.

The operations described must be performed quickly, as there is nearly always some leakage taking place.

In writing an account of these electrostatic experiments the results obtained should be described, and the conclusions drawn from them stated. It is important that the account should be illustrated by diagrams indicating the positions of *and charges on* all the pieces of apparatus used in each of the various stages.

§ 4. CHARGE AND POTENTIAL

Potential in electricity is analogous to *pressure* in hydrostatics, or to *temperature* in heat. We use the conventional statement that *positive* electricity tends to pass from places of *high* to places of *low* potential. It is often convenient to regard the potential of the earth as zero.

It is important to notice that the deflection of the leaves of an electroscope does not necessarily indicate the charge on the electroscope *as a whole*. The deflection indicates the *potential* of the electroscope always, and may be taken to indicate its *charge* only when there is no other body near to it.

Since positive electricity is said to flow from points at higher to points at lower potential if these points are connected by a conductor,

the test of potential is to connect the body to earth ; if the body *gives up* positive electricity to the earth (or receives negative from the earth) its potential was positive. If it *receives* positive from the earth (or gives up negative to the earth) its potential was negative. If it neither gains nor loses electricity, it was at zero potential.

EXPT. 211. Demonstration that the Divergence of a Gold-Leaf Electroscope indicates its Potential.—CASE 1. Bring a charged glass rod to an electroscope ; the electroscope has induced upon it two equal and opposite charges. It is *uncharged* on the whole, yet the leaves diverge. If earth-connected, positive electricity leaves the electroscope and goes to earth, therefore the electroscope was at a positive potential. *Before earth-connecting it*, it was showing a divergence, yet it was uncharged : therefore the divergence does not indicate the charge on the electroscope in this case.

CASE 2. Repeat the operation of bringing a charged glass rod to the electroscope. After earth-connecting the electroscope, keep the glass rod still near. The electroscope now has a negative charge. The leaves are, however, quite closed, therefore the divergence does not indicate the charge in this case — there is a considerable charge, yet no divergence.

CASE 3. Electrify an electroscope positively, and remove all bodies to a distance. The leaves diverge, the electroscope has a positive charge ; in this case, therefore, the divergence may be taken to indicate the charge.

Consider the potentials in the three cases.

CASE 1. As already explained, the electroscope had a positive potential though zero charge (on the whole). The leaves were diverging.

CASE 2. The electroscope had a zero potential (being earth-connected) although it had a charge. There was no divergence.

CASE 3. The electroscope has a positive potential as well as a positive charge.

Thus divergence and potential go together, and we see that the **divergence of the leaves of an electroscope indicates its potential**. It only indicates the charge *as well*, when the electroscope is remote from other bodies.

The divergence indicates only the magnitude, not the sign, of the potential ; the potential might be either positive or negative for a given divergence. This can only be tested by other means, namely—

Bringing up a positive conductor *raises* the potential of the electroscope. If, therefore, the leaves diverge further, the electroscope has a positive potential. If they collapse a little it had a negative potential ; *raising* the potential having in this latter case the meaning *diminishing its negative value*.

CAPACITY

When a charge is given to an isolated conductor, the resulting potential depends on the size and shape of the conductor : for the same charge, the larger the conductor the lower is the potential to which it is raised. The **Capacity** of a conductor is defined as the

charge required to raise its potential by one unit. When a second conductor is brought near the first, the potential of the first is diminished (p. 365). The effect depends on the size of the second conductor, and if this be earth-connected the effect is usually very large, being virtually equivalent to making the earth form part of the second conductor. Such an arrangement forms a **Condenser**, which may be defined as a system of conductors placed so that the capacity of one part of the system is increased in consequence of the proximity of the other part. The capacity of a condenser is measured by the charge required on the first part to increase the difference of potential between the two parts by one unit. Two parallel metal plates separated by an insulator or dielectric form a simple condenser. The capacity is proportional to the area of a plate and inversely proportional to the distance between them. It also depends on the dielectric constant, or specific inductive capacity, of the insulator.

EXPT. 212A. Examination of a Parallel Plate Condenser.—Use two vertical plates mounted on insulating supports. Connect one plate to the disk of an electroscope, and give it a charge (p. 365). Examine the effect of altering the distance separating the two plates, and of inserting a plate of insulating material between them. Repeat these experiments after having connected the second plate to earth.

More advanced experiments on condensers are given in later chapters.

THE CONDENSING ELECTROSCOPE

The condensing electroscope is an ordinary gold-leaf electroscope fitted with a disk of a size rather larger than usual. A second disk of the same size, and mounted on an insulating handle, is laid on the first disk. The disks are insulated from each other by a thin coat of insulating varnish spread over the upper disk. The two disks constitute a parallel plate condenser, and when the upper disk is earth-connected the electroscope becomes a conductor of considerable capacity: a considerable charge is now required to raise the potential of the electroscope to *unit* potential. If, therefore, the electroscope is connected to any apparatus which is maintained at a constant potential, it will take up a charge much greater than it would take up if the earth-connected disk were not upon it.

It may happen that the potential to which it is thus raised is insufficient to cause an appreciable divergence of the leaves, and the existence of this electric potential would be undetected by the electroscope when used in the ordinary way.

If, however, we charge up the condensing electroscope while the upper disk is present, we obtain on the electroscope a charge of considerable magnitude, though the potential is too low to affect the

leaves. On removing the wire connected to the electroscope disk, and immediately afterwards removing the earth-connected disk from the electroscope, the electroscope becomes a conductor of small capacity. A charge which gave it a certain potential before will now give it a potential a great many times larger. Consequently the leaves may be caused to diverge now by the charge on the electroscope, although the same charge was insufficient to affect the leaves when the capacity was greater.

EXPT. 212B. Use of a Condensing Electroscope to detect the Positive and Negative Poles of a Cell.—Remove the upper disk from the electroscope, and touch the cap with a wire connected with one pole of any Voltaic cell, the other pole being earth-connected. Notice that no divergence can be observed.

Place the insulated disk on the electroscope disk and again touch the cap with the wire, the upper disk being earth-connected while the wire is touching the electroscope. Remove the wire — no divergence is observed ; remove the upper disk — the leaves open out slightly owing to the larger potential produced by the *same* charge, now that the capacity of the electroscope has been diminished.

Test the sign of the charge, using an ebonite rod.

Repeat the experiment with the other pole of the cell, meantime earth-connecting the pole previously used. Show that the charges obtained from the two poles of the cell are *opposite* in character, and that the *zinc plate* is negative in all cells in which a zinc plate is used.

Test the signs of the poles of an accumulator to see if they are correctly marked.

CURRENT ELECTRICITY—INTRODUCTORY


§ 1. CHEMICAL GENERATION OF ELECTRICITY

It can be shown by means of a condensing electroscope that when two plates of any two different metals are immersed in the same vessel of almost any liquid, one plate will acquire a higher potential than the other. When these two plates are connected *momentarily* by a wire, an electric charge naturally flows from one plate to the other in consequence of their difference of potential, but the two plates are not *discharged* as a result of this. If the wire connecting them is removed, and the plates are again tested, they will be found to give a potential difference as before, the electroscope usually being insufficiently sensitive to detect any slight difference which may exist between the present and former values of this potential difference (P.D.).

Thus when the plates are placed in this liquid, there is a continual renewal of the charges on them, as a result of the chemical action in the cell. If a wire is connected permanently to the two poles, a *continuous* discharge or a **current of electricity** flows through the wire. Although we now regard the electric current in a metal as a **flow of negative electrons**, we shall still speak of the **conventional current** as a **flow of positive electricity**.

By experimenting with various forms of solutions and different kinds of plates, certain specially active cells have been invented by different experimenters.

In the simple cell of Volta, plates of copper and zinc are immersed in dilute sulphuric acid (1 in 10). The zinc plate tends to dissolve in the acid in accordance with the equation



This is typical of the action in other primary cells.

To prevent the **polarisation** (p. 398) of the cell due to the film of hydrogen formed at the copper plate, some depolarising liquid may be employed.

The **electromotive force** of a cell is equal to the energy drawn from the source and dissipated in the circuit when unit quantity of electricity flows round the circuit.

The practical unit for expressing electromotive force (E.M.F.) or P.D. is the **Volt**, which is 10^8 C.G.S. units. The **International Volt** is realised experimentally by taking the E.M.F. of the Weston cadmium cell as 1.0183 international volts at 20°C . The E.M.F. of the Clark cell is 1.433 volts at 15°C .

TABULATED DESCRIPTION OF SOME PRIMARY CELLS

Name	Plates	Exciting Liquid	Depolarising Liquid	Approximate E.M.F. in Volts	Remarks
Simple	+ Cu, Zn	H_2SO_4 , Aq.	None	1.0	Rapid polarisation
Daniell	Cu, Zn	H_2SO_4 , Aq.	CuSO_4 concentrated	1.14	Constant, satisfactory
Grove	Pt, Zn	ZnSO_4 , Aq.	CuSO_4 concentrated	1.07	No acid fumes
		H_2SO_4 , Aq.	HNO_3 concentrated	1.9	Expensive, acid fumes
Bunsen	C, Zn	H_2SO_4 , Aq.	HNO_3 concentrated	1.7	Acid fumes
Leclanché	C, Zn	NH_4Cl , satd.	MnO_2	1.4	Good for intermittent use
Bichromate	C, Zn	H_2SO_4 , Aq.	H_2CrO_4 from $\text{K}_2\text{Cr}_2\text{O}_7$	1.8	Satisfactory. Withdraw Zn plate when not in use
Clark	Hg, Zn	ZnSO_4	Hg_2SO_4	1.433	Constant
Weston	Hg, Cd	CdSO_4	Hg_2SO_4	1.0183	Very constant

The so-called 'dry cell' is a form of the Leclanché cell in which the solution is mixed with other materials to form a *moist* paste.

Care of Cells.—The power of a cell, or the rate at which it can supply current, is limited by the size of the plates, by the rate at which the necessary chemical actions can take place, and by other properties such as **internal resistance**, which will be discussed in Chapter IV. If a primary cell is overworked by *short-circuiting*, or by connecting the poles together by a short piece of metal even for a moment, it will be more or less *run-down* or *polarised*, and will not work satisfactorily for some minutes, if indeed it is not damaged permanently.

It is therefore important to avoid overworking any cell in this way, especially a secondary cell or lead accumulator. This accumulator is made of plates of lead loaded with spongy lead on one plate and with lead peroxide on the other (see p. 405). Any *momentary* overload causes very rapid evolution of gas *inside* the plates as well as at the surface, and the plates buckle, or the loading is blown out from the plate. This means that the accumulator is severely damaged, and if the process is repeated may be ruined entirely. It is mere childish folly to ruin these expensive cells and thereby diminish the efficiency of the laboratory for the sake of seeing a momentary flash.

In connecting up any electric circuit a good rule to adopt is to make the connection to the source of supply, whether it be a cell, a battery or the electric mains, **LAST OF ALL**.

§ 2. THE MAGNETIC ACTION OF ELECTRIC CURRENTS

In 1819, Oersted discovered that a magnetic needle was deflected when placed near a wire carrying an electric current. The magnet tends to set itself with its axis at right angles to the direction of the current. The current gives rise to a magnetic field in the surrounding space. In the case of a long straight wire the lines of magnetic force take the form of circles. The centre of each circle is a point in the wire, and the plane of the circle is perpendicular to the wire.

Suppose the wire is at right angles to the plane of the paper and that the *conventional* current is flowing *into* the paper at the point A. Then a positive pole would be urged round a circle, centre A, in the clockwise direction. A convenient way of expressing this result is to say that if a right-handed corkscrew is screwed so that its point travels in the direction of the *conventional* current, the direction in which it is turned (or the direction in which the thumb moves) gives the direction of the magnetic force.




FIG. 220.—Lines of Force due to Current

This result should be tested by examining the action of a current on a small compass needle. Connect the ends of an insulated copper wire to the terminals of a battery composed of one or two Daniell cells, and observe the deflection produced when the wire is placed in different positions with relation to the magnetic needle. Verify the fact that when the wire is doubled on itself, or twisted together so that the currents in neighbouring portions are in opposite directions, little effect is produced on the compass needle.

Magnetic Field of a Solenoid.—A solenoid is a spiral of wire having many turns wound uniformly and close together. When a steady current passes through it an external magnetic field is produced similar to that due to a bar magnet, and an internal field that is nearly uniform provided the turns are very near together. Wind a spiral of insulated wire on a glass tube about 15 cm. long and 1 cm. in diameter. Connect the ends of the spiral to the terminals of an accumulator, using a rough resistance of about 5 ohms and a commutator. Examine the action of the ends of the spiral on a small compass needle. Repeat the experiment after inserting a number of iron wires in the inside of the tube.

EXPT. 213. Construction of a Simple Electromagnet.—Wind an insulated copper wire round a bar of soft iron so as to form a spiral winding round the bar. Connect the ends of the wire through a commutator and a resistance of 5 ohms (as above) to an accumulator. The iron will be magnetised by the magnetic field due to the current, and the system forms an **electromagnet**. If a corkscrew were turned so that the thumb

followed the direction of the current round the turns of the spiral, the point of the corkscrew would advance in the direction of the lines of magnetic force. The lines of magnetic force run through the iron bar from the S. pole to the N., consequently the end where the point of the screw would enter the iron is the S. pole, and the end where the point of the screw would emerge is the N. pole. Test this result with the compass needle and examine




FIG. 221.—Construction of Electromagnet

the power of the electromagnet of attracting small pieces of iron.

Testing the Sign of Battery Poles.—The foregoing results may be applied in order to determine the signs of the poles of a battery or other source of current, taking proper precautions to avoid excessive current through the length of wire connected to the terminals. Remembering that the current is said to flow from the + terminal through the external circuit to the - terminal, the sign of each terminal can immediately be given.

The signs of the terminals can also be determined by examining the chemical actions produced by the current (p. 432 and pp. 490-491).

§ 3. THE MAGNETIC FIELD DUE TO AN ELECTRIC CURRENT IN A STRAIGHT WIRE

It has been pointed out above that the lines of magnetic force due to a current in a long straight wire are in the form of circles. Each circle has its centre at a point on the wire, and the plane of the circle is perpendicular to the wire. The direction of the circle is perpendicular to the wire. The direction of the magnetic force round the circle, and the direction of the conventional current, are related in the same way as the directions of rotation and translation of a right-handed screw.

At a point where the length of the perpendicular drawn to the wire is r , the value of the magnetic force is $2I/r$, where I is the current strength in electromagnetic units.

For a definition of the electromagnetic unit of current see the theory of the tangent galvanometer (p. 381).

In an actual experiment we have to consider the magnetic field of the earth as well as the field due to the current. It is convenient to arrange for the wire to be vertical and, ignoring the vertical component of the earth's field since this has no effect on a horizontal needle, to trace lines of magnetic force in a horizontal plane.

The lines of force may be traced by means of a small compass in the same way as the lines of force due to a permanent magnet are traced.

EXPR. 214. Plotting the Magnetic Field of a Straight Current.—A convenient apparatus consists of a large rectangular framework with a




FIG. 222.—Magnetic Force due to Straight Current

covered copper wire passing several times round the frame so as to multiply the magnetic effect of the current (Fig. 223). One end of this wire is joined to one terminal of a small accumulator, the other to a key. The electric circuit is completed by connecting the other terminal of the accumulator to the key with a short length of platinoid wire. If direct




FIG. 223.—Field of Straight Current

current is used for lighting the laboratory, the current may be taken from the mains, using a lamp in series with the apparatus to adjust the strength of the current (p. 490).

Place the frame with the vertical sides close to the edge of a table and arrange the horizontal drawing board so that it rests securely on the table.

Trace the lines of force due to the combined fields when the current is flowing either downwards or upwards. Pay special attention to the lines of force (1) close to the coil and (2) near the 'neutral' point.

Having found the position of the neutral point as accurately as possible, measure the distance r from this point to the wire.

At a distance r cm. from the wire the magnetic force due to the current is

$$F = 2nI \text{ dyne per unit pole,}$$

where n is the number of wires down the side used, each wire carrying the same steady current, I electromagnetic units.

This magnetic force is balanced by the horizontal component of the earth's field, a typical value being $H = 0.18$ dyne per unit pole.

Hence

$$\frac{2nI}{r} = 0.18.$$

Calculate the value of I , the current in electromagnetic units, and deduce the value in amperes (one electromagnetic unit is equal to 10 amperes).

VARIATION OF THE STRENGTH OF THE MAGNETIC FIELD CLOSE TO A CURRENT FLOWING IN A STRAIGHT WIRE

It has been stated already (p. 374) that the strength of the magnetic field due to a current in a long straight wire is given by $F = 2I/r$ at a point distant r from the wire.

It is possible to show that F is inversely proportional to the distance from the wire by either of the methods previously described for comparing the strengths of magnetic fields.

EXPT. 215. Variation of the Strength of the Magnetic Field due to a Straight Current using a Magnetometer.—Place the wire vertically as in the previous experiment, and draw a horizontal line passing through the wire in the direction of the magnetic meridian. At some distance r from the wire along this line place a magnetometer, and note the deflection θ produced in the magnetometer when the current is flowing in the wire. Do this at various distances from the wire, and arrange a table showing corresponding values of r , θ , $\tan \theta$, and $r \tan \theta$.

The field due to the current is east and west at any point north or south of the wire, and hence the strength of the field is proportional to $\tan \theta$. The last column, $r \tan \theta$, will be found constant, and hence $\tan \theta$, or F , is proportional to $1/r$.

EXPT. 216. Variation of the Strength of a Magnetic Field due to a Straight Current by plotting Lines of Force.—This method is virtually the same as that of Expt. 215. Instead of using a magnetometer to observe the deflections at different points along the north and south line drawn through the wire, the field is plotted at different points where it crosses this line, using a compass needle for this purpose. The tangent to the line of force where it crosses the north and south line is drawn, and the angle between this tangent and the north and south line is the angle θ .

This is measured with a protractor, and a table drawn up as in Expt. 215.

Suitable distances are 5, 6, 7, 8, 10, 12, 15, and 20 cm. from the wire.

The Method of Oscillations.—Imagine a line passing magnetic east and west to be drawn through a vertical wire carrying a current. The field F due to the current in the wire at any point in this line is either due north or south; hence on one side of the wire the strength of the total field will be $F + H_0$, while on the other side it will be the difference between F and H_0 , H_0 being the horizontal component of the earth's field.

A short heavy needle (p. 347) could be placed at some point on this east and west line, and its period of swing observed before switching on the current, that is the period of the needle could be found in the earth's field alone. Let this period be T_0 , and C the constant $4\pi^2 I/M$ (p. 347).

$$\text{Then} \quad H_0 T_0^2 = C, \quad \text{or} \quad H_0 = C/T_0^2.$$

If the current were switched on, the behaviour of the needle would depend on its position and also on the direction of the current. On

one side of the wire it would start to swing more rapidly than in the earth's field alone, and with its poles pointing in the same direction as at first. On this side, the field of the current and the field of the earth assist each other. On the other side the two fields are in opposition, and the swings would be slower than in the earth's field, or the needle might be reversed. If H_0 is stronger than F the needle swings less rapidly, but if F is stronger than H_0 it is turned completely round.

It is important that the needle should be used on the side where the fields assist each other: in very weak fields the torsion of the fibre has a greater percentage effect than in stronger fields, and as we take no account of the torsion, the error due to it is correspondingly increased. In the following discussion it will be assumed that the needle is placed on the side where the fields assist each other.

The strength of the composite field at any point being H , and the period T , we have

$$H = F + H_0, \quad \text{and also} \quad H = C/T^2.$$

$$\text{Hence} \quad F = H - H_0 = C \left\{ \frac{1}{T^2} - \frac{1}{T_0^2} \right\}.$$

Now if F is proportional to $1/r$, we shall have $F_1 r_1 = F_2 r_2 = F_3 r_3$, etc., taking F_1, F_2, F_3 , etc., as the strengths of the field at distances r_1, r_2, r_3 , etc., from the wire.

If the corresponding periods of oscillation are T_1, T_2, T_3 , etc., we can write

$$F_1 = C \left\{ \frac{1}{T_1^2} - \frac{1}{T_0^2} \right\}, \quad F_2 = C \left\{ \frac{1}{T_2^2} - \frac{1}{T_0^2} \right\}, \quad \text{etc.},$$

and therefore we can show that $F_1 r_1 = F_2 r_2$, etc., provided we show that

$$\left\{ \frac{1}{T_1^2} - \frac{1}{T_0^2} \right\} r_1 = C \left\{ \frac{1}{T_2^2} - \frac{1}{T_0^2} \right\} r_2 = \text{etc.}$$

The constant C occurs in each expression, and therefore can be cancelled throughout, and we shall have proved F proportional to $\frac{1}{r}$ if we show that $r \left\{ \frac{1}{T^2} - \frac{1}{T_0^2} \right\}$ is constant.

EXPT. 217. Variation of the Strength of the Magnetic Field due to a Straight Current by the Method of Oscillations.—Place the wire in a vertical position; draw a line passing magnetic east and west through the wire, and measure off different distances along the line, say 5, 6, 7, 8, 10, 12, 15, and 20 cm. from the wire.

Place a small oscillating needle (p. 347) at some point on the line and determine its period of oscillation *before* switching on the current. Call this T_0 .

Switch on the current, observing the behaviour of the needle when this is done. If the needle swings *more rapidly than before*, and still points in the same direction, the experiment may be proceeded with; *if not, reverse the direction of the current* through the wire, when the needle will be found to point as in the earth's field alone, but will swing *more rapidly*.

The needle is now oscillating in a field of strength H , which is the sum of the strength of the field F due to the wire, and the horizontal component of the earth's field H_0 .

Place the needle at each of the points marked along the east and west line on this side of the wire where the two fields assist each other. Observe the period of oscillation in each position.

Arrange the results of the observations as follows :—

Period of needle in earth's field, $T_0 = \dots$ sec.

1

Distance from wire in cm. r	Period of needle in sec. T	$\frac{1}{T^2}$	$\frac{1}{T^2} - \frac{1}{T_0^2}$	$r \left\{ \frac{1}{T^2} - \frac{1}{T_0^2} \right\}$
5				
6				
7				
8				
10				
15				
20				

The last column will be found to be constant, thus showing that the magnetic force due to a current in a long straight wire varies inversely as the distance from the wire.

§ 4. THE MAGNETIC FIELD DUE TO A CIRCULAR COIL CARRYING AN ELECTRIC CURRENT

It has been shown that an electric current sets up a magnetic field in the surrounding space. An important case is that of a circular coil of wire carrying an electric current. The lines of magnetic force at all points in the plane of the coil are perpendicular to that plane. At any such point *inside* the circular boundary the direction of the line of magnetic force is related to the direction of the conventional current in the same way as the direction of translation to the direction of rotation of a right-handed screw (Fig. 224).




FIG. 224.—Magnetic Force due to Circular Current

EXPT. 218. Plotting the Magnetic Field of a Circular Coil carrying a Current.—A convenient apparatus for this experiment consists of a circular coil fixed with its plane vertical at the centre of a horizontal board. The board is raised from the bench so that its plane cuts the coil across a horizontal diameter. Drawing-paper is fixed down to the board with pins, a slot being cut in the paper to allow it to pass over the top of the coil, and the lines of force near to the coil are traced with a compass-needle in the same way as the lines of force due to a permanent magnet are traced.

The lines of force will not represent the field of the coil *alone*, but the composite field due to the coil and the earth. The coil may be placed in *two* positions: (a) with its plane at right angles to the magnetic meridian, (b) with its plane in the magnetic meridian.

Send a current through it from some *constant* source of current, adjusting the current by means of suitable resistances to a convenient value.¹ Trace the lines of force when the current is flowing round the coil, paying special attention to the lines of force (1) close to the coil and (2) near the neutral points.

EXPT. 219. Variation of the Strength of the Magnetic Field due to a Circular Coil with the Distance along the Axis.

(i) **By plotting Lines of Force.**—If in the foregoing experiment the coil is placed with its plane in the magnetic meridian, the field due to the coil at all points along its axis will be east and west. The actual field is compounded of the field of the coil and the horizontal component of the earth's field, and therefore the lines of force at points along the axis will *not* be exactly east and west, but will be inclined to this direction at greater and greater angles as the distance from the coil is increased.

Find the angle between the lines of force and the magnetic north at several points along the axis of the coil, by tracing the lines for a short distance as they cross the axis at these points. Choose the points at the distances from the coil indicated in the first column of the following table. If the angle between the line of force and the magnetic north is θ , the strength of the field F due to the coil is proportional to $\tan \theta$.

Tabulate the results as below:—

Distance from Coil along Axis	θ	$\tan \theta$
7.5 cm.		
10		
12.5		
15		
20		
25 and 30		

Plot a curve showing the variation of $\tan \theta$ with distance. This indicates the way in which F varies with the distance along the axis.

(ii) **By use of a Magnetometer which can slide along the Axis.**—A convenient type of apparatus to use for this purpose is a tangent galvanometer of the Stewart and Gee pattern (Fig. 225). Set up the coil with its plane vertical and parallel to the meridian, using the needle of the magnetometer to make this adjustment.

Consult Expt. 220 and Fig. 227 for details of the connections to be made. An accumulator may be used provided the resistance in series with it is a sliding rheostat (*not* a box) and has a value of *at least* 5 ohms. Long leads are required between the galvanometer and the commutator.

Send round the *thin* wire coil a current sufficient to give a deflection of 75° or 80° when the magnetometer needle is exactly in the plane of

¹ Accumulators may be used if proper precautions are taken. Current from the lighting mains (with a fuse in circuit) can be used conveniently for this experiment wherever direct current is supplied; a lamp resistance suitable for adjusting the current to the required value is described on p. 490.

the coil; keep this current constant. Slide the magnetometer box along the axis by steps of 1 cm., and note the reading of the magneto-




FIG. 225. Stewart and Gee Tangent Galvanometer

meter at each distance. Continue this motion as far as the apparatus will allow, or until the deflection is reduced to 5° .

Repeat the measurements on the other side of the coil.

Tabulate the results as below :—

Distance along Axis d	Deflection One Side (θ_1)	Deflection Other Side (θ_2)	$\tan \theta_1$	$\tan \theta_2$

Plot a curve showing the variation of $\tan \theta$ on *both sides* of the coil. This curve should be symmetrical and should have a maximum value when the needle is at the centre of the coil itself.

This method is preferable to the method (i) where the field is plotted, as it enables the readings to be carried on right up to and *through* the middle of the coil. Method (i) must perforce stop near the plane of the coil (unless the centre is cut out), and the measurements near to the coil are not very accurate owing to the rapid curving of the lines thereabouts.

CHAPTER III

APPARATUS FOR THE MEASUREMENT OF CURRENT

§ 1. THE TANGENT GALVANOMETER

A **galvanometer** is an instrument for measuring the strength of an electric current. By means of the tangent galvanometer we can measure the strength of a current in **absolute electromagnetic units** (C.G.S. units, defined below). Since one **ampere**, the practical unit of current strength, is defined as one-tenth of the C.G.S. unit of current, it is then possible to express the strength of the current in terms of the ampere.

The tangent galvanometer is said to be an **absolute instrument**, because its indications can be reduced to give the value of the current in absolute units, based on the units of length, mass, and time. As it is designed on lines derived by theory *its indications cannot be wrong, provided the conditions demanded by theory are satisfied*. The tangent galvanometer is one of the **standard instruments for the measurement of current**, and the calibration of all other forms of current meter can be made using a tangent galvanometer as the standard.

THEORY OF THE TANGENT GALVANOMETER

The C.G.S. unit of current may be defined as that current which flowing through a wire 1 cm. long bent into an arc of a circle of 1 cm. radius produces a force of 1 dyne on unit magnetic pole at the centre.

If a current of I units be flowing through l cm. of wire bent into an arc of r cm. radius, the magnetic force F at the centre is proportional to l and inversely proportional to r^2 .

$$F = \frac{Il}{r^2} \text{ dyne per unit pole.}$$

The direction of the force is perpendicular to the plane of the circle, and is related to the direction of the current as is the direction of translation to the direction of rotation in a right-handed corkscrew (Fig. 224).

If the wire forms one complete circle, $l = 2\pi r$, hence

$$F = \frac{2\pi r}{r^2} \times I = \frac{2\pi I}{r} \text{ dyne per unit pole.}$$

For a circular coil containing n turns, the force is n times this.

In the simplest form of tangent galvanometer a circular coil is placed *with its plane in the magnetic meridian* so that when a current flows




FIG. 226.—Tangent Galvanometer

AA, circular frame carrying vertical coil or coils, CC
 BB, base provided with levelling screws
 MM, magnetometer box containing magnet NS and pointer

through the coil the magnetic force due to it is at right angles to the meridian. A magnetometer is placed at the centre of the coil, the needle of which is acted on by this force F and by the horizontal component H of the earth's field (Fig. 226).

These fields being mutually perpendicular, the needle will be deflected from the direction of the earth's field through an angle θ such that $F = H \tan \theta$, see p. 338.

If the galvanometer coil consists of n turns,

$$F = \frac{2\pi n I}{r}.$$

But, since

$$F = H \tan \theta,$$

we obtain $\frac{2\pi n I}{r} = H \tan \theta$, or $I = \frac{Hr}{2\pi n} \tan \theta$.

Since H can be measured in C.G.S. units (p. 355), this equation gives the current I in terms of quantities which can all be expressed in C.G.S. units.

The form of the tangent galvanometer is sometimes more complicated. In the general case $F = GI$, where G is called the **galvanometer constant**.

If I is unity, $G = F$, or the galvanometer constant is numerically equal to the strength of the magnetic field at the centre of the coil when unit current is flowing through it.

Then
$$I = \frac{H}{G} \tan \theta, \text{ or } I = K \tan \theta,$$

where K is called the reduction factor, or simply the factor,¹ of the galvanometer.

When $\theta = 45^\circ$, $\tan \theta = 1$, and $I = K$, or the reduction factor is numerically equal to the current required to produce a deflection of 45° .

EXPT. 220. To set up a Tangent Galvanometer and to measure a Current in Absolute Units.—Examine the instrument provided noting any particulars supplied as to the coil or coils. Make a *rough* estimate of the galvanometer constant, G , and the reduction factor K , so as to find the current in amperes that would give a deflection of 45° . For the present experiment a coil corresponding to *about* 0.05 ampere would be suitable. Place the galvanometer in such a position that the pointer of the needle in the magnetometer box at the centre of the coil lies along the *zero line* of the magnetometer scale. If the instrument is properly designed and correctly made, the coil will now be exactly over the needle, the plane of the coil being therefore in the magnetic meridian.

In some forms of tangent galvanometer the magnetometer box has no arrangement fitted whereby it can be fixed relatively to the coil. In this case, before anything else is done, the zero line must be set as accurately as may be along the axis of the coil, and care must be taken to prevent it from being moved during the experiment. The adjustment given above must next be made.

Adjust the level of the instrument so that the needle swings freely. Make the connections shown in Fig. 227, a single Daniell cell B being




FIG. 227.—Connections for Tangent Galvanometer

connected *last of all*. R is a resistance of *about* 20 ohms; TT are long flexible leads (*twin flex*). Send a current through the selected coil of the instrument, adjusting the resistance in series so as to give a deflection between 30° and 50° . Use a commutator K to reverse the direction of the current. Read both ends of the needle, with the current flowing first in one direction then in the other. Measure the radius of the coil as accurately as possible and count the number of turns through which the current was flowing. Calculate the strength of the current in absolute units, and also in amperes.

NOTE.—For descriptions of Commutators and Resistors, see the chapter 'Notes on Electrical Apparatus' (pp. 484-490).

¹ Some writers call K the constant of the galvanometer. As K is not constant this cannot be recommended.

§ 2. AMMETERS

The tangent galvanometer determines the *absolute* value of the strength of an electric current, but its use for practical current measurement is inconvenient. Two of the most important objections to its use are—

(a) The deflection of the needle is not proportional to the current.

(b) The deflection for a given current depends on the external magnetic field H .

The first difficulty can be got over by graduating the scale so that the readings are proportional to the tangents instead of proportional to the angles.

The second objection is more serious. Any instrument in which the determination depends on an external magnetic field is unsuited for use in the neighbourhood of large masses of iron, while in such places as Electric Supply Stations it cannot be used at all, owing to the enormous *variable* fields set up by the working of dynamos and other electrical machinery. Further, great inconvenience attends the use of the tangent galvanometer because it must be placed in a definite position relative to the field and cannot be used in any other position.

The **ampere** is one-tenth of the electromagnetic C.G.S. unit of current. Other units are the **milli-ampere** (10^{-3} ampere) and the **micro-ampere** (10^{-6} ampere).

Instruments arranged so as to secure *direct* readings of the strength of a current in amperes (or multiples or sub-multiples of an ampere) are usually called *ampere-meters*, or, as the word is usually contracted, **ammeters**. These ammeters are designed in various ways: some depend on the elongation of a wire due to the heating effect of the current flowing through it; others on the attraction, or mutual turning effect, between two coils carrying the current; but the majority depend on the rotation of a small coil carrying a definite fraction of the current when placed in the strong magnetic field between the poles of a permanent magnet.

THE MOVING-COIL AMMETER

This instrument is very important, but to understand its action requires a greater knowledge of the subject than the student at this stage is supposed to possess. This lack of knowledge need not prevent its *use*, however, as the method of using it is so simple. A description of the apparatus is given in a later chapter (p. 482).

THE ATTRACTED IRON AMMETER

A form of ammeter simple to understand is the **Attracted Iron Ammeter**. This is described briefly on p. 481.

In the simplest form of attracted iron ammeter¹ there is suspended from a spiral spring a bar of iron, whose lower end just enters a long coil, or solenoid, of wire.

When a current passes round this coil, the iron bar is magnetised and is attracted some distance into the coil. The amount of motion which takes place depends on the force of attraction and the stiffness of the spring. The iron moves down until the attracting force is just equalised by the extra tension of the spring due to its elongation.

Now for a given current there is a definite pull exerted on the iron by the coil, and therefore the spring will always stretch to the same amount when this current passes round the coil. The relation between the pull on the iron and the current in the coil is, however, not simple by any means; in fact, no single law which would apply to every case could be given to express this relation. The instrument thus differs from the tangent galvanometer in that the relation between *extension* and *current* is *empirical*, or can be found only by trial, while the tangent relation between the deflection and current in a tangent galvanometer can be predicted from theoretical considerations.




FIG. 228.—Attracted Iron Ammeter

EXPT. 221. Calibration of an Attracted Iron Ammeter.—Set up a tangent galvanometer for use

(p. 383). Connect in series with it through a reversing key, the ammeter to be calibrated, a rough regulating resistance (with a length of bare platinoid wire to give closer adjustment if required), and a cell capable of supplying large currents. Use the *thick* wire turns of the galvanometer. The connections are as in Fig. 229. The cell is to be connected *last* of all.

An ordinary resistance box must not on any account be used in this experiment: the large currents used would completely ruin the coils.




FIG. 229. Calibration of an Ammeter

- A, ammeter reading to 3 or 5 amperes
- R, resistance of about 6 to 7 ohms
- B, 2-volt accumulator
- G, tangent galvanometer
- K, reversing switch

Both the ammeter and the regulating resistance must be kept as far as possible from the tangent galvanometer, so as to diminish the effect

¹ In Fig. 228 a graduated spring-balance is shown. An alternative plan is to use a long spiral spring calibrated as in Expt. 54. Smaller currents can then be used.

of the magnetic fields due to them on the needle of the galvanometer. The wires leading to the tangent galvanometer should be twisted together so that the magnetic field due to one may neutralise that due to the other. *Twin* flexible connections are very useful in this case.

Observe the reading of the pointer of the spring balance and of the needle of the galvanometer when a current is passing round the circuit.

Repeat the observations for different values of the current, choosing values which will give deflections of the galvanometer increasing by approximately 5° at a time.

Determine the number of turns (usually one or two in this experiment) in the coil of the galvanometer, and the radius of the coil. The value of H , the horizontal component of the earth's magnetic field, can be found by the method described in the magnetism course (p. 355).

The expression for the current in absolute units (p. 382) is

$$I = \frac{rH}{2\pi n} \tan \theta,$$

or in amperes

$$I \text{ (amp.)} = \frac{5rH}{\pi n} \tan \theta.$$

The results should be arranged in tabular form under the headings :—

Ammeter Reading	$\tan \theta$	I (amp.)
-----------------	---------------	----------

Plot a curve showing ammeter readings as abscissae, and currents as ordinates. This curve can then be used at any time to reduce ammeter readings to currents in amperes.

Any form of ammeter or milliammeter may be calibrated by the method just described provided due care is taken in selecting suitable resistances and suitable galvanometer coils. Preferably the deflections to be observed should not be much greater than 60° or less than 30° .

EXPT. 222A. The Calibration of an Ammeter already graduated.—Set up the tangent galvanometer as described on p. 383. Join up in series an adjustable resistance (about 5 to 7 ohms), an ammeter reading to 3 or 5 amperes and a 2-volt accumulator.

Note the following points :—

(1) For an ammeter reading to 3 or 5 amperes use the galvanometer terminals connected to the single turn of thick copper wire.

(2) Use a commutator so as to be able to reverse the current through the galvanometer (not through the ammeter) and take readings on both sides of the zero.

(3) Be careful to connect the + pole of the accumulator to the + terminal of the ammeter. (This is immaterial with a hot-wire instrument.)

(4) As most ammeters contain a strong permanent magnet, the ammeter must be placed as far as possible from the tangent galvanometer.

(5) Twin wires must be used from the commutator to the ammeter, or else the two wires used must be twisted together; otherwise the

field due to the current in these wires will have an appreciable effect on the galvanometer reading.

Take a series of readings of the ammeter and galvanometer for different values of the resistance. The resistance should be adjusted so as to alter the current by about half an ampere between the readings.

Measure carefully the diameter of the coil of the tangent galvanometer, using a pair of beam compasses.

Calculate the galvanometer constant G , and also the reduction factor K .

$$G = \frac{2\pi n}{r}, \quad K = \frac{H}{G} = \frac{rH}{2\pi n}.$$

Then calculate the current through the galvanometer in absolute units and deduce the value in amperes.

$$I = \frac{rH}{2\pi n} \tan \theta$$

in electromagnetic units, and one absolute electromagnetic unit equals 10 amperes.

The table of observations should be arranged as below :—

Ammeter Reading A , in Nominal Amperes	Tangent Galvanometer				$\frac{A}{I}$
	Deflection θ	$\tan \theta$	I (abs. units)	I (amp.)	

EXPT. 222B.—The Calibration of a Milliammeter already graduated.—This calibration is similar to that in Expt. 222A, but a larger adjustable resistance is required, and a coil of the tangent galvanometer containing many turns must be used.

DISCUSSION OF EXPERIMENTAL RESULTS

The errors of an ammeter may be divided into two types :—

(a) If the last column, giving the ratio of A to I , is a constant, the instrument is *self-consistent*, for the current is proportional to the indications of the ammeter even if not actually equal to them. Any error, therefore, is a *proportional* error, and the true current can be obtained by multiplying the current indicated by the ammeter by a certain factor which is the same for all parts of the scale.

To determine the Correction Factor, calculate the mean of the approximately equal values of A/I . The reciprocal of this quantity is the correction factor, for the true current is given by multiplying the ammeter reading by the mean value of I/A .

(b) If the values of A/I are not constant within the limits of experimental error, arrange a correction table as follows :—

Reading, A	True Current, I	Correction, I - A

A correction curve should be plotted, with $I - A$ as ordinate and A as abscissa. The ordinate corresponding with any reading gives the correction to be *added* to that reading to give the true current. Any zero error may be included in this curve.

NOTE.—In case (a) the value of I is calculated on an assumed value of H . If A/I is not unity, the divergence may be due to an error in the assumed value of H . The value of H determined in the experiment on the earth's field *for the particular place where the galvanometer is used* should be taken. If H is not known with certainty, it should be determined and I recalculated before concluding that the ammeter is incorrect.

§ 3. OHM'S LAW

Ohm's Law (1827) states that when two points are taken on a conductor in the form of a line, the ratio of the difference of potential E between those points to the current I flowing through the conductor is a constant, that is, it depends only on the form, dimensions and physical condition of the conductor. This constant ratio is termed the **resistance** R of the conductor. Thus

$$E = IR.$$

The name **resistor** may be given to any apparatus used because of the electrical resistance it possesses.

If E and I are measured in C.G.S. electromagnetic units, then R will also be in C.G.S. units. If practical units are employed I will be in amperes, E in volts, and R in ohms. The ohm = 10^9 C.G.S. units. For purposes of practical measurement the **International Ohm** is defined as the resistance of a column of mercury at 0°C ., 14.4521 gm. in mass, of a constant cross section, and of length 106.300 cm.

The reciprocal of the resistance is termed the **conductance**.

Ohm's Law may be extended to a complete circuit, if E now represent the electromotive force (E.M.F.) in the circuit and R the total resistance of the circuit.

Hence the current flowing round the circuit is given by

$$I = \frac{E}{R}.$$

It is assumed that the insulation is perfect, and no leakage of electricity occurs at any place.

The current has the same value at each point of the circuit, and may be measured by introducing a tangent galvanometer at any part of the circuit. The strength of the current is then given by

$$I = K \tan \theta,$$

where K is a constant called the **reduction factor**, or simply the **factor**, of the galvanometer.

Combining these two values for I we obtain

$$\frac{E}{R} = K \tan \theta,$$

or

$$\frac{E}{K} = R \tan \theta.$$

Hence if E , the electromotive force in the circuit, is constant, $R \tan \theta$ must be a constant quantity.

EXPT. 223. An Experiment illustrating Ohm's Law and the Law of the Tangent Galvanometer.—Join up in series with the galvanometer a 2-volt accumulator, a resistance box, and a key. As the internal resistance of the accumulator is small, and a large current would damage the resistance coils, at least 30 ohms must always be kept in the circuit, so R must be not less than 30 ohms. Sometimes the tangent galvanometer is provided with a number of terminals on one side of the stand. In this experiment the two terminals connected with the largest number of turns should be used so that the current may pass through all the coils of the galvanometer. Commence by having in the circuit all the resistance in the box (when the plugs are taken out of the box, resistance is put in the circuit), and observe the deflection of the tangent galvanometer with the current flowing first in one direction and then in the other. Take the mean of the two readings as the measure of the true deflection.

Make a series of observations, taking out in succession plugs corresponding to resistances of (say) 210, 190, 170, 150, 130, 110, 90, 70, 50, and 30 ohms.

Make a table of the results thus :—

R ohms	Deflection θ	$\tan \theta$	$R \tan \theta$

If $R \tan \theta$ is constant R must be proportional to $\cot \theta$. Plot a graph, taking values of R as abscissæ and the values of $\cot \theta$ as ordinates. This should yield a straight line.

The constancy of the last column of the table is a consequence of the two laws $I = K \tan \theta$ and $I = E/R$.

In taking R , the resistance in the box, as the *full* resistance of the circuit, it is assumed that the resistances of the galvanometer and of the battery are negligible. If this is not the case, a value x equal to the sum of these (assumed known) should be added to R and another column $(R+x) \tan \theta$ drawn out. This will be more nearly constant than $R \tan \theta$.

If x is not known, an approximate value for x can be obtained from the first and last numbers in the column $R \tan \theta$.

Let the first resistance be R_1 and the deflection corresponding to this θ_1 , the last resistance being R_2 and the deflection θ_2 . Then we know that

$$(R_1+x) \tan \theta_1 = (R_2+x) \tan \theta_2,$$

whence

$$x = \frac{R_2 \tan \theta_2 - R_1 \tan \theta_1}{\tan \theta_1 - \tan \theta_2}.$$

Substitute this value of x in the expression $(R+x) \tan \theta$ and calculate the value of $(R+x) \tan \theta$ for each set of observations.

The type of variation of the column $R \tan \theta$, if accurately determined, affords an interesting example of the effect of a *systematic error* involved in an experiment. It will be found that $R \tan \theta$ *on the whole increases steadily* as the higher resistances are approached. This is due to the fact that the quantity x which has been neglected becomes of less and less *relative* importance as the total resistance gets larger, so that the values of $R \tan \theta$ approach the true constant $(R+x) \tan \theta$ more and more closely as R is increased.

Whenever a *regular* increase or decrease takes place in a quantity which should be constant, as one factor of the constant is altered steadily, a *systematic error* of this type should be looked for in the experiment or in the method of working out.

RESISTANCE BY THE METHOD OF SUBSTITUTION

When a resistance box, containing a number of coils of known resistance arranged in series, is available, a simple method of finding the value of an unknown resistance is that known as the **Method of Substitution**. A current from a cell or battery of constant E.M.F. is passed through the unknown resistance and through a galvanometer, and the deflection of the galvanometer is observed.

The type of galvanometer used is immaterial provided a reasonable deflection can be obtained with the resistance and E.M.F. available. If the deflection be too large, it may be diminished by *shunting* the galvanometer, that is by joining its terminals by a resistance, such as a piece of platinoid wire, so that only a fraction of the whole current passes through the galvanometer. A tangent galvanometer will serve well for this experiment in general.

The unknown resistance is then replaced by the resistance box, and the resistance of the latter adjusted till the galvanometer deflection has the same value as before. Then obviously, if the E.M.F. has remained constant, the unknown resistance must be equal to that obtained by the use of the resistance box.

EXPT. 224. Determination of a Resistance by the Method of Substitution.—Connect up *in series* as in Fig. 227 a cell B , a galvanometer G , and the resistance R which is to be determined. Remember that the cell is to be connected *last of all*. If a tangent galvanometer is used, it should be set up with a commutator K , in the manner described on p. 383, with the current passing through *all* the turns of the galvanometer. Where

this is not possible, the coil having the largest number of turns must be used.

The cell used may be a Daniell cell, since that gives a constant electromotive force, or it may be a secondary cell. In the latter case, since the internal resistance of the cell is small, *great care must be taken in the second part of the experiment when the resistance box is substituted for the unknown resistance.*

Measure the deflection with the unknown resistance in the circuit.

Replace the unknown resistance by the resistance box, *from which all the plugs should have been removed*, and adjust the value of the resistance in the box down to such a value that the deflection may have the same value as before. *The resistance must not be reduced below 30 ohms in any case.* Then the sum of all the numbers from which plugs are absent in the resistance box represents the value of the unknown resistance. Repeat the determination after reversing the current.

Note on Determination of Resistance by Substitution.—The degree of accuracy obtainable by this is not at all large for it depends on the accuracy of reading deflections, and therefore is inaccurate to the same degree as the readings of the deflections may be inaccurate, say to 2 or 3 per cent.

Also, the adjustment of the resistance in the resistance box is only possible in definite steps of 1 ohm (or possibly 0.1 ohm if a 'decimal' ohm box is used). The value of the equivalent resistance substituted for the unknown can never be correctly adjusted except in the rare cases when the unknown resistance is an integral number of ohms (or tenths of an ohm).

Furthermore the limits of resistance for which the method is at all suitable depend largely on the galvanometer used. For resistances between 30 and 70 ohms an ordinary tangent galvanometer is useful. Above 70 ohms or thereabouts, a more sensitive type of galvanometer must be used. The method is entirely unsuited for low resistances.

The only way to test whether the unknown resistance is of magnitude suitable for determination by this method is to connect it up to the roughest form of galvanometer available. If the deflection is small, 5° or so, the method may be used, but a more delicate galvanometer must be employed. If the deflection is between 10° and 70° the galvanometer first chosen may be used. If the deflection is above 70° with the roughest galvanometer available, the method is quite unsuitable for this particular resistance and another way must be used (see Wheatstone's Bridge, p. 411).

RESISTANCES IN SERIES AND IN PARALLEL

For resistances in Series

$$R = R_1 + R_2 + R_3 + \text{etc.}$$




FIG. 230.—Resistances in Series and in Parallel

If resistances R_1 , R_2 , R_3 , etc., are connected in *series*, their equivalent resistance R is the *sum* of the separate resistances.

It is assumed that each separate resistor obeys Ohm's Law, and that the insulation is perfect throughout. Resistances connected in *parallel*, however, have an equivalent resistance *less than any one* of the constituent resistances; the total *conductance* in this case is the sum of the conductances of the constituent resistances, or

For resistances in Parallel

$$\frac{1}{R} = \frac{1}{R_1} + \frac{1}{R_2} + \frac{1}{R_3} \text{ etc.}$$

The student should derive this result by applying Ohm's Law to the various resistances. The combined resistance of a number of 'branches', or resistors in parallel, is always less than that of any individual branch.

EXPT. 225. An Experiment on Resistances in Series and in Parallel.—Measure the value of two separate resistances R_1 and R_2 by the method of substitution. Next place the two resistances in series with one another, and measure the resultant resistance, R , also by the method of substitution.

Verify the result that $R = R_1 + R_2$.

Finally arrange the two resistances in parallel with one another and measure the equivalent resistance, S , in the same way.

Verify the result that $\frac{1}{S} = \frac{1}{R_1} + \frac{1}{R_2}$.

GALVANOMETER SHUNTS

When a resistance of S ohms is placed in parallel (or as a shunt) with a galvanometer of resistance G ohms the current flowing through the galvanometer is reduced in general. When, however, the potential difference applied to the galvanometer terminals is kept constant, shunting the galvanometer has no effect on the current flowing through it.

It is assumed that the total current flowing round the circuit is unaltered by the introduction of the shunt. This will be practically true provided the resistance of the remainder of the circuit is large compared with the resistance of the galvanometer.

Let I = total current flowing round the circuit,

I_g = current through the galvanometer,

I_s = current through the shunt,

then, when no electrical leakage occurs, $I = I_g + I_s$. Hence $I_s = I - I_g$.

We must now find what fraction of the total current passes through the galvanometer.

Let E = difference of potential between the terminals A and B. By Ohm's Law $E = I_g G$, and also $E = I_s S$.

So $I_g G = I_s S$, the currents through the galvanometer and the shunt being *inversely* proportional to the resistances.




FIG. 231.—Principle of Galvanometer Shunt

Hence, since $I_s = I - I_g$, $I_g G = (I - I_g) S$.

Therefore $I_g (G + S) = IS$, or, finally, $I_g = I \left(\frac{S}{G + S} \right)$.

If, for example, $S = \frac{1}{9} G$ we see that $I_g = \frac{1}{10} I$.

Further, if the ratio I/I_g is found, the value of the resistance of the galvanometer G can be found in terms of S .

If a tangent galvanometer be used, the current is given by the equation $I = K \tan \phi$, where K is the reduction factor and ϕ the deflection of the galvanometer due to the current I . Denoting the deflection without the shunt by ϕ , and the deflection when shunted by ϕ_1 , we have

$$\frac{I}{I_g} = \frac{K \tan \phi}{K \tan \phi_1}$$

But

$$\frac{I}{I_g} = \frac{G + S}{S}$$

therefore

$$\frac{G + S}{S} = \frac{\tan \phi}{\tan \phi_1}$$

whence

$$G = S \left(\frac{\tan \phi}{\tan \phi_1} - 1 \right).$$

The student must deduce this from the above.

EXPT. 226. Determination of the Resistance of a Galvanometer by Shunting.—Connect up, as shown in Fig. 232, a secondary cell B , a




FIG. 232.—Resistance of Galvanometer by Shunting

reversing switch K , and a resistance R (which must be at least 40 ohms) with the galvanometer G and the shunt S .

Observe the deflection of the galvanometer before connecting the shunt to it, then connect up the shunt and find the deflections corresponding with *various* shunt resistances ; a suitable range of S for an ordinary tangent galvanometer would be from 1 to 20 ohms.

The current must be reversed for each reading and the mean of the deflections taken as the true value of ϕ_1 .

Arrange the observations in a table as shown :—

S	ϕ_1	$\tan \phi_1$	$\frac{\tan \phi}{\tan \phi_1} - 1$	$S \left(\frac{\tan \phi}{\tan \phi_1} - 1 \right)$
1	$\phi =$			
2				
3				
4				
5				
7				
10				
15				
20				
∞				

When no shunt is connected, the shunt resistance is infinite, the deflection in this case is the full deflection ϕ .

The last column will be approximately constant, its mean may be taken as the value of G .

NOTE.—The method of working out the value of G in this experiment is based on the assumption that the total current is not appreciably altered when the shunt resistance is connected up. Unless R is at least 20 times the value of G , this assumption is not sufficiently near to the truth. If, therefore, the value of the numbers in the last column is greater than 5 per cent of R , the experiment should be repeated, using a resistance R of the requisite magnitude.

When G is only 5 per cent of R the maximum variation of current cannot exceed 5 per cent, even when G is entirely short-circuited, and the errors in the deflections observed may introduce errors of this magnitude into the result. The *best* value of G corresponds with a shunt S which gives $\tan \phi_1 = \frac{1}{2} \tan \phi$.

The value of G may also be calculated from the expression

$$\frac{RG}{S(R+G)} = \frac{\tan \phi}{\tan \phi_1} - 1,$$

even when R is less than 20 times G .

KIRCHHOFF'S LAWS

For the two laws stated by Kirchhoff as to the conditions determining currents in a network of conductors, see page 431.

CHAPTER IV

ELECTROMOTIVE FORCE AND INTERNAL RESISTANCE OF A CELL

§ 1. SIMPLE DISCUSSION OF THE ACTION OF A VOLTAIC CELL

THE following discussion is not to be taken as a theory of the fundamental electrolytic and chemical actions which are concerned in the action of a voltaic cell, but is to be used merely as a useful *working hypothesis* for dealing with the electromotive force (E.M.F.) and the potential difference (P.D.) between the terminals.

NOTE.—We shall for the present adopt the old convention, and regard the current as a flow of *positive* electricity.

CELL ON ' OPEN CIRCUIT '

Two plates of different metals immersed in a suitable solution at once acquire a difference of potential. In the following treatment the case of a simple cell will be considered, the terms copper and zinc being used to indicate the positive and negative plates respectively, though the general account of the happenings detailed will apply to *any type of cell whatsoever*.

As soon as the plates are put in the liquid, positive electricity begins to move through the liquid towards the copper. This positive electricity may be supposed to come from the zinc plate, which is accordingly left negatively charged. The motion of the positive electricity is due entirely to the chemical nature of the cell, and the electromotive force producing the flow of electricity may be termed an **Electromotive Force of Chemical Action** or a Chemical E.M.F.

This chemical E.M.F. urges positive electricity from the zinc plate to the copper plate through the liquid in the cell, that is to say, the **E.M.F. of a cell acts from the negative pole to the positive pole of the cell.**

This statement is universally true for all cells, and it must be noted that the term the *E.M.F. of a cell* means simply the force driving electricity through the cell, and as such it can only be used with reference to the interior action of the cell.

The positive electricity carried across the cell from the zinc to the copper raises the potential of the copper plate above that of the zinc.

There are now *two* forces acting on any positive charge inside the cell. This charge is urged from the zinc to the copper by the E.M.F. of the cell, and is urged from the copper to the zinc in consequence of the *potential difference* between these two, this P.D. having been acquired as a result of the action of the chemical E.M.F. of the cell.

The P.D., so far from being identical with the E.M.F. of the cell, as is often imagined to be the case, is only a result of the action of this E.M.F. ; inside the cell the P.D. and the E.M.F. act in opposition.

The plates are not connected externally in any way, since the cell is on open circuit, and therefore the potential difference continues to rise, due to the accumulation of electricity on the two plates. It cannot rise indefinitely, however, for there is only a limited E.M.F. acting inside the cell. The potential difference will rise to such a value V' that the tendency of the positive electricity to flow from zinc to copper under the E.M.F. of the cell is just balanced by its tendency to flow from copper to zinc due to the P.D. When this balance between the E.M.F. and the P.D. occurs, no motion of electricity will take place in either direction through the cell, and all action ceases.

Thus on open circuit, or generally, when no current is flowing in either direction through the cell, the P.D. between the plates of the cell V' will be equal to the E.M.F. of the cell.

On open circuit

$$V' = E.$$

It is impossible to measure E directly ; we can only measure an E.M.F. by the P.D. it creates, therefore to measure the E.M.F. of a




FIG. 233.—Cell on Open Circuit




FIG. 234.—Cell on Closed Circuit¹

cell we measure the P.D. across its terminals when on open circuit, the value of this P.D. (V') being equal to the E.M.F. of the cell, E .

CELL ON 'CLOSED CIRCUIT'

Outside the Cell.—Suppose the plates of the cell to be connected by a wire of resistance R . The electricity at once begins to flow through

¹ In this diagram the conventional *positive* current only is shown. Inside the cell *ions* travel in both directions.

this wire under the action of the P.D. between the plates. There is no chemical action in the wire at all, and hence the P.D. is the only force driving electricity through it, and therefore the electricity will flow from copper to zinc through the wire.

At once, as soon as the wire is connected up, the potential difference between the two plates will begin to diminish owing to the passage of electricity from one plate to the other. If V be the value of the potential difference at any instant, the current flowing through the wire will be

$$I_1 = \frac{V}{R},$$

I_1 representing the current in the *external circuit*, that is the current in the wire connecting the plates.

Inside the Cell there is still the E.M.F. of the cell acting, and the value of this will not have altered in the slightest (polarisation effects will be considered later) since it is a property of the chemical constitution of the cell. Its action is not now opposed by the potential difference V' , but by a diminished P.D., V . The E.M.F. will therefore begin to drive electricity through the cell again, from zinc to copper, the *net* driving force being the difference between the E.M.F. of the cell and the value of the now diminished P.D., V . If the resistance of the cell (its *internal* resistance) is B , the current flowing inside the cell from zinc to copper will be

$$I_2 = \frac{E - V}{B}.$$

Thus, we have going on simultaneously a flow of electricity away from the copper plate through the *external* circuit equal to

$$I_1 = \frac{V}{R}$$

units of electricity per second, and a flow of electricity towards the copper plate from the inside of the cell equal to

$$I_2 = \frac{E - V}{B}.$$

As V gets smaller and smaller, the rate of loss of electricity from the copper plate, I_1 , will diminish, and the rate of gain of electricity, I_2 , will increase. When these two become equal, V will become steady again, though of course less than V' , and we shall have

$$I_1 = I_2 = I \text{ (say)}$$

and

$$I = \frac{V}{R} = \frac{E - V}{B}.$$

Thus, when a cell has its external circuit completed through a simple resistance R , the P.D. between the plates falls to some value V , such that the current inside the cell from zinc to copper is equal

to the current flowing outside the cell from copper to zinc. From the relation between the new P.D. (V), the E.M.F. (E) of the cell, we can easily show that $BV = R(E - V)$ and $RE = V(R + B)$, where B is the internal resistance of the cell and R the external resistance. These relations can also be proved by a different method (pp. 403-404).

It will, of course, be realised that the adjustment of the P.D. to the value $V' = E$ is almost instantaneous, and the P.D. falls to its steady value V in an extremely minute fraction of a second when the external circuit is closed.

When a current is driven through a cell from copper to zinc (or from positive to negative) the potential difference applied has to be greater than E , because it overcomes E and also overcomes the resistance of the battery. The student is recommended to investigate this case in the same manner as above, and to show that the current driven through the cell or battery from positive to negative is given by

$$I = \frac{V - E}{B},$$

where V is the applied P.D. This result is useful in charging accumulators.

Effect of Polarisation.—Polarisation occurs in a cell due to any change in the chemical constitution of the cell. If too large a current is taken from the cell, the liquid round the zinc becomes 'used up', or the oxidising agent near the positive plate is unable to cope with the rapid generation of hydrogen there, and so the plate becomes coated with hydrogen. The chemical constitution of the liquid just near the plates is thereby changed, and the plates themselves are altered in character. The E.M.F. of the cell is changed in consequence and is not restored to its original value until diffusion of the liquid and oxidation of the hydrogen has reproduced the original conditions. It is assumed in the foregoing discussion that the cell is never overloaded to such an extent as to produce polarisation.

§ 2. COMPARISON OF ELECTROMOTIVE FORCES OF TWO CELLS

SUM AND DIFFERENCE METHOD USING A GALVANOMETER

This method enables us to compare the electromotive forces of two cells, but does not give an absolute measure of the electromotive force.

In addition to the cells or batteries to be compared, a galvanometer or some other instrument for measuring the strength of a current is required, together with a resistance to adjust the current to a suitable value. Let E_1 be the E.M.F. of the first cell, the resistance of which is B_1 , and E_2 the E.M.F. of the second cell, the resistance of which is B_2 . Let G be the resistance of the galvanometer and R the resistance of the rest of the circuit. None of these resistances need be known, but they must *all* be constant during the whole of the experiment.

The cells are first connected in series with the resistance and the galvanometer, arranging the cells so as to *assist* each other: the E.M.F. in circuit now is the sum of E_1 and E_2 .

By Ohm's Law and the definition of resistance

$$\frac{\text{E.M.F. in circuit}}{\text{Resistance of circuit}} = \text{Current flowing round circuit,}$$

or
$$\frac{E_1 + E_2}{R + G + B_1 + B_2} = I_1.$$

I_1 is the current flowing in the circuit, and is measured by the deflection of the galvanometer.

One of the cells is now reversed—for preference this should be the *weaker*, say E_2 , though it is immaterial which cell is reversed if the galvanometer is used with a commutator.

The E.M.F. now in circuit is $E_1 - E_2$, and the current will have some value I_2 given by

$$\frac{E_1 - E_2}{R + G + B_1 + B_2} = I_2$$

I_2 is measured by the deflection of the galvanometer and then, *since none of the resistances have been altered*, we have

$$\frac{E_1 + E_2}{E_1 - E_2} = \frac{I_1}{I_2}, \quad \text{or} \quad \frac{E_1}{E_2} = \frac{I_1 + I_2}{I_1 - I_2}.$$

EXPT. 227. Comparison of E.M.F.s by the Sum and Difference Method using a Tangent Galvanometer.—The method may be used to compare the E.M.F.s of a Leclanché and of a Daniell cell, or to compare either of these with that of an accumulator.

Set up a tangent galvanometer G with a commutator K as described on p. 383, connecting in series with the galvanometer, a resistance box, R , from which *all the plugs have been removed*. The current should go through all the coils of the galvanometer.

Arrange the two cells B_1, B_2 in series so as to assist each other, and connect them so as to send a current through the galvanometer and the resistance box in series, the connections being made so that the current through the galvanometer can be reversed (Fig. 235).

Reduce the resistance of the box by inserting plugs until the deflection of the galvanometer is about 65° . *In no case must the resistance of the box be reduced to less than 30 ohms.*




FIG. 235.—E.M.F.s by Sum and Difference

Read the deflection of the galvanometer with the current passing through it, first in one direction, then in the other: let the mean deflection be θ_1 . Then the current I_1 is given by

$$I_1 = K \tan \theta_1,$$

where K is the reduction factor of the galvanometer (this need not be known since we require only the *ratio* of I_1 to I_2).

Reverse the weaker of the two cells as shown in Fig. 235, but do not alter any other connection; if possible avoid shaking the cells while disconnecting B_2 and connecting it up reversed, otherwise their internal resistances may be changed.

If θ_2 is the mean deflection observed with B_2 reversed,

$$I_2 = K \tan \theta_2.$$

Then since

$$\frac{I_1}{I_2} = \frac{K \tan \theta_1}{K \tan \theta_2} = \frac{\tan \theta_1}{\tan \theta_2},$$

it follows from p. 399 that

$$\frac{E_1}{E_2} = \frac{I_1 + I_2}{I_1 - I_2} = \frac{\tan \theta_1 + \tan \theta_2}{\tan \theta_1 - \tan \theta_2}.$$

Calculate in this way the ratio of the E.M.F.s of the two cells used. If one cell is a Daniell, with a solution of ZnSO_4 as the exciting liquid, its E.M.F. may be taken as 1.07 volts, and the E.M.F. of the other cell can be calculated on this assumption from the ratio obtained by experiment.

THE POTENTIOMETER

The potentiometer is an apparatus used for the comparison of electromotive forces. It is usually in the form of a long uniform wire




Fig. 236.—Principle of the Potentiometer

stretched on a flat board, which is fitted with a sliding key so that contact may be made with any desired point on the wire. When the wire is very long, it is often arranged in zigzag fashion on the board so as to economise space, or a number of parallel wires

may have their ends so connected by thick pieces of copper that a current may be passed through them in series. In considering the theory of the apparatus it will be simpler to think of a single straight wire (Fig. 236).

A constant battery S (which may consist of one or two secondary cells) is used to send a steady current through the uniform wire AD . The point A is connected with the positive pole of the battery, so that there is a fall of potential from the point A to the point D . If the wire be uniform, the potential will diminish in a regular way as we pass from A to D .

The object of the experiment is to compare the E.M.F.s of two cells, which may be called E_1 and E_2 . The first cell has its positive terminal connected to the point A, its negative terminal is connected through a galvanometer G to the sliding key, which makes contact with a point P on the potentiometer wire. By moving the key backwards and forwards, a point P_1 is found such that no deflection of the galvanometer is observed when the key is pressed down. When this point is found no current flows through the galvanometer and also no current flows through the cell E_1 . As we shall see, this means that the electromotive force E_1 of the cell exactly balances the difference of potential between A and P_1 . For if no current flows through the galvanometer, the potential of the point P_1 must be the same as the potential of the pole of the cell connected to the galvanometer, so that the fall in potential through the cell must be exactly equal to the fall of potential along the wire between A and P_1 . There is, however, no current flowing through the cell, therefore *the P.D. between the plates is equal to the E.M.F. of the cell* (p. 396). The condition that is satisfied, therefore, is that the electromotive force E_1 of the cell under test is exactly equal to the difference of potential between A and P_1 .

The same process is then carried out with the cell E_2 , and a point P_2 is found, such that the electromotive force E_2 exactly balances the difference of potential between A and P_2 .

$$\text{Hence } \frac{E_1}{E_2} = \frac{\text{Diff. of potential between A and } P_1}{\text{,, ,, ,, A and } P_2}$$

If the steady current through the potentiometer wire be I,

P.D. between A and $P_1 = I \times \text{Resistance of } AP_1$ and

P.D. between A and $P_2 = I \times \text{Resistance of } AP_2$.

$$\text{Thus } \frac{E_1}{E_2} = \frac{\text{Resistance of } AP_1}{\text{Resistance of } AP_2} = \frac{\text{Length of } AP_1}{\text{Length of } AP_2},$$

assuming the wire to be uniform.

The comparison of E.M.F.s is carried out by comparing the lengths of the potentiometer wire necessary to secure a balance.

It is of course assumed that the battery S maintains a constant current during the experiment. The P.D. between the terminals A and D of the wire when this steady current is flowing, must be greater than the E.M.F. of either cell.

EXPT. 228. Comparison of the E.M.F.s of two Cells by means of a Potentiometer.—Connect an accumulator S (or in some experiments two in series) through a low resistance to the ends of a potentiometer wire ¹

¹ In practice 10 metres of resistance wire is frequently used, being arranged in zigzag fashion on a base-board. The wire of an ordinary metre-bridge would be overheated if it were connected directly to an accumulator, and if a resistance is in series with it the P.D. between its ends will be less than 2 volts. A metre of nichrome wire having a resistance of about 5 ohms may be convenient for some experiments.

AD, the positive terminal of the battery being finally connected to A. To A connect the positive terminal of one of the cells E_1 to be compared, connecting its negative terminal to a galvanometer. The sliding key P which moves along the potentiometer wire is connected through a *high* resistance which may be of the order of 5000 ohms¹ to the other terminal of the galvanometer. The key P is moved along the wire until a point is found where no deflection is produced in the galvanometer when P is depressed so as to make contact with the wire. The length AP_1 on the potentiometer wire is then measured. The second cell E_2 is then substituted for E_1 , and the length AP_2 determined.




FIG. 237.—Connections for Potentiometer

Since there may be some change taking place in one or other of the cells in use in the experiment, it is necessary to repeat the observations, using first one and then the other of the two cells under test. It is accordingly convenient to introduce a two-way switch, so that it may be possible to change quickly from one cell to the other. By changing

over rapidly in this way, the adjustments can be made in a very short time, and thus there will be less chance of error due to variation of the steady current in the wire.

The apparatus would then be arranged as in Fig. 237. K represents the two-way switch which connects A to E_1 or E_2 at will. Determine the mean values of AP_1 and AP_2 , and calculate the ratio of E_1 to E_2 . If the wire is uniform

$$\frac{E_1}{E_2} = \frac{\text{Mean length of } AP_1}{\text{Mean length of } AP_2}.$$

As a confirmation of the first comparison connect the two cells in series (a) so as to assist one another, (b) so as to oppose one another, and compare the resultant E.M.F.s. If l_1, l_2 are the readings on the potentiometer wire corresponding to these two cases we have

$$\frac{E_1 + E_2}{E_1 - E_2} = \frac{l_1}{l_2}$$

and therefore

$$\frac{E_1}{E_2} = \frac{l_1 + l_2}{l_1 - l_2}.$$

NOTE.—It is obvious that if the *negative* pole of the constant cell were connected to A_1 and the *negative* pole of the cells under test were also connected to A_1 , the experiment could be carried out just as well: the *rise* of potential from A to P along the wire would be equal to the E.M.F. of the cell when no current flows in the galvanometer.

§ 3. MEASUREMENT OF THE INTERNAL RESISTANCE OF A BATTERY

The internal resistance of a battery can be measured by means of a voltmeter and a suitable resistance. If a cell with an E.M.F. of E

¹ This resistance may be short-circuited by a key when balance is nearly reached.

volts and an internal resistance of B ohms be connected to a wire of resistance R ohms, then according to Ohm's Law the current, I , in amperes will be given by the equation

$$I = \frac{E}{R + B}.$$

In an ordinary voltmeter the resistance is very large, so that the current passing through the coils is extremely small. It may, indeed, be assumed that no current whatever flows through the voltmeter. Theoretically it would be better for the present experiment to use an *electrostatic* voltmeter, which would measure the potential difference between the terminals of the cell without taking any current.

The potential difference between the terminals when these are not connected together is V' volts, V' being equal to the E.M.F. of the cell (E). When the terminals are connected by a wire, the potential difference will be less than V' .

As this point sometimes causes difficulty it may be useful to consider an analogy. Suppose we have an endless pipe through which water can be driven by means of a turbine, T (Fig. 238). When




FIG. 238.—Hydro-dynamic Analogy

the stop-cock S is closed the turbine develops a certain pressure which can be measured by means of a vertical pipe as shown. When the stop-cock is opened, the pressure indicated by the level in the pipe will diminish and as the aperture is increased will diminish still further. The pump has a mechanical effect which might be called a water-motive-force. The column of water measures the pressure difference produced. The tap and tube constitute a resistance in an external circuit. The student should refer to the introductory part of this chapter (pp. 395-398) where the electrical analogy is worked out in detail.

Let V denote the P.D. between the terminals of the cell when they are connected together by a resistance R . Then the current through R by Ohm's Law is V/R , being due entirely to the P.D. between the terminals. But the current in the circuit is $E/(R + B)$, and so

$$\frac{V}{R} = \frac{E}{R + B},$$

$$\therefore V = \frac{ER}{R + B} = \frac{E}{1 + B/R}.$$

Thus V is less than E , but if R is very large compared with B , the difference $E - V$ will be very small.

If R is not very large, and we can find E/V , we can calculate B by means of the equation

$$\frac{E}{V} = \frac{R+B}{R}, \text{ or } B = R \left(\frac{E}{V} - 1 \right)$$

For an alternative proof of this see pp. 395-398.

To determine B , then, we compare the E.M.F. of the cell with the P.D. between its terminals when it is short-circuited by a wire of known resistance R , which should not be much greater than B .

If R is taken equal to B , $V/E = \frac{1}{2}$, so that the potential difference between the terminals is only one-half that on open circuit.




FIG 239.—Internal Resistance of Cell

EXPT. 229. Determination of the Internal Resistance of a Primary Cell by Use of a Voltmeter.—Connect the terminals of the cell to the voltmeter. In using a moving coil voltmeter be careful to connect the cell so that the current enters the voltmeter at the terminal marked +. If the connection be made incorrectly, the pointer may be bent and the instrument damaged.

Observe the deflection, which gives the value of V' , the P.D. on open circuit.

NOTE.—It is assumed that no current passes through the voltmeter; therefore the circuit is still 'open' and $V' = E$.

Then connect the terminals of the cell with various resistances, noting the corresponding deflections of the voltmeter in each case. A resistance box may be used, if care is taken not to pass the current through it for more than two or three minutes at a time.

The resistances chosen should be of such magnitudes that some give deflections greater than, and others less than, half the original deflection V' . Six different resistances may be used, *three* giving values *above* $V'/2$ and *three* below.

It is convenient to start with an external resistance of 10 ohms, and to work upwards or downwards as required.

Tabulate the observation as below :—

P.D. on open circuit $V' (=E) = . . .$

E	V	$E - V$	$\left(\frac{E - V}{V} \right) R$

NOTE.—The internal resistance, and even the E.M.F., of most batteries varies a good deal with the current they are sending in consequence of temporary changes in the liquid near the plates (p. 398). B is consequently a somewhat indefinite quantity.

In the above method it is assumed that E does not change when the cell is short-circuited. In some forms of Leclanché the cell *polarises* very rapidly when short-circuited, and its E.M.F. rapidly falls. In such cases the method is not applicable. This method should not be applied to a secondary cell; to obtain accurate readings it would be necessary to make R too small, the cell would be damaged, and the resistance box might be 'burnt out'.

The accuracy of this 'deflection' method is not very great. It is, however, an extremely instructive experiment when taken in conjunction with the discussion of the action of a cell dealt with on pp. 395-398. In any case the resistance of a cell is such a variable quantity that the *order of magnitude* of the resistance is the result really aimed at. When one considers that shaking a cell or substituting a new zinc plate for an old one may reduce the resistance of the cell by half in some cases, it will be realised that any method which is correct to within 20 per cent is good enough for this purpose. If the resistance of a particular cell is required very accurately, Mance's method, using a Post Office Box, should be employed (see Wheatstone's Bridge, pp. 414, 423).

INTERNAL RESISTANCE OF A SECONDARY CELL

A secondary cell has a very low internal resistance. The method of finding the internal resistance already described is not suitable in such a case because the current requisite to produce a measurable fall of P.D. would be too great, and would damage the cell. This is because a voltmeter has to be used which covers the whole range up to the full E.M.F. of the cell, and as the variation of P.D. obtainable with the biggest current allowable is only 1 or 2 per cent of this maximum, the measurements are not exact. The following method, which is applicable to any cell of low internal resistance, overcomes this difficulty, and as a very sensitive voltmeter may be used, the *change* of P.D. may be measured accurately.

EXPT. 230. Determination of the Internal Resistance of a Secondary Cell.

—Connect two *similar* cells in parallel as in Fig. 240, with a sensitive voltmeter across their + terminals. In series with one of the cells, connect a resistance R and an ammeter A , including a key K in the circuit. When the key K is *open*, the voltmeter will indicate no P.D., since the cells are similar. Depress the key K and take the reading of the voltmeter (v) and of the ammeter (I).

The current I flows from cell E_1 only, the voltmeter resistance being supposed infinite. If B be the resistance of cell E_1 , the P.D. across its terminals falls an amount IB which is registered on the voltmeter as v . Hence $B = v/I$.

If the E.M.F. (E) of the first cell be known and R be also known, I may be taken as E/R , and $B = vR/E$. The ammeter may then be dispensed with.




FIG. 240.—Internal Resistance of Secondary Cell

INTERNAL RESISTANCE OF A CELL BY MEANS OF A POTENTIOMETER

It has already been pointed out in the comparison of E.M.F.s by the Potentiometer that the P.D. between the terminals of a cell can be measured by balancing it against the P.D. between two points on a




FIG. 241.—Internal Resistance by Potentiometer

wire carrying a current. If we connect up a potentiometer as shown in Fig. 236, and adjust the contact to some point P such that no current flows through the galvanometer, the P.D. between P and the negative plate of the cell is zero (otherwise a current would flow through the galvanometer). A is

at the same potential as the positive plate of the cell, therefore the P.D. between A and P is the same as the P.D. between the plates of the cell.

In the case considered, there is no current flowing through the cell E, and therefore this P.D. V' is equal to the E.M.F. of the cell (pp. 395-398).

If, now, we short-circuit the cell through a resistance R (Fig. 241), the P.D. between the cell terminals is reduced to some value V given by the relation (pp. 403-404)

$$\frac{E}{V} \text{ or } \frac{V'}{V} = \frac{R+B}{R},$$

B being the internal resistance of the cell. Thus, the point P will now be at a higher potential than the negative plate of the cell E. Hence the galvanometer will now be deflected if contact is made at P. Balance will, however, be restored if we make contact at some point P_1 , nearer to A than P. The P.D. between A and P_1 must be equal to the reduced P.D., V , now existing between the two plates of the cell.

Now

$$\frac{V}{V'} = \frac{AP_1}{AP},$$

if the wire is uniform.

Hence

$$\frac{R}{R+B} = \frac{AP_1}{AP} \cdot \frac{l_2}{l_1}.$$

B can therefore be calculated from the known values of R , l_1 , and l_2 , for

$$B = R \left[\frac{l_1 - l_2}{l_2} \right].$$

EXPT. 231. Determination of the Internal Resistance of a Cell by means of a Potentiometer.—Determine the internal resistance of a Daniell cell by the method described.

DISCUSSION OF THE POTENTIOMETER METHOD OF DETERMINING THE INTERNAL RESISTANCE OF A CELL

This method of measuring Internal Resistances is not much more suitable than the voltmeter method previously described. The cell has to be kept short-circuited through the resistance R for a considerable time, while finding the balance-point P_1 . During this time it is discharging at an appreciable rate, and is rapidly becoming polarised. The result of this is very confusing if its cause is not realised. If the point P_1 is found and the cell disconnected from the resistance for a moment, an entirely different balance-point may be found on reconnecting and testing for balance, in consequence of the cell having recovered somewhat while disconnected.

For accurate work a tapping key should be inserted in the resistance circuit as shown in Fig. 241. This should be depressed *momentarily* while P_1 is being sought, and released again as soon as P_1 is raised from the wire for adjusting to a fresh position along AB .

The second key must, of course, be depressed *before* P_1 , and not raised until *after* P_1 has been raised from contact with the wire.

By the use of this second key greater accuracy is obtainable, but the method possesses all the defects due to polarisation to as great a degree as the voltmeter method: its main advantage is that it is a *null* and not a deflection method. In theory it has other advantages over the voltmeter method: the voltmeter has always an appreciable current flowing through it although supposed to have none, hence E' is never measured correctly by the voltmeter. In the present method the current in the cell is certainly zero when the cell is not short-circuited, and therefore E is obtained accurately.

The greater difficulties met with in use, and the confusion entailed owing to the 'drift' of P_1 towards A due to polarisation, render the potentiometer method of measuring internal resistance suitable only for advanced students.

§ 4. FURTHER APPLICATIONS OF THE POTENTIOMETER

THE POTENTIAL DIVIDER

It is sometimes desirable in experimental work to obtain a difference




FIG. 241A.—Principle of Potential Divider

of potential smaller than that normally available from a given supply. One method of doing this is illustrated in Fig. 241A.

Let the supply be used to send a steady current I through a number

of resistances R_1 , R_2 , R_3 arranged in series. If the potentials at the points A, B, C, D are V_A , V_B , V_C , V_D respectively Ohm's Law gives

$$V_A - V_D = I(R_1 + R_2 + R_3),$$

$$V_B - V_C = I R_2.$$

Dividing the second result by the first we find

$$\frac{V_B - V_C}{V_A - V_D} = \frac{R_2}{R_1 + R_2 + R_3},$$

since the current I has the same value at all points.

If then we keep the *sum* of the resistances, $R_1 + R_2 + R_3$, constant the current I will remain unchanged, but by properly choosing R_2 we can adjust the potential difference between B and C so as to be any desired fraction of $V_A - V_D$.

One way of proceeding used by Lord Rayleigh is to make $R_3 = 0$, so that the points C and D coincide. We may join two large resistance boxes in series and arrange for the total resistance used to remain constant by inserting a plug in one box whenever we remove a plug in the other, having first of all arranged a suitable value for the total resistance. Another plan is to use a long uniform wire for the total resistance and then tap off from it at two selected points B and C. The resulting P.D. will be determined by the length of BC as compared with the total length of the wire.

The principle of the potentiometer¹ depends, as we have seen, on the comparison by a null method of electromotive forces or differences of potential. In the final adjustment no current whatever passes through the measuring instrument. The accuracy possible is great, and by using the method in association with Ohm's Law many important measurements may be made.

Measurement of the Strength of an Electric Current.—Suppose we wish to measure accurately the strength of a current I , being provided with a standard resistance (say 1 ohm) and a standard cell of known E.M.F. When the 1 ohm coil is included in a circuit containing a battery, a regulating resistance and perhaps an ammeter, a certain current flows round the circuit and there will be a definite potential difference (V volts, say) between the ends of the 1 ohm coil. By using a potentiometer we can compare this P.D. with the E.M.F. in volts of the standard cell, and so find the value of V in volts. Then by applying Ohm's Law ($V/I = R$) we find directly the current I in amperes. This enables us to test the reading of the ammeter in the circuit.

The principle of the method is quite straightforward, but the various connections tend to become somewhat complicated, rendering the method suitable only for the more advanced student.

¹ This principle must not be confused with that of Wheatstone's bridge, described in the next chapter.

Comparison of Resistances.—Two resistances may be compared by sending a steady current through the two arranged in series (Fig. 256), and then comparing by the potentiometer method the differences of potential between the terminals of the two resistances. Here too the connections are complicated, and simpler methods are described later (pp. 411-419, 423-427).

THERMOELECTRICITY

Thermoelectric Couples.—When a closed circuit is formed of wires of two different metals, and one junction is at a higher temperature than the other, an electromotive force (E.M.F.) is produced tending to set electricity in motion round the circuit. The electric energy in this thermoelectric or Seebeck effect is obtained from a transformation of heat. The E.M.F. depends on the *difference* of temperature between the junctions, and also on the actual temperatures.

The E.M.F. is comparatively large when antimony and bismuth are the two metals in the thermocouple, and these are frequently used in constructing a thermopile. The current flows as in Fig. 241B from the antimony (A) to the bismuth (B) through the cold (C) junction. For our present purpose it is more convenient to use a thermocouple of iron and copper, and provided the temperatures of the junctions do not differ greatly from atmospheric temperatures the thermoelectric current flows from iron to copper through the cold junction. Since this temperature is conveniently the 'ice point', ICE may be used as a mnemonic. The cold junction may be kept at 0° C. by immersion in a mixture of broken ice and water. The temperature of the hot junction may be adjusted by using a suitable bath or furnace. By connecting




FIG. 241B.—Thermoelectric Couples

two copper wires to the terminals of a low resistance galvanometer and joining the ends by an iron wire, it is easy to show that heating one junction by a spirit lamp gives a deflection which will increase to a maximum value and then diminish — ultimately to zero. The temperature for which the E.M.F. is a maximum is called the **neutral temperature** (about 290° C. for copper-iron). The *maximum* E.M.F. for a copper-iron thermocouple is roughly 1.5 millivolts.

EXPT. 241A. Measurement of E.M.F. of Copper-Iron Thermocouple.—Use Rayleigh's potentiometer method (p. 428) with two resistance boxes R_1 and R_2 in series as shown in Fig. 241c.

Since the E.M.F. is of the order of a millivolt, use as the constant

source S a Daniell cell having an amalgamated zinc plate in a saturated solution of zinc sulphate. The E.M.F. is very nearly 1.07 volt, and if the sum of R_1 and R_2 is constant and equal to 10,700 ohms the current will be $E/10,700$ or $1/10$ milliamperes and the potential drop across 1 ohm will be $1/10$ millivolt. It is assumed that the internal resistance of the cell is negligible in comparison with $R_1 + R_2$.

For R_2 the series resistance coils of a Post Office box may be used, since these coils range from 1 to 5000 ohms, giving a possible total of




Fig. 241C.—E.M.F. of Thermocouple

11,100 ohms. For R_1 a resistance box with 8 coils from 1 to 50 ohms is more than sufficient. Decimal ohm boxes, if available, may be used in addition.

For the two junctions a piece of iron wire (Fe) has its ends joined to two lengths of copper wire (Cu) by twisting or soldering; accidental contacts are prevented by means of narrow glass tubes or beads TT. One junction is kept in melting ice at 0°C .; the other is heated in a suitable bath. For an elementary experiment it will suffice to use a beaker of water which may be heated on a sand bath to 100°C . Since the E.M.F. acts from iron to copper through the cold junction, care must be taken to join the copper wire from the cold junction to the point A of the potentiometer to which is connected the positive (copper) plate of the Daniell cell. Start the experiment with the cold junction at 0°C . and the other junction in cold water at about room temperature. Find the value of R_1 required to give no deflection of the galvanometer, remembering that when a plug is removed from R_1 a corresponding plug must be inserted in R_2 . Warm the water slowly and take a series of observations at various steady temperatures at intervals of about 10° . Further readings may be taken while the water is cooling. Tabulate the results expressing the E.M.F. in microvolts.

For details of experiments at higher temperatures or using other thermocouples see Allen and Maxwell's *Text-Book of Heat*, Part I, pp. 62-65.

MEASUREMENT OF RESISTANCE

§ 1. OHM'S LAW

OHM'S Law states that when two points are taken on a linear¹ conductor the ratio of the difference of potential, E , between those points to the current, I , flowing through the conductor is a constant. This constant ratio E/I is termed the resistance, R , of the conductor. The reciprocal of R is the conductance.

A resistor is a piece of apparatus used on account of its possessing resistance.

The most direct method of measuring resistance is to measure the difference of potential, and the current. If the difference of potential in volts is measured by a voltmeter, and the strength of the current in amperes by an ammeter, the resistance will be obtained in ohms.

Note carefully that the ammeter is connected *in series* with the resistance to be measured, while the voltmeter is connected across the ends of the resistance, so that, with a moving-coil instrument, the coil of the voltmeter is *in parallel* with the resistance. The terminals marked + on the ammeter and the voltmeter must be connected to the + pole of the battery. In this method the resistance of the conductor is measured while a current is flowing through it. The method is therefore applicable in cases where other methods fail; for instance, we can measure in this way the resistance of an incandescent electric lamp while it is glowing (Expt. 247, p. 443).

This is a rough method only, though very convenient in many cases. It depends on the observed deflections of the ammeter and voltmeter, and is thus not so accurate as a *null* method of measuring resistance. If the ammeter and voltmeter have not been calibrated, the result may be erroneous owing to errors of graduation.




FIG. 242.—Measurement of Resistance by Ammeter and Voltmeter

§ 2. WHEATSTONE'S BRIDGE

The comparison of resistances can be carried out in a convenient way by the arrangement known as Wheatstone's Bridge. This consists

¹ By a *linear* conductor is meant a conductor in the form of a line, such as a fine wire. If a graph is drawn showing the relation between E and I a straight line should result, or we obtain a linear graph provided Ohm's Law is obeyed.

of four resistances P , Q , R , and S joined together so as to form four sides of a quadrilateral $ABDC$. If the two corners A and D are joined to the terminals of a cell, a current entering at A divides and flows partly along ABD and partly along ACD . There must be a fall of potential as we pass along ABD , and also as we pass along ACD . By properly adjusting the resistances P , Q , R , and S , the potential at the point B may be




FIG. 243.—Principle of Wheatstone's Bridge

made to have the same value as the potential at C . When this is so, no current would flow through a galvanometer joined to the points B and C . We now proceed to find the condition that must hold between the resistances in the four arms of the bridge for this to be the case.

Let the currents through the arms P , Q , R , and S be I_1 , I_2 , I_3 , and I_4 respectively, and the potentials at the points A , B , C , and D be V_A , V_B , V_C , V_D respectively. For the sake of generality we do not at first assume that $I_1 = I_2$ and $I_3 = I_4$.

Applying Ohm's Law to each branch or arm of the bridge in turn we obtain (since $V_A - V_B$ is the P.D. between A and B)

$$V_A - V_B = I_1 P \quad . \quad . \quad . \quad (1)$$

$$V_A - V_C = I_3 R \quad . \quad . \quad . \quad (2)$$

$$V_B - V_D = I_2 Q \quad . \quad . \quad . \quad (3)$$

$$V_C - V_D = I_4 S \quad . \quad . \quad . \quad (4)$$

But when the bridge is balanced $V_B = V_C$, so that the left-hand side of equation (1) becomes identical with the left-hand side of equation (2). Hence the right-hand sides must be equal.

$$\text{Therefore} \quad I_1 P = I_3 R \quad (5)$$

$$\text{Similarly from (3) and (4)} \quad I_2 Q = I_4 S \quad (6)$$

$$\text{Dividing (5) by (6) gives} \quad \frac{I_1 P}{I_2 Q} = \frac{I_3 R}{I_4 S} \quad . \quad . \quad . \quad (7)$$

But if no current flows along BC , $I_1 = I_2$, and $I_3 = I_4$ and equation (7) reduces to

$$\frac{P}{Q} = \frac{R}{S} \quad . \quad . \quad . \quad (8)$$

When this condition is satisfied and no current flows through the galvanometer, we say that the bridge is balanced.

Properties of Conjugate Conductors.—The battery might have been placed in the arm joining B and C, and the galvanometer in the arm joining A and D, and exactly the same condition would have been required for no current through the galvanometer. The two arms AD and BC are then said to be **conjugate arms** of the bridge. Two arms of a network of conductors are said to be conjugate arms if the current in either arm is entirely independent of any E.M.F. in the other. A cell in either of the arms BC or AD would send no current through the other, therefore BC and AD are conjugate arms of the network. The condition that BC and AD should be conjugate arms is that $P/Q = R/S$.

Determination of the Resistance of a Wire.—Equation (8) shows that if we know the *ratio* of two of the resistances (R to S say) and the actual value of a third (Q), then the fourth resistance (P) is determined when B and C are at the same potential. Similarly if we know the *ratio* of P to Q and the actual value of R , we can find the value of S .

Determination of the Resistance of a Galvanometer—Thomson's (Kelvin's) Method.—The resistance of a galvanometer also can be found by Wheatstone's Bridge.

The galvanometer is connected in the arm AB, the resistance of the galvanometer G being now equal to P . As a constant current flows along AB, a steady deflection is produced in the galvanometer. When the resistances are related in such a way that $P/Q = R/S$, B and C will be at




FIG. 244.—Resistance of Galvanometer

the same potential, and on connecting B and C on current will flow through BC.

When the condition $P/Q = R/S$ is *not* satisfied, some current will flow along BC if these points are connected. Hence the distribution of current through the rest of the network will be altered. Consequently the current in the galvanometer will be altered. Thus, unless B and C are at the same potential, the galvanometer deflection will be altered when B and C are connected. The degree of alteration will depend on the current which flows along BC, therefore to ensure sensitiveness the resistance BC should be made as small as possible, a short piece of copper wire being generally used.

The resistances are adjusted until connecting B and C does not alter the steady deflection of the galvanometer, and $G (=P)$ is calculated from the relation $G/Q = R/S$ which then holds.

Determination of the Internal Resistance of a Cell—Mance's Method.
Suppose a cell is placed in the arm AB, the resistance of the cell being




FIG. 245.—Resistance of Battery

B. Then if $B/Q = R/S$, the arms BC and AD are conjugate arms of the network, and any E.M.F. introduced in the arm BC will not affect the current in AD.

There will be a steady current through the arm AD due to the E.M.F. in AB, and the galvanometer will therefore be deflected permanently. If the condition

$B/Q = R/S$ is satisfied, this deflection will not be affected by any E.M.F. introduced in the arm BC, and so we can test if this relation holds by introducing an E.M.F. in the arm BC: this can be done by connecting a cell across the points B and C.

The *magnitude* of the E.M.F. introduced in the arm BC is quite immaterial, except in so far as it affects the sensitiveness of the test. It can be shown¹ that introducing a cell of small E.M.F. and of very low resistance is as sensitive a test as a cell of larger E.M.F. but greater resistance would offer. We may imagine that an ideal 'cell' of infinitesimal E.M.F. and very low resistance in the arm BC is equivalent to connecting the points B and C by a copper wire and key of low resistance.

In practice this gives a satisfactory means of detecting any error in the adjustment of the resistances. When no change in the deflection of the galvanometer is produced on connecting B and C with a copper wire, the relation $B/Q = R/S$ holds good.

THE SLIDE-WIRE BRIDGE

The method of Wheatstone's bridge may be applied by using the apparatus known as the slide-wire bridge. As the wire employed is frequently one metre in length, this is also often termed the metre bridge.²

A long uniform wire is stretched on a base-board between the two points A and D. The ends are connected by means of thick copper strips, of negligible resistance, to the terminals F and L. HK is another thick

¹ The proof, depending on Kirchhoff's laws (p. 431), is long and cannot be given here.

² As already mentioned (p. 408) the principle of Wheatstone's bridge is not identical with that of the potentiometer, although both depend on Ohm's Law. Compare Fig. 236 with Fig. 246.

copper strip, provided with terminals at H, B, and K. The unknown resistance P is joined to the terminals F and H, so as to complete the circuit in the gap between them. A known resistance of suitable magnitude (that is, not very different from P) is joined to the terminals K and L. In making these connections, short, thick wires or flat strips of copper must be used, so as not to introduce additional unknown resistances. A movable key or jockey, by means of which contact may be made with the slide-wire




FIG. 246.—Slide-wire Bridge

at any point desired, slides along the base-board. Its position may be read off on a fixed scale. The 'ratio arms' of the bridge are the two parts into which the slide-wire is divided by the movable key.

In carrying out the measurement a cell is connected to the end terminals A and D, a key being included in this part of the circuit so that the current can be cut off when no observation is being made. A galvanometer is connected to the central terminal B and to the movable contact C. An astatic or pointer galvanometer is frequently used in elementary work. The object of the manipulation is to find the point at which contact must be made with the slide-wire so as to give no deflection of the galvanometer needle. It is best to start by noting the direction in which the needle moves when contact is made, first near one and then near the other end of the slide-wire. If these deflections are in opposite directions the point sought for must lie somewhere between them. If the deflections are in the same direction in the two cases, it indicates that one of the resistances P or Q is very much greater than the other, or that there is a faulty connection in some part of the apparatus. It is impossible to get an accurate result unless P and Q are at least of the same order of magnitude. Assuming that suitable values have been chosen, the point on the slide-wire for no deflection should be found somewhere in the central portion of the wire. The 'balance point' should be in the middle 'third' of the wire in all cases.

Much time can be saved in carrying out the experiment by learning how to increase and how to decrease the deflection of the needle. Suppose that when contact is made near one end of the slide-wire the deflection is clockwise. Then to increase the swing the contact should be made whenever the needle is swinging in the clockwise direction, and should be broken when the needle is swinging in the opposite direction. To diminish the swing and bring the needle to rest, contact should be made when the needle is swinging in the counter-clockwise direction, and should be broken when the needle is swinging in the clockwise direction.

Having determined as accurately as possible the point on the slide-wire corresponding to no deflection, the distances $AC = l_1$ and $CD = l_2$ are measured.

Then as $\frac{P}{Q} = \frac{R}{S}$, and $\frac{R}{S} = \frac{l_1}{l_2}$, assuming the wire to be uniform, we find

$$\frac{P}{Q} = \frac{l_1}{l_2}$$

Hence, finally

$$P = Q \times \frac{l_1}{l_2}$$

EXPT. 232A.—Measurement of Resistances (a) *Singly*, (b) *in Series*, (c) *in Parallel*.—For this experiment lengths of resistance wire (platinoid or manganin) may be taken, but it is more convenient to use resistance coils of the form shown in Fig. 254. These ‘resistors’ should be marked by some distinguishing letter, and except in a rough measurement the value of any resistance should not differ too much from the resistance of the slide-wire (probably about 1 ohm). One of these resistors (A say) is selected and taken as P in Fig. 246. The known resistance Q may be a small resistance box or a ‘decimal-ohm’ box. The clean plugs should be inserted and removed carefully with a slight screwing motion. Connections between resistors and bridge should be made with thick wires or strips with clean ends. A Daniell cell or a dry cell is suitable, and it should not be connected until all the other connections have been checked. Find the balance point and calculate the value of A as described above. Then *interchange* the known and the unknown resistors and make a fresh determination of the resistance of A. Take the mean of the results obtained. In the same way find the mean values of the resistances of B and C. Next find the resistances of any pair of resistors (b) in series, (c) in parallel and compare the results with those calculated from theory (pp. 391-392). Give the results in tabular form.

RESISTIVITY OR SPECIFIC RESISTANCE

The resistance of a wire of length 1 cm. and of cross-sectional area 1 sq. cm. is called the **resistivity** or the **specific resistance** of the material of which the wire is composed. **Conductivity** is the reciprocal of this.

Let X be a wire 1 cm. in length, and having a cross section of 1 sq. cm. The shape of the cross section is immaterial. Let the resistance of this wire be S ohms. Let Y be a second wire of the same




FIG. 247.—Specific Resistance

material, l cm. in length, and having a cross section of A sq. cm. Let its resistance be R ohms. Since the resistance of a wire is directly proportional to its length, and the length of Y is l times the length of X, the resistance of Y will be l times that of X in consequence of the difference in length. Again, the resistance of a wire is *inversely* proportional to the area of cross section; hence, since the cross-sectional area of Y is A times the cross-sectional area of X, the resistance of Y will be $1/A$ times that of X in consequence of the difference in cross section.

Consequently
$$R = \frac{lS}{A}, \quad \text{or} \quad S = \frac{RA}{l}.$$

So if we can measure R , A , and l we can determine S , which is the resistivity of the material. The resistivity may be expressed in ohms per unit length of a wire of unit cross section. Note carefully that the dimensions of resistivity are ohms \times cm.

EXPT. 232B. Determination of the Specific Resistance of a Wire, using a Slide-wire Bridge.—To measure the resistivity select a wire about a metre in length, free from kinks. Measure its length¹ to the nearest millimetre, and measure the diameter very carefully with a micrometer screw gauge. As the area of cross section A depends on the square of the diameter ($A = \pi d^2/4$ for a wire whose cross section is circular), an error in this measurement is serious; the percentage error in d is doubled in the square of d , so that the result is wrong to *twice* the extent of the error of d . Express the length in centimetres, and the area of cross section in square centimetres.

Next connect the wire across one of the gaps P in the thick copper strip of the slide-wire bridge, connecting a 'decimal-ohm' box across the corresponding gap Q on the other side of the bridge (Fig. 246). Thick copper connectors must be used for joining the box to the sides of the gap, and these must be cleaned where they fit under the connecting screws. The connections for the battery and the galvanometer are shown in the same figure. A Daniell cell is suitable for this purpose, with some form of simple astatic galvanometer. Adjust the decimal-ohm box to a resistance of 1 ohm. Slide the jockey along the slide-wire, making contact with the wire at various points; *the jockey must not make contact with the wire while it is moving along*, otherwise the wire will be worn unevenly in various parts and the accuracy of the bridge destroyed.

Find two points at which definite deflections are produced, but in opposite directions at the two points; the balance-point must lie between these two.

By working between these two points, successive pairs of points can be found which give deflection in opposite directions, each pair being closer together than the previous pair. It may happen finally that two points are found at which the deflection produced in the galvanometer is inappreciable, though at any point beyond either of them a deflection can be observed. The balance-point may be taken as the centre of that part of the wire between these points.

The resistance of the wire P can be calculated by means of the expression

$$P = \frac{l_1}{l_2} Q,$$

Q being the value of the resistance in the resistance box, l_1 , the length of the wire from A to C , and l_2 , the length of the remainder from C to D .

The point C should be in the middle 'third' of the slide-wire; if this is not the case a different value of Q must be taken to bring C into this part of the wire. Three different values of Q must be used in any case, and the corresponding balance points found, the values of P being calculated for each case. If the experiment has been performed accurately these three values of P will be the same to a very close approximation; their mean is taken as the true value of P .

From the value of the resistance thus obtained, and the dimensions of the wire already determined, calculate the specific resistance of the material of the wire from the expression

$$S = \frac{RA}{l}.$$

¹ The length required is not the whole length of the wire, but the length which is between the terminals when the resistance is being measured.

Expt. 233. Determination of the Resistance of a Galvanometer.—For this experiment connect up the slide-wire bridge as in Fig. 248. Q is a decimal-ohm box adjusted to 1 ohm at first, r is a large resistance which need not be known. In this case the galvanometer itself forms the unknown resistance P in one of the arms of the bridge. The connection BC is made with a piece of copper wire. It is clear that as soon as the battery is connected to the points A and D , a current must flow through the galvanometer and cause a deflection of the needle. The bridge is




FIG. 248.—Resistance of Galvanometer

balanced when this deflection is unaltered upon making contact between the points B and C by means of the jockey key. When this condition is satisfied no current flows in BC , and the potential at B must be the same as that at C , and, as in the previous case,

$$\frac{P}{Q} = \frac{R}{S}.$$

If a key be used in the battery branch, it should be a plug key and not a tapping key, since it is necessary to get a steady current through the bridge before making contact at C . If the steady deflection of the galvanometer be large, the alteration produced by making contact at C will be very small. A large deflection may be reduced by employing a smaller current. This is secured by introducing a resistance box r in the battery branch, using sufficient resistance to give a convenient deflection. In the case of a mirror galvanometer with a moving needle, the controlling magnet may be used to bring the spot of light back on to the scale.

The method is not easy to carry out, the difficulty being that the galvanometer is deflected considerably the whole of the time, and often the needle is in a position where the sensitiveness of the galvanometer is only small. As a result of this, the adjustment of the point C may be altered appreciably without making any noticeable change in the deflection; consequently the accuracy obtainable is not very great when a metre bridge is used. Considerably greater accuracy is obtained with a P.O. box if suitable means are adopted (Expt. 236).

Expt. 234. Determination of the Resistance of a Cell.—The cell whose resistance is to be measured is placed in the position of the unknown resistance P , so that it forms one arm of the bridge. The galvanometer is connected directly to the two extreme points of the bridge A and D . In this case also a steady current flows through the galvanometer as soon as the connections have been made. The jockey C is adjusted so that no alteration is produced in the deflection of the galvanometer by making connection at C . When this condition is satisfied $P/Q = R/S$ (p. 413). If the steady deflection of the galvanometer be too large, a resistance r

must be introduced in series with the galvanometer so as to diminish the current passing through it. The connections are the same as those used when determining the resistance of a galvanometer, except that the galvanometer and battery are interchanged. Q is adjusted to 1 ohm to




FIG. 249.—Resistance of Cell

start with, and the point C is found where the steady deflection of the galvanometer is unaltered on depressing the jockey.

If the point C is not in the middle third of the wire when Q is 1 ohm, a different value of Q must be used, choosing this value so as to bring C near to the middle of the wire.

The resistance of the battery is then calculated from the expression

$$B = Q \cdot \frac{l_1}{l_2}$$

THE POST-OFFICE BOX

In the account of Wheatstone's bridge we have seen that when the bridge is balanced the four resistances P , Q , R , S , which form four sides of a quadrilateral figure, satisfy the relation

$$\frac{P}{Q} = \frac{R}{S}$$

If we know the ratio of P to Q , and R is a known resistance, then the fourth resistance S , previously unknown, is determined.

In the Post-Office Box we find sets of resistance coils representing three of the arms of the bridge, namely, two *ratio arms*, P and Q , and an *adjustable arm* for the known resistance R . The fourth arm S is the unknown resistance whose value is to be found.

The distinguishing characteristic of the ratio arms P , Q is that they are two portions of the box, usually comprising together the whole of one bar, with identically similar sets of resistances, 10, 100, 1000, and sometimes 10,000 ohms in each. The whole of the rest of the resistances in the box comprise the third arm R of the bridge. The actual arrangement of the resistances in the box differs in different patterns, but the student should have little difficulty in identifying the ratio arms and the adjustable arm, and then determining the points corresponding to A , B , C , D in Fig. 243. In this diagram the battery is connected to the terminals A and

D, and the galvanometer to the terminals B and C. It should, however, be noted that the positions of the battery and galvanometer may be interchanged without affecting the final result, that is, the battery may be connected to the terminals B and C and the galvanometer to A and D. A tapping key must be inserted in the battery circuit, and a second in the galvanometer circuit. In some forms of Post-Office Box these keys are included in the box, and the connections between the keys and the corners




FIG. 250.—Two Forms of Post-Office Box

of the bridge are indicated by white lines traced on the ebonite cover of the box. The battery key must be depressed *first*, to avoid self-induction effects.

Another arrangement sometimes used is a double key which makes contact first for the battery, and subsequently for the galvanometer.

The unknown resistance should be connected to the points C and D by means of short thick wires, or flat copper strips, of small resistance.

A mirror galvanometer, which may be either of the moving needle or of the moving coil type, is generally used with the Post-Office Box. For a description of these instruments see the section on galvanometers, pp. 475-481.

The top of the box is usually marked at different points with the cryptic letters, C, Z, E, L, G, or perhaps a letter B is used instead of C and Z. These mean respectively Carbon, Zinc (or Battery), Earth, Line, and Galvanometer.

If the box be connected up by the aid of these letters, the experiment usually works successfully, but little benefit is gained from it. The student should avoid using them, and should rely on the connections worked out by himself with the aid of suitable diagrams.

The Galvanometer Shunt.—If a very sensitive galvanometer be used, it must be provided with a shunt, so that its sensitiveness may be varied to suit the requirements of the moment. In its simplest form the shunt consists of a resistance which is placed in parallel with the galvanometer (Fig. 231). A delicate galvanometer is provided usually with a shunt box containing a number of resistances which may be marked $1/9$, $1/99$, $1/999$. This means that the resistances in the box are respectively $1/9$, $1/99$, and $1/999$ of the resistance of the galvanometer. In the present experiment the plug belonging to the shunt should be placed at the outset in the hole marked $1/999$. In this case only $1/1000$ of the current in the galvanometer circuit passes through the coils of the galvanometer, and consequently the instrument is not very sensitive.

When an approximate balance has been obtained, the plug may be shifted to the hole marked $1/99$, or that marked $1/9$. For the final adjustment the plug may be removed altogether so that the full current passes through the galvanometer, and the arrangement is as sensitive as possible.

EXPT. 235. Determination of the Resistance of a Wire by Means of a Post-Office Box.—Connect up the wire, the battery, and the galvanometer to the P.O. Box after working out the proper connections by the aid of the foregoing description and diagrams (pp. 411-412, 419-420).

When the connections have been made, remove the plugs marked 10 in the ratio arms of the bridge. The ratio of P to Q is then 10 : 10, that is a ratio of equality; and for the bridge to be balanced, R, the adjustable arm, must be equal to S, the unknown resistance. Shunt the galvanometer with the 1/999 shunt if a shunt box is supplied, and see that all the plugs in R are in place. Make contact momentarily with both keys and note the direction in which the mirror of the galvanometer is deflected. As this deflection is probably very great, it is usually better in this stage of the experiment to watch the mirror itself instead of the spot of light on the scale. Next remove the plug in R marked 'infinity', and again note the deflection. It should be in the opposite direction to that previously observed. From these observations the experimenter should construct a simple rule to be borne in mind during the remainder of the determination: 'When the deflection is to the right (or to the left, or away from me, as the case may be) the resistance of the adjustable arm is too large'.

Replace the infinity plug and take out another (say 1000 ohms) and notice the deflection, seeing whether the resistance is too large or too small. Determine in this way limits between which the resistance must lie, and proceed till the value of the resistance S is found correct to the nearest ohm. Suppose S is found to be between 6 and 7 ohms.

To determine the next decimal place, that is to find the value of S correct to 0.1 ohm, remove the plug from the 100-ohm coil in P and insert the plug in the 10-ohm coil. Then the resistance in P is 100 ohms, that in Q is still 10 ohms. The ratio of P to Q is 100 : 10 or 10 : 1. Consequently, when the bridge is balanced, R must be 10 times S. Adjust the resistance R till an approximate balance is obtained. If S lies between 6 and 7 ohms, R must lie between 60 and 70 ohms. Suppose it is found to lie between 63 and 64 ohms. Then the value of S lies between 6.3 and 6.4 ohms.

Next remove the plug from the 1000-ohm coil in P and insert the plug in the 100-ohm coil. Then the resistance in P is 1000 ohms, that in Q is still 10 ohms. The ratio of P to Q is 1000 : 10 or 100 : 1. Consequently, for a balance, R must be 100 times S. It is clear that R must now lie between 630 and 640 ohms. Suppose it is found to lie between 638 and 639 ohms. Then the value of S must lie between 6.38 and 6.39 ohms.

With a sensitive galvanometer yet another decimal figure may be found by noting the resting-points of the spot of light on the scale when R is adjusted to 638 and to 639 ohms, and using the method of 'proportional parts'. If, for example, 638 ohms give 6 mm. on one side, and 639 ohms give 9 mm. on the other side of the galvanometer zero, a difference of 1 ohm in R causes a change of 15 mm. Therefore a change of 6 mm. means 0.4 ohm, so that $R = 638.4$ ohms and $S = 6.384$ ohms.

Determine in this way the resistance of a coil to within 0.1 per cent.

Determine also the resistance of a piece of wire, and calculate the specific resistance of the material of the wire.

When the unknown resistance S is large, it may not be possible to find its value correct to the $\frac{1}{100}$ th part of an ohm, or even to the $\frac{1}{10}$ th part of an ohm, with the coils supplied in the ordinary Post-Office Box. In such a case it should be noted that, as a rule, the bridge is most sensitive when the four arms of the bridge are approximately equal.

When the unknown resistance is very large, it may be necessary to

make the resistance Q 10 times or even 100 times the resistance P in order to obtain a balance by adjusting R . Then the resistance S will be 10 times (or 100 times) the resistance R .

EXPT. 236. Determination of the Resistance of a Galvanometer.—The principle of the method is the same as with the slide-wire bridge (p. 414). The galvanometer forms the fourth arm of the bridge, as the unknown resistance S . A tapping key is not used in the battery branch. As soon




FIG. 251.—Resistance of Galvanometer

as the connections are completed the spot of light usually goes right off the scale. The use of a galvanometer shunt is not admissible in this case.

The chief difficulty met with in this form of experiment is due to the great sensitiveness of the galvanometer. This causes it to stay obstinately pressed against one side of the case, however much the controlling magnet is turned. To avoid this trouble, the following means should be employed:—*First*, introduce a considerable resistance in the battery arm; a resistance adjustable up to 10,000 ohms may

be used conveniently if the galvanometer is a specially sensitive one. *Secondly*, use ratio arms of the lowest possible resistance, both equal to 10 ohms if possible. *Thirdly*, reduce the sensitiveness of the galvanometer by lowering the control magnet until the period of swing is very short. See the notes on galvanometers, p. 477. (This third method is not possible in the case of suspended-coil galvanometers.)

It will now be found that the spot of light does not move much beyond the scale, if at all, and it can be brought back by use of the control magnet, or by turning the top of the suspending fibre in a suspended-coil galvanometer.

Make the requisite adjustment of R so that when the key K is pressed there is no change in the position of the spot of light.

It will generally be found that R can be varied over a wide range without affecting the position of the spot, as the arrangement is now so insensitive. The sensitiveness may now be increased again *very gradually*, first by raising the control magnet. On reaching the limit of increased sensitiveness—consistent with control of the position of the spot—obtainable by this means, the ratio arms may be *both* increased to 100 ohms each. This allows a bigger current to pass through the galvanometer, and a large increase of deflection results. Correct this deflection by rotating the control magnet, but do not *lower* the magnet again; then adjust R as before to give no change in the position of the spot on pressing the key.

With a galvanometer of the suspended-coil type, the ratio arms are increased at once to 100 and the increased deflection corrected by further twisting the fibre.

The adjustment will now be more delicate than before. The sensitiveness is increased still further by increasing the ratio arms to 1000. Not until the extreme limit of sensitiveness has been reached in this way must the resistance r be diminished. If necessary, the ratio arms may be adjusted later to give 10/1 in the case of galvanometers of resistance lower than 1000 ohms, the same precautions being taken as to sensitivity and control.

The battery and key *must* be connected as shown in Fig. 251 if these means of reducing the sensitiveness are employed, otherwise reducing the resistance of the ratio arms will not have the desired effect.

If the experiment be carried out carefully as described above, the resistance of the galvanometer can be determined quickly and conveniently. This method enables a student to carry out this experiment with a gratifying sense of certainty.

EXPT. 237. Determination of the Resistance of a Battery.

The battery forms the unknown arm S of the bridge. Keys are not used for the battery or the galvanometer, but a tapping key is employed in the diagonal branch BC. The methods available for diminishing the steady deflection of the galvanometer are exactly the same as those described in the determination of the resistance of the galvanometer. The simplest statement of the arrangement is to say that the positions of the battery and of the galvanometer are merely interchanged, every other connection, including the resistance r , being left absolutely the same as in the measurement of the galvanometer resistance; and the adjustments are made in exactly the same way.

When P, Q, and R are adjusted so that the galvanometer deflection remains unaltered when the key K is depressed, the battery resistance is given by

$$\frac{P}{Q} = \frac{R}{B'}$$




FIG. 252.—Resistance of Battery

§ 3. WHEATSTONE'S BRIDGE : CAREY FOSTER'S METHOD

The ordinary slide-wire pattern Wheatstone's Bridge is not susceptible of very great accuracy when employed in the usual way. It is impossible to find the position of the balance-point to within 1 mm., and with a slide-wire 1 m. long this uncertainty introduces a possible error of $\frac{1}{250}$ at least. If the balance-point be not at the middle of the wire, the uncertainty of the result is greater than this. A longer slide-wire can be used if desired, and the relative magnitude of an error of 1 mm. is correspondingly reduced; but the use of a slide-wire longer than 1 m. is inconvenient.

In Carey Foster's arrangement the *effective* length of the slide-wire is increased without actually using a wire of more than the normal length, by introducing resistances in series with the wire, one at each end. The connections are as indicated in Fig. 253. The arms of the bridge, P and Q (Fig. 243), are the resistances R_1 and R_2 respectively, the remaining arms R and S being composed of X plus a length l_1 of bridge-wire, and Y plus the remainder of the bridge-wire (l_2).

When the bridge is balanced, we have the relation (8), Chap. V, § 2, p. 412,

$$\frac{P}{Q} = \frac{R}{S}$$

now stated as

$$\frac{R_1}{R_2} = \frac{X + l_1\rho}{Y + l_2\rho}, \quad (1)$$

where ρ is the resistance of 1 cm. of the bridge-wire. If X and Y are together equal to about ten times the resistance of the bridge-wire, the terms $l_1\rho$ and $l_2\rho$ are of the order of 10 per cent of X and Y . Any




FIG. 253.—Carey Foster's Method

error in reading l_1 is thus reduced to about $\frac{1}{10}$ th of the relative magnitude it has when the bridge is used in the ordinary way, an error of 1 mm. corresponding with an error of $\frac{1}{2500}$ in the result instead of $\frac{1}{250}$.

By elementary algebra (*componendo*) equation (1) leads to the relation

$$\frac{R_1}{R_1 + R_2} = \frac{X + l_1\rho}{X + Y + (l_1 + l_2)\rho}. \quad (2)$$

Now let the resistances X and Y be interchanged, and a new balance point found at distances l_1' and l_2' from the ends of the wire. Then we have

$$\frac{R_1}{R_2} = \frac{Y + l_1'\rho}{X + l_2'\rho}, \quad (3)$$

from which we obtain by the same method as above

$$\frac{R_1}{R_1 + R_2} = \frac{Y + l_1'\rho}{X + Y + (l_1' + l_2')\rho}. \quad (4)$$

The left-hand sides of equations (2) and (4) are identical and the denominators of the fractions on the right-hand side are exactly equal since $l_1 + l_2 = l_1' + l_2'$.

Hence

$$X + l_1\rho = Y + l_1'\rho \quad (5)$$

or

$$X - Y = (l_1' - l_1)\rho. \quad (6)$$

This result is of great importance because by means of it we can determine the value of ρ by using known resistances X and Y as in Expt. 238A. Further, when we have once determined ρ for the slide-

wire we can use equation 6 to find the *difference* between two nearly equal resistances, one of which may be a standard coil.

End Corrections.—If the bridge-wire is soldered imperfectly at the ends where it joins the copper strips, the joint may introduce an appreciable resistance into the arms R and S, and the true ratio R_1/R_2 should be expressed as

$$\frac{R_1}{R_2} = \frac{X + l_1\rho + \lambda_1\rho}{Y + l_2\rho + \lambda_2\rho},$$

λ_1 and λ_2 being the **end corrections** expressed as equivalent lengthenings of the two parts of the wire.

By following the method of working already described, the effects of these end corrections can be eliminated when using the slide-wire bridge in Carey Foster's arrangement. This result, which was described in full in earlier editions, is now left as an exercise for the student.

Slight errors due to thermoelectric E.M.F.s can be eliminated by reversing the battery connections and taking the mean of the readings for l_1 and for l_1' .

Carey Foster's method is only suitable in dealing with two resistances X and Y provided they are nearly equal, as for comparing a home-made resistance with a standard resistance to which it is supposed to be equal. This is, however, a type of experiment which frequently has to be performed in practice, and the arrangement described is a convenient method of carrying it out with simple apparatus. One great advantage of the method lies in the fact that R_1 and R_2 need not be known accurately: it is only necessary that they should be approximately equal and absolutely constant. They should have about the same value as X and Y.

EXPT. 238A. Determination of ρ in Carey Foster's Bridge.—Remove the coils from the end gaps of the bridge, and close the first gap with a thick copper strip. Then $X = 0$. In the other gap insert a decimal-ohm box, connecting it to the terminals of the bridge by copper strips of negligible resistance. Use a resistance of 0.1 ohm in this box for Y. Determine the point of balance, and let it be x_1 cm. from the end I of the wire. Interchange the positions of the copper strip and the decimal-ohm box, and let the new position of the balance-point be y_1 cm. from the same end of the wire.

Then by substituting in the general equation

$$X = Y + (l_1' - l_1)\rho,$$

we find

$$0 = 0.1 + (y_1 - x_1)\rho,$$

so that

$$\rho = \frac{0.1}{x_1 - y_1}.$$

Similarly if 0.2 ohm is used for Y, and the corresponding balance points are x_2, y_2 cm. from the end of the wire,

$$\rho = \frac{0.2}{x_2 - y_2}.$$

Since the difference between x_2 and y_2 is greater than the difference between x_1 and y_1 , this result is more accurate than the former.

By using still larger values for Y still greater accuracy is secured, but Y must be less than the resistance of the slide-wire itself.

Calculate ρ the resistance of the bridge-wire per cm. Having determined the value of ρ as in Expt. 238A, use the result to find the resistance of the coil under test in terms of the standard ohm.

EXPT. 238B. Construction of a 1-ohm Coil.—Determine the resistance of a piece of manganin or constantan wire by means of a metre bridge (p. 417). Calculate what length of the wire must be used to make a resistance of 1 ohm.




FIG. 254.—1-ohm Coil

If very great accuracy be not required, cut off a piece a few centimetres longer than this. Solder it to two stout copper strips, or to two terminals mounted on the top of a wooden bobbin. Redetermine its resistance, and shorten the wire to the required amount by twisting the middle part of the loop together, soldering the twisted part of the wire when the adjustment is correct.

If very great accuracy be required, cut off a length of wire about 10 per cent longer than the calculated length for 1 ohm. Solder it to two terminals as already described, and redetermine its resistance very accurately. Calculate what length of similar wire would have to be connected *in parallel* with it in order that the resistance of the two together, when connected in parallel, shall be 1 ohm.

If the above instructions have been carried out carefully, the length required for the parallel wire should be about ten times as long as the piece originally cut off.

Cut off this length, and solder it in parallel with the first length across the terminals of the bobbin. Take each loop of wire, and draw it out so that the halves of the loop lie close together and parallel. Wrap the two loops separately round the bobbin, taking the halves of each loop round and round in the same direction. Fix the double end of each loop to the wood of the bobbin with sealing-wax, taking care not to make too sharp a bend at the end of the loop.

Wrap tape round the coils thus formed and immerse the whole in molten paraffin wax.

It is desirable to test the resistance before wrapping and waxing the coil, if great accuracy is required. If the resistance is not quite exact, the final adjustment is made by twisting together the end of the loop to the middle of the longer wire, soldering together the twisted end when the adjustment is exact.

EXPT. 239. Standardisation of a 1-ohm Coil by Carey Foster's Bridge.—Connect two nearly equal resistances across the middle gaps of a slide-wire bridge. Two coils of approximately 1 ohm each are suitable for this purpose; these constitute the resistances R_1 and R_2 (Fig. 253).

In the extreme gaps insert the resistance to be standardised, and a standard resistance of 1 ohm; the standard resistance is represented by Y in Fig. 253, and the other resistance is X .

Find the point of balance when a galvanometer and a cell are connected as in Fig. 253—let this be l_1 cm. from the end I of the wire as shown.

Interchange the resistances X and Y , and again find the balance

point; this will probably be in a different position, say at a distance l_1' from the end I.

Then

$$X = Y + (l_1' - l_1)\rho,$$

where ρ is the resistance of the bridge-wire per cm.

COEFFICIENT OF INCREASE OF RESISTANCE WITH TEMPERATURE

The ratio of the difference of potential between two points of a wire to the current through the wire is constant only when the temperature is constant. In other words, the resistance of a wire varies with temperature, and, in general, the resistance at a higher temperature is greater than the resistance at a lower temperature. The increase of resistance per degree rise of temperature is approximately constant for the same wire. The Coefficient of Increase of Resistance with Temperature is the Increase of Resistance per degree, divided by the Resistance at 0° C.

Thus, if

$$R_0 = \text{resistance at } 0^\circ \text{ C.},$$

and

$$R_t = \text{resistance at } t^\circ \text{ C.},$$

the mean value of the coefficient over this range is

$$a = \frac{R_t - R_0}{R_0 t}.$$

Thus, if a is constant,

$$R_t = R_0 (1 + at).$$

To determine a , it is necessary to measure the resistance at two different temperatures. It is convenient to select the freezing point and the boiling point of water as the temperatures of observation. The value then obtained for a is the mean value between 0° C. and 100° C.

The accuracy with which a is determined depends on the accuracy with which the *change* in resistance may be measured. Since $R_t - R_0$ is the *small* difference between two large quantities, each resistance must be measured most carefully. Thus, if the change of resistance be $\frac{1}{10}$ of R_0 , an error of 0.1 per cent in R_0 or R_t becomes an error of 1 per cent in $R_t - R_0$. An accurate P.O. Box may be used for measuring the resistances, but when the resistance is of the order of 1 ohm Carey Foster's method (p. 423) is to be preferred for this determination.

EXPT. 240. Determination of the Temperature Coefficient of Resistance for Platinum.—A small coil of fine platinum wire, having a resistance of about 1 ohm, is fitted with thick copper leads and placed inside a glass tube closed at the lower end. The leads outside the tube are of flexible wire. An exactly similar set of leads simply soldered together at the lower ends is also provided. These are called the *compensating leads*. The ends of the leads are fitted with copper connecting forks, those connected with the platinum being lettered PP and those attached to the compensating leads being lettered CC. A metre bridge with four gaps is required. In the two inner gaps of the bridge connect two *exactly equal* resistances R , R (1-ohm coils are suitable). Connect the terminals marked PP in one of the outer gaps. Connect one of the C terminals to one side of the other gap, the other C terminal to a terminal of an adjustable resistance box S containing ohms and decimals of an ohm. The second terminal of this resistance box must be connected to the other side of the gap by a thick copper strip. Connect a mirror galvanometer to the terminals A and D, and the battery to B and C.

The battery is connected to the tapping key on the slide-wire to obviate heating effects due to the current, for with this arrangement the current only flows during the moment the adjustment is being tested. The adjustment for balance is correct when there is no *immediate* deflection on depressing the tapping key. If the key is kept down for a




FIG. 255.—Temperature Coefficient of Resistance

short time, the platinum becomes heated by the passage of the current, its resistance changes, and the balance is no longer correct.

The arrangement described forms a Wheatstone's network, shown diagrammatically in Fig. 255. When the point of balance is found,

$$\frac{R}{R} = \frac{P + r + xp}{r + S + (100 - x)\rho}$$

where P = resistance of platinum coil,

r = resistance of connecting (or compensating) leads,

x = distance of point of balance from one end of bridge-wire,

ρ = resistance of 1 cm. of bridge-wire.

Now

$$\frac{R}{R} = 1,$$

consequently

$$P + r + xp = r + S + (100 - x)\rho$$

or

$$P = S + (100 - 2x)\rho.$$

NOTE.—The value of P should be calculated from the result obtained when S is adjusted so that the balance point is as near as possible to the middle of the slide-wire.

Determination of ρ .—Place the tube containing the platinum coil in melting ice, and obtain a balance point with S equal to 1 ohm; let this be x_1 cm. from the end of the wire. Alter S to 1.1 ohms and find the new balance point; let this be x_2 cm. from the end. Alter S to 1.2 ohms, and let the balance point be x_3 cm. from the end.

Then

$$P = 1 + (100 - 2x_1)\rho,$$

$$P = 1.1 + (100 - 2x_2)\rho,$$

$$P = 1.2 + (100 - 2x_3)\rho.$$

Hence

$$1 + (100 - 2x_1)\rho = 1.1 + (100 - 2x_2)\rho,$$

so that

$$\rho = \frac{0.1}{2(x_2 - x_1)}.$$

Similarly, from the first and third observations,

$$\rho = \frac{0.2}{2(x_3 - x_1)}$$

The second value is probably the more correct, though the average might be taken for use.

Determination of P at the Freezing Point and the Boiling Point.—The resistance of the platinum spiral can be calculated from the observations already made, since the value of ρ has been determined.

The resistance at the boiling point is determined by finding a point of balance when the tube containing the coil is placed in a hypsometer and surrounded by steam. The value of S must be adjusted so that the point of balance comes on the bridge-wire and as near the middle as possible. The temperature of the boiling point should be corrected for atmospheric pressure at the time of the experiment.

Calculate the mean value of the temperature coefficient of resistance between the freezing point and the boiling point.

The mean coefficient for any given range of temperature may be determined by finding the resistance R_1 and R_2 at the limits of the range. The temperatures t_1 and t_2 may be found by using a mercury thermometer to take the temperature of the bath in which the platinum spiral is immersed.

Then $R_1 = R_0(1 + \alpha t_1)$ and $R_2 = R_0(1 + \alpha t_2)$.

Hence, by division,

$$\frac{R_2}{R_1} = \frac{1 + \alpha t_2}{1 + \alpha t_1},$$

giving

$$\alpha = \frac{R_2 - R_1}{R_1 t_2 - R_2 t_1}.$$

§ 4. COMPARISON OF RESISTANCES BY THE FALL OF POTENTIAL METHOD

When two resistances are included in the same circuit so that the same current is flowing through each, we can compare the resistances




FIG. 256.—Comparison of Resistances

if we can compare the potential differences between the ends of the two resistances.

Let DE and FG be two resistances, whose values are r_1 and r_2 respectively, and let them be included in a circuit containing any other resistance R and a battery B . Then the same current I flows through each part of the circuit.

If V stands for the potential at any point, we have, in accordance with Ohm's Law,

$$V_D - V_E = Ir_1$$

and

$$V_F - V_G = Ir_2$$

Consequently

$$\frac{V_D - V_E}{V_F - V_G} = \frac{r_1}{r_2}$$

Hence, if we can compare the fall of potential between D and E with that between F and G, we can find the ratio of r_1 to r_2 . This method is specially suitable for low resistances.

EXPT. 241. Comparison of two low Resistances.—Connect in series a 2-volt cell, a large adjustable resistance R , and the two low resistances r_1 and r_2 , as in Fig. 256.

If we determine the ratio of the differences of potential between DE and FG, we can find the ratio of r_1 to r_2 : if either of these is known, the value of the other can be found.

In order to compare the fall of potential in one case with that in the other, all that is necessary is to connect the points D and E to a *high-resistance* galvanometer (virtually a voltmeter) and observe the deflection, and afterwards to connect the points F and G to the same galvanometer and again observe the deflection. A double-pole throw-over switch is convenient for this experiment (p. 487).

If d_1, d_2 are the deflections (assumed small) in the two cases,

$$\frac{V_D - V_E}{V_F - V_G} = \frac{d_1}{d_2}$$

Hence

$$\frac{r_1}{r_2} = \frac{d_1}{d_2}$$

Compare in this way the resistance of a metre of copper wire of about 20 standard wire gauge, and a standard resistance of 0.1 ohm. Find the resistance of the copper wire in ohms, and from this and the dimensions of the wire determine the specific resistance of copper.

This is a very useful method of comparing resistances, and deserves more attention than it has received. The principle is applicable in the case of the comparison of very small resistances. In some cases a quadrant electrometer may be used in place of the high-resistance galvanometer. It is, of course, a deflection method, and is therefore not so accurate as Kelvin's Double Bridge, which is a null method. This experiment is too advanced to be described in this book.

§ 5. MEASUREMENT OF HIGH RESISTANCES

The ordinary form of Post-Office Box may be used to measure resistances up to 1,000,000 ohms. By having resistances of 10 ohms and 1000 ohms in the ratio arms P and Q (Fig. 250) the unknown resistance may be 100 times as large as the resistance of the adjustable arm, which is usually not greater than 10,000 ohms. Thus the unknown resistance may be 1,000,000 ohms. To measure a resistance greater than this a modification of the substitution method may be employed. A battery of constant E.M.F. is used to send a current through the high resistance placed in series with a sensitive galvanometer, and the deflection is ob-

served. The same battery is then connected through a large adjustable resistance to the galvanometer, but the galvanometer is now *shunted* so that only a known fraction of the total current passes through it. If it be possible to obtain the same deflection as before, the unknown resistance can be calculated. If the adjustable resistance be not large enough to make this possible, the deflection obtained with the largest available resistance is noted, and the calculation is carried out on the assumption that the deflection is proportional to the current through the galvanometer. Another method that may be used in such a case is to vary the applied E.M.F. in a known manner, as by varying the number of cells in a battery composed of cells of equal E.M.F.

In measuring high resistances the various parts of the apparatus must be insulated carefully: thus no wires should be allowed to touch the table, as the resistance of the wood may be comparable with the resistance that is being measured.

EXPT. 242. Measurement of the Resistance of a Carbon Strip.—A suitable high resistance for this experiment may be constructed by fixing two terminals to an ebonite base, and drawing lines from one terminal to the other with a black-lead (graphite) pencil. The apparatus should be provided with a cover to protect the carbon strips from damage.

Connect the unknown resistance in series with a battery giving an E.M.F. of 6 or 8 volts, a plug key and a sensitive mirror galvanometer. Observe the deflection d_1 produced when the whole of the current passes through the galvanometer.

Remove the unknown resistance, and in its place put an adjustable large resistance — a Post-Office Box will serve the purpose. Shunt the galvanometer with a coil having a resistance $\frac{1}{1000}$ of the galvanometer resistance, so that only $\frac{1}{1000}$ of the total current passes through the galvanometer. Adjust the resistance so that the deflection obtained is the same as that previously observed. Then as the *total* current is now 1000 times that in the first part of the experiment, the unknown resistance must be 1000 times the resistance in the resistance box.

If it be impossible to obtain in this way a deflection as small as that observed in the first part of the experiment (d_1), note the deflection (d_2) obtained with 10,000 ohms in the box and the galvanometer shunted so that $\frac{1}{1000}$ of the total current passes through it. Since the deflection may be assumed proportional to the current, and the current is inversely proportional to the resistance, the unknown resistance has the value

$$1000 \times 10,000 \times \frac{d_2}{d_1}.$$

Calculate the unknown resistance from the deflections observed.

KIRCHHOFF'S LAWS

Two generalisations due to Gustav Kirchhoff are useful in solving problems about currents in a system of wires forming a network.

The first law relates to the 'continuity of current' when a number of conductors meet at a point, and states that when the currents are steady there is no accumulation of electricity at any point.

LAW I. The algebraic sum of all the currents which meet at any point is zero, or $\Sigma I = 0$. Currents flowing towards the point must be given one sign, those flowing from it the opposite sign.

LAW II. In any closed circuit or mesh the algebraic sum of all the electromotive forces in that circuit is equal to the algebraic sum of the products of the current and resistance in each branch of that circuit, or $\Sigma E = \Sigma IR$. Attention must be paid to the sign of each E.M.F. and each current.

CHAPTER VI

ELECTROLYSIS—ELECTROCHEMICAL EQUIVALENTS

§ 1. ELECTROLYSIS

LIQUIDS which are decomposed when an electric current passes through them are termed **electrolytes**, and the process of decomposition is called **electrolysis**. Solutions of salts and acids in water, and certain compounds, when fused, are decomposed by the passage of a current, the products of decomposition appearing only at the plates where the current enters or leaves the electrolyte. These plates are termed the **electrodes**, that where the current enters being called the **anode**, the other the **cathode** or **kathode**. Thus, inside the **electrolytic cell**,¹ or **voltameter**, as it was often called, *the conventional current flows from the anode to the cathode*. The metallic (electropositive) ions, including hydrogen ions, are carried along with the current towards the cathode. In his *Experimental Researches* Faraday writes: 'I propose to distinguish such bodies by calling those *anions* which go to the anode of the decomposing body; and those passing to the *cathode*, *cations*; and when I shall have occasion to speak of these together, I shall call them *ions*'.

It was proved by the experiments of Faraday that the mass M of a radicle set free by the passage of a current is directly proportional to the quantity of electricity, Q , which has passed through the voltameter. But $Q = It$, where I is the strength of the current (assumed steady) and t the time during which the current has passed. Hence M is proportional to It .

If the same current be passed through several voltameters in series containing different electrolytes, the number of ions that enter into chemical action in a given case is proportional to the **chemical equivalent** of the ion concerned. The chemical equivalent is the mass of an ion or radicle, which will replace, or combine with, one part by mass of hydrogen. In the case of an element the chemical equivalent is equal to the atomic mass divided by the valency. Thus for silver, atomic mass 107.88, valency 1, the chemical equivalent is 107.88. For copper, atomic mass about 63, the chemical equivalent in a cuprous

¹ The large vessel used in industry is called an *electrolytic bath* or *vat*.

salt like cuprous chloride (CuCl) is 63, because copper here is univalent, while in a cupric salt like cupric chloride (CuCl_2) the chemical equivalent is $63/2$ because copper here is divalent.

The **electrochemical equivalent**, e , of an ion is the mass in grams which is set free by the passage of unit quantity of electricity. It follows from this definition that

$$M = eQ = eIt.$$

It also follows from the statements above that the electrochemical equivalent is directly proportional to the chemical equivalent, or the electrochemical equivalent of an ion is equal to the chemical equivalent of the ion multiplied by the electrochemical equivalent of hydrogen.

The **Practical Units of Quantity or Current of Electricity** are frequently defined in terms of the amount of chemical action produced by the passage of electricity through an electrolyte. Thus, the **International Coulomb**¹ has been defined as the quantity of electricity which liberates 0.001118 gm. of silver from a neutral solution of nitrate of silver in water. Again, a current of one **International Ampere**¹ is that current which liberates per second 0.001118 gm. of silver from a neutral solution of nitrate of silver in water. Thus, the electrochemical equivalent of silver is, from this definition, 0.001118 gm. per coulomb. The chemical equivalent of silver (referred to *hydrogen*) is 107.02; hence the electrochemical equivalent of hydrogen is 0.0001045 gm. per coulomb.

The quantity of electricity required to liberate one *gram-atom* of any univalent element is called one **Faraday**, and the faraday is equal to $107.88 \div 0.001118 = 96500$ coulombs approximately.

One gram-atom means that mass for which the number of grams is the same as the number representing the atomic mass of the element. Taking the atomic mass of oxygen as 16, one gram-atom of silver contains 107.88 gm.

§ 2. DETERMINATION OF ELECTROCHEMICAL EQUIVALENTS

ELECTROCHEMICAL EQUIVALENT OF HYDROGEN

When a current of electricity is passed between platinum electrodes through a dilute solution of sulphuric acid in water, decomposition takes place, and oxygen is evolved at the anode, hydrogen at the cathode. In this case the current can be made to pass continuously only if the electromotive force available is greater than about 1.5 volts, for the products of decomposition on the electrodes act like the plates of a cell. This cell has an E.M.F. which *opposes* the passage of the

¹ The *Legal* or *International* Coulomb and Ampere defined in this way differ by a very small amount from the Coulomb and Ampere defined by means of the magnetic action of a current.

current, the **Back E.M.F.** set up being about 1.5 volts. If the strength of the current passing through the solution be extremely small, it may happen that the hydrogen liberated is dissolved by the water and no visible evolution of bubbles of gas takes place, but with a stronger current bubbles should be evolved freely and the water soon be saturated with gas, so that all the hydrogen liberated subsequently may be collected. This gas is now in the form of neutral *molecules*.

Other solutions may be used in place of the sulphuric acid solution, for example in preparing very pure hydrogen a solution of barium hydroxide $\text{Ba}(\text{OH})_2$ is frequently employed.

In order to determine the electrochemical equivalent of hydrogen it is necessary to pass a known current for a known time, to collect the hydrogen evolved, to measure its volume under known conditions, and to calculate its mass.




FIG. 257.—Voltmeter for Mixed Gases

To measure the current a tangent galvanometer may be used, for this measures the current in *absolute* units. It is, however, often more convenient to use a moving coil ammeter, reading, say, from 0 to 3 amperes, which has been standardised already by comparison with a tangent galvanometer (p. 386). Care must be taken to connect the terminal of the ammeter marked + to the positive terminal of the battery. A current of from 1 to 2 amperes is usually convenient, and a suitable current may be obtained by varying the number of cells in the battery, or by introducing sufficient resistance in the circuit when the current is taken from the electric-light mains where direct current is supplied.¹ Several different forms of apparatus have been constructed for collecting the gas evolved.

I. Apparatus for Mixed Gases.—The glass portion of the apparatus is constructed as in Fig. 257. The gas evolved from both electrodes is collected in one and the same tube, which is graduated in c.c. Two volumes of hydrogen are evolved to one volume of oxygen, so that of the total volume of gas collected only two-thirds are hydrogen. The graduated glass tube can be refilled with water by tilting the apparatus on its side repeatedly. In this way the apparatus can be prepared for use expeditiously without the risk of dilute acid being splashed about on the laboratory table.

EXPT. 243. Determination of the E.C.E. of Hydrogen. I.—The method of making the connections is shown in Fig. 258.

When these connections have been made, complete the circuit for a few moments by means of the plug key, in order to see that a suitable deflection is obtained on the ammeter, and that bubbles of gas are given

¹ For a convenient type of lamp resistance see p. 460.

off from the electrodes. If the current is obtained from a battery of storage cells, a piece of resistance wire (platinoid or manganin) may be introduced as one of the connecting wires, in order to adjust the current to the strength desired. Before beginning the actual experiment remove the bubbles of gas that have collected in the graduated tube during the preliminary adjustments.

Start the current and the seconds hand of a stop-watch, or clock, at the same instant, and allow the evolution of gas to continue till the graduated portion of the tube is filled with the mixed gases.¹ Readings of the ammeter must be taken every half-minute, and from these readings the mean value of the current must be calculated. When the full amount of gas has been collected, stop the current and the stop-watch at the same instant, and find the value of t , the time in *seconds* during which the current has been flowing. Determine also the volume, V c.c., of gas collected under the conditions of the experiment, remembering that only two-thirds of the total quantity of gas is hydrogen.

This volume, V c.c., requires to be corrected for temperature and pressure, that is, we require to find what the volume would be at 0°C . and under a pressure of 760 mm. of mercury.

Correction for Temperature.—This correction is most easily applied by using the *absolute scale* of temperature, since the volume of a given mass of gas is directly proportional to its absolute temperature. To convert temperatures on the centigrade scale to temperatures on the absolute scale it is only necessary to add 273° to the reading of the centigrade thermometer. The volume of the gas at 0°C . (or 273°K .) would be

$$V \times \frac{273}{T},$$

where T is the temperature of the room on the absolute scale.

Correction for Pressure of Aqueous Vapour.—Let P be the actual pressure in mm. of mercury of the gaseous mixture in the tube at the end of the experiment.

Let B be the height of the barometer in mm. The pressure P in the tube differs from the atmospheric pressure on account of the difference in water level between A and D (Fig. 257).

Let h = the difference in level in mm. between A and D . The pressure due to the difference of level between A and D = $h/13.6$ mm. of mercury, since the density of mercury is 13.6. Hence $P = B + h/13.6$.

The total pressure P is made up of a pressure P' due to the hydrogen and oxygen, and p due to the aqueous vapour in the tube. The space in the tube is saturated, therefore p = saturation vapour pressure of water in mm. of mercury at the temperature of the room. (See Appendix, p. 563.)

Thus, $P' = P - p$, or $P' = B + h/13.6 - p$, and consequently the volume of the hydrogen and oxygen together under standard pressure (760 mm.) at 0°C . is

$$\begin{aligned} V_0 &= V \times \frac{273}{T} \times \frac{P'}{760} \\ &= V \times \frac{273}{T} \times \frac{B + h/13.6 - p}{760}. \end{aligned}$$

¹ The evolution of gas must not be continued long enough for the electrodes to become uncovered by liquid; if this happens there is some risk of a serious explosion taking place with this form of apparatus.



FIG. 258.—Determination of Electrochemical Equivalent

CHAPTER VII

THE HEATING EFFECT OF AN ELECTRIC CURRENT

§ 1. JOULE'S LAW

THE relation between mechanical energy W and heat energy H and the determination of Joule's equivalent, defined as the constant ratio W/H , has been discussed on pp. 310, 317. Joule also investigated the relation between electrical energy and heat energy. From his experiments we conclude that an expenditure of energy is necessary to transfer electricity through any material substance. Even the best conductor possesses a certain property to which this fact is due. This property we call the **resistance**, R , of the conductor, and according to Ohm's Law R is constant under constant physical conditions and equal to E/I .

The principal units employed for the scientific measure of *energy* are :—

The **erg** = 1 dyne centimetre.

The **joule** = 1 newton-metre or 10^7 ergs.

The **gram calorie**, or heat unit of energy = 4.2×10^7 ergs = 4.2 joules (more exactly 4.185 joules).

The **kilowatt hour** or **Board of Trade Unit** = the energy supplied by an engine working for a period of 1 hour, the power of the engine being 1 kilowatt (see below).

The difference of potential between two points in an electric circuit is equal to the work done in carrying unit quantity of electricity from one point to the other. Hence, if a quantity of electricity Q is carried between two points when the P.D. is E , the work done $W = EQ$.

If a steady current I flow for time t , $Q = It$, and therefore the work done $W = EIt$.

If E is in volts, I in amperes, t in seconds, W is in joules. For the difference of potential between two points is one volt when one joule of work has to be done in carrying one coulomb of electricity from one point to the other against the electric forces.

If a steady current of one ampere flow between two points between which the P.D. is one volt, the *rate* of doing work is one joule per second, or one **watt**.

The units employed for measuring *power* or *activity* (rate of doing work) are the following :—

The C.G.S. unit = 1 erg per second.

The watt = 1 joule per second.

The kilowatt = 1000 watts.

The British horse-power = 33,000 ft. lbs. per min. = 746 watts.

The measurement of electric power depends on the measurement of *current* and *difference of potential* ; the *energy* depends on these and also on the *time*.

When the energy of an electric current is not used in doing mechanical work or in chemical action it appears as heat in the conductor. According to Joule's Law the heat produced is equivalent to a certain amount of mechanical energy, in accordance with the equation

$$W = JH.$$

If W is in joules, H in calories, $J = 4.2$ joules per calorie very nearly, for 1 gram calorie is equivalent to 4.2 joules.

Then
$$JH = EIt.$$

Since $E = IR$ we may also write $JH = I^2Rt.$

NOTE.—This last equation is true whether work is being performed by the current or not, the *portion* of the applied potential difference required to overcome a resistance R being IR if a current I is being passed, however the rest of the P.D. is being employed. The heating effect therefore is measured always by I^2Rt , and is often referred to by electrical engineers as 'the IR^2 loss'.

EXPT. 246A. Determination of the Mechanical Equivalent of Heat by an Electrical Method using a current of about 10 amperes.—In order to test the accuracy of this result it is necessary to measure the heat produced by the passage of a given current, for a given time, under a known difference of potential.

When a large current of from 8 to 12 amperes is available, an appreciable change of temperature may be obtained in two or three minutes.

The heat produced is measured by immersing a coil of resistance wire carrying the current in a large calorimeter (capacity about half a litre) containing a liquid of known specific heat. In the case of water a certain amount of electrolysis takes place, but provided the potential difference employed does not exceed 8 or 10 volts, and the resistance of the immersed spiral is low (about 0.5 ohm), this does not materially affect the result. The spiral is connected by thick copper leads to two terminals fixed to the wooden cover of the calorimeter. The cover is provided with a hole for the thermometer and another for the stirrer. *Efficient stirring is most important in this experiment.*

The calorimeter is weighed empty, and again when full of water.

The electrical quantities are measured most conveniently by using




FIG. 262.—Calorimeter with Heating Coil

an ammeter and a voltmeter. The apparatus should be connected as in Fig. 263.

B is a battery comprising 4 or 5 secondary cells, provided with a fuse.

K is a plug-key.

A is the ammeter for currents up to about 15 or 20 amperes.

V is a voltmeter reading to about 5 volts.

C is the calorimeter.

R is a resistance consisting of a wire frame rheostat, or a bare resistance wire.

Having connected up the apparatus, using *thick* copper wires to make the connections in the main circuit, adjust the strength of the current to a suitable value. Wait a few minutes for the temperature of the calorimeter to become steady, stirring occasionally, then take the reading of this initial temperature θ_1 .

Start the current when the seconds hand of a watch passes the 60 mark, and allow the current to flow for say 3 minutes, stirring thoroughly meanwhile. Take readings of the ammeter and the voltmeter every half minute. Stop the current after a known interval of time and read the final temperature θ_2 .




FIG. 263.—Heating Effect of Current

Let m = mass of calorimeter (inner vessel only),

M = mass of water,

s = specific heat of metal of calorimeter,

θ_1 = initial temperature,

θ_2 = final temperature.

Then the heat given to the calorimeter and its contents is

$$H = (M + ms)(\theta_2 - \theta_1).$$

Calculate the value of J in the equation

$$JH = EIt,$$

noting that the time must be measured in seconds.

The experiment may be repeated for a different value of the current.

Instead of measuring E with a voltmeter, the resistance R of the immersed spiral may be measured by means of the slide-wire bridge, and the value of J found from the equation

$$JH = I^2 R t.$$

EXPT. 246B. Determination of the Mechanical Equivalent of Heat by an Electrical Method using a current of about 3 amperes.—The method is similar to that just described, but, as a smaller current is used, a longer time (say 20 minutes) is required, and in consequence the correction for cooling is more important. Start the current when the temperature is 5° or 6° below the temperature of the room, and finish when the temperature is as much above that of the room. Two or three accumulators in series may be used to give a P.D. of about 3 volts between the terminals of the heating coil, which should have a resistance of about 1 ohm. Take readings of the ammeter and voltmeter every minute, work out the values of EI and take the mean, using this *mean* value in calculating EIt .

Experiments may be carried out with the same apparatus to test the conclusions of Joule (1840-3) that the quantity of heat is proportional to (a) I^2 when R is constant, (b) R when I is constant, (c) the time t when EIt or $I^2 R t$ is constant.

NOTE.—Sometimes a non-conducting liquid such as paraffin oil, turpentine, or aniline oil is used in the determination of the electrical equivalent of heat. The specific heat of the liquid must be known, and *care must be taken to avoid overheating.*

§ 2. THE EFFICIENCY OF AN ELECTRIC LAMP

When electrical energy is used for purposes of illumination it is important to know the relation between the rate at which energy is supplied and the candle-power produced. Electrical engineers often speak of the number of watts per candle-power as the *efficiency* of the source of light. It would be more correct to term this the *inefficiency*, and to use the term efficiency to denote the candle-power per watt.

EXPT. 247. **Determination of the Efficiency of an Electric Lamp.**—The candle-power of the lamp under test may be measured by one of the methods described in the Chapter on Photometry, p. 247.

To measure the rate at which energy is supplied to an incandescent lamp, it is necessary to measure the current passing through the lamp and the difference of potential between its terminals.

Connect up the apparatus as in Fig. 264.

L is the lamp.

R is an adjustable wire-frame resistance.

A is the ammeter, connected *in series*. V is the voltmeter, connected *in parallel* with the lamp.




FIG. 264.—Efficiency of Electric Lamp

Care must be taken to see that connection is made to the proper terminals for both ammeter and voltmeter, before switching on the current. Note the readings of the ammeter and the voltmeter for a particular value of the resistance R.

Measure the candle-power of the lamp in this condition.

Take a series of readings in this manner for different values of the resistance R. Finally cut out the whole of the resistance R, and take a set of readings when the lamp is supplied with current at the voltage for which it was designed.

1. Calculate the number of watts per candle at the specified voltages.
 2. Calculate also the candle-power developed per watt.
 3. Calculate the resistance of the lamp when glowing at different candle-powers.
 4. Calculate the heat produced in the lamp in calories per second.
- Tabulate the results, and illustrate them by means of graphs.

It is instructive to carry out experiments of this kind both with a metal filament and a carbon filament lamp.

The variation of the resistance of the carbon filament with temperature (estimated *qualitatively* by the colour) differs in an interesting way from that of the resistance of the metal filament.

ELECTROMAGNETIC INDUCTION

§ 1. INDUCED CURRENTS

IN 1831 Faraday showed that an electric current was produced in a closed circuit whenever the number of lines of magnetic induction passing through the circuit was changed. Such a current is termed an **induced current**.

The *total* number of lines of magnetic induction threading the circuit is called the **magnetic flux** (N) through the circuit. The alteration in the magnetic flux may be due to

- (1) Starting or stopping currents in neighbouring conductors,
- (2) Variations in the strength of those currents,
- (3) The motion of conductors carrying currents,
- (4) The motion of permanent magnets with reference to the circuit under consideration,
- (5) Changes in the strength of the current in a particular circuit (**self induction**).

An induced current indicates the existence of an electromotive force (E.M.F.) in the circuit.

The results in all these cases may be summarised in the statement, due to Faraday and Neumann, that the E.M.F. induced in a circuit is equal to the rate of decrease of the number of lines of magnetic induction passing through the circuit, the positive direction of the E.M.F. being related to the positive direction of the magnetic induction in the same way as the direction of rotation to the direction of translation in a right-handed screw.

An *increase* in the magnetic flux gives rise to a *negative* E.M.F.

EXPT. 248. Illustration of the Laws of Electromagnetic Induction.—These laws are illustrated in the present experiment by the aid of two *coaxial* coils. One coil, the **primary** (of fairly thick wire) is connected in series with a secondary cell, an adjustable resistance, and a key; the other, the **secondary** (having many turns of finer wire), is connected with a sensitive galvanometer.

The coils may be wound round the rim of wooden discs,¹ the primary being laid flat on the table and the secondary supported above it on a block of wood. Sometimes the coils are in the form of solenoids (pp. 373-374) and the secondary surrounds the primary.

N.B.—In all the following description it is assumed that the coils and galvanometer are viewed from above.

¹ Simple coils without any wooden frame may easily be wound by using fairly stiff insulated wire, tying together with string, and soldering on terminals.

In the first place it is necessary to determine in which direction the wire is wound in each of the two coils.

To find the Direction of Winding in the Coils.—Prepare three small paper labels, slit in such a way that they may be attached to a terminal. On one side of each, mark a + sign with a curved arrow round it pointing in the clockwise direction. Call the terminals of the primary coil A and B—these




FIG. 265.—Apparatus for Induced Currents

R = resistance

G = galvanometer

K = reversing switch

To avoid confusion, the secondary coil in the diagram has been displaced to the right.

need not be marked. Connect the positive terminal of the battery to A, and the negative terminal of the battery through a rough regulating resistance, R, to B. Bring a compass needle close to the upper face of the coil, and note the way in which the needle points. If the north end of the needle points towards the top of the coil, this end acts like the south pole of a magnet, since lines of force enter the coil at this end.

This means that the current in the coil circulates clockwise, as viewed from above, when the current enters at A. If this is so, attach a label to terminal A; if it is not so, attach a label to terminal B, and check the result by connecting the positive pole of the battery to B.

Call the terminals of the secondary coil C and D and proceed as before, connecting the positive of the cell to the terminal marked C. If the current in the secondary is clockwise, mark the terminal C with a label; if it is not so, attach the label to terminal D.

To find the Direction of the Secondary Current for an observed Deflection of the Galvanometer.—Call the terminals of the galvanometer E and F. Connect E to the positive terminal of the cell, and then connect F *momentarily* with the negative terminal of the cell through a large resistance. When a sensitive galvanometer is used, it is of special importance that the resistance should be very large. Notice whether the momentary galvanometer deflection is clockwise or anticlockwise. If it is clockwise attach the third label to terminal E, if anticlockwise attach the label to terminal F of the galvanometer.

Suppose the north pole of the galvanometer needle to go to the east, then this north pole moves east when the current enters at E, and hence the direction of circulation of the current in the galvanometer can be found from the motion of the needle.

Connect up the secondary coil to the galvanometer as in Fig. 265, being careful to connect the labelled terminal of the galvanometer to that terminal of the secondary which has no label. For in this way a clockwise current in the secondary would *leave* the secondary by the unmarked terminal, and then enter the galvanometer by the marked terminal and give a clockwise deflection.

Consequently the deflection of the galvanometer will now show *directly* whether any current in the secondary is clockwise or anticlockwise.

To demonstrate the Laws of Electromagnetic Induction.—Having made these preliminary observations and obtained the result expressed in the last

sentence, connect up the primary coil with its marked terminal connected with the positive terminal of the cell, and with its unmarked terminal connected to the negative with a large adjustable resistance in series.

The current in the primary will now circulate round the primary coil in the clockwise direction.

Then carry out the following experiments, noting in each case the direction of circulation of the current in the secondary as shown by the deflection of the galvanometer needle :—

1. *Current started in Primary.*—The deflection of the needle is anti-clockwise. Therefore a *clockwise* current started in the primary induces an *anti-clockwise* (inverse) current in the secondary.

2. *Current stopped in Primary.*—The deflection of the needle is clockwise. Therefore a *clockwise* current stopped in the primary induces a *clockwise* (direct) current in the secondary.

Note the deflection as before and deduce the direction of the secondary current induced in each of the following cases :—

3. Current in primary suddenly increased.
4. Current in primary suddenly diminished.
5. Secondary suddenly moved away from primary, keeping primary current constant.
6. Secondary suddenly brought up to primary again.
7. Current in primary suddenly reversed.

It will be found that switching on the primary current produces an effect of the same kind as 3 and 6.

Switching off the primary current produces an effect of the same kind as 4, 5 and 7.

We can thus deduce another Law of Induced Currents :—

The induced current in the secondary coil is always in such a direction as to oppose any change in the magnetic field through the secondary. It only lasts while the change is being produced.

In the suppositions made, switching on the current introduces *downward-directed* lines of force. The induced current circulates anti-clockwise and thus creates *upward-directed* lines of force, which however only persist for a moment, the induced current dying away almost instantaneously.

These are all examples of mutual induction. We may express the results by saying that there is *mutual inductance* between the primary and secondary circuits.

Verify that the above law holds good for all changes in the magnetic field, however produced.

This may be done by bringing up a bar-magnet and finding the direction of the induced current :—

- (a) When the north pole of the magnet is inserted in the coil, *i.e.* the magnet is inserted with its north pole downwards.
- (b) When the north pole is withdrawn suddenly.
- (c) When the magnet is inserted with its south pole downwards.
- (d) When the south pole is withdrawn suddenly.

Place a bundle of iron wires in the coil, and repeat the first series of experiments. Show that the effects produced are always of the same kind as with air in the coil, but that the induced currents are of much greater magnitude.

The last result is explained by saying that iron is more permeable than air to magnetic lines. If H denote the strength of the magnetic field, or the number of C.G.S. lines per sq. cm. in air, and B the corre-

sponding quantity in iron, the ratio of B to H is called the **Permeability**, μ , of the iron. Thus

$$\mu = \frac{B}{H}.$$

The term **magnetic Flux** is applied to the number of the magnetic lines passing through the iron. The C.G.S. unit of magnetic flux is the **maxwell**. The maxwell corresponds to one C.G.S. magnetic line. The practical unit of magnetic flux is the **weber**. One weber equals 10^8 maxwells.

THE INDUCTION COIL

The object in view in the construction of an induction coil is the production of a high induced electromotive force that is mainly unidirectional. Let M denote the coefficient of mutual induction or the mutual inductance of two coils, M is the number of times the secondary is threaded by lines of magnetic induction when unit current flows in the primary.¹ Then if a current ² i flow in the primary, the number of times the secondary is threaded by lines due to this current is Mi and the magnetic flux $N = Mi$. If N is in maxwells and i is in amperes, the mutual inductance is in henries. The E.M.F. will then be in volts.

$$\begin{aligned} \text{But the induced E.M.F.} &= \text{Rate of decrease of } N, \\ &= \text{Rate of decrease of } Mi, \\ &= M \times (\text{Rate of decrease of } i), \end{aligned}$$

provided M is a constant quantity.

Thus to make the induced E.M.F. large, the two factors on the right-hand side must be made large. To make M large, the secondary coil is wound with a large number of turns, and an iron core is used to concentrate the magnetic lines. To make the rate of decrease of the current large, the original current in the primary must be large and it must be cut off very rapidly.

Thus the essential features of the induction coil are :—

- (1) A primary coil of a small number of turns of thick wire, and therefore of low resistance.
- (2) A secondary coil of a large number of turns, involving the use of fine wire and consequently large resistance.
- (3) A core consisting of a bundle of soft iron wires.
- (4) An interrupter, to break the primary current very rapidly.

A condenser is usually fitted with its plates connected to the two points of the primary between which the break occurs.

¹ If there are n turns in the secondary, each line threads the circuit n times.

² As the current may vary, i is used instead of I .

Fig. 266 shows the construction of a Ruhmkorff's coil fitted with a hammer contact-breaker. The battery B is connected to the primary P through the commutator K, connection being completed through the point of the screw A and the back of the hammer-head H. The hammer-head is mounted on a spring D, the tension in which can be adjusted by the insulated screw T. When the current passes round the primary, the iron core is magnetised and attracts the soft iron H, which flies forward and breaks the contact. The magnetic field is thus destroyed,




FIG. 266.—Ruhmkorff's Coil

and an E.M.F. is induced in the secondary due to the sudden withdrawal of the magnetic lines. The hammer-head, being no longer attracted, returns to its former position and makes contact once more. A condenser C is provided in the base of the apparatus so that the E.M.F. due to the self-induction of the primary may charge up the condenser instead of producing a spark at the point of break. In this way the primary current is reduced to zero more rapidly, or the rate of diminution of the current is increased. An E.M.F. is also induced in the secondary on making contact, but this is much smaller than that at break, since the primary current takes some time to rise to its full value in consequence of self-induction.

NOTE.—When the contact is broken, a further phenomenon is that, as the condenser and the primary of the Ruhmkorff coil form an oscillating system, an oscillating E.M.F. is induced in the secondary.

EXPT. 249. The Induction Coil.—It is assumed that the induction coil is fitted with the ordinary hammer-break. Release the lock-nut on the screw carrying the platinum point, and withdraw the screw so that there is no contact with the platinum on the hammer-head. Turn the adjusting screw T till there is no extra tension on the spring D. Connect the terminals of the coil to a suitable battery, introducing a piece of fuse wire melting at 10 amperes to prevent an excessive current from damaging the coil. With a coil of medium size a battery giving an E.M.F. of about 8 volts will be suitable. Turn the handle of the commutator into the *on* position. Advance the screw carrying the platinum point till contact

takes place with the hammer-head. The interrupter should commence to work, and when the terminals of the secondary are set at a small distance apart, sparks should pass between them. The screw should be clamped in this position by means of the lock-nut. The stiffness of the spring may now be adjusted by turning the milled head. Occasionally the platinum points fuse together and the action ceases. Should this happen, momentarily reverse the current; this will often start the interrupter working again. If it does not, switch off the current and turn back the screw carrying the platinum point. After long working the platinum contacts become pitted and may need polishing with fine emery paper, but this should never be attempted by the student.

Determine the maximum length of spark that can be obtained from a given setting of the spring. Assuming that the spark length is approximately proportional to the P.D., and that 30,000 volts are required for a spark 1 cm. long, calculate the E.M.F. induced in the secondary of the coil.

Connect the coatings of an insulated Leyden jar to the secondary terminals, and examine the character of the spark.

Examine the discharge through 'vacuum tubes' connected to the terminals of the coil. With a moderate vacuum, near the positive electrode is a long luminous positive column, while the negative electrode is surrounded by a blue luminous layer—the negative glow. If possible exhaust a discharge tube by using a high vacuum pump and note carefully the appearance of the discharge as the pressure is diminished.

Cathode Rays.—When a sufficiently high vacuum is obtained, the effects just described disappear and the Crookes's dark space surrounding the negative electrode increases in size until it reaches the glass walls of the tube. When this stage is reached the walls exposed to the cathode become fluorescent under the action of cathode rays proceeding from that electrode. The rays themselves are invisible but cause phosphorescence in various materials, and in a partial vacuum the track of the rays is sometimes revealed by the luminescence of gaseous molecules. They travel in straight lines from the cathode as shown in the Crookes's tube in Fig. 266A. The rays are emitted mainly in a direction normal to the cathode, and may be concentrated on a particular spot by using a saucer-shaped cathode. As was shown by Hertz and by Lenard, they can penetrate small thicknesses of matter.




FIG. 266A.—Shadow of Metal Cross *b* thrown on Wall of Tube by Cathode Rays

revealed by the luminescence of gaseous molecules. They travel in straight lines from the cathode as shown in the Crookes's tube in Fig. 266A. The rays are emitted mainly in a direction normal to the cathode, and may be concentrated on a particular spot by using a saucer-shaped cathode. As was shown by Hertz and by Lenard, they can penetrate small thicknesses of matter.

In Fig. 266B the path of a narrow beam of rays is shown by a phosphorescent streak *a* on a screen. When a transverse magnetic field is applied with the lines of force running into the diagram, the path is along *b*, and when the field is reversed, the path is changed to *c*.

Cathode rays are associated with an electric charge (Perrin, 1895), and at sufficiently low pressure they are deflected by an electrostatic

field. The experiments of J. J. Thomson in 1897 gave ' the first definite proof that the cathode rays consist of a stream of negatively charged particles moving at a very high velocity, and possessing a mass very



FIG. 266B.—Deflection of Cathode Rays by a Magnetic Field

small compared with that of the lightest chemical atom ' (E. Rutherford). The moving particles or negative electrons exert mechanical pressure and convey kinetic energy as is shown by the heating effect produced when they are concentrated on a target. See also pp. 362-364.

X-Rays or Röntgen Rays.—In an X-ray tube a stream of cathode rays falls upon a metal target, or anti-cathode, and a beam of X-rays starts from the region thus bombarded. In an early form of tube, Fig. 266c, the cathode was made saucer-shaped so that the cathode stream was brought to a focus on the surface of the target. The anode




FIG. 266C.—X-ray Focus Tube

was usually placed behind the anti-cathode with which it was connected, its position being chosen so as to be outside the Crookes dark space. In modern tubes the vacuum is much higher and a pure electron discharge is produced by the emission of electrons from a metallic filament heated by an electric current.

X-rays produce fluorescence on a screen coated with barium platino-cyanide, and also photographic

and electrical effects, producing conductivity in a gas through which they pass. The most striking characteristic of the rays is their great penetrating power, especially for elements of small atomic weight. They are *not* deflected by a magnetic or an electric field, and it is now agreed that X-rays are akin to ultra-violet light, but have very much shorter wave-lengths.

An X-ray bulb should be examined by the student, and its action demonstrated to him by connecting the electrodes to the two terminals

of an induction coil. This should be done with the commutator in the off position. Now make only a *momentary* contact by turning the commutator. If that half of the bulb which is in front of the anti-cathode shows green fluorescence the commutator has been turned the right way. The X-rays may then be detected by using a fluorescent screen, and their penetrating power illustrated by interposing (say) a box of weights. The bulb should be run for only short periods and great care should be taken not to expose the skin unduly to the X-rays.

THE TRANSFORMER

A **Transformer** is an apparatus for producing by means of an electric current another of different strength and voltage. The induction coil is one instance, but the earliest form is Faraday's Ring Transformer, in which an iron ring is provided with two windings as in Fig. 267. The current in the primary, P, gives rise to lines of magnetic induction which form a closed magnetic circuit in the iron ring. When the strength of the current in the primary is varied, an E.M.F. is induced in the secondary, S. The magnitude of this E.M.F. depends primarily on the material of the core, and on the relative numbers of turns in the primary and the secondary.




FIG. 267.—The Transformer

When an alternating current is sent through the primary, an alternating E.M.F. is induced in the secondary. If the number of turns in S be greater than the number of turns in P, the voltage at the ends of S will be greater than that at the ends of P approximately in the ratio of the number of turns. Neglecting energy losses, the current is diminished in the same ratio as the voltage is increased. This arrangement is called a *step-up* transformer. The converse of this is the *step-down* transformer, in which the voltage is decreased while the current is increased.

Expt. 250. The Ring Transformer.—Connect the primary of a ring transformer through a commutator to a battery of accumulators in series with a rough regulating-resistance and an ammeter. Connect the secondary to a ballistic galvanometer (p. 478). Observe the *throw* of the galvanometer produced by a sudden reversal of the current in the primary.

Repeat the observations for different values of the primary current, and plot a curve showing the relation between the throw of the galvanometer and the strength of this current.

The throw of the galvanometer is proportional to the quantity of electricity passing through it, and this in turn to the change in the magnetic flux through the iron ring. The current in the primary is a measure of the

magnetising force producing these magnetic lines. Thus the curve serves to indicate the **permeability** of the iron to lines of magnetic induction, for different values of the magnetising force.

§ 2. COIL SPINNING IN A MAGNETIC FIELD

Let a plane coil of wire spin or rotate with constant angular velocity




FIG. 268A.—Spinning Coil

ω about an axle which is at right angles to a uniform magnetic field of strength H . In Fig. 268A the axle about which the coil spins passes through O and is perpendicular to the plane of the paper. The coil may be circular or rectangular in shape, the dotted line through O being an axis of symmetry through its geometrical centre and

normal to its plane. At any moment this axis makes an angle θ with the direction of the field H , and $\theta = \omega t$. Note that the *axis* of the coil is perpendicular to the *axle* about which the coil rotates. When $\theta = 0$ or π , the flux through the coil is a maximum; when $\theta = \frac{\pi}{2}$ or $\frac{3\pi}{2}$, the flux is zero. If A is the area of the face of the coil and n the number of turns of wire, the magnetic flux $N = nHA \cos \theta$. The electromotive force is the *rate* of decrease of N , and by using the differential calculus it is found that

$$\text{E.M.F. at any instant} = nHA\omega \sin \theta = E_0 \times \sin \theta,$$

where $E_0 = nHA\omega$, and is the maximum value of the E.M.F.

An alternative method of dealing with this problem is provided by Faraday's conception of E.M.F. being induced by a conductor cutting lines of magnetic induction. The result also illustrates the important Law of **Lenz**: Whenever there is relative motion between a circuit and a magnetic field, the current induced is such as to produce mechanical forces opposing the motion.

When a coil rotates in a magnetic field, there is induced in the coil an E.M.F. which is *alternating* in character (Curve I, Fig. 269). With a uniform rate of turning, the induced E.M.F. has its maximum value when the plane of the coil passes through the plane of the field,




FIG. 268B.—Commutator for Direct Current

and is zero when the coil is in a position perpendicular to the plane of the lines of force.

Methods of measuring the Induced Current.—An ordinary galvanometer connected to such a coil would give no deflection if the coil were rotated always in one direction unless a commutating device were fitted. In one convenient form of commutator (Fig. 268B) the ends of the coil are connected to two halves of a split cylinder of brass on an insulating cylinder mounted on the axle of the coil. Two springs, or *brushes*, fixed to the framework supporting the axle of the coil press




FIG. 269.—E.M.F., etc., due to Spinning Coil or Earth Inductor

against the split cylinder at opposite ends of a diameter. As the coil rotates, these springs make contact alternately with the two parts of the split cylinder, and are therefore connected alternately to the two terminals of the coil. By suitably arranging the position of these *brushes*, the position of commutation can be made to correspond with the position where the E.M.F. is zero, and thus a *rectified* or *unidirectional* current is sent through the *external circuit* (the apparatus connected to the brushes), and it is produced by the *alternating* E.M.F. generated in the coil (Curve II, Fig. 269).

This current, passing through a galvanometer, would produce a practically constant deflection, corresponding with the *mean* value of the current: the galvanometer deflection does not follow the variations of current, on account of the inertia of the moving system (Curve III, Fig. 269).

In some cases no commutator is fitted to the coil, the ends of the coil being connected to 'slip rings', from which the current is taken by a pair of brushes, B_1 , B_2 (Fig. 270). When this is the case the coil must be used with a hot-wire milliammeter or millivoltmeter if rotated continuously, as it gives alternating current. An alternative method

is to use it with a ballistic galvanometer, the deflection of the galvanometer being observed when the coil is rotated suddenly through half a revolution. Starting when the coil is perpendicular to the field, it is turned rapidly through half a revolution, until it is again perpendicular to the field but with its faces reversed. The deflection of the galvanometer produced by this motion is proportional to the total number of lines cut by the coil; that is, to the intensity of the field perpendicular to the face of the coil in the initial position.




FIG. 270.—Slip-rings for Alternating Current

The Earth Inductor (Fig. 271) is an instrument illustrating the principles just described. A circular coil is made to rotate about a diameter of the circle in the magnetic field of the earth.

EXPT. 251. Determination of the Angle of Dip by Means of an Earth Inductor.—Assuming the coil fitted with a commutator, place the coil of the earth inductor so that its plane is vertically east and west when in 'commutating position', or when the brushes are not in contact with either side of the split cylinder. This ensures that the current is commutated as it passes through its zero value.

Connect the brushes to the terminals of a sensitive galvanometer, placing in series with the galvanometer a large adjustable resistance.




FIG. 271.—The Earth Inductor

A suspended-coil galvanometer is most suitable for this experiment, as the oscillations of the moving coil are destroyed very quickly, since it is short-circuited by the coil of the earth inductor and the series resistance. It is of no use whatever to shunt the galvanometer, unless a series resistance

is also used, as the E.M.F. induced is a fixed quantity for a given field and speed, and the same current would flow through the galvanometer whether shunted or not, being driven by the same P.D. Rotate the coil at a speed which can be maintained steady for a little while, and adjust the resistance until the galvanometer deflection is about *half* the maximum deflection which can be measured: a convenient rate of revolution is from 60 to 80 turns per minute. Endeavour to maintain a steady speed while measuring the rate of revolution with the aid of a watch. Place the watch so that the seconds hand can be observed with ease while the coil is being rotated. Turn the coil at such a rate that the deflection given by the galvanometer is constant, then find the time required for 100 revolutions.

With a little practice consistent results can be obtained. It is desirable that the student should practise making these measurements *alone*, so as to acquire facility in making several types of observations simultaneously.

Having become accustomed to the method of carrying out the experiment, the following observations should be taken: (1) Find the time taken for 100 revolutions of the coil, and observe the mean deflection produced when the coil is rotating about a vertical axis and the commutator reverses as the plane of the coil is east and west. Let the time for 100 revolutions be t_1 and the deflection δ_1 . Three separate determinations should be made of these quantities. (2) Turn the coil so that its axis is horizontal, and take a similar set of observations when the commutator reverses as the coil passes through the horizontal position. If necessary, the direction of rotation of the coil should be opposite to that in the first case, so as to get the deflection in the same direction as before. The resistance of the circuit must not be altered at all. Let the time for 100 revolutions be t_2 and the deflection be δ_2 .

In any single experiment δ is proportional to the induced current, and therefore to the induced E.M.F., since the resistance is maintained constant. The induced E.M.F. is proportional to

$$\frac{n}{t} \times \left\{ \begin{array}{l} \text{Field strength perpendicular to} \\ \text{coil in commutating position} \end{array} \right\},$$

where n is the number of revolutions in time t .

Thus if H and V are the horizontal and vertical components of the earth's field respectively, we have

$$\delta_1 = K \frac{100}{t_1} H,$$

and

$$\delta_2 = K \frac{100}{t_2} V,$$

so that

$$\frac{V}{H} = \frac{\delta_2 t_2}{\delta_1 t_1}.$$

From the observations made, determine the ratio of the vertical and horizontal components of the earth's field. This ratio is the tangent of the angle of dip ϕ , and hence the angle of dip can be found from the expression

$$\tan \phi = \frac{V}{H} = \frac{\delta_2 t_2}{\delta_1 t_1}.$$

As a check on this result the axis of rotation of the coil is placed in various positions in the magnetic meridian and the coil rotated as rapidly as possible. In one position no deflection of the galvanometer will be observed, however rapidly the coil is rotated. This means that the field perpendicular to the plane of the coil in the commutating

position is zero, or that the axis of rotation lies along the angle of dip. Measure the inclination of the axis of rotation of the coil to the horizontal in this position, and compare it with the result obtained in the above experiment.

EXPT. 252. Estimation of the Relative Accuracy of this Type of Experiment.—If the coil be rotated so that its plane is perpendicular to the angle of dip when in the commutating position, the field measured when the coil is rotated will be the earth's *total* field. The deflection δ_3 , obtained when the coil makes 100 revolutions in t_3 seconds in this position, will be given by

$$\delta_3 t_3 = K \ 100 \ T,$$

where T is the strength of earth's total field.

Now

$$T^2 = H^2 + V^2,$$

therefore $(\delta_3 t_3)^2$ should be equal to $(\delta_1 t_1)^2 + (\delta_2 t_2)^2$, which can be found from the results already obtained.

Find $(\delta_1 t_1)^2$ and $(\delta_2 t_2)^2$, and compare their sum with the value of $(\delta_3 t_3)^2$ obtained in the present experiment. The closeness of their agreement may be taken as a measure of the relative accuracy of the experiment.

NOTE.—If a galvanometer of the suspended-coil type is used with a lamp and scale, it should be possible to obtain agreement within about 3 or 4 per cent.

EXPT. 253. Ballistic Method of experimenting with the Earth Inductor.—Similar experiments can be carried out with a ballistic galvanometer whether the coil is fitted with a commutator or not, the galvanometer being connected to the coil without any additional resistance, and the ballistic swing determined when the coil is rotated through half a revolution. The deflections of the galvanometer, when the coil is rotated through half a revolution, are proportional to the strengths of the field perpendicular to the coil in the initial positions.

Thus, starting with the coil plane vertically east and west, the first swing of the galvanometer being Δ_1 , we have

$$\Delta_1 \propto H.$$

With the coil plane horizontal, the first swing of the galvanometer being Δ_2 , we should have

$$\Delta_2 \propto V.$$

Hence

$$\frac{\Delta_2}{\Delta_1} = \frac{V}{H} = \tan \phi.$$

If Δ_3 be the deflection when the coil plane is perpendicular to the angle of dip, we should find

$$\Delta_3^2 = \Delta_2^2 + \Delta_1^2 \text{ approximately.}$$

When the axis of the coil is along the lines of force, there will be no deflection on rotating the coil through half a revolution.

§ 3. ELECTROMAGNETIC MACHINES—DYNAMOS AND MOTORS

A **dynamo**, or a **motor**, consists of a coil or of a system of coils called the **armature**, so mounted that it can revolve in a magnetic field. In the dynamo, the armature is forced to rotate, and a current is taken from the machine, the current being produced by the E.M.F. induced in the armature due to its motion in the field. In the motor, a current

is supplied from an external source, and motion of the armature results from the force exerted by the magnetic field on the coils carrying the current. In direct-current machines the current is led into, or taken away from, the armature coils by means of brushes and a commutator, similar in principle to that described on p. 452.

The law of Faraday and Neumann (p. 444) as to the E.M.F. induced in a circuit may be expressed in mathematical form by writing

$$E = - \frac{dN}{dt},$$

where N is the magnetic flux (number of lines of magnetic induction) through the circuit.

Faraday introduced the conception of an E.M.F. being set up in a conductor whenever the conductor cuts across lines of magnetic induction. It may be shown that this E.M.F. is equal to the number of lines cut per unit time. In Fig. 272A a wire AB slides with uniform velocity v on two fixed rails AD and BC at a distance l apart. The rails are connected by a stationary conductor CD . Lines of magnetic induction run at right angles into the plane of the diagram, and the number of lines per unit area, the flux density is B . If AB moves from left to right the magnetic flux through the area $ABCD$ is decreasing and an E.M.F. is set up round the circuit $ABCD$ in a clockwise direction (p. 444). In unit time the wire moves from AB to $A'B'$, where $AA' = BB' = v$ and the area swept out $ABB'A' = vl$. Since E is equal to the rate of decrease of the magnetic flux N , it is clear that

$$E = Bvl.$$

This is true if *all* the magnitudes are in C.G.S. units; it is also true in practical units, E being in volts, B in webers per sq. metre, l in metres, and v in metres per second. The product Bvl is equal to the number of magnetic lines cut per second.




FIG. 272A.—Wire cutting Magnetic Lines

ELECTRIC MOTOR AND ELECTRIC DYNAMO

Sir Ambrose Fleming, whose pioneer work on thermionic valves is described later, has given convenient rules for summarising the actions in the electric motor and the electric dynamo.

When a straight wire carrying a current I is placed at right angles to a uniform magnetic field H , it experiences a *mechanical force* tending to move the wire in a direction which is perpendicular both to the direction of the current and to the magnetic field.

The value of the mechanical force on a length l cm. of wire is IHl dynes, if I and H are in C.G.S. electromagnetic units.

ELECTRIC MOTOR (LEFT-HAND RULE)

To find the *sense* of this mechanical force place the forefinger, the middle finger and the thumb of the **LEFT HAND** mutually at right angles to each other (Fig. 272B). Hold the **FORE** finger so that it points in the direction of the magnetic **FORCE**, and the **MIDDLE** finger in the direction of the current **I**; then the **thUMB** points in the direction of **Motion** of the conductor.




FIG. 272B.—Fleming's Rules (LEFT and RIGHT HAND)

ELECTRIC DYNAMO (RIGHT HAND RULE)

When a straight wire is made to move so as to cut at right angles the lines of force of a uniform magnetic field, an electromotive force is set up in the wire, tending to cause an induced current to flow through it. To find the direction of this induced current, place the **FORE** finger of the **RIGHT HAND** so that it points in the direction of the magnetic **FORCE**, this finger being at right angles to the direction of the middle finger and the thumb. Then, when the **thUMB** points in the direction of **Motion** of the wire, the **mIDDLE** finger is in the direction of the **Induced current**.

A convenient way of distinguishing between these two rules is to associate the name of **FLeMing** with the **Left-hand** rule, which applies to the electric **Motor**, and the name of **FaRaDaY** with the **Right-hand** rule which applies to the electric **Dynamo**.

It should be noticed that these rules are based on the laws of the electromagnetic field as given by Clerk Maxwell, and are complementary to one another. As stated above, they refer to the *conventional* (positive) current and not to the negative *electronic* current.

THE DYNAMO (DIRECT CURRENT)

The magnetic field in which the armature rotates may be produced either by permanent magnets or by electromagnets. In the former case the dynamo is known as a *magneto-machine* (Fig. 272c). In the latter case the dynamo itself is used generally to supply its own *excitation current* or *field current*, the current being taken from the armature round the field coils. The residual magnetism of the field magnets is sufficient to *start* the generation of current, and the induced current *builds up* the magnetic field as the speed increases: the requisite energy is supplied by the driving power. If the whole of the current from the armature passes through the field coils, the machine is said to be *series-wound* (Fig. 273). If the field coils are connected across the brushes so as to be in parallel with the external circuit, it is called a *shunt-wound machine* (Fig. 274). A combination of the two systems is




FIG. 272c.—Magneto-machine




FIG. 273.—Series Winding




FIG. 274.—Shunt Winding




FIG. 275.—Compound Winding

used largely, and is known as *compound-winding* (Fig. 275); a compound-wound machine is designed to give a steady P.D. in the external circuit for widely different loads when the speed is constant.

For a given field strength the E.M.F. (E.) induced in the armature coils is proportional to the speed of revolution, but the P.D. between the brushes will not necessarily obey quite the same law. If different loads are thrown on the machine, that is if different amounts of current are taken from the machine, there will be a variation in the P.D. between the brushes due to the resistance of the armature. If the resistance of the armature is R , and a current I flows through the armature, an amount IR of the induced E.M.F. will be absorbed in driving the current through the armature coils, and the P.D. available at the brushes will only be

$$V = E - IR.$$

THE MOTOR

Any machine which may be used as a dynamo can be employed as a motor by supplying current to it. Thus we have series-wound, shunt-wound, and compound-wound motors as well as dynamos.

The way in which the current in a motor varies is one of the most important points to deal with, and most of the phenomena associated with motors may be considered in this connection.

When the armature is rotating, it is a conductor cutting lines of force. There is therefore induced in it an E.M.F. (E.) proportional to the rate of revolution and to the field strength, and this E.M.F. is in opposition to the current which causes the motion, or is opposed to the applied P.D. (V). The current I flowing through the armature is driven by the excess of the applied P.D. over the back E.M.F. induced by the motion, and is given by the equation

$$I = \frac{V - E}{R},$$

Variation of Current with Speed.—With a constant field, E is proportional to the rate of revolution of the armature; hence, *if the speed be diminished, E is diminished and the current increases.*

Variation of Current with Load.—When a bigger load is put on the machine, and more mechanical work is done by it, the amount of energy supplied to the machine must be increased, so that I must increase if the P.D. of supply be constant.

Variation of Speed with Load.—If the load be increased, I must increase as above; for this to be possible E must diminish according to the equation stated above.

Hence, as the load increases, the speed of the motor will diminish provided the field strength is constant, but the *power* or *rate of working* will be increased in consequence of the increase in I. This is not necessarily the case for compound-wound motors; in these the field coils are generally wound so that increased load causes a diminished field, and therefore E diminishes, the current increasing to the required amount without alteration of speed.

Variation of Speed with Excitation for a Given Load.—For a given load, $V \times I$ must be (approximately) constant, and hence the speed will adjust itself till the required current is flowing. If the strength of the field in which the armature rotates is increased, the induced E.M.F. will increase accordingly for a given speed. Thus, I will reach its required value at a lower speed than before, and the motor will run *slower* for increased excitation. Reduced excitation will demand a higher speed before E reaches the value which reduces I to its required magnitude, and thus the motor runs *faster* for a given power when the excitation is reduced.

EXPERIMENTS WITH A MAGNETO-DYNAMO

EXPT. 254. Variation of the E.M.F. of a Magneto-dynamo with Speed.—Couple the armature shaft of a magneto-dynamo to the shaft of a variable speed motor, and to a speed indicator, by flexible springs. Connect across the brushes of the dynamo a voltmeter of suitable range, and note the voltage indicated by the voltmeter at various speeds. Draw a curve showing the relation between E.M.F. and speed. Since the field is produced by a permanent magnet the excitation is constant, and the E.M.F. of the machine should be exactly proportional to the speed.

EXPT. 255. Variation of the Terminal P.D. of a Magneto-dynamo with Load at Constant Speed.—Couple the machine with a motor and speed indicator as in Expt. 254. Connect the brushes to an ammeter and a variable resistance in series, and also connect a voltmeter across the brushes. Run the machine at a constant speed, and adjust the variable resistance so that different currents are taken from the machine. Note corresponding readings of the ammeter and the voltmeter.

Plot a curve showing the variation of terminal P.D. with load (current), and deduce the resistance of the armature.

NOTE.—The value of the resistance obtained in this way is usually rather higher than the true value. The voltage drop across the terminals when the current is increased is not entirely due to internal resistance; the field is actually weakened by the field produced by the armature current, or, as it is called, by the 'armature reaction'.

Other types of experiment will suggest themselves, and the student should consider any special uses for this machine.

Similar experiments might be performed with dynamos in which the field is produced by the current generated in the dynamo itself. Since this excitation current will vary with the speed, and in the case of a *series*-dynamo with the load also, the curves will not be the same as those obtained with a magneto-machine.

EXPERIMENTS WITH A MAGNETO-MOTOR

EXPT. 256. Variation of the Speed of a Magneto-motor with its applied P.D.—Couple the armature shaft to a speed indicator. Connect in series with the armature a variable resistance and a battery of cells, and across the terminals of the machine connect a voltmeter. Alter the resistance in series with the machine and note the readings of the voltmeter and the speed indicator.

Plot a curve showing the relation between the speed and the P.D. applied between the brushes.

EXPT. 257. Variation of Power, Speed, and Load. Efficiency of a Magneto-motor.—Connect the motor to a battery of cells in series with an ammeter and a resistance, and also connect a voltmeter across the terminals of the machine. Attach to the armature shaft a speed indicator.

By means of a brake-band operating on a large pulley attached to the armature shaft, similar to that described in the determination of the mechanical equivalent of heat by Callendar's apparatus (p. 313, Fig. 189), apply various loads to the motor.

Take a large number of readings of corresponding values of the current, terminal voltage, speed, and braking force.

The power supplied to the motor is measured by the product of the current and voltage. If these are measured in amperes and volts, the power is given in *watts* or *joules per second*.

The rate at which work is done by the motor is given by the angular velocity multiplied by the frictional couple exerted by the brake. If the difference in tension between the ends of the brake-band is $T - T_0$ dynes, and the number of *revolutions per second* is n , the work done per second is

$$2\pi n \cdot (T - T_0) R \text{ ergs per second,}$$

where R is the radius of the pulley round which the brake-band passes. This must be divided by 10^7 to reduce the rate of working to joules per second or *watts*.

Calculate in watts the rate at which work is done by the motor and also the rate at which power is supplied. The ratio of the two gives the *efficiency* of the motor, which can also be calculated from the expression

$$\epsilon = \frac{2\pi n(T - T_0)R}{I \times V \times 10^7}.$$

Find the variation of efficiency with load at constant speed, and also find the variation of efficiency with speed at constant load. This latter variation can best be found by obtaining a series of curves for efficiency and load at different (constant) speeds, and deducing the variation of efficiency with speed at constant load from these curves.

EXPERIMENT WITH A SHUNT-MOTOR

EXPT. 258. Variation of the Speed of a Shunt-motor with Field Strength.—Connect the armature of a shunt-motor in series with an ammeter A_1 and a variable resistance R_1 across the terminals of a battery, and place in series with the *shunt* coils a variable resistance R_2 and an ammeter A_2 . Connect a voltmeter across the armature brushes.

Couple the armature shaft to a speed indicator and note the variations of speed of the motor as the *shunt* current is diminished. Note also the reading of the ammeter A_1 , when the resistance R_1 is altered so as to keep the P.D. across the armature brushes constant.

Note that as the shunt current *diminishes*, the speed *increases*, and that this increase in speed is also associated with an *increase* of the armature current.

Plot curves showing (a) speed variation with shunt current; (b) armature current variation with shunt current.

NOTE.—On no account must the shunt current be entirely cut off, otherwise the motor may accelerate to an unsafe speed and the armature may fly to pieces.

Experiments similar to those already described may be carried out with a compound-wound motor (Fig. 275) only when the motor is furnished with a suitable starter, and special care is taken to avoid *unsafe speed* of the rotor and also *overloading* of the windings. The motor manufacturer should be consulted as to the maximum safe speed and the rating of the windings.

ALTERNATING CURRENT (A.C.)

The instantaneous value of the E.M.F. set up in a coil spinning steadily in a uniform magnetic field (p. 452) is given by the formula $e = E_0 \sin pt$, where p is the pulsance (pp. 124, 177) or angular velocity ω , and is 2π times the frequency expressed in cycles per second. E_0 ,

the maximum value or amplitude of the E.M.F. $= nHAp$ and so is directly proportional to p . The graph for e is a sine curve as shown in Fig. 269, Curve I.

When the coil is connected to an external circuit by slip-rings (Fig. 270), an **alternating current (A.C.)** will flow round the circuit, and in general this will be represented by a sine curve of the form $i = I_0 \sin(pt - \alpha)$, where i is the instantaneous value of the current, I_0 is the maximum value, and the angle α is the **phase difference**. This angle, sometimes expressed as a fraction of a period or as a time interval, occurs in the formula because in general the current i does not assume its maximum value at the same instant as the E.M.F.

Virtual or Root Mean Square Value of Current or E.M.F.—An alternating current may be measured by using a hot-wire ammeter, in which a fine wire expands in consequence of the heating effect of the current, and the instrument indicates the expansion produced. The heating effect in a wire of given resistance is proportional to the *square* of the current, and so the *average* value of i^2 in the A.C. circuit must be equal to the actual value of I^2 in the equivalent D.C. circuit. The current I may be called the **virtual value** or the **effective value**, for it is the direct current which is equivalent in heating effect to the alternating current. It can be shown that this **virtual current** I is equal to the square root of the average value of i^2 , and it may be called the **root mean square (R.M.S.) current**. This result depends on the mathematical theorem that the average value of $\sin^2\theta$ taken over a complete cycle is $1/2$, and it follows that $I = I_0/\sqrt{2} = 0.707 I_0$, where I_0 is the maximum value of the current.

Similarly the virtual or R.M.S. value of an E.M.F. is given by $E = E_0/\sqrt{2} = 0.707 E_0$, where E_0 is the maximum value of the voltage. Unless otherwise stated, the values quoted for current or E.M.F. are always R.M.S. values. For example in 200 volt A.C. mains the R.M.S. value is 200 volts, and the maximum value is $200\sqrt{2}$ or 282 volts.

Impedance and Reactance.—In dealing with D.C., Ohm's Law may be used in the simple form $I = V/R$. For A.C. the corresponding relation is $I = V/Z$, where in place of a pure resistance R we must substitute a more complicated quantity, known as the **impedance**, Z . Thus the impedance is the ratio of the R.M.S. value of the voltage applied to an electric circuit to the R.M.S. current flowing in the circuit. The impedance is given by


$$Z = \sqrt{R^2 + X^2},$$

where

$$X = Lp - \frac{1}{Cp},$$

L being the inductance and C the capacitance. These expressions hold when R , L , and C are connected in series.

The quantity X is known as the **reactance** of the A.C. circuit, and may be described as the component of the impedance which is due to inductance and capacitance. The magnitudes Z , R , and X may be treated as vectors and represented by the sides of a right-angled triangle, the **impedance triangle**, having Z as the hypotenuse. The angle between R and Z is the phase angle α in the equation $i = I_0 \sin(pt - \alpha)$ where $I_0 = E_0/Z$. The value of this angle is given by



Resistance

$$\tan \alpha = \frac{X}{R} = \frac{Lp - 1/Cp}{R}$$

FIG. 275A.—Impedance Triangle

The phase difference α between the E.M.F. and the current indicates that these are (in general) *out of step* with one another by an amount depending on the relative values of R , Lp and $1/Cp$, all of which may be expressed in ohms. When the inductive reactance Lp is greater than the capacitive reactance $1/Cp$, the current is said to lag behind the voltage, and when Lp is less than $1/Cp$ the current leads in advance of the voltage.¹ When the value of p is such that $Lp = 1/Cp$, the angle $\alpha = 0$ and the current and voltage come into phase with one another. The circuit behaves as a non-inductive resistance of value R , and is then said to be in electrical resonance with the supply. This may be illustrated by 'tuning' in radio circuits.


EXPERIMENTS WITH ALTERNATING CURRENTS

In an elementary physical laboratory experiments on A.C. are restricted by the cost of apparatus and the low frequency of supply mains. In Great Britain the usual mains frequency is 50 cycles per second (50~, or 50 c/s) so that the pulsance is $2\pi \times 50$ or 100π , which may be taken as 314 approximately.

Resistances.—Many of the adjustable resistances in ordinary use produce a considerable magnetic field when D.C. is flowing so that they combine resistance and inductance. A non-inductive coil is designed so that the self-inductance is almost negligible. As shown in Fig. 254 this is done by doubling the insulated wire on itself and winding it round a bobbin. When properly constructed this approximates, for moderately low frequencies, to a pure resistance, represented by

¹ A *leading* current (which reaches its maximum sooner than the voltage) can only occur provided a sufficient number of cycles have been completed. This explains a difficulty often felt — it is not the *future* voltage which determines the current, but the present and *past* voltage.

Inductors.—These are coils designed so that they may have small resistance but large self-inductance. An inductor (sometimes called a 'choking-coil') is represented by



For high inductance an air-cored coil must be of large dimensions and have many turns. Large coils made by the firm of W. G. Pye, Ltd., Granta Works, Cambridge, are useful for experiments on mutual and self-induction. The self-inductance of such a coil may be of the order of 0.1 henry. Iron-cored coils are of much smaller size, but have the disadvantage for the present purpose that the inductance varies with the current. An air-cored coil having an inductance of 1 henry has a constant reactance (Lp) of 314 ohms at 50 c/s.

Condensers.—The capacitance of an air condenser is usually very small, and mica condensers of large capacitance are expensive. For many purposes paraffin paper condensers can be employed. To avoid danger due to breakdown at a weak spot a fuse should be used in the circuit. A capacitor for which C is 1 microfarad ($1\mu F$) would have a capacitive reactance ($1/Cp$) of approximately 3180 ohms at 50 c/s. A pint-size Leyden jar of English flint glass has usually a capacitance of about $0.0015\mu F$, and the gallon size about $0.003\mu F$, and these will stand a high potential difference. These values are, however, much too small for experiments at mains frequency.

It is often convenient to assume that the actual circuit is replaced by an equivalent circuit (Fig. 275B) made up of pure resistance (R), pure inductance (L), and capacitance (C) in series.




FIG. 275B.—Ideal A.C. Circuit

A.C. Source.—The voltage of the mains, usually from 200 to 250 volts, is too high for most simple experiments. To secure a voltage of a few volts two methods are possible: (1) the use of a step-down transformer (p. 451), (2) the use of a potential divider (p. 407). The use of a well-insulated transformer is to be preferred.

Transformers giving any desired output voltage and current can readily be obtained. The 'bell-ringer' type of transformer is useful where low voltage (3, 5, or 8 volts) and small current (less than 1 amp.) are required. The firm of Meccano Limited, Liverpool 13, supply (with instructions) various transformers giving for example 3.5 or 9 volts, 12 volts, and 3.5 or 20 volts. The 'Variac' transformer, of which there are several types, gives a continuously variable voltage over a wide

range. It has, however, the disadvantage that there is direct connection between the output terminals and the mains.

EXPT. 258A. Reactance of an Air-Cored Coil.—(i) It is instructive in the first place to verify the relation between the alternating P.D. (V) and the current (I) in a pure resistance of known value (R). For this purpose an A.C. voltmeter, of as high resistance as possible, reading to 25 volts and an A.C. ammeter reading to 1 amp. are suitable. A fixed, non-inductive resistance of 25 ohms, which must be capable of carrying a current of 1 amp. is connected, in series with the ammeter, to the secondary of a transformer giving various voltages up to 25 volts. The voltmeter is connected directly to the two ends of the resistance. V is varied and a series of readings of V and I (not too small) made. Verify that V/I is constant and equal to R . The experiment may be repeated for other values of R . This verifies the relation $V = RI$ in the absence of reactance, and also indicates the order of accuracy to be expected in subsequent experiments.

(ii) When the circuit has inductive reactance X , the quotient V/I is no longer equal to the resistance R , but to the impedance Z of the circuit, where $Z^2 = R^2 + X^2$. In the absence of magnetic materials X and Z are constants at a given frequency, but vary when the frequency is varied.

Measure the resistance R_e of a large air-cored coil, which should be capable of carrying a current of 1 amp., by means of Wheatstone bridge. Replace the resistance of the previous experiment by the coil. In reckoning the voltage which may safely be applied, begin by assuming that the reactance is negligible; the impedance of the coil would then be equal to R_e and the current would not exceed 1 amp. if V were made numerically equal to R_e . It will now be found that the voltage may be increased considerably, if a suitable coil is used, without exceeding a current of 1 amp. Observe several corresponding values of V and I as in (i) and show that the value of V/I is constant. This constant is the impedance Z_e of the coil at the mains frequency ($f = 50$ c/s). Calculate the value of the reactance X from the relation $Z_e^2 = R_e^2 + X^2$. Determine also the inductance of the coil, remembering that

$$X = L\omega = 2\pi Lf.$$

Note that if R_e is relatively large the value of X determined by this method is liable to large errors, since it involves the small difference of two large quantities. A Pye coil, of the larger size, is convenient for this experiment; a suitable range for the transformer and voltmeter is then 50 volts.




FIG. 275C.—A.C. Vector Diagram

(iii) Repeat experiment (ii) with a pure resistance R_e connected in series with the coil, using a value of the external resistance roughly equal to the coil impedance and arranging the voltmeter to read the total voltage across the two components. In this way determine the impedance of the combination. Using the value of X already found, show that the impedance

is now equal to $\sqrt{(R^2 + X^2)}$ where R is the total resistance $R_e + R_e$. Draw a vector diagram to scale representing the impedance of the coil and of the combination (Fig. 275c).

(iv) Apply a voltmeter to the coil, the external resistance, and the combination in turn, as shown at V_1 , V_2 and V , and show that $V_1 : V_2 : V = AC : CC' : AC'$. Notice that $V_1 + V_2 \neq V$, but that V is the 'vector' sum of V_1 and V_2 . Note also that the phase angle between V_1 and V_2 , the angle between AC produced and CC' , or the angle CAB , differs from 90° because of the inherent resistance of the coil.

A.C. Circuit having Capacitance

NOTE.—It must be remembered that the secondary winding of a transformer is a source of E.M.F. with an internal impedance consisting of an *inductance* with a *very low resistance*. If a condenser is connected to the transformer it is possible that the negative reactance of the condenser may neutralise the positive reactance of the transformer giving a circuit which is resonant, having a total impedance equal to the resistance of the transformer winding. In this event dangerously large currents will be produced. To prevent this an external resistance of suitable magnitude should be connected in series with the condenser.

Suppose that a pure resistance of, say, 300 ohms connected *in series* with a condenser of capacitance $10 \mu F$ is subject to an alternating voltage at 50 c/s. The capacitive reactance X is 318 ohms and the impedance Z is 437 ohms. Thus an applied potential of 40 volts would give a current of the order of 100 mA. The student should verify these statements.

EXPT. 258B. **Reactance of a Condenser.**—Connect one or more resistances of 100 ohms *in series* with a capacitor of nominal capacitance of about $10 \mu F$. Radio resistors capable of dissipating 1 or 2 watts are suitable, but the actual values of the resistance should be measured on a Wheatstone bridge. Calculate the maximum permissible current and adjust the conditions of the experiment, with regard to the applied voltage and meter ranges, accordingly.




FIG. 275E.—Circuit Diagram for Capacitive Reactance

Connect to the source of supply at 50 c/s, measure V and I , and calculate the impedance Z of the combination. From this value of Z and the known value of R calculate the capacitive reactance of the condenser, and deduce its capacitance.

Measure also the P.D. (V_1) across the condenser and that (V_2) across the resistance and test the relation $V^2 = V_1^2 + V_2^2$. This assumes that the condenser behaves as a pure capacitor, V_1 and V_2 differing in phase by 90° .

Frequency of Alternating Current.—The normal supply of A.C. in Great Britain is maintained very accurately at 50 c/s and so lies within




FIG. 275D.—Circuit Diagram for Inductive Reactance

the range of audio frequencies (from about 30 to 30,000 c/s). A note having a pitch corresponding to the frequency 50 c/s may be heard in a telephone receiver by using the transformer principle. The phone is connected to a coil of several turns of fine wire wound round one end of an iron rod or a bundle of iron wires. The other end of the rod is wound with a coil of thicker wire connected to the A.C. supply mains through a lamp resistance (p. 490).

An alternating current may be used to maintain *forced* vibrations in a solid *vibrator*, which may be either a steel tuning fork or an iron rod clamped at some point of its length. The effect is most marked when there is approximate agreement between the *free* frequency of the vibrator and that of the A.C. supply. This provides one way of determining frequency by a method due to Melde.

Melde's Experiment.—A string stretched between two points A and B (Fig. 124) and set in transverse vibration may vibrate as a whole, the ends being nodes and the central part an anti-node. But it is also possible for stationary vibrations of the type shown in Fig. 114 to take place, the string vibrating in segments or parts, and then the term *partial* is used to describe the vibration of the segments. In Melde's experiment the string is set in *resonant* vibration by a succession of impulses having the same frequency of one of its partials, or modes of vibration. This is done by attaching one end of the horizontal string to the vibrator, the other end passing over a smooth pulley and supporting a known load M gm. so that the string is stretched by a tension T or Mg dynes as in Fig. 126.

The velocity of propagation of a wave along a string is $\sqrt{T/m}$, where m is the mass of unit length of the string (p. 180). If d is the distance between consecutive nodes, the wave-length λ is $2d$. This is the distance travelled by the wave in a complete cycle. Hence the period of vibration is $2d/\sqrt{T/m}$ and the vibration frequency, n , which is the reciprocal of the period is given by

$$n = \frac{1}{2d} \sqrt{\frac{T}{m}} = \frac{1}{2d} \sqrt{\frac{Mg}{m}}.$$

In resonant vibration this frequency is the same as that of the driving vibrator provided the driving point vibrates at right angles to the direction of the string.

Expt. 258C.—Frequency of A.C. Supply by Melde's Method.—The vibrator drawn to $\frac{1}{2}$ size in Fig. 275F was designed in the Royal Technical College, Glasgow. The rod of steel (No. 16 S.W.G.) is about 23 cm. long and is clamped near its middle point. This allows a certain amount of adjustment for tuning. The coil of No. 24 double cotton-covered wire is wound on a former about 7.6 cm. long and 6 cm. diameter with an axial hole about 1.5 cm. in diameter. The thread attached to the end of the rod may be parti-coloured, or may be either black or white with a contrasting background.

The coil is supplied with A.C. from the mains through a carbon filament lamp as a resistance or from a transformer, and the rod is thus magnetised longitudinally, first in one direction and then in the other. A permanent horse-shoe magnet near the end of the coil produces oscillations by interacting with the magnetised rod, the necessary energy being derived from the electric supply.

Adjust the apparatus so as to give resonant vibrations, first by altering the position of the rod in its clamp, and secondly by altering




FIG. 275F.—Electric Vibrator for Melde's Experiment

the load on the far end of the string. The second adjustment is made so as to give well-defined segments on the string. Then measure the distance between two nodes near the two ends of the string, and deduce d the inter-nodal distance. Find m , the mass per unit length of the string, by weighing a known length, and calculate the value of the frequency n by means of the formula above. Repeat the determination for several values of d by using different loads.

Although this method of finding the frequency is not at all accurate, the experiment is very instructive and should be carried out as carefully as possible. The difference between the calculated frequency and the known frequency of the A.C. supply should be clearly stated, and *the sources of error considered.*

COMPARISON OF CAPACITIES

METHODS FOR THE COMPARISON OF CAPACITIES

THE capacity or capacitance of a condenser may be defined as the quantity of electricity required to increase the potential difference between the conductors by unity. The name **capacitor** is sometimes given to a condenser.

The capacity of a condenser is one **farad** when one coulomb of electricity is required to change the P.D. between the plates by one volt. One **microfarad** = 10^{-6} farad = 10^{-15} E.M.U.

When two condensers are charged to the same potential, the quantities of electricity on the condensers are proportional to their capacities. If, therefore, we discharge two such condensers separately through a ballistic galvanometer, observations of the first throws produced will enable us to compare the capacities of the two condensers.

EXPT. 259. Comparison of Capacities—Ballistic Galvanometer Method.

—Connect a secondary cell to a condenser by means of a two-way key, so that in one position of the key the cell is connected to the terminals of the condenser. Connect a galvanometer to the condenser and key, so that in the other position of the key the galvanometer is connected across the condenser terminals and the cell is on open circuit. Special 'condenser' keys or 'discharging' keys are supplied for this purpose, but any quick-acting two-way switch will serve satisfactorily, provided it is insulated well. Sometimes two tapping keys are used. Make the connections as in Fig. 276.




FIG. 276.—Capacity of Condenser

The sudden deflection produced when the key is switched quickly over from position I to position II should be observed. The condenser is then removed, the second condenser being put in its place, and the experiment repeated.

The ratio of the two deflections may be taken as the ratio of the capacities of the two condensers, the deflections being proportional to the quantities of electricity discharged round the galvanometer, to within the limits of accuracy of experiment.

The condensers must be changed over rapidly, in case the E.M.F. of the cell should change. For this reason *two* similar two-way keys may be used, or a double discharging key. The connections would then be as

shown in Fig. 277. Only one key should be used at a time, the other key not being left in contact with either side if this be possible.

It is often possible to facilitate experiments on current electricity by the use of additional keys, etc., in this way.

The comparison of capacities may be made by *charging* instead of *discharging* each condenser. For this purpose the galvanometer is connected between the condenser and the key in Fig. 276.

EXPT. 260. Comparison of Capacities by Wheatstone's Bridge Method.—The capacities to be compared must be connected with a pair of resistances, a galvanometer, a battery and a two-way key, as in Fig. 278.

Adjust the resistances R_1 and R_2 until, on switching the two-way key across in *either* direction, there is no deflection of the galvanometer. Then

$$\frac{C_1}{C_2} = \frac{R_2}{R_1}.$$

For the absence of any deflection means that there is never any difference of potential between C and D, and no current ever flows through the galvanometer. If this is so, the condenser C_1 must be charged up entirely through the resistance R_1 , and C_2 entirely through R_2 , and they must reach their final potentials simultaneously.

Now the rate at which the condensers are charged up through these respective resistances will be proportional to the reciprocals of the resistances, and the charges Q_1 and Q_2 gained in equal times will be proportional to $1/R_1$ and $1/R_2$. But the condensers reach the same final potential together, hence Q_1 and Q_2 are proportional to C_1 and C_2 , or—

$$\frac{C_1}{C_2} = \frac{R_2}{R_1}.$$

If either condenser is charged up before the other, a little

current will flow through the galvanometer towards the condenser which has not yet obtained its full charge, and hence if the resistances are not adjusted suitably there will be a slight deflection of the galvanometer one way or the other.

NOTE.—This method, although a null method, does not possess any great sensitiveness. The only quantity of electricity which flows through




FIG. 277.—Comparison of Capacities




FIG. 278.—Wheatstone's Bridge Method

the galvanometer is a small part of the difference of the charges on the condensers when one of them has acquired its full charge. The charges themselves are in general not large, and would be insufficient to cause more than a measurable deflection on the galvanometer. The deflection produced by part of the small difference between the two charges, is therefore very small indeed, and the adjustment of the resistances can be varied usually over a wide range, without causing any appreciable deflection of the galvanometer. The method is most sensitive if R_1 and R_2 are considerable and the galvanometer is of low resistance, but it is unsatisfactory unless the condensers to be compared are large.

EXPT. 261. Comparison of Capacities — Method of Mixtures.—Connect up an 8-volt cell in series with two large adjustable resistances




FIG. 279.—Method of Mixture

(1000 to 10,000 ohms). Arrange the condensers to be compared so that they can first be connected across these resistances, can then be disconnected, their charges mixed, and the residue discharged through a galvanometer.

The method by which this is done is indicated in Fig. 279.

When the double throw switch is put over so that A is connected to C and B to D, the condensers C_1 and C_2 are charged to potentials equal to those between the ends of the resistances R_1 and R_2 respectively.

If these are indicated by V_1 and V_2 , the charges on the condensers will be C_1V_1 and C_2V_2 respectively.

On switching over so that A and B are connected to E and F respectively, the positive charge on C_1 is mixed with the negative

charge on C_2 through the wire PRQ, while the negative charge on C_1 is mixed with the positive on C_2 through the switch. The pairs of plates are connected simultaneously together through the galvanometer, and any residual charge after mixing is discharged through the galvanometer. By suitably adjusting R_1 and R_2 the residual charge can be reduced to zero, and no deflection will be produced in the galvanometer. ...

When this is the case,

$$C_1V_1 = C_2V_2,$$

but V_1 and V_2 are proportional to R_1 and R_2 .

Thus

$$C_1R_1 = C_2R_2,$$

or

$$\frac{C_1}{C_2} = \frac{R_2}{R_1}.$$

This method being a null method is preferable to the method using a ballistic galvanometer (Expt. 259). It is also much more sensitive than the Wheatstone's bridge method, and can be used for quite small capacities.

A high-resistance galvanometer of great sensitiveness is the most suitable type of galvanometer to use for this experiment.

NOTES ON ELECTRICAL APPARATUS

§ 1. TANGENT GALVANOMETERS

Single Coil Tangent Galvanometer.—The simple type of tangent galvanometer has already been described on p. 382. It consisted of a vertical coil of wire placed with its axis east and west, carrying at the centre of the coil a magnetometer box for measuring the intensity of the field due to the current I in the coil. I is measured in C.G.S. electromagnetic units. This unit is 10 times the practical unit, the ampere.

If F be the strength of the field at the centre of the coil,

$$F = \frac{2\pi nI}{r} \text{ dyne per unit pole,}$$

where n = the number of turns in the coil,

and r = the radius of the coil in centimetres.

If the needle be deflected through an angle θ° from the meridian as in Fig. 205, p. 338, we have also $F = H \tan \theta$.

Hence
$$\frac{2\pi nI}{r} = H \tan \theta,$$

or
$$I = \frac{rH \tan \theta}{2\pi n}.$$

The simple type of tangent galvanometer is usually constructed with one, two, or three coils, all wound on the same framework. These coils have different numbers of turns, and slightly different radii.¹ By use of one or other of these coils the galvanometer may be made suitable for measuring currents of two or three different orders of magnitude, in other words its 'sensitivity' may be varied.

Thus if the three coils have respectively 1, 10, and 100 turns and a current of 1 ampere gives a deflection of 45° when flowing in the single turn, that coil will be suitable for use in the measurement of currents from about 0.3 to 3 amperes. The coil with ten turns could be used conveniently for currents ranging from 0.03 to 0.3 ampere. This smaller current circulates ten times and therefore produces the

¹ If the number of turns cannot be counted, and the diameter of the coil cannot be measured, these quantities are, or should be, marked on the base of the instrument by the maker.

same effect as a current of ten times its magnitude, flowing in the single turn. In the same way the coil with 100 turns would be suitable for the measurement of currents from 0.003 to 0.03 ampere.

General Case.—When the galvanometer is not of this simple type, the equation for the current can be written in the form

$$I = \frac{H}{G} \tan \theta,$$

an equation which holds good for all types of suspended needle galvanometers, however constructed, provided the needle is parallel to the plane of the coil when in its mean position. In this expression H is the strength of field acting on the needle due to any control magnet and the earth, while G is the strength of field due to the coil when unit current passes through the coil.

The Helmholtz Galvanometer.—A special type of tangent galvanometer was devised independently by Gauguin and von Helmholtz. In




FIG. 280.—Helmholtz Galvanometer

this instrument there are *two* coils so arranged that their distance apart is equal to the radius of either coil.

The magnetometer box is placed midway between the two coils. This arrangement produces a more uniform magnetic field than a

single coil. The axis of the coils is placed east and west. The instrument is used in exactly the same way as the simple type of tangent galvanometer.

The galvanometer constant G , occurring in the equation

$$I = \frac{H}{G} \tan \theta,$$

is given by $8.99N/r$ for I in absolute units, N being the number of turns in *one* coil, and r the radius of the coil in centimetres.

The magnetic force at a point on the axis of a circular coil of radius r , at a distance x from the centre, is $F = \frac{2\pi Nr^2 I}{(r^2 + x^2)^{3/2}}$. In this galvanometer $x = \frac{1}{2}r$, and two coils are used. From this the above value of G can be deduced.

ABSOLUTE MEASUREMENT OF CURRENT

The *absolute* value of the current I corresponding with any deflection θ of a galvanometer needle, can be found from the equation

$$I = \frac{H}{G} \tan \theta,$$

provided H is known and the quantity G can be calculated from the dimensions and arrangement of the galvanometer coil or coils. If, however, the number of turns in the coil be large, their position cannot be determined accurately, nor can their effect on the needle be calculated exactly. To obtain a very sensitive type of galvanometer, the number of turns has to be made so large that accurate calculation of G is no longer feasible.

It is possible to use sensitive types of galvanometers for the absolute measure of currents of very small magnitude, but a description of the methods of doing so is beyond our scope.

Theoretically there is no upper limit to the currents for which a tangent galvanometer can be made suitable. The sensitivity of a single-turn galvanometer can be reduced, either by increasing the radius of the coil, or by using the magnetometer box displaced along the axis. In either case there is a quite accurate expression obtainable for the field at the centre, and hence very large currents could be measured with a tangent galvanometer of suitable construction.

§ 2. SENSITIVE TYPES OF SUSPENDED NEEDLE GALVANOMETERS

SENSITIVITY OF A GALVANOMETER OF THE SUSPENDED NEEDLE TYPE

The *sensitivity* of a galvanometer may be expressed as the relation between its deflection θ and the current I . If θ/I be large, the galvanometer gives a considerable deflection θ for a small current I .

Now I is proportional to $\tan \theta$ in all forms of suspended needle galvanometer, provided the needle lies in the plane of the coil when no current is flowing. Hence θ/I is not constant.

We may, however, take $\tan \theta/I$ as a measure of the sensitiveness of the galvanometer, approximately, for *small deflections*; or

$$\text{Sensitivity} \approx \frac{\tan \theta}{I} \approx \frac{G}{H}.$$

If we wish to increase the sensitivity of the galvanometer, we must therefore increase the ratio of G to H or increase the effect of the field G in some way which does not increase the effect of H , or else diminish the effect of H without altering the effect of G . The methods of increasing the sensitivity may be grouped under the following heads:—

1. Use of an astatic combination for the galvanometer needle.
2. Decrease in the value of the controlling field H .
3. Increase in the actual value of G .

The Principle of the Astatic Combination.—An astatic galvanometer has a compound magnetic system suspended in place of the simple needle used in the tangent galvanometer. In its simplest form the suspended system consists of two light needles fitted in a rigid framework with their magnetic axes in opposite directions.




FIG. 281.—Astatic System of Needles

The two needles are magnetised almost equally and are mounted one *inside* the coil and the other *outside*.

Effect of the Controlling Field on an Astatic Combination.—If the magnetic moments of the needles be M_1 and M_2 , the effect of the controlling field is proportional to $H(M_1 - M_2)$, since the needles are magnetically opposed.

Effect of the Field due to the Current on an Astatic Combination.—By placing the needles one inside and the other outside the coils, they are in two parts of the *coil* field which are in *opposite* directions, and as the needles are *also* opposed the couples exerted on the two needles are in the *same* sense. The total couple exerted on the needle by the field of the coil is consequently proportional to $G(M_1 + M_2)$ very roughly, the approximation being only very rough because the strength of the field outside the coil acting on the needle M_2 is not nearly equal to G the strength of the field inside the coil.

The sensitivity of an instrument of this type is thus greater than that of a single needle instrument with similar coils, by a factor $\frac{M_1 + M_2}{M_1 - M_2}$ (roughly), so that with nearly equal needles an astatic galvanometer may be extremely sensitive.

If M_1 and M_2 are too closely equal, the instrument becomes unstable, and therefore care must be taken to avoid this.

An instrument using a needle of this type is not *absolute* on account of the unknown value of $\left(\frac{M_1 + M_2}{M_1 - M_2}\right)$. It cannot be relied upon to give consistent deflections for the same current from day to day, as a slight

change in M_1 or M_2 has a large effect on the denominator of this factor, and consequently on the sensitiveness.

The Control Magnet.—Frequently a control magnet is fitted above the coil of a galvanometer; the height of the magnet above the coil can be adjusted, and the magnet can also be rotated about a vertical axis.

The needle of the galvanometer is then under a resultant field H , due to the field of this magnet and the field of the earth combined. The value of H is thus adjustable over a wide range. For great sensitivity the magnet is adjusted until its field almost completely overcomes the earth's field. If, on the other hand, the galvanometer is required to be insensitive, as when determining its resistance by Thomson's method, the magnet is brought down close to the needle and its field arranged so as to assist the earth's field, H then being very great. A weak control field causes a very slow swing of the needle, a stronger field causing a correspondingly quicker swing, hence for great sensitiveness the magnet must be adjusted to give a very slow swing to the needle; the sensitiveness is proportional to the square of the period of swing.

A great advantage of the use of the control magnet is that the controlling field can be directed as desired, by turning the control magnet, or any permanent deflection due to a steady current can be corrected by rotation of the magnet.

Method of obtaining an Increase in the Galvanometer Constant G .—To increase the field due to unit current it is necessary to use a coil of small radius r and with a large number of turns n . These requirements are to a certain extent antagonistic, the radius of the outside turns increases as the number of turns is increased, and there is a limit to the extent to which n may be usefully increased.

SIMPLE TYPE OF ASTATIC GALVANOMETER

In the simple type of astatic galvanometer the coils are wound flat so that fairly long needles can be used: the flattening of the coil is equivalent to a reduction of the radius and makes for increased sensitiveness; although if the coil is flattened, G cannot be calculated.

This type of galvanometer is used chiefly to detect minute currents in rough experiments with Wheatstone's bridge.

A useful exercise is to calibrate a galvanometer of this type using a 2-volt cell and a resistance box adjustable to 10,000 ohms. Calculate the current, assuming the cell to give 2 volts, and plot curves giving the variation of I with θ and of I with $\tan \theta$.

By combining an Astatic Magnetic System with a control magnet, galvanometers of great sensitiveness can be made. Sometimes the two parts of the Astatic System are placed in separate coils one above the other, wound oppositely so as to give couples in the same sense acting on each of the needles.

The **Figure of Merit** of a galvanometer is usually determined by the current in amperes required to give a deflection of 1 mm. on a scale at a distance of 1 metre, when a lamp and scale method is used for measuring the deflection.

HIGH AND LOW RESISTANCE GALVANOMETERS

A galvanometer may be made with a large constant G , by the use of fine wire in winding the coils. This entails great resistance, but that is no

disadvantage for work where a definite quantity of electricity has to be measured by discharging it round the galvanometer. Thus if a condenser is charged and the charge has to be measured, the whole charge will pass round the coil of the galvanometer, however large its resistance.



FIG. 282.—Sensitive Galvanometer

On the other hand, in testing for balance in using a Wheatstone's bridge, the adjustment has to be made until two points are at the same *potential*, and a galvanometer must be used which will detect the smallest *potential difference* possible. In such a case, the current flowing through a high-resistance galvanometer would be much smaller than that through a low-resistance galvanometer for the same P.D. In the case of the high-resistance galvanometer, the current would be small but would pass through a large number of turns. With the low-resistance galvanometer a much larger current would pass, but through a smaller number of turns. Usually, the galvanometers being similar in design, a smaller deflection would be obtained with the high than with the low resistance galvanometer in a case of this type, and hence, for detecting small potential differences, a low-resistance galvanometer should be used.

This may be summed up by saying that a high-resistance galvanometer is extremely *current sensitive*, while a low-resistance galvanometer has a great *potential* sensitiveness. High-resistance galvanometers are used for the *measurement* of relatively large potential differences and for the *detection* of minute currents. Low-resistance galvanometers are used for the measurement of relatively large currents and for detecting small potential differences.

BALLISTIC GALVANOMETERS

When the duration of the current is extremely short, the *quantity* of electricity passing through the coil of the galvanometer may be measured by observing the *throw*, or first swing, of the needle, provided the time which the current lasts is small compared with the time of swing of the needle and provided the damping is slight. A galvanometer of this type is termed a *ballistic galvanometer*.

§ 3. SUSPENDED-COIL GALVANOMETERS

A suspended *needle* galvanometer possesses the great disadvantage that it is susceptible to any variation in the external magnetic field.

By use of a suspended *coil* galvanometer, this difficulty is got over entirely : this type of galvanometer also possesses the advantage that it can be set up facing in any direction desired.

If a wire of length l cm., carrying a current I absolute C.G.S. units, be placed perpendicular to a field of strength H dynes per unit pole, the wire experiences a force of $HI l$ dynes, the direction of the force being perpendicular to the wire and to the magnetic field.

If a rectangular coil be placed so that the plane of the coil lies in the direction of the field H , a current I flowing through the coil will




FIG. 283.—Suspended-Coil Galvanometer

cause a couple of $HIldn$ to act on the coil, d being the breadth of the coil, l its length, and n the number of turns in the coil. The product ld is equal to A , the area of the rectangle.

For a coil of *any* shape the couple is $HI nA$, where A is the area of the face of the coil.

In a suspended-coil galvanometer, the coil, supported by a fine strip of phosphor-bronze, is suspended between the poles of a very powerful magnet (Fig. 283). The current is led into the coil by the suspending fibre and leaves by a loosely wound helix attached to the base of the coil.

Any motion of the coil due to the couple $HI nA$ is opposed by a resisting couple exerted by the suspension.

When the coil is deflected through an angle, the couple acting on the coil, if the field is uniform, is $HI nA \cos \theta$, due to the magnetic

field, and the restoring couple is $k\theta$, due to the suspension, k being the torsion coefficient of the suspending fibre. The coil comes to rest when $HInA \cos \theta = k\theta$,

or

$$I = \frac{k\theta}{HnA \cos \theta}.$$

For small deflections $\cos \theta$ may be taken as unity, and the sensitiveness is expressed as $\frac{\theta}{I} \approx \frac{HnA}{k}$.

Hence for sensitiveness we require a coil of large area, and of many turns, hanging in a very strong field H , and suspended by a fibre for which k is very small. The coefficient k is the restoring couple for unit twist, and is exceptionally small for a wire of beryllium-copper alloy.

In some forms a bifilar suspension is used, the current entering and leaving by the two suspending fibres; this type is not very common.

Method adopted in Suspended-Coil Galvanometers to make the Deflection proportional to the Current.—The factor $\cos \theta$, which occurs in the expression for I above in the case of a suspended-coil galvanometer with a uniform field, can be avoided.

The pole-pieces of the magnet are ground concave so as to form portions of a cylinder. Between them there is a cylindrical soft-iron core, its axis being coincident with the axis of these cylindrical surfaces. In the annular space between the core and the pole-pieces, the field is very nearly *radial*, and may be considered as *radially symmetrical* over a considerable angle on either side of the mean line. In this annular space the coil moves, and the field is in the same plane as the face of the coil in all positions, provided the coil is not displaced more than 30° from the position where it lies symmetrically across from one pole to the other. The strength of the field is uniform over the range, and therefore the coil is subjected to a couple $HInA$ when carrying a current I , irrespective of its position.

If it is deflected by the current through an angle θ from its zero position (which may be anywhere in this range), the deflection will be given by

$$HInA = k\theta,$$

so that

$$I = \frac{k\theta}{HnA}.$$

'Dead-beat' Type of Galvanometer.—If the coil is wound on a light, conducting frame, or is enclosed in a conducting tube which moves with the coil, the motion of the coil is impeded by currents induced in the frame or tube due to its motion across the lines of force.

A galvanometer of this type moves up to the deflection θ corresponding with the current in the coil, and comes to rest at once. The deflection θ is not affected by the induced currents, as they have a zero value as soon as the motion ceases.

Method of 'damping' the Oscillations of a Suspended-Coil Galvanometer.—If the coil is not mounted on a conducting frame, its oscillations can be reduced by 'short-circuiting' the galvanometer, when it is required at rest in its zero position. This is done by connecting the terminals to a tapping key; the key is left open during any experiment, but when the galvanometer is to be brought to rest the tapping key is depressed. The E.M.F. in the coil due to its motion across the field can then send an induced current through the coil, this current opposes the motion and the coil comes to rest immediately. The key should only be pressed as the coil is almost in its mean position, otherwise the motion towards the mean position will be very slow and time will be wasted. The coil must be at rest with the tapping key *open* before the next deflection is taken.

In using a P.O. Box it is sufficient usually to depress the galvanometer key alone, no auxiliary tapping key being required.

§ 4. AMMETERS AND VOLTMETERS

AMMETERS

An **ammeter** is an instrument graduated in such a way that the current flowing through it can be read off at once in amperes, or fractions of an ampere, by means of a pointer moving over a divided scale. In general, a galvanometer is an essential part of an ammeter.

For large currents a **shunt** is incorporated in the instrument, so that only a fraction of the total current passes through the galvanometer coil, the shunt being adjusted until currents of the required value give a suitable deflection of the pointer. For a multiple-range ammeter several shunts are provided, so that different fractions of the current flow through the coil.

The following example (based on the theory given on pp. 392-394) illustrates the method of calculating the shunt required to convert any kind of galvanometer of a given sensitiveness, into an ammeter reading over a certain range :—

Suppose a current of 0.0002 ampere through the galvanometer coil gives the full deflection on a given instrument, the coil having a resistance of 15 ohms. If it is required to use this as an ammeter reading to 5 amperes a shunt S must be provided, so that when a total current of 5 amperes is flowing, the current in the coil is 0.0002 ampere: the instrument then giving its full deflection for a total current of 5 amperes.

The value of S can be worked out as follows :—

$$\frac{\text{Current through Coil}}{\text{Total Current}} = \frac{\text{Resistance of Shunt}}{\text{Resistance of Shunt} + \text{Resistance of Coil}}$$

Hence $0.0002 = \frac{S}{S + 15}$. This gives $S = \frac{0.003}{4.998}$, or $S = 0.0006$ ohm approximately.

In a similar way the magnitude of the shunt required for any range of current can be calculated. The shunt is usually calculated approximately, and then is adjusted *after fitting*, till the ammeter reads correctly when a known current is sent through it.

Attracted-Iron Ammeters.—For rough work attracted-iron ammeters are largely used. The current flows round a coil and attracts a piece of iron with a force depending on the current flowing. The iron is attached to a

pointer which is moved over a scale as the iron moves, the moving system being pivoted on delicate steel pivots. The motion is controlled by a balance weight and a hair-spring, so that the pointer always takes up the same position for a given current, returning to zero when the current is switched off. The scale of such an instrument is very uneven, and must be graduated empirically by sending known currents through the instrument, and marking the position of the pointer to correspond.

Attracted-iron ammeters may be used for alternating current as well as direct, if a thin piece of very soft iron is used.

Hot-wire Ammeters.—In this type of ammeter the current, or a fraction of the current, flows through a thin wire stretched between two fixed supports. The wire, being heated, expands. Another wire is attached to the middle of the heated wire and passes round a thin spindle on which the pointer is mounted, the spindle being rotated by a hair-spring so as to keep this second wire taut.

When the hot wire expands, its middle point is pulled sideways by the second wire, until all the sag of the hot wire is taken up. The rotation of the spindle turns the pointer through a corresponding angle, and thus the motion is recorded on a scale.

Hot-wire ammeters may be used for either alternating or direct current. The scale is not at all uniform, being much more 'open' for large currents than for small.

Moving-coil Ammeters.—A moving-coil ammeter is constructed exactly like a suspended-coil galvanometer except for the mode of suspension. The coil is usually

mounted on pivots, and its motion is controlled by one or two hair-springs, which also serve to conduct the current up to and away from the coil.

By the use of concave pole pieces and a coaxial cylindrical iron core the deflections are made proportional to the current, so that the scale is practically uniform, the coil being allowed to move only over the region where the field is radial. A suspended-coil ammeter must be connected so that the current




FIG. 284.—Moving-coil Ammeter

always goes through it in the proper direction ; it is only suitable for use with direct current (D.C.), unless a *rectifier* is provided.

The requisites of a good ammeter are (1) accuracy and (2) low resistance. An ammeter must have a low resistance so that it may be inserted in a circuit through which a current is flowing and yet not alter appreciably the value of the current in the circuit. This means that any additional resistance introduced into the circuit must be very small.

VOLTMETERS

A **voltmeter** is used to indicate the difference of potential between the two points across which it is connected. In theory it should take no current whatever, otherwise the P.D. between these two points may be changed when the voltmeter is connected across them.

This condition is only satisfied in Electrostatic Voltmeters, the usual type of voltmeter being a high-resistance galvanometer which only approximates to this ideal: *in theory we assume that the current in the voltmeter is a negligible quantity, in practice this is not realised.* The higher the resistance of the voltmeter, the more accurately will it indicate the P.D. *originally existing* between the points to which it is connected (see example below).

Any type of galvanometer suitable for use as an ammeter can be adapted for use as a voltmeter. The difference in the construction is, that whereas the galvanometer is *shunted* with a *very low* resistance to make it into an *ammeter*, it has a *very high* resistance in *series* with it when required for use as a *voltmeter*.

Moving-coil Voltmeter.—The usual type of voltmeter is a suspended-coil galvanometer similar to the galvanometer part of the moving-coil ammeter already described. In series with it is a coil of high resistance. The value of the resistance required for a given range can be calculated as follows :—

Suppose the moving-coil galvanometer gives its full deflection for a current of 0.0002 ampere as assumed before (p. 481), and that its resistance is 15 ohms. This can be made into a voltmeter reading up to 5 volts by including in the instrument a resistance R in series with the coil, R being so adjusted that a current of 0.0002 ampere goes through the coil when the P.D. across the terminals of the instrument is 5 volts. Evidently R is given by the equation

$$0.0002 = \frac{5}{R + 15}, \text{ so that } R = 24985 \text{ ohms, or } 25000 \text{ ohms very nearly.}$$

If a resistance of this magnitude is connected in series with the moving-coil galvanometer, the whole would be a voltmeter of range 0 to 5 volts.

The value of the resistance required for any other range could be calculated in a similar way.

A moving-coil voltmeter of this type is suitable only for use with direct current (D.C.), unless a *rectifier* is provided.

Hot-wire voltmeters can be constructed in a similar way, the moving system being identical with that of a hot-wire ammeter.

It is of great importance to note that, assuming the graduations to be accurate, the voltmeter reading is the P.D. between its own terminals.

The Effect of the Finite Resistance of the Voltmeter.—This is illustrated in the following example :—

A cell of E.M.F. 2 volts has an internal resistance 20 ohms. Its poles are connected to a voltmeter. What will be the voltmeter reading if the voltmeter resistance is (a) 20, (b) 200, (c) 2000 ohms ?

If E is the E.M.F. of the cell and V the P.D. across the voltmeter terminals,

$$E = \left\{ \frac{R+B}{R} \right\} V,$$

where R is the external resistance and B the internal resistance.

In this case R is the voltmeter resistance.

$$(a) R = 20 \text{ ohms.} \quad V = 2 \frac{20}{20+20} = 1 \text{ volt.} \quad \text{Error, 50 per cent.}$$

$$(b) R = 200 \text{ ohms.} \quad V = 2 \frac{200}{200+20} = 1.82 \text{ volts.} \quad \text{Error, 10 per cent.}$$

$$(c) R = 2000 \text{ ohms.} \quad V = 2 \frac{2000}{2020} = 1.98 \text{ volts.} \quad \text{Error, 1 per cent.}$$

The quantities V are the voltages which would be registered by the various voltmeters.

With a voltmeter of yet higher resistance, the error would be reduced still further.

With a cell of lower resistance, the accuracy would also be greater.

Cheap voltmeters usually have fairly low resistance, and can only be relied on when the resistances of the conductors between the points to which they are connected are extremely low.

§ 5. COMMUTATORS

A commutator is an arrangement for reversing the direction in which the current flows through a particular piece of apparatus (usually a galvanometer) without disconnecting any wires. A commutator must possess at least four terminals. Of these two (marked G_1 and G_2) must be connected to the apparatus in which it is desired to reverse the current,




FIG. 285.—Parallel and Diagonal Type Commutators

and the other two (we may call them the battery terminals, P and N) to the source of current. The only difficulty is to decide which two are to form a pair. Commutators may be divided into two types, (1) the parallel type and (2) the diagonal type (Fig. 285).

In the parallel type the battery terminals, P and N , are in a line parallel to the line joining the apparatus terminals. In the diagonal type the battery terminals are diagonally opposite one another. The connections in the first position are shown by continuous lines, and the connections in the second position by dotted lines. In the first position the terminal G_1 becomes positive, G_2 negative; in the second position G_2 becomes positive, G_1 negative. The student should notice that in the first type there is a diagonal connection (PG_2 , NG_1), in the second type there is no diagonal connection.

The method of connecting up any commutator can be worked out in the following way :—

Choose one terminal of the commutator and label it P . Note the terminal connected with it in one position of the moving part of the commutator; call this terminal G_1 . Then “reverse” the commutator by

moving over the switch arm. The terminal to which P is now connected is labelled G_2 .

Now find a terminal to which G_2 is connected when P is in the first position, and call this N; it will generally be found that when P is connected to G_2 , N is connected to G_1 at the same time. P and N are used as the battery terminals and G_1 and G_2 are the galvanometer terminals of the commutator.

If only four terminals are fitted, N must obviously be the remaining terminal after P, G_1 , and G_2 have been decided on.

If it should happen that N is *not* connected with G_2 when P is connected with G_1 , and *vice versa*, it is evident that the wrong terminal has been chosen for P, and the investigation must be recommenced, choosing another terminal as P. This will occur only very rarely, the pairs G_1 and G_2 , and P and N being always interchangeable.

This method is not applicable to a plug commutator.

Various forms of commutator are illustrated in Figs. 286-289.

Fig. 286 is a convenient form¹ which deserves to be more widely used. The central disk, which can be rotated about a vertical axis, carries two metal strips which make contact with the four metal studs.

Fig. 287 is a double plug switch belonging to the diagonal type, and the battery must be connected to terminals which are diagonally opposite one




FIG. 286.—Wheatstone Commutator




FIG. 287.—Double Plug Switch

another. The plugs must never be inserted in *adjacent* holes, but always in holes which are diagonally opposite one another.

A useful form of commutator by W. G. Pye & Co., Granta Works, Cambridge, is shown in Fig. 288. The moving arm, carrying two terminals, turns about a vertical axis and has laminated brushes attached to ensure good rubbing contact.

If these upper terminals are called G_1 and G_2 and the lower terminals

¹ It appears to be peculiar to the Wheatstone laboratory, King's College, London.

on the base P and N (on the left and right, respectively), the terminal G_1 is positive and G_2 negative in the position shown. On rotating the moving part through a right angle in the clockwise direction, G_1 becomes negative




FIG. 288.—Reversing Key (W. G. Pye & Co.)

and G_2 positive. In some experiments it may be advisable to clamp the base to the laboratory table.

Fig. 289 is known as Pohl's commutator. A and B are the battery terminals. The apparatus in which the current is to be reversed is con-




FIG. 289.—Pohl's Commutator

nected either to C and D, or to E and F. The rocking part S dips into mercury cups. This form is not recommended for an elementary laboratory. A rocking commutator of the Pohl type can be constructed without mercury cups if spring contacts are fitted at the two ends and hinge contacts at the middle.

§ 6. KEYS AND SWITCHES

Plug Key.—This key is used for making a good connection of low resistance when a current has to be maintained for a considerable time. Gambrell's form (p. 488) has been found reliable.

Tapping Key.—In this key contact is made only when the spring is depressed, the spring automatically breaking contact when the pressure is removed. It is convenient for use whenever a current is only required momentarily, as in damping the oscillations of a suspended-coil galvanometer.

Two-way Switch.—This is a convenient form of switch when it is necessary to change a connection rapidly from one piece of apparatus to another, as in the case of the Potentiometer (Fig. 237) A hinged arm can be turned

so as to make contact with one or other of two metal studs. One terminal is connected to the hinge, and one to each of the studs.




FIG. 290.—Tapping Key




FIG. 201.—Two-way Switch

Double Pole Throw-over Switch.—This is a useful type of switch provided with six terminals, and its construction may be understood at once from




FIG. 292.—Double Pole Throw-over Switch

the diagrams. In the position shown in full line in Fig. 293 the connections are from A to C, and B to D. In the other position, A and E are connected, and B and F.




FIG. 293.—Double Pole Throw-over Switch

A Pohl commutator becomes a switch of this type if the cross connections from D to E and C to F are removed (Fig. 289).

§ 7. RESISTORS AND RHEOSTATS

The name resistor is given to any apparatus that is used on account of its having the property of electrical resistance.

The simplest form of resistance for laboratory use is a length of bare platinoid or manganin wire. For resistances up to about 1 ohm a length of about 1 metre of wire (No. 22, S.W.G.) serves as an adjustable resistance by fixing one end to a point in the circuit and sliding the free part of the wire under a binding screw till the required resistance is obtained. Nichrome

is an alloy possessing high resistivity, but its temperature coefficient is larger than that of platinoid or manganin.

Resistance Coils.—Bobbins provided with terminals to which are attached the ends of a coil of silk-covered resistance wire are useful both as known and as unknown resistances. Standard coils are made as in Expt. 238.

Resistance Boxes.—A resistance box contains a number of coils constructed to have resistances which are exact multiples and sub-multiples of one ohm. These are wound on small bobbins so as to have as little self-induction




FIG. 294.—Construction of Resistance Boxes

as possible (see Expt. 238, Fig. 254), and are soaked in paraffin wax or coated with shellac varnish.

They are enclosed in a box, usually with an ebonite top, the ends of the coils being brought through the ebonite and connected to thick brass blocks which are mounted on the top of the vulcanite.

Between the blocks conical brass plugs can be fitted (Fig. 294), the plugs being ground so that they fit half into each block, thus making a connection of extremely low resistance between the brass blocks.

If the plug *a* is removed, the current must flow through the resistance coil, the ends of which are attached to A and B, in order to pass from one block to the other. When the plug is inserted, the resistance offered to the passage of the current is negligible. Thus, in using a resistance box, the *total resistance introduced in the circuit by the box is equal to the sum of the resistances indicated at the side of the holes from which the plugs have been removed.*

The plug must be inserted with a slight screwing motion in addition to the pressure required. The plug should always be screwed in a *right-handed direction* even when removing it, otherwise the plug head may be screwed off without removing the plug from the hole. Whenever the plug is removed from between two blocks, the plugs on either side should be pressed into their holes again, as the blocks will have 'sprung' slightly towards the vacant hole and the plugs on either side will be loosened.

This difficulty is avoided in Gambrell's plug contact shown on the right of Fig. 294. The plug *h* is a metal cylinder made conical *inside*, so as to fit over the two outer conical surfaces *d, e* of the socket, and a central pin *k* fits into a hole in the socket. The result of pressing the plug on to the socket is to force all the surfaces into contact, and the two halves of the socket cannot be unduly strained. This form is recommended for accuracy.

Resistance boxes must never be used for heavy currents, as the coils would be overheated and the box 'burnt out'. A box should never be used by a student in conjunction with a secondary cell without special permission. In any case, the resistance in the box must never be reduced

to less than 30 ohms when a secondary cell is used.

Sliding Rheostat.—The resistance wire is wound round an insulating cylinder. One end of the wire is attached to one terminal of the rheostat. The second terminal is attached to a sliding contact piece which can be moved parallel to the cylinder, so as to make contact with the resistance wire at some selected point.

Wheatstone's Rheostat.—Two parallel cylinders are mounted side by side, so that each can rotate about its axis. One cylinder is of brass, the other of some insulating material. A screw thread is cut on the latter cylinder, and a length of resistance wire lies at the bottom of the thread. One end of this wire is attached to the metal cylinder, so that, when this is rotated, the wire is wound off the insulating and on to the metal cylinder. The turns of wire on the metal are short-circuited, so that the resistance in use is that of the wire on the insulating cylinder only. This arrangement gives a *continuous* adjustment of resistance.

Adjustable Carbon Resistances.—A number of circular sheets of carbonised cloth are placed between two metal plates which may be pressed together by means of a nut and a screw. The resistance is altered by altering the pressure between the plates.

In another form solid plates of carbon are pressed together in the same fashion, and the resistance is varied by altering the number of plates or the pressure between them.

Adjustable Resistance Frame.—A convenient form of adjustable resistance in common use is that which consists in a rigid frame on which are stretched




FIG. 295.—Adjustable Resistance Frame

a number of spiral coils of wire arranged in zigzag fashion (Fig. 295). A metal handle connected with one terminal of the rheostat moves over a series of metal studs connected with successive spirals. With the handle in one extreme position the current must pass through *all* the spirals, but as the handle moves from stud to stud the current passes through fewer and fewer spirals, till the other extreme position is reached when the current usually passes direct through the handle to the second terminal of the rheostat. This frame is useful as a rough regulating resistance for fairly large currents, say from 1 to 20 amperes.

Such resistance frames are marked usually with their approximate *full* resistance and by the current which they are designed to carry without overheating. This current must not be exceeded.

These resistances must never be used as standards for comparison, the indicated resistances being only approximately correct.

Rough Fixed Resistances.—A useful type of fixed resistance which is convenient for various purposes where a current has to be reduced to somewhere near a definite amount is the *grid* type. These are usually marked with the approximate resistance and the voltages for which they are designed. From these, the current they are designed to take can be calculated, and this must never be exceeded. These grids will only take this current provided they are well ventilated; if enclosed so that they are not cooled by convection currents, they would overheat and fuse.

Lamp Resistance.—For many experiments current may be used from




FIG. 296.—Lamp Resistance

the lighting mains if suitable resistances are employed to regulate it. A convenient and cheap apparatus is shown in Fig. 296. This can be made in deal or mahogany, using ordinary *batten* lamp-holders. The connections are as shown in Fig. 297. C, D, and E are lampholders screwed to the base and connected in parallel.




FIG. 297.—Connections of Lamp Resistance

The current for the experiment is taken from the terminals A and B. The polarity of A and B can be found by pole-finding paper, and, by the use of one, two, or three lamps, different currents may be obtained for purposes of experiment. The current passed by a carbon-filament lamp is about three times the current passed by a metal-filament lamp of the same candle power. A larger number of lamp-holders may be fitted if desired.

§ 8. TESTS FOR POLARITY

Pole-finding Paper—testing Polarity of D.C. Lighting Mains, etc.—Ordinary litmus paper may be used for finding the polarity of cells, or mains, where direct current is supplied through a suitable resistance. The paper should be moistened and the two wires placed close together on the paper, but they must not touch each other. The point of contact of the *positive* will show

a red mark after a moment or two, the *negative* giving a *blue* coloration. When testing the polarity of the lighting mains great care must be taken ; the bare wires must not touch each other, nor must either wire come into contact with the fingers or any metallic fixtures such as gas or water pipes. *Failure to observe these precautions may result in a severe shock to the experimenter, or in serious burns.*

Starch paper, or paper soaked in a solution of starch and potassium iodide, turns *blue* at the *positive* terminal when two wires are placed in contact with the paper (first moistened).

Methods of determining the polarity of the terminals by means of the magnetic action of the current have been described on p. 374. *In applying these methods to the lighting mains sufficient resistance must be placed in the circuit to prevent the current being excessive.* The lamp resistance described on p. 490 is suitable for the purpose.

One of the mains of the supply company is usually earthed. In the case of a two-wire system the second main may be either above or below the potential of the earth. In the case of a three-wire system the middle wire is earthed. Of the other two, one is above, the other below the potential of the earth. Thus, if the live mains are at +100 and -100 volts respectively, lamps or apparatus requiring 200 volts would be connected across these live mains. If only 100 volts is needed for any purpose, the apparatus is connected between *either* live main and the earthed wire.

§ 9. HIGH POTENTIAL DIFFERENCES

For experiments in which differences of potential of the order of 100 or 200 volts are needed a *high tension battery*, composed of a large number of dry cells or accumulators in series, is frequently employed. By connecting the two points to selected terminals the potential difference required may be 'tapped off' from the battery. *Avoid short-circuiting any part.*

An alternative method is to use a potential divider (p. 407), the principle of which is shown in Fig. 236. The potential difference required is obtained by connecting the two given points to the points A and P. The source S may be a battery consisting of a considerable number of large cells, or direct current (D.C.) mains may be employed. *In using either source, all the precautions mentioned in § 8 must be observed.* The resistance of the potentiometer wire AD must be suitable, and the wire must be able to carry the current from the source without over-heating. For example, when D.C. supply mains giving 200 to 250 volts are used, the wire AD may have a resistance of from 1000 to 2000 ohms and a current carrying capacity of about 0.3 amp. For greater safety the current may be taken through a lamp resistance (p. 490), the potentiometer being connected between A and B (Fig. 297).

§ 10. SECONDARY CELLS OR ACCUMULATORS

The *density* of the solution in a lead cell indicates the condition. For a new cell prepare the solution from the maker's instructions. As a rule the density of a fully charged cell should be about 1.25 and should not fall below 1.17. NOTE : 1, use only *pure* water and *pure* acid ; 2, avoid over-charge and over-discharge ; 3, do not let a cell stand discharged.

The plates of an Edison (iron-nickel) cell are of steel ; the active material is an oxide or hydroxide of nickel for the positive, and is iron for the negative plate. The electrolyte is a 20 per cent solution of caustic potash (KOH). The E.M.F. is from 1.35 to 1.40 volt.

CHAPTER XI

HIGH-FREQUENCY OSCILLATIONS—ELECTRO-MAGNETIC RADIATION

§ 1. ELECTRICAL OSCILLATIONS PRODUCED BY CONDENSER DISCHARGE

WHEN a charged condenser is discharged across a narrow spark-gap, the actual flow of electricity across the gap consists of several surges in opposite directions. In the first surge the electricity acquires a kind of 'momentum' and the condenser becomes 'over-discharged', the plates acquiring charges opposite in sign to those they possessed initially. When the first surge is completed, the plates now discharge across the gap again, again becoming 'over-discharged', under suitable conditions. This process continues until the potential difference between the plates after one of the surges is insufficient for a spark to pass across the gap. The final charges on the plates may be of the same sign as the charges initially carried by them, but it is equally probable that they will be of the *opposite* sign.

EXPT. 202. Residual Charge on Condenser after Discharging through a Spark Gap.—Charge a Leyden jar by connecting the inner coating to a Wimshurst machine, the outer coating being 'earthed'.

Touch the knob of the Leyden jar with a metal plate or ball mounted on a long vulcanite rod and test the sign of the charge on the plate or ball by means of an electroscope (see Part VI., Chap. I., paragraph 2, pp. 365-366).

Now take a wire supported by a long vulcanite rod, put one end under the jar so as to make contact with the outer coating, then, *holding the extreme end of the vulcanite rod*, bring the other end of the wire towards the knob of the Leyden jar. As soon as a spark passes between the wire and the knob, take the wire away again. *The wire must not touch the knob.*

Determine the sign of the charge on the inner coating of the jar by touching the knob of the Leyden jar with the insulated metal plate or ball already referred to, and testing the sign of the charge which this plate or ball takes up.

Repeat the experiment several times and note how often the residual charge on the inner coating is of the same sign as the initial charge, and how often it is of the opposite sign.

If in any *single* experiment the sign of the charge on the knob is found to have become reversed, that observation is evidence of the oscillatory character of the discharge.

IMPORTANT.—*On no account must the knob of the Leyden jar be touched with any part of the body or clothing or with any conductor held*

in the hand. Any wire or other conductor brought up to the knob of the Leyden jar must be insulated by supporting it at the end of a long insulating rod, the OTHER end of which is held in the hand.

NOTE.—High-frequency circuits differ in practice from low-frequency circuits partly because it is difficult to construct *pure* resistors, inductors, and capacitors (p. 465), and the current distribution in a conductor depends on frequency. A resistor usually has some small inductance and consequently behaves as a reactance (p. 464). The inductance of leads and the capacitance between different elements cannot be neglected. Some of the errors due to such causes may be avoided by shielding.

§ 2. ELECTRO-MAGNETIC RADIATION

When an oscillatory discharge passes across a spark-gap, electromagnetic radiations are set up in the surrounding space. These can be detected under suitable conditions by means of a large loop of wire bent so as to bring its ends very close together, the separation being of the order of 0.25 mm. Such a loop, when held close to a spark-gap across which sparks are passing, will pick up the radiations from the conductors leading to the spark-gap, this being made evident by the occurrence of feeble sparks across the gap in the loop.

The existence of these radiations was discovered and demonstrated experimentally in this way by Hertz in 1888.

Hertz showed that these waves or radiations were of the same character as light waves, in that they obeyed the same laws of reflexion as, and could be refracted like, light waves. The wave-lengths of these **Hertzian Waves** are many millions of times greater than the wave-lengths of visible radiations.

The experiments of Hertz confirmed the theory put forward many years earlier by Clerk Maxwell, that electromagnetic waves and light waves are identical in their properties.

§ 3. DETECTION OF ELECTROMAGNETIC RADIATIONS

For the detection of electromagnetic radiations several methods have been employed.

Cohereers.—The discovery of what is known as ‘coherer-action’ was made by Branly (1890), who invented the *coherer*¹ and used it for detecting the existence of electromagnetic radiations. Branly’s coherer consists of two metal rods mounted in a glass tube with their neighbouring ends separated by a distance of a few millimetres, the

¹ The phenomenon manifested in Branly’s detector had been noticed previously by Varley (1866) and by Onesti (1884). In 1879 Hughes employed his microphone in experiments on electric waves.

space between the ends being loosely filled with metal filings (Fig. 298).

When the filings are loosely shaken together, the resistance of such a tube is very high. If, however, a beam of electro-magnetic radiation falls on the tube and on the metal rods, the resistance of the tube falls to a comparatively low value. Shaking the tube restores the resistance to a high value again.




FIG. 298.—Simple Form of Branly's Coherer

The high resistance is probably due to the filings being separated by extremely thin surface films; when electromagnetic waves strike the tube and the conducting rods, the surges produced break through these films and the filings are thus made to cohere.

For descriptions of other forms of coherers reference should be made to historical books on wireless telegraphy or 'radio.'

EXPT. 263. Action of a Coherer.—Take two pieces of brass rod $\frac{1}{4}$ inch in diameter and about three inches long, and a piece of glass tubing, having a length of about 3 inches and a bore *slightly* greater than the diameter of the rods. Smooth the ends of the rods and fix one rod into the glass tube with sealing-wax, the end of the rod being about the middle of the glass tube. Now put a few nickel filings into the open end of the tube, allowing these to drop on to the end of the rod inside the tube. The filings introduced should be sufficient, when shaken down, to fill about $\frac{1}{4}$ of an inch of the length of the tube. Insert the second rod into the open end, and fix it with sealing-wax in such a position that there is a small space between the end of the rod and the short column of filings. When the tube is now placed in a horizontal position, the filings will lie loosely between the ends of the rods, filling about two-thirds or three-quarters of the intervening space.

Connect the coherer just made in series with a 50-ohm coil, a Leclanché cell, and a milliammeter (Fig. 299). Observe that the current taken by the milliammeter is very small.

Now discharge a condenser (Leyden jar) anywhere in the close vicinity of the coherer, and observe that the milliammeter reading increases immediately to a value in the neighbourhood of 20 milliamperes.

A similar effect can be produced by placing an electric bell close to the coherer, and causing the bell to ring by means of an electric current. The spark which occurs at the contact breaker gives rise to waves sufficiently powerful to cause the filings to cohere.

Observe, also, that tapping the coherer sharply, after the sparking has ceased, causes the reading of the milliammeter to fall almost to zero again.

Instead of the 50-ohm coil and the milliammeter, a small 2-volt 'pea'-lamp can be used in simple series with the Leclanché cell and the coherer. At first the lamp will not glow, but the sparking will cause it to do so, thus showing that the resistance of the circuit has diminished very considerably. Tapping the coherer will cause the glow to disappear.




FIG. 299.—Action of a Coherer

NOTE 1.—An accumulator cell may be used instead of the Leclanché cell, but in no case should a battery or cell having an E.M.F. exceeding 2 volts be used. A higher potential difference than 2 volts is liable to break down the surface films and to cause the filings to cohere even in the absence of electromagnetic impulses.

NOTE 2.—An improved coherer can be made by using silver rods instead of brass, or soldering (preferably *hard-soldering*) a silver disc over the ends of the brass rods. A mixture consisting of 96 per cent nickel filings and 4 per cent silver filings is better than filings all of nickel.

Magnetic Detector.—If electromagnetic waves are received by an earth-connected wire (an aerial), an electric current is set up in this wire, the current being oscillatory. The oscillations of this current are very rapid, being of the same frequency as the electromagnetic waves by which they are set up. If a small coil of wire is inserted between the lower end of the aerial wire and the earth, the current will pass through this wire and will set up a rapidly alternating magnetic field along the axis of the coil.

Marconi devised a form of detector in which an endless loop of finely stranded soft-iron wire was made to pass slowly through a coil similar to that just described. Before entering the coil the wire was magnetised by causing it to pass across the poles of a magnet. The magnetism was retained by the wire as it passed through the coil, provided no oscillations were being produced in the coil. If, however, electrical oscillations were taking place in the coil, the rapidly alternating magnetic field along the axis of the coil caused the magnetism of the moving iron wire to be destroyed.




FIG. 300.—Marconi's Magnetic Detector

Any change in the magnetism of the iron inside the coil resulted in a current being induced in a 'secondary' coil wound over the first, and caused a click in telephones connected across the end of this second coil (Fig. 300). Thus an audible indication was obtained when the aerial was receiving electromagnetic waves.

It is difficult to devise any simple laboratory apparatus to demonstrate this effect.

§ 4. DETECTION OF ELECTROMAGNETIC RADIATIONS BY RECTIFICATION METHODS

The system of electromagnetic waves sent out when a spark discharge occurs, dies away very rapidly. Such a series of waves, or

wave-train, can be represented diagrammatically as in Fig. 301. It is called technically a **damped wave-train**.

By the use of three-electrode valves or triodes (see Chapter XII) electromagnetic waves of constant amplitude can be produced, giving




FIG. 301.—Damped Wave-Train




FIG. 302.—Continuous Wave-Train

a wave-train of the type represented in Fig. 302. Such a wave-train is called a **sustained wave** or, more commonly, a **continuous wave-train**.

The electric current set up in an aerial wire receiving a wave-train is of the same form as the wave-train which produces it. A damped wave-train sets up an alternating current which rapidly dies away to zero, while a continuous wave-train causes alternations of constant amplitude to be set up in the aerial wire.

The frequency of alternation is altogether too high for any audible sound to be produced by passing the current through a telephone, even if the diaphragm of the telephone could respond efficiently to an alternating current of such frequency, and even if the self-inductance of the telephone coils would permit any appreciable current of such a frequency to pass through the coils.

Delicate instruments for detecting alternating currents of very small magnitude might be used if the waves received by the aerial were very powerful, as in the vicinity of the station generating or transmitting the waves, but not otherwise, as the sensitivity of such instruments is somewhat small compared with the sensitivity obtainable in instruments for detecting and measuring uni-directional current.

The invention, called by Fleming an oscillation-valve, and its power of rectifying alternating currents of both low and high frequencies, rendered the detection of electromagnetic waves comparatively easy. This form of thermionic valve is described in Chapter XII.

Shortly after Fleming's discovery, it was found that certain crystals (such as zincite and bornite), when held lightly in contact, possessed similar rectifying properties, as did also certain crystals when in light contact with the end of a fine metal wire (say of copper, silver or gold).

Rectification of Electrical Oscillations.—The contact thus formed will transmit a current much more readily in one direction than in the other. A similar departure from Ohm's Law is observed when almost

any two conducting materials are placed in contact, provided the area of contact is sufficiently small and the contact pressure is sufficiently light. It is possible to obtain this effect with the end of a fine platinum wire held in extremely light contact with a disk of platinum. A crystal of carborundum (silicon carbide) in contact with steel is frequently used, the pressure being adjusted by means of a spring so as to give good rectification.

Such a system placed between the lower end of an aerial wire and the earth will, let us suppose, conduct a current much more readily from the aerial to the earth than in the reverse direction. The current which flows through the crystal system will then be more or less unidirectional, so that a damped wave-train received by the aerial will cause a current of the type indicated in Fig. 303 to flow through the crystal, the reverse half of each alternation (indicated in dotted line) being practically suppressed owing to the high resistance offered by the crystal system to a current flowing in this direction. A crystal combination, or a combination consisting of a crystal and a metal wire, having properties of this type, is called a **crystal detector**.

The full line curve shown in Fig. 304 represents the current passing through the crystal detector when the aerial is receiving a continuous wave-train, or represents a **rectified continuous wave**.




FIG. 305.—A Rectified Current indicated by the dotted line produces a single impulse (full line) when passed through an inductive circuit such as a telephone




FIG. 303.—Rectified Oscillations due to Damped Wave-Train




FIG. 304.—Rectified Oscillations due to Continuous Wave-Train

Provision must be made, of course, for the half-waves suppressed by the crystal detector to pass from the earth to the aerial by some other conducting system. In wireless reception this is usually done by connecting the crystal detector in parallel with the **aerial tuning inductance**. (See Expt. 265, and Fig. 312.)

A rectified train of damped waves would be 'smoothed' in passing through any apparatus having an appreciably large self-inductance, such as the coils of a telephone or of a sensitive galvanometer, and its effect on such apparatus would resemble that of a single impulse (Fig. 305).

A rectified train of continuous waves would be smoothed in a similar manner, and its effect would resemble that of a steady or only slightly varying current (Fig. 306).

Thus, a rectified group of damped waves would cause a single click in a telephone, or a sudden deflection in a galvanometer. A rectified continuous wave would produce nothing more than a faint rustling sound in a telephone, due to slight accidental variations of amplitude. In a galvanometer, however, a rectified continuous wave would produce a sensibly constant deflection.




FIG. 306.—A Rectified Continuous Wave (dotted line) produces an approximately constant current (full line) in the telephone

In wireless telegraphy, damped wave-trains produced by 'spark' transmitters are now mainly of historical interest. Each spark gives rise to a single click in the telephones at the receiving station, and, if the sparks follow each other at short intervals, a succession of clicks is heard in the telephones. These give rise to a composite note if the sparks occur regularly and in sufficiently rapid succession, the pitch of the note being that corresponding to the number of sparks per second at the transmitter.

Stations which transmit continuous waves cannot be heard by a receiving station in which the receiver is a simple rectifying system with the rectified current passing through telephones, unless the amplitude of the waves sent out is varied. It is possible, however, to **modulate** the waves so that their amplitudes vary, thus causing corresponding variations in the rectified current at the receiving station and in the attraction of the telephone diaphragm. If the frequency of these variations lies within the range of frequencies to which the telephone can respond, the diaphragm takes up vibrations corresponding to the modulation. Thus, if the modulation causes the amplitude of the continuous wave to vary so that it passes through successive pairs of alternate maxima and minima 256 times per second, the telephone diaphragm vibrates in and out 256 times per second and emits the note 'middle C' (physical pitch).

By suitable means, the modulation can be made to depend on the vibrations produced by any sound, thus musical notes and speech can, as it were, be superposed or impressed upon the high-frequency electromagnetic waves as variations in the amplitude of the waves. When such waves are received on an aerial, and the resulting current is rectified by a crystal and caused to pass through a telephone, the music or speech is reproduced by the telephone with remarkable accuracy if the modulation at the transmitting station is good.

EXPT. 264. Rectifying Action of a Crystal Detector.—Make up a galena-catwhisker crystal detector of the form commonly used in wireless receiving sets. The catwhisker is usually in the form of a very short helix of fine wire mounted on an adjustable brass rod. The galena crystal can be conveniently mounted in a small brass cup by filling the cup with Wood's metal and partially embedding the crystal in the molten metal. The brass rod carrying the catwhisker is supported between metal springs, through which electrical connection can be made to the rest of the apparatus. The brass cup in which the galena crystal is mounted is fixed to the base of the detector support and a connection is taken from the cup, preferably through a terminal, to the rest of the apparatus.

Connect the detector in series with a micro-ammeter with centre zero, or with a galvanometer, and, through a reversing switch, to a potentiometer connected across a battery of small cells having a total E.M.F. of 4 to 6 volts (Fig. 307). If a galvanometer of high sensitivity is used, it is advisable to shunt this before commencing the experiment. A few trials will enable a shunt of suitable magnitude to be selected. The value of the shunt should not be altered during the experiment. It is also advisable to include a resistance of the order of 100 to 1000




FIG. 307.—Rectifying Action of a Crystal Detector

ohms in the micro-ammeter and detector branch of the circuit, in case the crystal detector should be accidentally short-circuited, due to the metal parts coming into contact with each other.

Using a low potential difference across the detector and the micro-ammeter or galvanometer, observe the deflection given by this instrument. Reverse the potential difference applied (by throwing over the reversing key) and observe the deflection again.

Increase the potential difference in small steps and repeat the observations for each value of the potential difference.

The magnitude of the potential difference applied in each pair of observations should be measured or calculated.

Plot your observations, using potential differences across the detector as abscissae and corresponding values of the current as ordinates, and draw a curve through the points thus obtained. Note that these points do not lie on a straight line through the origin, as they would if the flow of current through the detector obeyed Ohm's Law, that is if the resistance of the contact were independent of the P.D. applied and of the direction in which this P.D. acts across the contact. From the curve obtained, calculate approximate values for the resistance of the detector contact for currents in both directions when the P.D. across the contact is (say) 1 volt.

Make up a zincite-bornite detector by mounting a crystal of zincite in a small brass cup and a crystal of bornite in another small brass cup, supporting one of these in an adjustable support so that a fine edge or point of one crystal rests lightly on a flat surface of the other crystal. The way in which the upper brass cup is supported should permit of adjustment of the position of the upper crystal relative to the lower one.

Repeat the experiment described above, using this zincite-bornite combination. Observe that the resistance of the zincite-bornite detector is, on the whole, much larger than the resistance of the galena-catwhisker combination for corresponding values of the potential difference.

NOTE.—Before beginning the experiment with either detector, adjust the detector to give a marked difference between the current in one direction and the current in the opposite direction when a potential difference of about 0.5 volt is used. This adjustment should not be altered subsequently during the experiment as the crystal surface may not be uniformly sensitive.

§ 5. TUNED ELECTRICAL CIRCUITS—ELECTRICAL RESONANCE

If a charged condenser C (Fig. 308) is suddenly short-circuited through a coil L , the charge surges to and fro through the coil many times before all flow or surging ceases. The rate of decay of the surging depends on the resistance of the coil and on the amount of energy radiated as electromagnetic waves.




FIG. 308.—Circuit with Natural Oscillation Frequency

The period of the oscillations which take place, or the time taken for a complete *to and fro* surge, is equal to $2\pi\sqrt{LC}$, where L is the self-inductance of the coil and C is the capacity of the condenser, both these quantities being measured in *one system of units*. For example, in practical units L is in henries and C in farads.

It happens, owing to certain relations which exist between the absolute electromagnetic units and the electrostatic units, that the wave-length, in centimetres, of the oscillations which such a system would set up in the ether, is given by the same expression $2\pi\sqrt{LC}$, if L is measured in absolute electromagnetic units and C in electrostatic units.

Oscillations can be set up in such a circuit by causing sparks to pass across a spark-gap connected to the circuit (Fig. 309). The oscillations in the circuit are then heavily damped owing to the resistance of the spark-gap; the sharpness of tuning of the resultant oscillations (the narrowness of the frequency range emitted) is also greatly reduced, the oscillations obtained having frequencies which cover a fairly wide range.

To
Induction
Coil

Oscillations can also be produced in such a circuit by means of a three-electrode valve (see Chapter XII, § 12). The oscillations thus obtained are easily maintained at a constant amplitude; their range of frequencies, also, can be kept very small, and the oscillations are sharply tuned.

FIG. 309.—Circuit with Spark-gap inserted for production of Oscillation

To obtain efficient radiation, the simple oscillating circuit described above must be modified. This is done by attaching a long wire to one

end of the coil L or by making the coil L of large area, and of a comparatively small number of turns (Figs. 310 and 311).

The long wire radiator is called an **open aerial**; its addition alters the capacity and self-inductance of the system and therefore alters the frequency of the oscillations and, of course, the wave-length of




FIG. 310.—Radiating Circuit with Open Aerial. Also serves as Receiving Circuit if not excited to act as Radiating Circuit




FIG. 311.—Radiating Circuit with Closed Aerial. Also serves as Receiving Circuit, if not excited to act as Radiating Circuit

the radiation emitted. When an open aerial connected to one end of the coil L is used, the other end of the coil is generally connected to earth, though sometimes an insulated wire or network of wires is connected to this end to act as a **counterbalance** to the aerial, instead of an earth connection.

A vertical open aerial radiates equally in all horizontal directions.

If the coil L is made of large dimensions and used as a radiator, that is as a **closed aerial**, or **frame aerial**, no earth connection is required. Such a coil radiates most strongly in its own plane, the intensity of radiation in directions at right angles to the plane of the coil being practically zero.

Now if a circuit such as that shown in Fig. 310 is made up but is not connected to any spark-gap or valve which will set up oscillations in the circuit, it will pick up any electromagnetic waves which strike the aerial, or pass close to it, and the circuit will respond to these waves. Similarly a circuit with a closed aerial, as shown in Fig. 311, will respond to waves travelling past the aerial, the response being greatest to waves travelling in the plane of the coil, and zero, or nearly so, to waves travelling at right angles to this plane.

The oscillations set up in these circuits will have the same frequency as the waves which are being intercepted by the aerials. The response of either circuit will be small, therefore, unless the **natural frequency** (actually the 'resonance frequency') of the receiving circuit is approximately the same as the frequency of the waves intercepted by the aerial.

By altering the self-inductance of the coil L or by altering the capacity of the condenser C , the resonance frequency of the circuit can be made the same as that of the waves being received. The circuit will then be set in **resonant vibration**, the amplitude of the oscillations becoming very large, being, in fact, limited only by the extent to which energy is dissipated in the circuit due to its electrical resistance, or is abstracted from the circuit by re-radiation or in other ways.

To detect the oscillations taking place in such a receiving circuit energy is usually drawn from the circuit, in some way or another, to operate the apparatus used for the detection of the oscillations. Abstracting energy for this purpose limits the amplitude of the oscillations set up in the resonant circuit and also 'flattens' the resonance; that is, causes the oscillations to be of fairly considerable intensity even when the natural frequency of the receiving circuit is varied over an appreciable range.

EXPT. 265. Resonant Vibrations in a Receiving Circuit.—Make up a simple receiving set with a crystal detector and telephones, suitable for receiving signals from a local broadcasting station unless a privately owned transmitting set is available (Fig. 312). This set should have




FIG. 312.—Receiving Circuits with Crystal Detectors and Telephones. (a) Open Aerial Circuit; (b) Closed Aerial Circuit

As shown, 'tuning' is by altering capacity of condenser

either a variable self-inductance or a variable capacity, with a scale in terms of which the magnitude of the self-inductance or of the capacity can be expressed in some arbitrary manner (for instance the angle through which the adjusting knob is turned).

Using a galena-catwhisker detector, adjust the set to give maximum loudness of signals from whatever station is being used as the transmitting station.¹

Keep the set adjusted in this way and replace the telephone by a micro-ammeter or galvanometer. Note the current passing through this instrument.

Now vary the adjustment of the set by altering either the self-inductance of the coil L or the capacity of the condenser C , and take readings of the current through the micro-ammeter or galvanometer for several different adjustments. Plot a curve showing how the current

¹ A signal generator may be used to provide the signal, and is, in fact, preferable for purposes of measurement.

varies as the adjustment is altered, using as abscissae the readings on the scale provided. This gives a resonance curve for the receiving set under these conditions.

If the self-inductance and the capacity are *both* variable, carry out the experiment first with a constant self-inductance, varying the natural frequency of the set by altering the capacity. Then repeat the experiment with the capacity kept constant at some suitable value, the variation being now obtained by altering the self-inductance. Separate resonance curves should be plotted for these two sets of observations.

Substitute a zincite-bornite or other form of 'two-crystal' detector for the galena-catwhisker detector first used, and repeat the experiment. Note the difference between the sharpness of the resonance obtained when different types of detectors are used.

NOTE.—If the micro-ammeter used is not a centre-zero instrument, but indicates current in one direction only, take care to see that it is connected the right way round. If it is known that signals are being received (by trying with the telephones again) reverse the connections to the micro-ammeter if no deflection is obtainable.

It will be found that the resonance curve is much sharper with a crystal detector of high resistance than with one of low resistance. Verify that this is so by measuring the resistances of the two detectors as described in Expt. 264.

For the detection of electromagnetic waves by methods employing valves, see Chapter XII.

THERMIONIC VALVES

§ 1. EMISSION OF ELECTRONS FROM HOT BODIES

WHEN a metal is heated, it tends to lose negative electricity and thus to acquire a positive charge. At ordinary temperatures the effect is negligibly small but it assumes importance at temperatures round about 1000°C .

The negative electricity leaves the metal as **electrons**, which are particles of negative electricity each having a charge of magnitude $-e = -4.8025 \times 10^{-10}$ electrostatic units or -1.6020×10^{-20} absolute electromagnetic units, that is -1.6020×10^{-19} coulomb. The mass m of the electron is 9.1066×10^{-28} gm.

The emission of electrons from a hot metal is an effect analogous to the emission of molecules of vapour from the free surface of a liquid. Just as in an enclosed space the rate of evaporation is in time balanced by the rate at which molecules return to the liquid, so with the emission of electrons a **state of equilibrium** is established. The rôle of the saturated vapour is taken by a cloud of free electrons which constitute a **space-charge** around the metal. The density of this space-charge depends on the temperature and increases as the temperature is raised.

These conditions are modified if an electric field exists in the neighbourhood of the hot metal. When the hot metal is surrounded by a conductor maintained at a lower potential, a field is produced which tends to drive the electrons back into the emitter thereby reducing the space-charge. If, on the other hand, the conductor is maintained at a higher potential than that of the hot metal, electrons in the space-charge will be attracted towards the surrounding conductor and will pass across the intervening space as a steady stream. This constitutes a **thermionic current**. The direction of the conventional current is, of course, opposite to that of the electron flow.

The space-charge produces a screening effect similar to that of a conductor, so that if the difference of potential is small, comparatively few of the electrons present will pass across to the surrounding conductor. As the strength of the electric field is increased more electrons will join in the stream until, with a sufficiently intense field, the electrons will all be swept away as fast as they are emitted by the hot metal.

A further increase in the strength of the field cannot then cause any further increase in the current ; this limiting value of the thermionic current is called the **saturation current**. If N is the number of electrons emitted per second by the hot metal, a quantity which depends on the temperature and on the area and nature of the emitting surface, and $-e$ is the charge on one electron, the value of the saturation current is given by the product Ne .

The rate of emission of electrons depends very much on the particular metal from which the emission takes place and is limited by the temperature to which the metal can safely be heated. When tungsten is impregnated with thorium oxide, the rate of emission is greatly increased. The emission from oxides of the alkaline earths is also much greater than that from pure metals under similar conditions.

In a detailed discussion of the thermionic current the initial velocity of the electrons on emission must be taken into account. These velocities are distributed over a considerable range but the average velocity is not large ; for most practical purposes, therefore, the initial velocity may be neglected.

A hot body which is emitting electrons is cooled by the loss of the electrons just as a liquid is cooled by evaporation. This effect can easily be seen by watching a bright, hot tungsten filament when the potential of a surrounding conductor is suddenly raised from a value approximately equal to that of the filament to a value about 100 volts higher. It will be observed that the brightness of the filament falls off appreciably when the potential of the surrounding conductor is raised.

The conductor to which the electrons are attracted becomes appreciably heated by the 'bombardment' with electrons to which it is subjected. The electrons are absorbed by the conductor and the kinetic energy of the electrons transferred to the conductor appears in the form of heat.

§ 2. THE TWO-ELECTRODE VALVE OR DIODE

The phenomena described in the preceding paragraph can only be studied satisfactorily if the hot metal and the surrounding conductor are enclosed in an evacuated vessel, with suitable connecting wires sealed through the walls. The first recorded observation of such effects was made by Edison in 1884. Edison mounted a metal plate between the limbs of a horse-shoe-shaped filament of his electric lamp and observed that, under suitable conditions, a current passed between the plate and the filament. It was not until many years later that this was shown to be due to the emission of electrons from the hot filament.

In 1904 Fleming designed and constructed what he called an 'oscillation valve', in which a thermionic current was used as a means of detecting high-frequency electromagnetic oscillations. In Fleming's valve two electrodes were mounted inside an evacuated glass tube. The cathode was in the form of a metal filament, while the plate or




FIG. 313.—The Fleming Valve, for rectifying oscillations

anode was a plate or cylinder mounted close to or surrounding the cathode. The filament was directly heated by passing a current through it from a small battery of accumulators, and it then emitted electrons. The electrodes were connected to the circuit in which the electric oscillations were taking place, and since the electrons can flow only from the cathode to the anode the thermionic current flowed only during the 'positive' half of each oscillation. This property of producing rectification of the oscillations can be used for their detection as already described in Chapter XI. Apart from its use as a detector this two-electrode valve or diode is used as a rectifier of alternating current, for charging secondary cells, or for operating radio and X-ray equipment.

When thoriated or oxide-coated filaments were introduced, these were operated at much lower temperatures than the pure tungsten filaments previously employed. These were called **dull-emitters**, operating as they did at a dull red heat which was sometimes hardly visible, to distinguish them from the **bright-emitters** run at a bright red or almost white heat. Modern valves frequently employ **indirectly heated cathodes**. In these the filament is merely a heating element or heater. It is enclosed in a fine metal tube which is oxide-coated and forms the actual cathode, generally insulated electrically from the heater. The indirectly heated cathode offers several advantages over the directly heated type. It is possible to maintain the cathode at a uniform potential throughout its length, and heating may be accomplished either by means of D.C. or A.C. without causing fluctuations of the cathode potential. In reckoning the number of electrodes in a valve the heater is not counted.

§ 3. THE THREE-ELECTRODE VALVE OR TRIODE

A very great advance in the development of thermionic valves was made by de Forest, who introduced a third electrode to form a **three-electrode valve** or **triode**. The additional electrode is of an open mesh or spiral structure and is situated between the cathode and the anode. It is referred to as the **grid** (Fig. 314).

The way in which a triode behaves depends to a great extent on the

size and disposition of the electrodes and on such details as the proportion of open space in the grid. The general behaviour of a triode can be discussed, however, without reference to these details. It is convenient when dealing with the theory of valves to consider the cathode to be at zero potential. The potential of any other electrode is then referred to that of the cathode. When the cathode is directly heated its potential is not uniform throughout its length, and in this case the negative end of the cathode is chosen as the point of zero potential.

Just as in the diode, current can flow in the triode only when the anode is at a positive potential. The presence of the grid, when this electrode is maintained at zero potential, will shield the cathode more or less from the field of the anode. Because the field near the cathode is considerably weakened in this way the number of electrons escaping from the space-charge will be substantially reduced; a few of these electrons will be caught up by the grid, but most of those escaping from the space-charge will cross over to the anode. It follows, therefore, that the anode current is considerably reduced by the introduction of the grid. The electrons going to the grid will constitute a grid current, but with the grid at zero potential this current will be extremely small.

If a positive potential is now applied to the grid, the field near the cathode will be strengthened and the flow of electrons from the space charge will be increased. Most of these electrons will still pass through the spaces in the grid and travel on to the anode, so that raising the grid potential increases the anode current. The grid current will also increase since the grid will tend to trap more electrons when it is positive than when it is at zero potential. This grid current is often a serious disadvantage, so that positive grid potentials are generally to be avoided.

When the grid potential is made negative, the escape of electrons is retarded and the anode current is diminished. If the negative potential of the grid is made sufficiently large the anode current can be reduced to zero, even when the anode is at a high positive potential. This is called the condition of cut-off. Thus, if the potential of the grid is raised, the anode current is increased, and if the potential of the grid is




FIG. 314.—Early Type of Three-electrode Valve or Triode. (i) Straight filament surrounded by the grid as an open spiral of wire, and the plate as a cylinder of thin metal. (ii) A conventional method of representing the valve in diagrams

lowered, the anode current is diminished. Moreover, because of the proximity of the grid to the cathode, comparatively small variations of the grid potential can be made to control the magnitude of the anode current.

Valves with four or more electrodes are now in common use, but a description of the characteristics of these multi-electrode valves is beyond the scope of the present treatment.

Before experiments are carried out on a particular valve, the connections from the electrodes to the pins in the valve base must be ascertained; wrong connections to the external circuit might cause damage to the valve. The voltage applied to the filament or heater, and the potentials applied to the other electrodes, must be based on the operating conditions specified by the manufacturers. Unduly high anode potentials or high *positive* grid potentials must not be used, otherwise the anode may become overheated.

For low-power valves with directly-heated cathodes the cathode-heating current may be supplied from a **low-tension battery** of one or more large-capacity secondary cells, the anode potential being provided by a **high-tension battery** of small secondary or dry cells giving up to, say, 150 volts, with tappings at intervals. A small battery with tappings every $1\frac{1}{2}$ volts may be connected in series with the H.T. battery to give finer variations of anode potential, if desired. A **grid-bias battery** with tappings every $1\frac{1}{2}$ volts is also needed, to give various grid potentials as required, or a potential divider across a number of secondary cells may be used. The grid potential or **grid-bias** controls the anode current, as already described, and enables the valve to operate in the particular manner desired.

The negative end of the H.T. battery and one end, usually the positive, of the G.B. battery must be connected to the cathode of the valve.

Most modern valves have indirectly-heated cathodes consisting of a nickel tube coated with a 'dull-emitter' mixture of barium and strontium oxides, the nickel tube being heated internally by a loop or bundle of insulated tungsten wire through which alternating or direct current is passed. The nickel tube, when the valve is in use, is connected to earth through a resistance connected in parallel with a 'smoothing' condenser of capacity 1 mfd. to 5 mfd. The electrons emitted by the oxide coating of the cathode flow through this resistance as a 'negative' current from the earth, which maintains the cathode at a positive potential. With the grid earthed, therefore, the cathode is maintained at a higher potential than the grid, the resistance providing, in effect, a negative grid bias.

For experimental work a variable 'biasing' resistance of 50,000 ohms (max.) may be used, with a suitable milliammeter in series on the 'earth' side; the 'effective' grid bias is then obtained as the

product of the resistance in actual use and the current registered by this milliammeter.

If the anode current required is in excess of 10 mA, the use of a power supply unit or power pack is the most satisfactory method of obtaining the necessary anode potential. A suitable unit is described in § 9.

The valves discussed in this section are of the highly evacuated type. Sometimes, for special purposes, a small quantity of gas is deliberately introduced, which considerably modifies the behaviour of the valve. The electric discharge in gases and the characteristics of gas-filled valves are dealt with in §§ 5 and 6.

§4. THE CATHODE RAY OSCILLOGRAPH

A modern form of cathode ray tube known as the **cathode ray oscillograph** (or **oscilloscope**) has proved of great value in the accurate timing of events and in the study of high-frequency phenomena. It is




FIG. 315.—Cathode Ray Tube

similar in principle to the tube introduced by Braun and used by J. J. Thomson for determining the value of e/m (charge/mass) for the electrons in the cathode stream. Because of its charge an electron is acted upon by an electric field, and when in motion by a magnetic field; its mass is exceedingly small, and consequently it responds to alternating potentials or to magnetic fields due to high frequency currents. The resulting deflection of the beam is rendered visible by means of a fluorescent screen inside the tube.

The cathode ray tube (Fig. 315) is an evacuated tube shaped like a conical flask with a long cylindrical neck. The large end of the tube, slightly rounded for the sake of mechanical strength, is coated inside with luminescent material to form the screen. The cylindrical part contains the electrode system for obtaining a concentrated beam of electrons, called the **electron gun**; it comprises a cathode **C**, usually indirectly heated, a shield or grid **S** and a perforated anode **A₁A₂**.

which generally incorporates an electrode F, the purpose of which is to focus the beam to a sharply defined spot on the screen. Apart from the influence of this electrode device, the behaviour of the electron gun is very much that of a triode. The intensity of the beam and therefore the brilliance of the spot is controlled by the potential of the shield.

On emerging from the electron gun the beam passes through the deflector system; this may consist of two pairs of parallel plates, the plane of the first pair Y_1Y_2 being at right angles to that of the second pair X_1X_2 . If a difference of potential is applied between the X plates the luminous spot is deflected horizontally; a potential difference applied to the Y plates produces an independent vertical deflection of the spot. The plates are generally so designed that the deflection is proportional to the difference of potential, the sensitivity being different, however, in the two directions. Alternatively, magnetic deflection can be produced by means of coils placed outside the tube.

If the potential difference between one pair of plates is made to vary with time, the spot will sweep across the screen and, because of the afterglow of the screen and the persistence of vision, the spot will produce an apparently continuous trace, provided it travels with sufficient speed. A device which causes the spot to move across the screen in a predetermined fashion is called a **time base**, a very common form being a **linear time base** in which the spot moves from left to right at a uniform speed and then flies back rapidly to repeat the forward stroke at regular intervals. If an alternating potential difference is now applied to the Y plates the spot will oscillate up and down, with the result that the wave-form of the potential is traced out on the screen.

If two alternating potentials are applied simultaneously to the X and Y plates, the two oscillations taking place simultaneously in directions at right angles to each other will produce Lissajou's figures. These figures can be used as a means of comparing the two frequencies. Two alternating potentials — of the same frequency, but differing in phase — produce an ellipse. If the two amplitudes are made equal the ellipse passes from a straight line to a circle, as limiting cases, when the phase difference is varied from zero to 90 degrees. The phase relationship can therefore be determined from the form of the ellipse. This provides a simple method of observing the phase relationship between the current in a circuit and the applied E.M.F. The phase of the current is the same as that of the P.D. across a pure resistance; it can therefore be observed by including a resistance in the circuit and applying the P.D. across its ends to one pair of plates, while the P.D. across the source of E.M.F. is applied to the other pair of plates.

By making use of the phase-splitting property of a condenser and a resistance in series, it is possible to obtain an **elliptical time base**.

When a resistance R and a condenser C are connected in series, the current in both is in the same phase; consequently the P.D. across C is 90° out of phase with the P.D. across R . Connecting the X plates across R and the Y plates across C gives an ellipse with its axes horizontal and vertical. The relative values of C and R determine the shape of the ellipse at a given frequency. The elliptical time base is useful for the comparison of frequencies; the unknown frequency is injected into the appropriate lead to the Y plates, when the wave of unknown frequency is superposed on the ellipse. Since the spot traverses the ellipse at the frequency of the time base, a simple stationary pattern will be observed when the unknown frequency is a whole multiple of the frequency of the time base; the ratio is obtained by counting the number of positive peaks on the trace.

In some instruments the beam is split into two by means of a third Y plate in the centre of the beam so that a double trace is obtained on the screen. In the double-beam oscillograph the horizontal displacements of the two beams are synchronised, and independent variations of potential can be applied to the outer Y plates. Simultaneous traces of two wave-forms may be obtained in this way.

It is not possible to enumerate here all the many uses of the cathode ray oscillograph. It is used for the automatic tracing of curves; for example, valve characteristics may be studied by applying the alternating grid potential, or anode potential, to the X plates and the anode current (or rather the P.D. produced in a resistance by the anode current) to the Y plates. Again, the hysteresis curves for samples of iron may be traced by means of the oscillograph.

The cathode ray oscillograph is extensively used in radar, and it also finds applications in television. For television, linear time bases of different frequencies are applied simultaneously to both pairs of plates in such a way that the spot traces a series of parallel straight lines across the screen. These lines are so close together that they form what appears to be a uniformly luminous rectangle called a raster. The television picture is reproduced by modulating the brilliance of the spot as it moves over the screen.

A few simple applications of the cathode ray oscillograph are given in subsequent paragraphs.

§ 5. IONISATION CURRENTS IN GASES

When the vacuum in a thermionic tube is very high, the mean free path is so large that electrons pass from the cathode to the anode with very little chance of colliding with a gas molecule. The very small amount of gas present in a high-vacuum tube, or **hard valve**, may there-

fore be neglected in discussing the behaviour of the valve. In a **soft valve** an appreciable amount of gas is left in the tube, and collisions between the electrons and the gas molecules take place. If the individual electrons possess sufficient energy, disruption of the bombarded molecules may result. The molecule loses one or more of its electrons and becomes a **positive ion**, that is a positively charged molecule; the electrons expelled may continue as free electrons or become attached to other molecules to form **negative ions**. The negative ions are driven towards the anode by the electric field in the tube, while the positive ions travel in the opposite direction. These oppositely charged ions moving in opposite directions constitute an ionisation current which is added to the thermionic current. The ions, in turn, may acquire enough energy to produce further ions on colliding with gas molecules. This process, called **ionisation by collision**, is therefore cumulative and the ionisation current tends to increase indefinitely.

To prevent a catastrophic increase of current, the electric intensity must now be decreased so that the rate of production of ions is reduced. This is most easily accomplished by including a resistance of suitable magnitude in the circuit. When the circuit is closed, there is no current to begin with and the resistance in the circuit does not prevent the full potential difference being applied to the tube. As the current in the tube increases, so also does the potential difference across the external resistance, with a consequent reduction of the electric field in the tube.

Ionisation currents may be produced without the aid of a hot cathode; in this case it is generally necessary to apply very high potentials. The strength of the electric field required to start a discharge depends very much on the nature of the gas and on its pressure. At very low gas pressure it is practically impossible to produce a discharge in this way; on the other hand, tubes containing neon are commonly used directly on the supply mains. These neon lamps are usually fitted with a suitable resistance in the cap to prevent undue increase in the current.

The behaviour of a neon tube is of considerable interest. When the gas in the tube is once ionised by applying a sufficiently high potential, it is found that the potential difference across the tube can be decreased considerably before the tube ceases to conduct. When the tube is conducting, very small changes in the P.D. across the tube cause considerable changes in the current. Consequently if the circuit contains a sufficiently high resistance in series with the tube, quite considerable changes in the applied voltage produce very little effect on the P.D. across the tube. When the applied voltage is increased, the current increases and so does the P.D. across the external resistance. The net result is that the P.D. across the tube shows very little variation; in fact the effective resistance of the neon tube is almost in-

versely proportional to the current. Because of this property the neon tube provides a very useful voltage stabiliser.

EXPR. 266. The Neon Tube. Ionisation Currents in Gases.—A neon lamp *without* a protective resistance in the cap, or a neon tube of the type supplied for voltage stabilisation, is connected through an external resistance R , of say 3000 ohms, to a continuously variable D.C. supply. A power pack (§ 9) with a potential divider is very suitable for this purpose. Two voltmeters (0-250 volts) and a milliammeter (0-100 mA or more depending on the type of tube) are connected as shown in Fig. 316.

Starting at about 100 volts, gradually increase the applied voltage; and observe the potential difference V_2 across the tube, noting the highest value reached just *before* the tube lights up. Now reduce the voltage slowly and observe the lowest value of the potential difference across the tube just before the discharge ceases. This difference between the striking and extinction values of the voltage is of interest in connection with the application of a neon tube in a time base for use with a cathode ray oscillograph.

Now increase the applied voltage V_1 in small steps and observe corresponding values of V_1 , V_2 and the current I , until the maximum permissible value of the current has been reached. Note that, although the current varies considerably with the applied voltage, the potential difference across the tube remains very nearly constant. The experiment should be repeated with different values of the resistance R , care being taken that R is always high enough to prevent damage to the tube.

Not only does the neon tube compensate for variations in the supply voltage, but it also compensates for changes in the current in the associated circuit. If this current falls, an increase in voltage in the circuit is largely neutralised by an increase in the current through the neon tube. This effect may be demonstrated by connecting a large variable resistance, in series with a milliammeter, between the two electrodes of the neon tube. The effectiveness of this device depends on the value of R in the stabilising circuit.




FIG. 316.—Ionisation Currents in Gases

When a neon tube is used as a voltage stabiliser, the circuit across which the stabilised voltage is required is connected directly across the neon tube. The voltage available is determined by the operating voltage of the tube but lower values can be obtained by the use of a suitable resistance in series with the circuit. If higher voltages are required, two or more neon tubes may be connected in series.

In order to use a neon tube to provide a time base, a condenser is connected across the tube (Fig. 317 (a)). When a condenser of capacity C in series with a resistance R is connected to a battery of E.M.F. E , the condenser charges up exponentially; the difference of potential V across the condenser, at time t after the circuit is closed, is given by

$$V = E(1 - e^{-t/RC}).$$

Plotting V against t gives the continuous smooth curve of Fig. 317 (b).

If a neon tube is connected across the condenser, and if E is considerably greater than the striking potential V_1 , the condenser will charge up

to the point A; the tube will then become conducting and, if R is large compared with the resistance of the tube, the condenser will discharge rapidly through the tube until the extinction potential V_2 is reached at the point B. The tube now ceases to conduct and the potential difference across the condenser rises again to V_1 at the point C, and so on. This process is repeated at regular intervals, and the potential difference across the condenser is represented by the saw-tooth curve. The time taken for the condenser to charge from V_2 to V_1 is determined by the product RC and by E . If E is increased the continuous curve of Fig. 317 (b) rises




FIG. 317.—Neon Time Base

a greater height, and consequently it is steeper in the region V_1V_2 . Increasing E therefore increases the frequency. If the product RC is increased the condenser charges more slowly, so that the frequency is decreased.

With sufficiently large values of R and C the flashing may be made to take place quite slowly and the period can be determined by timing a suitable number of flashes with a stop clock or watch. When the product RC is decreased the frequency of the flashes becomes greater and the best method of observing the flashes is by means of a cathode ray oscillograph.

The circuit described above can be used as a time base by connecting the X plates of the oscillograph across the condenser. As the condenser charges up (from B to C) the spot will move horizontally across the screen; an amplifier will be necessary if a long trace is required. During the discharge (A to B) the spot will fly back quickly to its starting point ready for the next stroke. The time of fly back should be short relative to the duration of the forward stroke.

EXPT. 267. Neon Time Base.—Connect a variable resistance R of several hundred thousand ohms and a decade condenser box of $1 \mu\text{F}$ in series with a variable source of steady potential; if a power pack (§ 9) is used the output must be very well smoothed. A neon tube is connected across the condenser (Fig. 317 (a)). Adjust the values of R , C , and E until the tube begins to flash, and observe the effect of varying each of these quantities in turn.

Now connect the two sides of the condenser to the Y plates of a cathode ray oscillograph with a linear time base on the X plates and observe the wave-form. If the voltage E is low the upward stroke will show decided curvature; increasing E will increase the frequency of flashing and, at the same time, it will reduce the curvature of the trace.

In order to study the effect of R and C on the frequency, switch off the ordinary time base of the oscillograph and replace it by the neon time base by connecting the condenser across the X plates. The output of a calibrated audio-frequency oscillator is applied to the Y plates and its frequency adjusted to give a stationary wave-trace. The frequency of the oscillator divided by the number of complete waves on the trace

gives the frequency of the neon time base. Show, in this way, how the frequency of the neon time base is related to R and to C .

A time base of the form described can never be truly linear because of the curvature of the charge curve of the condenser. If the charging current can be limited to a constant value the condenser will then charge at a uniform rate and a linear time base will result. This can be done by replacing the resistance R by a saturated diode (see p. 505) or by a pentode (a valve with five electrodes).

The neon time base suffers from serious limitations. For high speed work a hard-valve time base is necessary. The action is then much more complicated but the fundamental principles are the same.

§ 6. SOFT VALVES

The effect of leaving an appreciable amount of gas in a thermionic valve has been described at the beginning of § 5. The ionisation which takes place in a soft valve alters the behaviour of the valve to a marked extent. A suitably constructed valve will pass quite large currents, and valves containing mercury vapour are commonly used for converting an A.C. supply into a D.C. supply on a large scale.

The gas-discharge triode has some interesting applications. The discharge in a gas-filled triode can be prevented from starting by applying a large enough negative potential to the grid. If the potential of the grid is gradually raised (towards zero) a point will be reached when the valve begins to conduct. Meanwhile there is a positive potential on the anode, and, as soon as anode current flows, ionisation takes place and the current increases rapidly until it is limited by external resistance. The grid is still at a negative potential, and, since it therefore attracts positive ions, a positive ion sheath forms around the grid. This effectively puts the grid out of action, with the result that the grid no longer has control over the anode current. Consequently, lowering the grid potential will not stop the anode current once it has started, and the only way to stop the discharge is to reduce or remove the anode potential.

A gas-discharge triode is used in place of a neon lamp in a soft-valve time base. It has the advantage of giving a much greater range of potential variation than a neon tube, and thereby removing the necessity of introducing an amplifier. Another interesting application is in the counting of α and β particles from radioactive substances. Each particle, on entering a specially constructed ionisation chamber, causes a momentary ionisation current through the chamber. This current is made to raise the grid potential of the valve, which has just sufficient negative bias to render it non-conducting, to the point where the discharge takes place. The relatively large current through the valve is then made to operate a mechanical counter; at the same time the anode circuit is broken momentarily, thus resetting the valve.

Several very ingenious circuits have been devised, making use of a chain of gas discharge valves, so that the mechanical counter is operated only by every n th impulse; this has the effect of increasing the speed of counting by overcoming the limitation imposed by the inertia of the mechanical device.

§ 7. THE CHARACTERISTICS OF A DIODE

The properties of a diode have been described in § 2. In the following experiments these properties are illustrated and their graphical representation explained.

EXPT. 268. Variation of Anode Current with Anode Potential.—The circuit for this experiment is illustrated in Fig. 318 (a) for a directly heated valve, and in 318 (b) for an indirectly heated valve.




FIG. 318.—Variation of Anode Current with Anode Potential and with Heating Current (Diode)

If a diode is not available a triode may be converted into a diode by connecting the grid directly to the anode; it is not sufficient to leave the grid unconnected as its potential is then liable to vary and vitiate the experiment. When a triode is used in this way, the potentials applied to the anode, of which the grid now forms a part, must be considerably less than when the valve is being used in the normal way as a triode. The value of the anode current serves as a useful guide to the permissible values of the anode potential.

Vary the anode potential V_A in small steps from zero up to the maximum permissible value, and record the value of the anode current I_A corresponding to each value of V_A . Since the voltmeter passes an appreciable current, it is important that it should be connected so that this current does not flow through the milliammeter mA, in addition to the anode current which is being measured. Plot a graph of I_A against V_A ; the resulting curve (Fig. 319) is the characteristic curve of the diode.

Since the graph is not a straight line through the origin, it follows that Ohm's Law is not obeyed. The small value of the current for small potentials

is due to **space-charge limitation** as already described, while the horizontal part obtained with large values of V_A represents saturation or **temperature limitation**. It is not normally possible to show saturation unless a bright-emitter valve is available. To obtain saturation with the normal heating current, an excessively high voltage would have to be applied to the anode, but if the electron emission is considerably reduced by decreasing the heating current it will then be possible to obtain the complete curve. Coated cathodes behave in rather a different way, and even with reduced temperatures the curve continues to rise slowly (broken line in Fig. 319). The emission with reduced temperature is liable to vary and satisfactory results cannot usually be obtained. Moreover, it is not generally advisable to run a coated cathode at a reduced temperature as this is liable to cause deterioration of the cathode.

EXPT. 269. Variation of Anode Current with Filament Current.—

Vary the filament current of a bright-emitter diode from a low value up to the normal working value, and observe corresponding values of the anode current I_A and the filament current I_F , when a sufficiently high anode potential is applied to produce saturation, at least approximately. If the anode current becomes excessive as the filament temperature increases, the experiment must be stopped before the normal working temperature is reached. The circuit arrangement is shown in Fig. 318*a*. Coated cathodes do not usually give very satisfactory results for reasons already mentioned.

Plot a graph of I_A against I_F ; the resulting curve shows how the rate of emission of electrons varies with the heating current. This variation of the thermionic emission by means of a filament rheostat was, at one time, used as a means of controlling the behaviour of a valve, but, with the introduction of coated cathodes, the filament rheostat is now practically obsolete.

The current in a saturated diode is independent of variations in the anode voltage within fairly wide limits. Under these conditions a diode included in a circuit provides a means of preventing the current in the circuit from exceeding a given value determined by the temperature of the filament. A diode used in this way is called a **current limiter**.

§ 8. RECTIFICATION BY MEANS OF A DIODE

Rectification, or the process of transforming an alternating current into a uni-directional current has been described on pp. 495-500.

EXPT. 270. The Diode as a Rectifier.—The circuit illustrated in Fig. 320 provides a very convenient arrangement for examining the behaviour of a diode, both as a half-wave and as a full-wave rectifier. The valve is of the type used in the power-supply circuit of a radio receiver for operation on A.C. mains. It consists of two diodes in one envelope, with separate anodes and with the cathodes connected together; the cathodes, if of the indirectly heated type, are sometimes connected to one end of the heater.

A transformer giving about 100 volts output is connected to the extreme ends AB of a rheostat of sufficiently high resistance to avoid overloading the transformer, and also to the two anodes A_1 and A_2 . A key K is inserted in the lead to A_2 . The sliding contact C is connected through a resistance R of 500 ohms to carry 100 mA., and a D.C. milliammeter (0-100 mA.) to the cathode.

(i) **Half-wave Rectifier.**—If the key K is left open, only one anode (A_1) operates and the valve behaves as a half-wave rectifier. Vary the position of the sliding contact and thus vary the alternating potential applied to the anode A_1 from zero to the maximum value, observing the actual values V on an A.C. voltmeter of suitable range connected directly across A and C. Observe the corresponding values of the D.C. current I and plot a graph of I against V . The form of the curve shows that, as the amplitude of the A.C. potential is varied, the current is




FIG. 320.—The Diode as a Rectifier

proportional to V . This effect is most marked at relatively low potentials and, when it occurs in a diode used as a detector, can give rise to serious distortion of weak signals.

If the milliammeter is of the usual moving coil D.C. type, the fact that a deflection is obtained shows that the current is direct and not alternating. The current is, however, pulsating and this will be evident from the vibration of the needle which will be readily observable if the inertia of the moving coil system is not sufficiently large to damp out the effect of the rapid pulses of current.

(ii) **Full-wave Rectifier.**—Set the sliding contact at the centre point of the rheostat, observing that the voltage V is now half the maximum value, and close the key K. When the alternating current is flowing in the direction AB, the point A and also the anode A_1 is positive with respect to the cathode. At the same time the anode A_2 is negative with respect to the cathode. Under these conditions A_1 passes current while A_2 does not. On the reverse half-cycle the conditions at A_1 and A_2 are reversed and A_2 passes current while A_1 is idle. It will be noticed that the current in the load resistance R is in the same direction on both half-cycles.

If K is now opened without altering the position of the sliding contact, the current, as indicated on the meter, will be seen to drop to half. This is because the effect of inertia in the meter is to give a reading corresponding to the *average* value of the current, and, since the full-wave rectifier gives twice as many pulses per second as the half-wave rectifier, the average value of the current is halved by changing over from full-wave to half-wave rectification.

If a cathode ray oscillograph is available, it is most instructive to observe the form of the rectified current by connecting the ends E and Y of the load resistance R to the Y plates of the oscillograph, the X plates of which are connected to a linear time base. A trace of the form of Fig. 269 II will be obtained with full-wave rectification, and, when the key is opened, every second peak will be eliminated.

§ 9. POWER SUPPLY UNITS

A radio receiver for operation on A.C. mains derives its high-tension supply from a transformer and rectifier, with the addition of a **smoothing filter** to eliminate the variations in the D.C. current from the rectifier. The secondary winding of the transformer is tapped at its centre point, and gives 250 volts or more on each side of the centre tap. At least two additional secondary windings are required, one to provide the heater current for the rectifier valve and the other to supply the heaters of the other valves in the receiver; these windings usually give 4 volts. The rectifier must obtain its heating current from a separate winding because the *cathode* of the rectifier is at a high *positive* potential with respect to the cathodes of the other valves.

A power supply unit or **power pack** is a very convenient accessory, made up separately for experimental purposes. A useful unit is illustrated in Fig. 321. C_1 and C_2 are electrolytic condensers of capacity




FIG. 321.—Power Pack

$8\mu\text{F}$. Electrolytic condensers are used because these provide large capacity in small bulk, but care must be taken to observe the correct polarity and to see that the condensers are rated for a voltage at least 50 per cent above the R.M.S. voltage of the transformer. Ch. is a choke of inductance 40 henries capable of carrying 100 or 120 mA. A fuse is included to protect the transformer and the rectifier from the effect of an accidental short-circuit.

The action of the smoothing filter comprising the choke and condensers may be understood by regarding the rectified current as consisting of two components, one D.C. and the other A.C. The condensers which are in parallel with the external circuit tend to absorb the A.C. component, being charged by the pulses of current from the rectifier, and discharging through the external circuit when the rectifier current is low; this tends to maintain a steadier current in the external circuit. The smoothing effect is further increased by the large inductance of the choke Ch. connected in series. The reservoir condenser C_1 should not normally have a capacity in excess of $8\mu\text{F}$,

but, the capacity of C_2 may be increased with advantage. If more complete smoothing is required, further chokes and condensers may be added, but this will not be necessary for most purposes.

The condensers may retain their charge for a considerable time when the mains supply is switched off, with the power pack on open circuit. Severe shocks may result on handling the apparatus in this condition, but the risk may be avoided by connecting a high resistance of say 100,000 ohms across the output terminals. A variable output voltage may be obtained by the use of a potential divider; this should have a resistance of 5000 ohms and be capable of carrying a current of 100 mA.

EXPT. 271. Smoothing Filters.—In order to demonstrate the effect of smoothing filters, a less efficient filter than that described above is more suitable since the remaining ripple is then more marked. The electrolytic condensers should be replaced by condensers of smaller capacity, say $2\ \mu\text{F}$. The voltage rating of those condensers should be sufficiently high to avoid the risk of break-down.

Apply the output, suitably reduced by means of a potential divider, to a cathode-ray oscillograph with a linear time-base; the arrangement of Fig. 320 can, of course, be used if preferred with the addition of the smoothing filter as in Fig. 321. Observe the effect of the different components of the filter by inserting C_1 alone, Ch alone, Ch and C_2 omitting C_1 , and finally all three components. The effect with both half-wave and full-wave rectification should be examined.

§ 10. THE CHARACTERISTICS OF A TRIODE

The properties of triodes, described in § 3, are conveniently expressed in the form of a set of characteristic curves. From such a set




FIG. 322.—Determination of Characteristic Curves of a Triode

of characteristic curves. The method of obtaining these curves and of deducing the value of the parameters is described below.

EXPT. 272. Variation of Anode Current with Anode Potential.—Anode Characteristics.—This experiment is similar to Expt. 268 except that the diode is replaced by a triode, the grid of which is connected to the cathode through a grid-bias battery. A reversing key K (Fig. 322) is inserted so that the grid potential may be made either positive or negative.

With the grid at zero potential (grid connected directly to cathode), make a series of observations of I_A and V_A as in Expt. 268. Repeat for

a series of fixed values of the grid potential V_G at intervals of, say, $1\frac{1}{2}$ volts from +3 to -9 volts. The actual values of V_G chosen will depend, as will the other potentials, on the type of valve; the figures given will be suitable for a small-power battery type of valve.

Plot a set of curves, one for each value of V_G , on the same diagram; these curves are the **anode characteristics** of the triode (Fig. 323). Note the similarity of the curves to the characteristic curve of a diode; and observe the effect of grid-bias in shifting the curve to the right or the left, without materially altering its form except when the grid potential is positive. After the initial portion, where the anode current is limited by the space-charge, the curves become practically straight lines.




Fig. 323.—Anode Characteristics of a Triode

The 'straight' part of the characteristic is of great importance in connection with the operation of the valve. Select two points A and B on the straight part of one of the curves in Fig. 323, and construct the right-angled triangle ABC as shown. So long as A and B lie on a given straight line, the ratio AC/CB is constant; in other words the quotient $\Delta V_A / \Delta I_A$ is constant. This quotient which will be represented by R_A has the *physical dimensions* of resistance. The true resistance of a conductor, as defined by Ohm's Law, is the quotient V/I . For a linear conductor (a conductor whose resistance is constant) the same result is obtained by taking the quotient $\Delta V / \Delta I$. This is not true of a valve, since the value of V_A / I_A depends on the value of V_A and is not constant. R_A is not the true resistance of the valve, but it measures the effective resistance so far as changes in V_A and I_A are concerned. R_A gives no information regarding the connection between the actual values of I_A and V_A , but it does provide a means of calculating the change in anode current which results from a given change of anode potential. It is therefore a most important quantity since, in practice, variations in the anode current are far more important than the actual values.

The parameter R_A is measured by the reciprocal of the slope of the characteristic curve, and so it is called the **anode-slope resistance** or the **differential anode resistance**. These terms are often shortened to **anode resistance** or to **A.C. resistance**, the latter term emphasising the nature of the quantity referred to. The term **anode impedance** is very commonly used, but its use is not altogether above criticism.

The value of R_A or AC/CB , obtained from Fig. 323, is

$$(50 \text{ volts}) / (4.1 \times 10^{-3} \text{ amp.})$$

or approximately 12,000 ohms.

Moving from one curve to the next along a vertical line corresponds to changing the grid potential while keeping the anode potential constant, whereas moving along a given curve corresponds to varying V_A , while keeping V_G constant. It will be observed that a small change ΔV_G in the grid

potential is as effective in changing the anode current as a much larger change ΔV_A in the anode potential. As a consequence the triode can be used as an amplifier, and the ratio of the changes ΔV_A and ΔV_G which produce the same change in I_A is called the **amplification factor** of the valve. This can be looked at in a different way; if V_A is increased by an amount ΔV_A the anode current will increase, but its original value can be restored by reducing V_G by an appropriate amount ΔV_G . The amplification factor μ is then determined by the relation

$$\mu = \Delta V_A / \Delta V_G \quad (I_A \text{ constant}).$$

As an example consider the two points X and Y on two different curves (Fig. 323), chosen so that I_A is the same for both points.

The length XY gives ΔV_A , while ΔV_G is the difference in the values of V_G for the two curves in question. The values obtained from the diagram are: ΔV_A equal to 40 volts and ΔV_G 4 volts, making μ equal to 40/4 or 10.

There is a third parameter, the **mutual conductance** g_m , related to R_A and μ by the equation $\mu = R_A \times g_m$. The significance of g_m will be discussed in connection with the next experiment. Its value for the valve in the above example is 10/(12,000 ohms) or 0.83 mA/volt.

Select points, corresponding to normal working conditions, on the curves obtained by experiment; and determine the values of the parameters R_A , μ , and g_m . The type of valve to which these values refer and the conditions under which they were obtained should be specified when stating the results.

The characteristics of a triode can be represented graphically in




FIG. 324.—Mutual Characteristics of a Triode

another way. Curves can be drawn for a set of fixed values of the anode potential, to show how the anode current varies with grid potential. To distinguish these curves from those previously described, the term **mutual characteristics** is applied. A set of mutual characteristics is shown in Fig. 324, referring to the same valve as do the curves of Fig. 323.

EXPT. 273. Variation of Anode Current with Grid Potential—Mutual Characteristics.—To obtain the mutual characteristics choose several values of V_A at regular intervals of some 10 or 20 volts in the neighbourhood of the normal working value of V_A . Keeping V_A constant, make a series of observations of corresponding values of I_A and V_G . When V_G is being altered, it is well to arrange that

the grid circuit is never broken while there is a high potential on the anode. One of the plugs should therefore be removed from the H.T. battery while the tapping on the G.B. battery is being changed, or a key

may be included in the anode lead. Plot a set of mutual characteristics as in Fig. 324. Choose the straight part of the characteristic corresponding to the normal working value of V_A , and determine the slope of the curve, MN/LN . This is the mutual conductance, $\Delta I_A/\Delta V_G$ which measures the rate of change of anode current with grid potential. From Fig. 324 it will be seen that g_m has the value $3\cdot3/4$ or $0\cdot83$ mA/volt for the valve in question.

The amplification factor μ can be found by taking two points P and Q, on different curves, such that I_A has the same value for both points. ΔV_G , represented by PQ, is 2.5 volts while ΔV_A is 25 volts, the difference in the values of V_A for the two curves. Now $\mu = \Delta V_A/\Delta V_G$ (I_A constant), giving $\mu = 10$.

Finally, R_A can be found from the relation

$$\mu = R_A \times g_m,$$

an expression which can be verified by substitution as follows :

$$\mu = (\Delta V_A/\Delta I_A) \times (\Delta I_A/\Delta V_G) = \Delta V_A/\Delta V_G$$

when ΔI_A has the same value in each case. The value of R_A in the example, which is typical of a small battery-operated audio-frequency amplifying valve, is $\mu/g_m = 10/(0\cdot83 \text{ mA/V}) = 12 \text{ V/mA}$ or 12,000 ohms.

The quantities R_A , g_m , and μ can thus be determined either from a set of anode characteristics or from a set of mutual characteristics. The term 'parameters' is preferable to the term 'constants' in referring to these quantities, because the actual values obtained depend to some extent on the values of V_A and V_G for which they are calculated. The conditions (V_A and V_G) under which they are determined should always be specified.

§ 11. GRID CURRENT

When the grid is at a positive potential (relative to the cathode), current will flow in the grid circuit since the grid behaves in this respect in much the same way as the anode of a diode. This may produce undesirable effects ; current which goes to the grid does not reach the anode so that the presence of grid current reduces the value of the anode current, but a more serious consequence is that when grid current flows the valve draws energy from the source. For this reason it is usual to arrange matters so that the grid never becomes positive ; there are, however, exceptions to this general rule.

Suppose, for instance, that an alternating potential of 2 volts R.M.S. is applied to the grid, equivalent to 2.8 volts peak value or amplitude. To avoid the grid potential becoming positive at any time, grid-bias of at least -3 volts must be applied. This may be done by connecting a 3-volt battery in series with the source of alternating potential, the positive end of this battery being connected to the cathode.

EXPR. 274. Measurement of Grid Current.—Under ordinary conditions the grid current is very small. A microammeter will therefore be required and it should be inserted in the grid circuit (between K and the grid in Fig. 322). With normal values of the anode potential, only very small positive grid potentials can be applied on account of the large

resulting anode current. Grid current may be observed more easily if the anode potential is reduced to, say, 50 volts. Under these conditions the grid potential may be increased considerably, the grid current measured and the effect on the anode current observed at the same time.

§ 12. THE TRIODE AS AN AMPLIFIER

Because of the fact, already referred to in § 10, that a small change of grid potential can produce relatively large changes in the anode current, the triode can be used to amplify small variations of potential. That is to say, a certain change of potential ΔV_g applied to the grid can be made to produce a larger variation of potential ΔV in some other part of the circuit. The amount of amplification produced is measured by the ratio $\Delta V/\Delta V_g$ which is called the **voltage amplification** of the circuit.

The simplest way of obtaining voltage amplification is by inserting a resistance R , known as the **anode load resistance**, in the anode circuit. Since the anode current flows through this resistance, there will be a drop of potential V , equal to RI_A , between the ends of R . An increase ΔV_g of grid potential will give rise to an increase ΔI_A in the anode current and an increase ΔV equal to $R\Delta I_A$ in the P.D. across R . Under suitable conditions ΔV will be greater than ΔV_g , and amplification results.

When an alternating potential of any wave-form is applied to an amplifier, it is usually required to produce an amplified potential wave of the same form; that is, the wave-form should not be distorted. To attain this result the conditions of operation must be adjusted so that the applied potential does not, at any time, carry the operating point off the straight part of the characteristic curves of the valve. It will therefore be sufficient, in discussing the behaviour of an amplifier, to treat the characteristics as straight lines and the valve parameters R_A , g_m , and μ as constants. Since there is nearly always a small amount of curvature, even in the so-called straight parts of the characteristics, there will always be a small amount of distortion present. This may, however, be neglected in an elementary treatment.

The first point that must be emphasised is that, owing to the drop of potential V in the load resistance, the actual anode potential is less than the potential difference across the H.T. battery by an amount V . Moreover, when the anode current varies in consequence of the varying grid potential, the anode potential is no longer constant. In fact, a little consideration will show that an *increase* in V_g is accompanied by a *decrease* in V_A . The mutual characteristics of Fig. 324 cannot therefore be used directly to determine the variation of anode current with grid potential in an amplifier.

The curves of Fig. 324 are referred to as **static characteristics** because they are obtained under static (or constant) conditions of anode potential. A similar set of curves can be drawn for various *constant values of the H. T. voltage*, instead of constant anode potentials, and these are called **dynamic characteristics**. The precise form of the dynamic characteristics depends not only on the valve but also on the value of the load resistance ; they relate therefore *not to the valve but to the circuit as a whole*. To obtain dynamic characteristics the circuit should be arranged as in Fig. 325. From a dynamic characteristic the value of ΔI_A , corresponding to a given value of ΔV_G , can be read off. $R\Delta I_A$ is the change in the P.D. across R and consequently the voltage amplification $\Delta V/\Delta V_G$ or $R\Delta I_A/\Delta V_G$ can be determined.




FIG. 325.—Amplification by means of a Triode




FIG. 326.—Static and Dynamic Characteristics

It is convenient, however, to be able to calculate the voltage amplification from the values of the valve parameters. In order to derive an expression for the voltage amplification it is necessary to investigate the relation between I_A and V_G under the conditions existing in the circuit. In Fig. 326, AP and BQ are the straight portions of two static (mutual) characteristics corresponding to V_{A1} and V_{A2} . Consider the point A ; this point corresponds to the potentials V_{G1} and V_{A1} and to the anode current I_{A1} . If V_G increases to V_{G2} while V_A remains

constant, the operating point moves along AP to C. The slope of AP is g_m , the mutual conductance, and therefore the equation of AP is

$$I_A = g_m V_G + I_0,$$

where I_0 is the anode current (OP) at zero grid potential.

* V_A does not remain constant however, and as V_A is changed the slope of the characteristic remains constant but I_0 does not. Since I_0 is the anode current for zero grid potential, the way in which I_0 varies with V_A is represented by the *anode characteristic* for V_g zero (Fig. 323). The equation of this characteristic is

$$I_0 = \frac{1}{R_A} V_A + k,$$

$1/R_A$ being the slope of the characteristic and k a constant. Substituting for I_0 in the previous equation gives

$$I_A = g_m V_g + \frac{1}{R_A} V_A + k.$$

If E is the H.T. voltage and V the drop of potential in R (Fig. 325), then

$$V_A = E - V = E - RI_A.$$

Therefore
$$I_A = g_m V_g + \frac{E - RI_A}{R_A} + k,$$

or since E and R_A are constants,

$$I_A = g_m V_g - \frac{R}{R_A} I_A + k'.$$

Collecting terms in I_A gives

$$I_A \left(1 + \frac{R}{R_A} \right) = g_m V_g + k'.$$

This is the equation of the line AB along which the operating point actually moves — the dynamic characteristic.

At A
$$I_{A1} \left(\frac{R + R_A}{R_A} \right) = g_m V_{g1} + k',$$

and at B
$$I_{A2} \left(\frac{R + R_A}{R_A} \right) = g_m V_{g2} + k'.$$

Subtracting these two equations and multiplying both sides by R leads to the result

$$R \Delta I_A \left(\frac{R + R_A}{R_A} \right) = R g_m \Delta V_g,$$

or
$$R \Delta I_A = R_A g_m \left(\frac{R}{R + R_A} \right) \Delta V_g.$$

Since $R_A g_m = \mu$ and $R \Delta I_A = \Delta V$,

$$\Delta V / \Delta V_g = \mu \left(\frac{R}{R + R_A} \right).$$

Consequently the amount of amplification which can be obtained by this method is equal to the product of the amplification factor μ of the valve and the factor $R/(R + R_A)$. The amplification is therefore always less than μ , but approaches μ as R becomes very large. In

practice the value of R is limited by the fact that when R is very large the potential drop V is also large, so that unreasonably high values of the H.T. voltage would be required in order to provide the necessary working potential at the anode. On the other hand, if R is too small the resulting amplification is also small. A satisfactory compromise is usually obtained by choosing R in the region of R_A or twice R_A . The voltage amplification when R is equal to R_A is $\frac{1}{2} \mu$, and when R is equal to $2 R_A$ it is $\frac{2}{3} \mu$.

EXPT. 275. Amplification produced by a Triode.—The most direct method of studying the amplification of a triode circuit is to connect a voltmeter of range 100 or 200 volts across the resistance inserted in the anode circuit (R in Fig. 325). The voltmeter must have a high resistance, and even then the shunting effect of the voltmeter must be taken into account; this means that the value of the load resistance R in the above formula for the voltage amplification must be taken equal to the resultant resistance of the parallel combination. The voltmeter will read directly the actual drop of potential V in the resultant load resistance. An alternative method which is perhaps even more instructive is to measure the anode current I_A by means of a milliammeter and to calculate V from the product RI_A .

In the first place the operating potentials should be chosen to correspond to normal working conditions. This can be done by selecting a suitable point on the static mutual characteristics, such as P in Fig. 324, and reading off the corresponding values of V_g and I_A . Setting V_g at the determined value, adjust the H.T. voltage E until the appropriate value of I_A is obtained. E will be considerably greater than V_A for the static characteristic on which P is situated. Now keeping E constant vary V_g and plot a graph of I_A against V_g . This is a dynamic characteristic corresponding to the chosen values of E and R , and it is instructive to plot this curve on top of the static characteristics already obtained for the same valve. This should be done for two values of R in the neighbourhood of R_A and of $2 R_A$.

The slope of the dynamic characteristic is $\Delta I_A / \Delta V_g$ under dynamic conditions, and since $R \Delta I_A$ is equal to ΔV the voltage amplification $\Delta V / \Delta V_g$ can readily be calculated for each value of the load resistance.

Compare the results with the values obtained from $\mu \left(\frac{R}{R + R_A} \right)$.

When an alternating potential is applied to the grid of an amplifier, the operating point moves along the dynamic characteristic, and not along the static characteristic. The extent to which the dynamic characteristic departs from a straight line gives a good indication, therefore, of the extent to which the amplified signal will be distorted.

The type of amplifier described above is very widely used, especially for amplification at audio-frequencies. There are, however, other possible arrangements. The disadvantage of the resistance load in dropping a considerable portion of the H.T. voltage may be overcome by replacing the resistance by a low-frequency choke, an iron-cored coil of large self-inductance. The impedance of this coil (see pp. 463-464) now provides the anode load so far as the alternating component of the anode current is concerned; it therefore determines the amplification obtained. The resistance of the coil may, however, be made

relatively small so that the *mean* anode potential, that corresponding to the D.C. component of the anode current, is not much less than the H.T. voltage applied. Since the amplification is determined by the impedance of the choke, its value varies with the frequency and falls off rapidly at low frequencies. The inductance of the choke must therefore be made sufficiently large to ensure that the rate of change of amplification with frequency is not too great even at the lowest frequencies with which the amplifier may have to deal. On the other hand, if the inductance is made too large a very large number of turns of wire will be required, and this introduces an undesirable stray capacity between turns. Also, hysteresis in the iron core tends to introduce distortion particularly if the iron core is near the saturation point.

It is frequently necessary to employ several 'stages' of amplification, the output from one stage being applied to another stage. This is done by applying the varying potential of the anode of one valve




FIG. 327.—A Two-Stage Resistance-coupled Amplifier

to the grid of the next. The anode is, however, at a high positive potential and this potential must obviously be prevented from reaching the grid of the next valve. The desired result is easily obtained by interposing a condenser, which should have a sufficiently large capacity to make its reactance small even at the lowest frequencies involved.

At the same time the grid potential must have its mean value adjusted to give the necessary operating conditions. This is done by connecting the grid to the cathode through a very high resistance, or *grid-leak*, and a grid-bias battery. The value of the grid-leak resistance must be sufficiently high to enable the grid to follow the potential variations applied to it by the preceding valve, and yet not high enough to prevent any accumulated charges on the grid from leaking away.

Fig. 327 shows a two-stage resistance-coupled amplifier. For an

audio-frequency amplifier, typical values of the components C_G and R_G are $C_G = 0.1 \mu F$, $R_G = 1 M\Omega$. The values of R_1 and R_2 will depend on the particular valves used. A condenser C of say $2 \mu F$ is connected across the H.T. battery so that the alternating components of the anode currents may not set up variations of potential across the internal resistance of the H.T. battery. The circuit of a **choke-coupled amplifier** is the same as that for resistance coupling, except that a choke replaces the load resistance.

Transformer coupling is also commonly employed, particularly between the final stages of an audio-frequency amplifier. The anode load of one valve is the primary winding of an iron-cored transformer




FIG. 328.—Transformer Coupling

which behaves in a similar manner to the choke already referred to. The signal is applied to the next valve by means of the secondary winding of the transformer. One advantage of this method lies in the fact that a moderate step-up effect can be obtained by means of the transformer. The step-up ratio should not normally exceed 2 or 3 to 1, as the very large number of turns required on the secondary winding for larger ratios introduces undesirable effects through stray capacity between turns.

The final stage of an audio-frequency amplifier is usually required to deliver *power*, for example to operate a loud-speaker. For this purpose a special power-valve, capable of handling larger anode currents than are required for voltage amplification, is necessary. This **output stage** must then be matched to the loud-speaker or other load by means of a suitable transformer. The impedance of a moving-coil loud-speaker is very much less than that of the output valve. It is not possible to discuss here the theory of matching, but it may be stated that the **step-down ratio** of the transformer should be equal to the square

root of the ratio (anode resistance of output valve)/(load resistance). Fig. 328 shows the arrangement of an amplifier with transformer coupling to an output valve, which is then matched by means of a second transformer to a loud-speaker.

Radio-frequency amplification introduces problems of its own, due largely to the importance assumed by stray capacities which are of minor consequence at audio-frequencies. These capacities which occur between various parts of the circuit and earth, or between the neighbouring turns of a coil, may offer paths of relatively low impedance to radio-frequency currents. The anode load in a radio-frequency amplifier generally takes the form of a tuned circuit or the primary of a transformer. Iron cores of the normal type cannot be used because of eddy-currents and hysteresis effects. At the lower radio-frequencies dust-cores are occasionally employed. These consist of fine particles of iron suspended in an insulating material to prevent eddy currents. At the higher radio-frequencies air-cored coils are used.

§ 13. THE TRIODE AS A DETECTOR

When a triode is used as an amplifier, the grid-bias is so adjusted that the variations produced in the anode current, by a signal applied to the grid, follow as closely as possible the variations of grid potential. Thus the valve operates entirely on the straight part of the characteristic. If, however, the negative grid-bias is increased so as to shift the operating point on to the curved part of the characteristic, the positive half-cycles of grid voltage produce a greater change in the anode current than do the negative half-cycles. The anode current increases by an amount on the positive half-cycles which is relatively much greater than the amount by which it decreases on the negative half-cycles, and the net result is that there is an increase in the *average* value of the anode current while the signal is applied. The necessary condition is thus obtained for the detection of radio-frequency signals. Because of the fact that use is made of the bend of the characteristic curve, this detector is called an *anode-bend detector*.

Fig. 329 shows the effect of grid-bias on the action of a triode. A signal of varying amplitude, represented by the curve (a), is applied to the grid with grid-bias suitable for producing amplification. The mean grid potential corresponds to the point P on the straight part of the dynamic characteristic, and the variation in anode current (a') is of the same form as that of the applied signal. When the operating point is moved to Q by means of additional grid-bias, the unequal amplification of opposite half-cycles (b) produces the conditions necessary for detection as indicated by the curves (b'). The symmetry of the curve (a') for the anode current means that the average value of

the anode current, indicated by the horizontal broken line through P, is not affected by the signal. When the valve is acting as a detector, the average anode current increases as shown by the curved broken line at (b') when the signal is being received.

An interesting application of this effect is found in the **valve voltmeter**. There are various types of valve voltmeter depending on the




FIG. 329.—Action of a Triode — (a, a') as an Amplifier, (b, b') as a Detector

rectifying or detector action of thermionic valves. These are extremely useful for measurements at radio-frequencies and can be designed to present a very high impedance across the input terminals, a particularly desirable feature in a voltmeter.

EXPT. 276. Anode-Bend Detector.—Fit up the circuit shown in Fig. 330. Connect to the input terminals a variable source of alternating potential; the secondary of a mains transformer giving some 5 volts, connected across a potential divider, will serve, but an audio-frequency oscillator operating at say 1000 c/s. is to be preferred since, at the low frequency of the mains, vibration of the pointer of the milliammeter may be troublesome.

Select an operating point on the straight part of the valve characteristic and apply the appropriate grid-bias V_g and anode potential V_A . Now apply an alternating potential ΔV_g and observe the value of the

anode current for different values of ΔV_g . I_A will remain constant so long as the applied signal is not large enough to cause overloading of the valve. Increase the negative grid-bias in steps, repeating the above set of observations each time the bias is altered. As the negative bias increases it will be found that the quiescent anode current will decrease, but that an applied signal will produce an increase in the value of I_A by an amount depending on the amplitude of the signal. It is interesting to plot graphs of I_A against the signal voltage ΔV_g for different values




Fig. 330.—Anode-Bend Detector

of the grid-bias. On continuing to increase the grid-bias, a point will be reached when weak signals will produce little or no effect on the anode current, and only strong signals will cause the anode current to rise. This indicates that the grid-bias is too great and that the valve, under these conditions, would be very inefficient as a detector of weak signals. Although a detector is actually concerned with radio-frequencies, audio-frequency is used here for convenience as similar results are obtained at any frequency.

The triode can operate as detector in quite a different manner. The grid and the cathode together can be made to act as a diode detector, the grid of the triode serving as the anode of the diode. Under these conditions the valve will pass grid current. Suppose that the grid is normally at zero potential and that an alternating voltage is superposed. During the positive half-cycles the grid will collect electrons and, if these are not allowed to escape too rapidly, the mean potential of the grid will be lowered. This will produce a decrease in the anode current while the signal is being received. The radio-frequency signal is applied to the grid through a *small* condenser (say $0.0003 \mu\text{F}$). The grid is connected through a grid-leak of 1 or 2 megohms to the cathode. The potential of the grid is depressed while a signal is being received, by an amount depending on the amplitude of the radio-frequency wave. Although the resistance of the grid-leak is sufficiently high to prevent the discharge of electrons from the grid during the period of one radio-frequency wave (which may be less than 1 micro-second), the resistance is not so high that it prevents the accumulated charge from leaking away during the period of an audio-frequency wave. The amplitude of the radio wave being received varies at the audio-frequency of the signal, and hence the variations of grid potential and of anode current are able to follow the wave-form of the audio-frequency signal. In designing a detector of this type, called a **grid-circuit detector**, the values of C_g and R_g , Fig. 331 must be chosen with relation to one another to give a suitable value of the **time constant** of the grid circuit.

EXPT. 277. Grid-Circuit Detector.—Since the operation of a grid-circuit detector depends on the time constant of the grid circuit, it is essential to apply a radio-frequency signal. This may have any convenient frequency, say 1 megacycle per sec., and may be obtained from a simple form of oscillator such as that described in § 14. A signal generator, capable of modulating the radio-frequency wave with an audio-frequency signal, is to be preferred, since the audio-frequency signal can then be heard on headphones after 'detection'.

Connect up the circuit of Fig. 331 (a) with the milliammeter in circuit. The small condenser C , of say $0.001 \mu\text{F}$, is included, as shown,




Fig. 331.—Grid-Circuit Detector

to provide a path for the radio-frequency component of the anode current. Observe the value of the anode current and then apply an unmodulated radio-frequency potential to the grid. The anode current will fall to a lower value.

If the radio-frequency potential is small, the change in anode current will be too small to measure accurately on a meter of sufficient range to accommodate the full anode current. A much more sensitive meter (say $0 - 1 \text{ mA.}$) may be used if arrangement is made to **back off** the steady anode current. This can be done by substituting for the milliammeter of Fig. 331 (a) the arrangement shown in Fig. 331 (b). An essential part of this circuit is the shunt S of sufficiently low resistance to reduce the sensitivity of the milliammeter to about a tenth of its normal value. The shunt is provided with a key which is normally closed as a safety measure. The key is opened only when the *correct adjustments have been made and while readings are being taken*. The shunted meter is connected into the anode circuit in the *reverse direction*, the connection to the H.T. battery being left open. A two-volt cell and a rheostat r of about 1000 ohms are connected to the meter in the normal direction and the current adjusted, taking the shunt factor into account, until the backing-off current is approximately equal to the normal value of the anode current. The H.T. battery is now connected and r adjusted until the meter reads zero. At this stage the shunt key is opened temporarily and a more accurate zero adjustment made.

The radio-frequency voltage is now applied and, if the deflection of the meter is not more than one-tenth of the full scale, the shunt key is opened and the reading taken. This reading is the *difference* between the backing-off current and the anode current. It is therefore equal to the *decrease* in the anode current. If the signal generator is provided

with an attenuator, various radio-frequency voltages may be applied and the corresponding changes in anode current observed; these should be represented on a graph. The experiment should be repeated with different values of the grid-leak resistance R_g , and the results compared.

When the conditions for rectification have been obtained, replace the milliammeter by the headphones T, and instead of constant amplitude radio-frequency use a modulated signal. A note will be heard in the headphones, the pitch of which corresponds to the modulation frequency.

§ 14. THE TRIODE AS A GENERATOR OF OSCILLATIONS

A circuit consisting of a coil of inductance L and a condenser of capacity C has a natural frequency of oscillation $1/2\pi\sqrt{LC}$ (Chapter XI, § 5). Oscillations started in such a circuit will die out in a very short time because energy is dissipated in the circuit, mainly in the form of heat. In order to maintain the oscillation at constant amplitude




FIG. 332.—Tuned Grid Oscillator

it is necessary to supply energy to the circuit to compensate for the energy loss. This can be done by making use of a valve amplifier. The oscillatory circuit is coupled to the grid of an amplifier; the oscillation is then reproduced in the anode circuit as a component of the anode current *which derives its energy from the H.T. supply*. The anode

current is made to pass through a coil L' which is coupled by mutual induction to the coil L (Fig. 332). In this way it is possible to feed back energy from the anode circuit into the grid circuit, since the varying anode current will cause an induced E.M.F. in the coil L .

Now the anode current variations are approximately in phase with the alternating grid potential, or in other words, while the grid potential is increasing so also is the anode current. The increasing anode current in L' will induce in L an E.M.F. which will either assist or oppose the oscillation in the grid circuit, depending on the direction of the inductive coupling. If the coupling is in such a direction as to oppose the oscillation, the latter will be damped out rapidly and the oscillation will cease. On the other hand, if the induced E.M.F. assists the oscillation, the damping in the circuit is neutralised to a greater or less extent. At some critical value of the mutual inductance M the energy fed back will exactly compensate for the energy lost, and the oscillation will be maintained indefinitely.

The coil L' is frequently called the reaction coil; other terms used

are retroaction, regeneration and feed-back, and these are to be preferred to reaction.

If the coupling is increased slightly beyond the critical value, the effect will be to increase the amplitude of the oscillation. This effect is cumulative and the amplitude will tend to increase indefinitely. In practice, however, a limit is set to the amplitude for a given value of M because the increasing amplitude carries the operating point on the characteristic beyond the limits of the straight portion of the curve. This results in a progressive decrease in the mutual conductance with increasing amplitude until a condition of equilibrium is reached. It is worth noting that undue increase in the coupling will introduce distortion of the wave-form by virtue of the curvature of the characteristic; on the other hand, if energy is withdrawn from the circuit, for example to energise a radiating aerial system, this additional energy must be drawn from the H.T. supply by increasing the coupling.

Under the conditions described above, the circuit acts as a **generator of oscillations, or oscillator**. The frequency of oscillation is determined by the constants of the oscillatory circuit, and may have any value within wide limits, ranging from low audio-frequencies to high radio-frequencies of the order of 300 megacycles per second.

In describing the action of an oscillator, the question has been approached from the point of view of a circuit in which oscillations were produced initially by some external source. An external source is unnecessary, however, because in general the initial building up of the anode current or some small variation in the anode current is sufficient to start oscillation in the tuned circuit; once started, the oscillation will rapidly grow to the equilibrium amplitude.

The values of C_g and R_g are of considerable importance. When the coupling is too small to cause the circuit to oscillate, a steady anode current will flow and the grid potential will be constant. If the coupling is increased until oscillation commences, there will be a sudden drop in the mean value of the anode current. The reason for this is that, when the grid potential swings to a positive value, electrons are collected by the grid. If R_g is large the resulting negative charge leaks away comparatively slowly, and consequently the mean grid potential is lowered. If R_g is increased sufficiently, for a given value of C_g , the negative grid potential may become so great that the anode current is entirely cut off; when this occurs, the circuit ceases to oscillate. The charge on the grid continues to leak away, however, and after a short time interval conditions are restored under which oscillation can begin again. The result is that short pulses of oscillation are produced, and those pulses recur at a frequency determined by R_g and C_g ; the condition is known as **squegging**.

The critical condition of oscillation can be deduced theoretically;

for the tuned-grid oscillator of Fig. 332 it is found to be $M = RC/g_m$, where M is the mutual inductance of the two coils, R and C the resistance and capacity respectively in the tuned circuit, and g_m the mutual conductance of the valve. The value of R in this expression may be considerably greater than the ordinary D.C. resistance because high-frequency currents tend to flow mainly near the surface of a conductor. This *skin effect* decreases the effective cross-section of the conductor and hence increases its effective resistance.

The oscillator described here is only one of many possible forms; the essential features of an oscillator designed to produce a pure sine wave are a tuned circuit in conjunction with some form of feed-back amplifier. It is sometimes useful to generate oscillations of approximately square wave-form, that is oscillations very rich in harmonics. This can be accomplished by means of a circuit known as a multi-vibrator in which the fundamental frequency depends on the time constant of a resistance-capacity combination.

EXPT. 278. The Triode as an Oscillator.—Select a valve with a high mutual conductance and arrange the circuit as shown in Fig. 332. A radio-frequency oscillator of convenient range is obtained by using a coil L of 100 turns wound on a bakelite tube 2" in diameter in conjunction with a variable condenser C of maximum capacity 0.0005 μF . The reaction coil L' may consist of 100 turns (or less) on a $1\frac{1}{2}$ " tube arranged to slide along an axis common to the two coils. In order to make the tuned circuit selective, that is sharply tuned, the resistance of the tuning coil should be kept low. If measurements are to be made on the condition of oscillation, however, it is an advantage to introduce resistance deliberately into the circuit. This may be done by winding the coil with Eureka wire; if 30 S.W.G. Eureka is used errors due to skin effect will not be serious at the frequencies in question; finer wire may be used but the resistance will be greater. If copper wire is used it should not be heavier than 40 S.W.G. The condenser C_1 is inserted to provide an easy path for the radio-frequency currents; 0.01 μF will be suitable, but the value is unimportant provided it is not too low.

Place the coils initially at a considerable distance apart and gradually decrease the distance between them; a sudden drop in the anode current indicates that oscillation has commenced. If there is no evidence of oscillation, try the effect of reversing the connections to the reaction coil. There should be no difficulty in making the circuit oscillate if suitable values of C_0 and R_0 are chosen; 0.0003 μF and 0.5 megohm should be tried to begin with.

The use of a cathode ray oscillograph provides a more interesting and instructive method of observing the oscillations. The oscillations are applied to the Y plates by means of a coil coupled to one of the coils of the oscillator; and a linear time base, run at high speed, is applied to the X plates. By this method changes of amplitude and wave-form may be observed, as also can variation of the frequency.

The condition of oscillation may be verified by gradually increasing the mutual inductance M between the oscillator coils until oscillation just begins. The mutual inductance must be known and, since this is not very easy to measure when the value is so small, a table is given for a pair of coils easily constructed. One coil consists of 100 turns of No. 30 S.W.G., D.C.C. wire closely wound on a tube of 2" diameter, and the

other of 100 turns of 32 S.W.G., D.C.C. on a $1\frac{1}{2}$ " tube. The coils are mounted co-axially, and the approximate value of M is stated³ for different distances d between the centre of the coils.

d (cm.)	2	3	4	5	6	7	8	9	10
M (μ H)	170	136	101	64	37.5	22.5	14	10	7

The value of g_m can be determined by short-circuiting R_0 and observing the value of the anode current, and then applying a grid-bias of 1 volt; the change in the anode current is equal to g_m . The values of R , C and g_m are substituted in the expression $M = RC/g_m$ and the result compared with the value of M determined experimentally or by graphical interpolation from the table given.

Values obtained in a typical experiment are :—

$$\left. \begin{array}{ll} M \text{ by direct measurement} & . \quad 11.2 \mu\text{H}, \\ R \text{ (Eureka coil)} & . \quad 100 \text{ ohms} \\ C & . \quad 0.0003 \mu\text{F} \\ g_m & . \quad 2.73 \text{ mA/V} \end{array} \right\} \frac{RC}{g_m} = 11.0.$$

The agreement is well within the limits of experimental error.

If a calibrated radio-frequency oscillator is available, the frequency of the experimental oscillator can be determined by the method of Lissajou's figures. This should be done for a number of different values of the tuning capacity C . Since the inductance L is constant, the frequency f is proportional to $1/\sqrt{C}$; plotting $1/f^2$ against C should therefore give a straight line graph.

The relative values of f can be determined approximately without the aid of a calibrated oscillator. The wave-length λ of the trace can be measured by keeping the speed of the time base constant and adjusting C to give a stationary pattern; this will be possible with several values of C . In this case a straight line will be obtained on plotting λ^2 against C .

The actual frequency may be determined by using the method of beats to be described in the next paragraph. A variable standard oscillator is used to produce beats with the unknown frequency; when the two frequencies are equal, the beat-frequency is zero. A better method is to tune the beat-note to a tuning fork; this can be done for two values of the standard frequency, the arithmetic mean of which is equal to the unknown frequency.

If the frequency of oscillation has been determined by one of the methods suggested, the expression $f = 1/2\pi\sqrt{LC}$ may be verified by substitution.

The effect of varying C_0 and R_0 should be tried, with the oscillator connected to an oscillograph. When the product R_0C_0 is made sufficiently large, squegging will take place; this is indicated by the trace becoming confused and at the same time showing a bright line corresponding to the trace obtained when there is no oscillation. If the speed of the time base is reduced considerably the individual pulses of oscillation can be clearly seen; the individual oscillations in each pulse will probably not be resolved with the slower time base and the pulses will appear as a series of blobs on a straight line.

The intermittent oscillation can also be rendered audible by means of a detector and headphones.

§ 15. 'HETERODYNE' BEATS

Signals from a continuous-wave (C.W.) transmitter, that is a transmitter sending out short trains of waves of constant amplitude, cannot be rendered audible by the process of rectification—or detection—alone; except perhaps by the production of a click in the telephones at the beginning and the end of each train of waves. C.W. signals are generally received by a heterodyne method. A local oscillator in the receiver generates an oscillation of frequency f_2 differing somewhat from the signal frequency f_1 ; the two oscillations are superposed, with the result that beats are produced with a frequency equal to the difference between f_1 and f_2 . By suitably adjusting the frequency of the local oscillator the beat-frequency may be brought into the audible range. Mixing of the two frequencies must be followed by detection in order to produce an audible note; the pitch of this note is determined by the beat-frequency.

The production of an audio-frequency oscillation by combining two radio-frequencies provides a very useful method of obtaining audio-frequency oscillation for laboratory purposes. The generation of low frequencies by means of a single oscillator calls for the use of large coils and condensers, with the additional disadvantage that a wide variation of capacity (or inductance) is necessary if a considerable range of frequency is to be covered. In a beat-frequency oscillator two radio-frequency oscillators are required, one of fixed and the other of variable frequency; the variation of capacity then required to give a wide range of audio-frequency is very small, and can easily be obtained by using a single variable condenser. After rectification of the beats, the radio-frequency component of the current is by-passed by means of a small condenser. The usefulness of the instrument is considerably enhanced by the provision of a scale calibrated directly in terms of frequency.

EXPT. 279. The Production of Heterodyne Beats.—Set up two radio-frequency oscillators constructed to give the same range of frequencies, placing the oscillators so as to avoid undue coupling between them. A coil connected to a crystal receiver, or to a triode detector with headphones in the anode circuit, is placed so that it can pick up oscillations from both oscillators. One oscillator is set to the middle of its range, and the other is varied over its entire range. A note should be heard which, at first, is of very high pitch. The pitch decreases, passes through silence, and then increases in pitch again as the tuning of the second oscillator is varied from one end of its range to the other.

The transmission of speech and music by means of radio waves was made possible by the development of the thermionic valve. High-frequency oscillations are necessary to provide a carrier-wave which, in order to convey intelligence, must be modulated in some way; that

is, some property of the wave must be varied in conformity with the wave-form of the sound to be transmitted. Modulation may consist in varying the amplitude, the frequency or the phase of the carrier wave.

When amplitude modulation is employed, currents from the microphone are amplified and then made to control the amplitude of the radio-frequency oscillation comprising the carrier. After further amplification the modulated current is fed to an aerial by means of which energy is radiated in the form of electromagnetic waves. At the receiver high-frequency currents are set up in the receiving aerial, the desired signal being selected by means of tuned circuits. A radio-frequency amplifier usually precedes the detector which is followed by an audio-frequency amplifier, and an output stage to provide the power necessary to operate a loud-speaker.

The problem of providing a radio-frequency amplifier, capable of operating efficiently at all frequencies covered by the receiver, is overcome by employing the heterodyne principle, in the superheterodyne receiver. Radio-frequency oscillations generated locally are heterodyned with the incoming carrier to give a low radio-frequency which is kept constant, for all values of the carrier frequency, by adjustment of the local oscillator. Further radio-frequency amplification is then carried out at the constant intermediate frequency.

Radio-telephony, which owes its existence to the thermionic valve, has now become a great industry, and the principle of carrier telephony has been extended as a means of providing a large number of 'channels' on a single line-telephone circuit. Radio waves have been used for exploring the ionosphere, a piece of scientific research which laid the foundations of radar.

So important has the valve become in the field of radio-communication that one is apt to overlook the fact that it is used extensively in other spheres. Industry, medicine and academic research have all benefited from a device which combines simplicity of construction with an unrivalled versatility. High-frequency induction furnaces, electric 'organs', and devices for automatically performing complicated mathematical operations may be mentioned as examples.

The development of the valve and the understanding of its behaviour owe much to investigations of a purely scientific nature; at the same time a vast amount of industrial research has been expended in bringing the valve to its present high state of perfection. In fact the thermionic valve is a very good example of the result of the combined efforts of science and industry.

PART VI

ADDITIONAL EXERCISES IN ELECTRICITY

1. Test by means of a gold leaf electroscope the sign of the charge produced on rods of glass, ebonite, and sealing-wax when rubbed by fur, flannel, and silk.

2. Find the positive terminal of the given cells, using a compass needle, a straight wire, and a regulating resistance. Verify the result by winding the wire into a rough coil.

3. Plot the lines of force round a long vertical wire carrying a current, and find from your diagram the intensity of the field of the wire at a distance of 15 cm. from the wire. Take the earth's horizontal field = 0.185 C.G.S. unit.

4. Plot the lines of force round a circular coil carrying a current, and from your diagram plot a curve showing how the field along the axis varies with the distance from the coil.

5. Connect the given cell by a commutator to a tangent galvanometer—(a) directly, (b) through a given resistance. Compare the currents in the two cases.

6. Connect two cells—(1) in series, (2) in parallel, (3) in opposition, to a tangent galvanometer. Compare the currents in the three cases.

7. Connect the two cells in series through a commutator to a tangent galvanometer and note the deflections obtained. Invert the connections of one cell and again note the deflections. What result can be deduced from these observations?

8. Compare the number of turns in coil A of the given tangent galvanometer with the number of turns in coil B, given a constant cell and a resistance box.

9. Measure the value of H , the horizontal component of the earth's magnetic field by means of a tangent galvanometer and an accurate ammeter. Follow the method described in Expt. 222, Fig. 229. Take a series of readings of current I and deflection θ , and plot the values of I and $\tan \theta$. Find from the graph the value of $I/\tan \theta$, and deduce the value of H .

10. Plot a curve showing the variation of the *tangent* of the deflection of the given tangent galvanometer, with the value of the resistance placed in series with the galvanometer. Shunt the galvanometer with 5 ohms, and repeat the observations, plotting the curve on the *same* paper as the first curve. Can you estimate *approximately* the resistance of the galvanometer from your results?

11. Connect the three given cells in series with a resistance box and a tangent galvanometer, adjusting the resistance till the deflection is about 55° . Keeping the resistance constant, group the cells in all possible ways, using any number and placing them in series or in parallel. Compare the currents flowing through the galvanometer in the various cases.

12. Measure the strength of the current through the given incandescent lamp by means of a tangent galvanometer. Express the result both in C.G.S. units and in amperes.

13. Wind a length of insulated wire over a glass tube about 20 cm. long and 1 cm. in diameter so as to form a solenoid. Plot a curve showing the relation between the magnetic moment of the solenoid and the current flowing through it, using a magnetometer and a tangent galvanometer.

14. Repeat the previous experiment when the solenoid is provided with a core consisting of a bundle of soft iron wires.

15. Given two coils of wire, a compass needle and a cell, determine which coil has the greater number of turns.

16. Given two coils of thick wire of the same diameter, a compass needle, a resistance box, and a cell, find the ratio of the number of turns in the first coil to the number of turns in the second.

17. Plot a curve showing the relation between the weight that can be lifted by an electromagnet and the current flowing through the coil.

18. Test the accuracy of the readings of the ammeter supplied, using a tangent galvanometer.

19. Find how the deflection of the given galvanometer varies with current.

20. Plot a curve showing the variation of deflection with current for an astatic galvanometer of known resistance, being given a set of resistances and a constant cell of known E.M.F.

21. Find the resistance of the two given coils by connecting them separately, then together, in series with a constant cell, a 30 ohm coil, and a tangent galvanometer, and noting the deflections obtained.

22. Determine the resistance of the given length of wire and calculate its diameter, having been given the specific resistance of the material.

23. Compare the specific resistances of the materials of the two given wires.

24. Find the electrical centre of the slide wire of a metre bridge. (The electrical centre is the point dividing the wire into two parts of equal resistance.)

25. Determine the ratio of the diameters of two wires of the same material by measuring their resistances.

26. Find what length of the wire A would have a resistance of 5 ohms.

27. Equal lengths of the wires A and B, placed in parallel, are to give a resistance of 5 ohms. What must be the length of each wire?

28. Cut off from the given coil a length of wire which shall have a resistance of 1 ohm, allowing 1 cm. at each end for connections. Check the result by direct measurement of its resistance.

29. Set up the resistance boxes supplied to form a Post Office Box, and use it to measure the given resistance coil.

30. Find the length of a tangle of wire, using a P.O. box. Its specific resistance will be given.

31. Find the resistance of the conductor formed by using one, two, three, and four strands of the given wire in parallel, each strand being 20 cm. in length.

32. Compare the resistance of the given coil at 0° C. with its resistance at 100° C.

33. Construct three voltaic cells from the materials supplied and compare their electromotive forces. State which is the positive pole in each case.

34. Determine the resistance that must be connected to the poles of a cell to reduce the potential difference between them to one half. What do you deduce from the result?

35. Plot a curve showing how the potential difference between the poles of a battery varies when different resistances are connected with the poles.

36. Being given a cell (e.g. an accumulator), a number of known resistances, and a low-range voltmeter, adjust the circuit so that exactly $\frac{1}{10}$ of an ampere passes through it.

37. Measure the E.M.F. due to polarisation when (a) platinum plates, (b) lead plates dip in dilute sulphuric acid.

38. Fit up a cell with copper and zinc plates in dilute sulphuric acid. Find how the current from the cell varies with the time.

39. Measure the current in amperes through a coil of known resistance by using a voltmeter.

40. Find the maximum current which can be carried by the fuse wire supplied.

41. Pass a current through a sheet of tin-foil from one marked point to another. Plot the equipotential curves on the sheet by connecting two pins to the terminals of a sensitive galvanometer.

42. Find the horizontal component of the earth's field, using a tangent galvanometer and a copper voltmeter. The electrochemical equivalent of copper will be given.

43. Find the deflection of the given galvanometer for a current of 1 ampere, assuming the electrochemical equivalent of copper to be known.

44. Measure the heat produced in the given electric lamp when connected across the lighting mains for a measured time. Hence calculate the current flowing in the lamp, and the resistance of the lamp, being given the difference of potential between its terminals.

45. Find the rate of production of heat in the given coil when a current of one ampere flows through it.

46. The inner of two coils is wound clockwise from A to B as viewed from above. The galvanometer supplied has its north pole deflected east if the current enters it at terminal E. Find the direction of the winding of the outer coil.

47. Find which end of the given magnet is its north pole, given a helix of wire, a sensitive galvanometer, and a voltaic cell.

48. Apply the laws of induced currents to determine the polarity of a magnetised piece of steel with unmarked ends. Test the result with a compass needle brought up to the steel.

49. Apply the laws of induced currents to test the poles of a box of cells and find which is the positive. Check the result with a piece of pole-finding paper.

50. Assuming the E.C.E. of hydrogen to be known, determine the E.C.E. of copper.

SUPPLEMENT

SUPPLEMENT

NOTES ON GEOMETRICAL OPTICS

§ 1. SIGN CONVENTIONS IN GEOMETRICAL OPTICS

THE fact that light travels in straight lines in a homogeneous medium leads to the conception of a ray of light as a beam having a cross section so small that it can be represented by a geometrical straight line. A pencil of rays may be parallel, as is the case when the source is at a very great distance ; it may be convergent, when the rays tend towards a point ; or it may be divergent, when the rays tend to separate from one another. These properties may be demonstrated by means of an optical disk, such as that designed by Hartl. In this apparatus the paths of several narrow beams of light obtained by passing light from a projection lantern through parallel slits appear as brilliant lines on a white screen. By adjusting the position of the source of light inside the lantern it is possible to secure parallel, convergent, or divergent beams on the face of the disk.

One of the most important effects produced by a curved reflecting or refracting surface in an optical instrument is to modify the convergence or divergence of a beam of light incident upon the surface. This power of changing the relative directions of the rays constituting the incident beam can be shown by directing a curved mirror towards the sun. It will be seen that a concave mirror (for example a shaving mirror) brings the reflected light to a bright focus at a distance depending on the radius of curvature of the mirror, while a convex mirror (such as a driving mirror attached to a motor car) causes the reflected light to spread out or diverge from a focus. Again, when sunlight falls on a thin lens that is thicker at the centre than at the edges, the beam of light is brought to a comparatively sharp focus, which may be called the ' solar focus ' of the ' burning glass '. These effects can also be shown by using an optical disk having suitable reflecting or refracting (cylindrical) surfaces attached to the face of the screen. Double-convex and double-concave lenses are usually supplied with this apparatus, the former producing convergence and the latter divergence.

When rays travelling parallel to the axis pass through a thin lens, the distance between the lens and the focal point is called the focal length of the lens, and the power of the lens in dioptries is expressed

by the reciprocal of the focal length in metres. The term 'power' refers to the property of changing the convergence or divergence of an incident beam. Divergence may be regarded as the opposite of convergence, and the property of causing convergence as the opposite of the property of causing divergence. In the optical industry lenses which produce convergence are called positive lenses, while lenses which produce divergence are called negative lenses.

In the elementary treatment of curved mirrors and thin lenses it is assumed that the aperture is small and that the rays considered make only small angles with the axis. It is then possible to obtain simple expressions connecting together the optical and geometrical properties of such mirrors and lenses. Since it is desirable that these expressions should apply in the most general way possible, certain conventions as to sign have been introduced. In fact, various systems of conventions can be used, each of which is self-consistent. The most important difference between the systems is that relating to the sign to be attributed to the 'power of causing convergence' and to the opposite property, namely the 'power of causing divergence'.

In 1934 a Committee of the Physical Society¹ recommended the adoption of a convention, universal among opticians, for the sign of the power of an optical system. This convention may be expressed briefly by saying that a positive lens tends to converge and a negative lens to diverge the light.²

General agreement has not yet been reached as to the sign conventions to be used in examining the relations between the positions of object and image.

CONVENTIONS IN COMMON USE

We shall call the systems of conventions here considered A, B and C respectively.³ In all these systems the position of an object or of an image is located with reference to some particular point, such as the pole of a reflecting or refracting surface or the optical centre of a thin lens. The conventions differ, however, as regards the way in which positive (+) or negative (−) signs are chosen for the distances concerned.

CONVENTION A

According to this convention, adopted earlier in this book and recorded on pp. 206 and 212, distances are to be considered positive

¹ *Report on the Teaching of Geometrical Optics* (published by the Physical Society).

² Strictly speaking, it is assumed in such a statement that the light is coming from a very distant object, so that we are dealing with a parallel pencil of rays.

³ These designations are due to L. R. Middleton, who has compared the resulting equations in *A Treatise of Light* (Bell, 1937).

when measured in a direction *towards* the source of light. If, then, we regard the 'front' of a mirror or lens as that surface which faces the incident light, we may say that distances 'in front of' the mirror or lens are to be counted positive; those 'behind' the mirror or lens are to be counted negative.

When this convention is used, the focal length of a concave mirror is positive, but the focal length of a thin converging lens is negative.

Thus convention A does not lead to the same result as that used by opticians, who call the focal power of a converging lens positive (p. 212).

CONVENTION B

According to this convention, distances are counted positive when measured from the pole in the *same* direction as that in which the incident light travels. In other words, distances 'behind' the mirror or lens are to be counted positive; distances 'in front of' the mirror or lens are to be counted negative. The focal length of a converging lens is then regarded as a positive quantity.

Comparison of Conventions A and B.—Since convention B differs from convention A only in the choice of the direction to be called positive, the sign of each distance, u, v, r, f , is reversed in changing from one convention to the other. This means that equations involving only reciprocals of a distance have exactly the same form under convention B as under convention A.

Thus we have, under convention A and convention B alike—

$$\text{For mirrors} \quad \frac{1}{v} + \frac{1}{u} = \frac{1}{f};$$

$$\text{for lenses} \quad \frac{1}{v} - \frac{1}{u} = \frac{1}{f};$$

$$\text{and} \quad \frac{1}{f} = (\mu - 1) \left(\frac{1}{r_1} - \frac{1}{r_2} \right).$$

Arguments in favour of convention A as against convention B fall into two main groups. They are concerned in the first place with the difficulty experienced by some students in realising the necessity for introducing sign conventions, and in the second with the ease with which a particular system will be understood, remembered, and applied. In all the elementary examples first dealt with the object will be a 'real' one, and it may appear an unnecessary complication to make the 'object distance' u negative, as is done in using convention B. The more negative quantities there are in u, v, f , the greater is the chance of error. In most problems that arise the object is given, and the value of either v or f is required. There is, therefore, an advantage in adopting a convention, such as A, which gives a positive value of u for a real object. In the elementary treatment of the subject, also, the first simple case usually treated is the formation of a real image of a real object by means of a concave mirror.

Here all the distances to be measured lie in front of the mirror, and to say, in accordance with convention B, that all these distances are to be considered negative is undesirable. For this conventional result not only appears unnecessary to the beginner, but it suggests to his mind that geometrical optics is a difficult subject.

CONVENTION C

When convention C is used,¹ distances are measured *along a ray of light*. Now the measurement of any length is a determination of the distance between *two* points, which may be called the 'end points' of the length to be measured. For an optical path such as we are here considering one of the end points is either a small object (a point source) or a small image; the other end point is usually situated on a reflecting or refracting surface. In the simplest optical experiments² this latter point is the pole of a spherical surface, which may be either reflecting or refracting, or in the case of a *thin* lens it is the point which is called the optic centre (pp. 211, 212).

A simple preliminary statement of convention C may be given by saying that when this convention is used, lengths which are measured along actual rays of light are considered positive, and lengths which are measured along virtual rays are considered negative. An alternative statement is that u (the object distance with reference to the pole of a mirror or the optic centre of a lens) is positive when the object is real, and negative when it is virtual; similarly v (the image distance with reference to the same points) is positive when the image is real, and negative when the image is virtual.

It is also necessary to adopt some convention as to the sign to be given to the radius of curvature of a spherical reflecting or refracting surface. To determine the sign in such a case we imagine a parallel pencil of rays travelling in the direction of the axis and falling on the surface. If the effect of the reflection or refraction is to produce convergence, the radius of curvature is positive, but if the effect on the parallel pencil is to produce divergence the radius of curvature is negative. The focal length obtained by using convention C is in agreement with the optician's definition of focal power.

All other distances involved in any optical calculation, such as the displacement of a lens from one position to another or the separation between two lenses, are positive.

The rules which are adopted according to convention C may thus be summed up as follows :—

¹ For a more detailed discussion of results based on convention C reference may be made to G. R. Noakes, *A Text-Book of Light* (Macmillan, 1937).

² Although we are confining our attention to 'paraxial rays', that is rays making only a small angle with the axis of the system, it should be pointed out that convention C is advantageous in the more general treatment.

1. All distances are measured to or from the *pole* of a spherical surface, whether reflecting or refracting, or from the *optic centre* of a thin lens.
2. Distances actually traversed by light rays¹ are considered as positive; distances which light has only travelled virtually are considered as negative.
3. The radius of curvature of a surface is considered as positive if the surface produce convergence for a *parallel beam of light*, but negative if the surface produces divergence.

When convention C is used in dealing with the wave theory of light, similar rules to those already stated must be adopted to determine the sign for the curvature of a wave front.

If U and V represent the curvature of a wave before and after reflection or refraction :

U is positive for a real object, negative for a virtual object ;

V is positive for a real image, negative for a virtual image.

We shall now consider the application of the rules for convention C to the experiments described in Part III on Light.

Spherical Mirrors (pp. 206-210). Using convention C the general formula for spherical mirrors is

$$\frac{1}{v} + \frac{1}{u} = \frac{2}{r}, \quad \text{where } \frac{1}{f} = \frac{2}{r}.$$

The equation is of the same form as that obtained by using conventions A or B.

Since a *concave* mirror has a *real* principal focus, the focal length is + and the radius of curvature is +.

Since a *convex* mirror has a *virtual* principal focus, the focal length is - and the radius of curvature is -.

It should be noticed that the equations given and the signs employed for spherical mirrors in Chapter II of *Light* are identical with those here given.

Thin Lenses (pp. 211-216).—Using convention C the general formula for thin lenses is

$$\frac{1}{v} + \frac{1}{u} = \frac{1}{f}, \quad \text{where } \frac{1}{f} = (\mu - 1) \left(\frac{1}{r} + \frac{1}{s} \right).$$

It should be noticed that the equation connecting *u*, *v*, and *f* is now symmetrical and of the same form as for mirrors. This makes the equations particularly easy to remember.

For a bi-convex lens in air, *r* and *s* are both positive and the focal length *f* is positive. The lens is converging.

For a bi-concave lens in air, *r* and *s* are both negative and the focal length *f* is negative. The lens is diverging.

Strictly speaking, the focal length depends not only on the material of the lens itself, but also on the refractive index of the surrounding medium.

¹ This includes distances traversed in the substance of a *thick* lens or between different components of an optical system.

The equations given in Chapters III, IV, and V of Light must be modified when convention C is used.

The formula $\frac{1}{v} - \frac{1}{u} = \frac{1}{f}$ now becomes $\frac{1}{v} + \frac{1}{u} = \frac{1}{f}$.

The formula $V - U = F$ now becomes $V + U = F$.

The formula $\frac{1}{f} = (\mu - 1) \left(\frac{1}{r} - \frac{1}{s} \right)$ now becomes $\frac{1}{f} = (\mu - 1) \left(\frac{1}{r} + \frac{1}{s} \right)$.

We may add the formula for refraction at a single spherical surface, which is :

$$\frac{\mu}{v} + \frac{1}{u} = \frac{\mu - 1}{r}.$$

The Graphic Construction for the focal length of a thin lens given on pp. 226-227 requires modification when convention C is used.

For a real object u is positive, and the value of u is marked off along the positive direction of the axis of X. For a real image the value of v is positive, and this is marked off along the positive direction of the axis of Y. Corresponding pairs of points, such as $u_1 v_1$, $u_2 v_2$, are joined by straight lines, and it should then be found that these lines intersect in a single point F. The distance of this point from each axis is equal to f . The same graphical method can be applied when the image is virtual, as is indicated by the dotted line in the lower part of Fig. 333.




FIG. 333.—Graphic Construction for Focal Length (Converging Lens)

EXPT. 129. Determination of the Focal Length of a Converging (Convex) Lens. Method II (p. 227).—In this method two positions of the lens are found for an assigned distance d between the object and the screen. This is only possible when d is greater than $4f$. Let a be the distance between the two positions of the lens. Then

$$u = \frac{d - a}{2}, \quad v = \frac{d + a}{2},$$

and on substituting in the formula

$$\frac{1}{v} + \frac{1}{u} = \frac{1}{f}$$

we obtain

$$f = + \frac{d^2 - a^2}{4d}.$$

In the particular case for which $a = 0$ the distance d has its minimum value and

$$f = + \frac{d}{4}.$$

Optical Instruments (pp. 230-238).—Chapter VI is concerned with optical instruments and with their **magnifying power**. Since the word 'power' has already been used in a specific sense in relation to lenses, we may substitute the expression **angular magnification** when considering instruments, such as telescopes and microscopes. These produce an image which subtends an angle at the eye different from the angle subtended by the object when viewed directly.

The Simple Magnifying Glass belongs to a category of its own. It enables an object to be seen clearly when brought close up to the eye, where it subtends a comparatively large angle. In this case the term **magnifying power** is understood to mean the ratio between the angle subtended by the image seen by the aid of the glass and the angle which would be subtended by the object if it were moved back far enough to be seen clearly by the unaided eye. The **least distance of distinct vision** for a normal eye is taken as 25 cm.

Thus, if an object of size AB (Fig. 334) were viewed with the unaided




FIG. 334.—Magnifying Power of Lens

eye at a distance of 25 cm., the angle subtended at the eye would be $AB/25$. This gives the largest retinal image which can be brought into clear focus by the unaided eye.

If now the object be viewed by means of a lens of focal length f placed close up to the eye, the largest retinal image which can be brought into clear focus will be obtained if the object distance u cm. is chosen so that the

image ab will be at a distance v equal to 25 cm. The angle subtended by this image (and, incidentally, by the object as well) will then be $ab/25$.

The Magnifying Power as already defined can thus be written as

$$\text{Magnifying Power} = \frac{ab/25}{AB/25} = \frac{ab}{AB}.$$

But when the lens is being used,

$$\frac{ab}{AB} = \frac{v}{u} = \frac{-25}{u},$$

the minus sign being necessary because the image is a virtual one.

Also we know that when convention C is used,

$$\frac{1}{v} + \frac{1}{u} = \frac{1}{f},$$

so that

$$-\frac{1}{25} + \frac{1}{u} = \frac{1}{f} \text{ or } \frac{1}{u} = \frac{1}{f} + \frac{1}{25}.$$

Thus

$$\text{Magnifying Power} = \frac{25}{f} + 1.$$

This equation, of course, assumes that f is measured in cm. Since 25 cm. is one-quarter of a metre, the relation can also be stated in the form

$$M = 1 + (\text{distance of distinct vision in metres}) \times (\text{power})$$

where the power of the lens is in dioptries, or

$$M = 1 + \frac{1}{4} (\text{power in dioptries}).$$

Linear Magnification.—For instruments such as projection lanterns and cameras we are concerned with **linear magnification**, m . This is defined as the ratio of the length of the image to the length of the object.

Before a sign is given to m some convention is needed, but on this matter agreement has not been reached. In the *Report* of the Physical Society the convention is adopted that when the image is upright the magnification is given the positive sign, and when inverted, the negative sign. Thus the magnification of an erect image is considered numerically +, and the magnification of an inverted image numerically - (see p. 237). For some purposes, as in specifying the scale of enlargement of a photograph, the inclusion of a sign would be pedantic. But in theoretical work it is convenient to assume that the axis of the optical system is horizontal, and to take upward displacements as positive and downward displacements as negative.

When convention C is employed, the formula for the linear magnification m is then

$$m = -\frac{v}{u}.$$

This equation is exactly the same for spherical mirrors and for thin lenses. For a real object (u positive) the image is inverted when real (v positive), and erect when virtual (v negative). In the experiments on the optical lantern (pp. 237-238) we must now write

$$\frac{1}{v} + \frac{1}{u} = \frac{1}{f}$$

for a lens of focal length f . Thus the focal length

$$f = \frac{v}{1 - m},$$

provided the proper signs are given to v and to m .

§ 2. THE SPATIAL SYSTEM

When a lighted candle is held in front of a plane mirror, the image formed is a **virtual image**. The reflected rays travel in the space in front of the mirror, but the directions of these rays are such that on being produced backwards they intersect at a place behind the mirror where the image appears to be situated. Thus the space *behind* the plane mirror may be described as the **virtual image space**. There is also the possibility of the formation of a **real image** in front of the mirror, but this requires additional apparatus. Suppose an optical lantern to be arranged to give a real image of a lantern slide on a screen some distance from the lantern and that the plane mirror be interposed not far from the lantern in the path of the light. In this case the reflected rays will form a real image situated in front of the mirror. Consequently the space in front of the reflecting surface may be described as the **real image space**.

In the experiments (Expts. 108 and 109) on the formation of an image by a concave mirror, a real image was formed *in front of* the mirror when a small object was placed at a distance from the pole greater than the focal length. But a virtual image is formed by a concave mirror, as in a shaving mirror, when the object is at a distance from the pole less than the focal length of the mirror. In both cases we are led to a division of the space in which the image can be formed into two parts, the **virtual image space** and the **real image space**. The same distinction may be introduced when dealing with a refracting surface, or with a thin lens. According to convention C distances in the **real image space** are considered positive (+), those in the **virtual image space** negative (-).

Similar treatment may be applied to the **object space**, for although in actual practice we generally have to deal with a **real object**, it is possible to introduce the conception of a **virtual object**, and in some optical instruments this is a very convenient idea. To illustrate the meaning of the term 'virtual object' we may suppose that a projecting lantern is arranged so as to form a real image of a lantern slide at a distance of 18 feet from the lantern. Now let a large plane mirror be placed (say) 6 feet from the lantern, the mirror being not quite normal to the incident beam but slightly tilted so as to reflect the light over the top of the lantern. Then a real image will be formed 12 feet in front of the mirror, that is 6 feet *behind* the lantern. Such an

arrangement is sometimes convenient in a small lecture room, as the lantern may be on the lecture table pointing towards the audience and the final image be formed on a screen behind the lecturer.

If we now fix our attention on the action of the plane mirror, we find that the usual behaviour of such a mirror is reversed. The real




FIG. 335.—Image and Object Spaces for a Reflecting Surface

image which would have been formed, were there no mirror present, acts as *virtual* object 12 feet behind the mirror and the mirror then produces a *real* image 12 feet in front of its reflecting surface.

In such a problem distances in the *virtual object* space behind the mirror would be considered negative (Fig. 335).

In view of the fact that in the last method recommended in the Report (Group II, Case I, or C) stress is laid on a clear distinction between object space and image space, this system may be called a 'spatial' system, and convention C the 'spatial' convention. It should, however,

be noted that it is possible to develop the relations between object and image without reference to these 'spaces', which may prove confusing to a beginner.

EXPT. 277. Formation of a Virtual Object.—Set up a small electric lamp on the table to serve as a real object. Arrange a suitable converging lens with its axis horizontal, to give a real image on a white card at a distance of one or two metres from the lamp. Place a plane mirror between the lens and the card in such a position that the reflected beam is horizontal and is travelling slightly to one side of the lens. Set up a second white card in the path of this beam and adjust it so that an image of the lamp is in sharp focus. This real image may be regarded as due to the 'virtual object' situated behind the mirror at the position occupied by the first card. Measure the distance of each card from the mirror. If the reflecting surface is plane these distances should be equal. Repeat the observations for four different positions of the component parts.

The use of the term 'virtual object' may also be illustrated by the following experiment which provides a method of finding the focal length of a diverging lens.

EXPT. 278. Determination of the Focal Length of a Concave Lens.
—IV. First find the positions of conjugate foci for a convex lens as in

Expt. 115, using one pin as the object and placing the second pin on the other side of the lens so as to coincide with the real inverted image. If a concave lens is now placed between the convex lens and this image, the latter may be regarded as a 'virtual object' for rays of light passing through the concave lens. Measure the distance from the concave lens to the point of pin No. 2. This distance represents the value of u with reference to the concave lens, but as the object is virtual it is to be regarded as a *negative* quantity. Next move pin No. 2 further away from the concave lens and again adjust it so as to coincide in position with the real image of pin No. 1 formed by light passing through both lenses. Measure the distance of this new position of pin No. 2 from the concave lens. This represents the value of v , but as the image is real it is to be regarded as a *positive* quantity. Calculate the focal length of the concave lens by substituting the values of u and v in the formula

$$\frac{1}{v} + \frac{1}{u} = \frac{1}{f}$$

The observations should be repeated for another position of pin No. 1. Calculate the focal power of the concave (diverging) lens in dioptries.

The image and object spaces for a reflecting surface are illustrated in Fig. 335. In the diagram the reflecting surface is plane but a similar result applies for a curved reflecting surface. It requires some effort of the imagination to picture these spaces as, in a sense, distinct, because actually they overlap and are co-extensive.

It is somewhat easier to visualise the object space and the image space in the case of a lens mounted in a large upright panel. These spaces are shown in Fig. 336 (a) and (b). Both spaces extend to infinity along the axis in both directions. Corresponding to any chosen point in the object space there is one and only one point in the image space. Such points are said to be *conjugate points*.




FIG. 336 (a).—Real and Virtual Parts of Object Space




FIG. 336 (b).—Virtual and Real Parts of Image Space

NOTE 1.—In carrying out 'pin methods' for lenses in a poorly lighted room it may be necessary to use artificial illumination. A convenient way of doing this is to set up an electric lamp *behind* the pin, placing a sheet of ground glass between them. In this case the pin is seen against a light background and the paper flag may be dispensed with.

An alternative plan (which is useful in many optical experiments) is to use instead of a pin a very small electric lamp, such as is fitted in a pocket torch. Current may be provided by an accumulator, and, if necessary, the brightness may be regulated by using an adjustable resistance in series with the lamp. When alternating current is available, a step-down transformer may be used to give the low voltage required for motor car lamps, which can be used to serve as objects in fully lighted laboratories. For preference the lamps should be 'under-run', that is a 12-volt lamp should be operated on 6 to 8 volts, or a 6-volt lamp on 3 to 4 volts, otherwise they appear undesirably bright. By placing a filter of coloured glass or gelatine in front of the lamp approximately monochromatic light may be obtained, should that be desirable for any particular experiment.

Methods of obtaining narrow beams of light for elementary optical experiments are described in the *Science Masters' Book, Physics* (Murray).

NOTE 2.—Attention may be drawn to the great advances that have been made in the developments of plastics, the name given to materials capable of being easily moulded, many of which possess valuable mechanical, optical, and electrical properties. Some of these are waxes and cements, described as thermoplastics, the changes in their properties being usually reversible with temperature. Shellac, however, is polymerised by heat, giving a harder product. In addition there are many other substances which set, can be vulcanised and polymerised by the application of heat. These include synthetic resins, rubber cements, and inorganic cements. Some of them are described in John Strong's *Modern Physical Laboratory Practice* (Blackie and Son, 1940), but the varieties are continually increasing. One of the most useful to the physicist is Bakelite, which is a polymerised phenol aldehyde, obtainable in several forms. Among other plastics with trade names which may be mentioned are Alkathene (polymerised ethylene), which is tough and flexible at low temperatures, and may be used as an insulator in the manufacture of electric cables, and Welvic (polyvinyl chloride compositions) developed for the sheathing and insulation of cables, and for the manufacture of sleeveings and tubings. It can be applied by extrusion over other dielectrics such as Alkathene or rubber. Another material of interest, known as Perpex, can be obtained as clear acrylic resin sheets and blocks, which have many applications, notably as a glazing material in aircraft. Transpex is a synthetic organic optical material developed by Imperial Chemical Industries for the construction of lenses, prisms, and mirrors for optical instruments.

It is well known that light after passing through a suitable plate of the crystal tourmaline acquires properties related to the axis of the crystal. The light now has two-sidedness or polarity, and is said to be *plane-polarised*. On the wave theory this indicates properties related to certain directions perpendicular to the direction in which the light is travelling, suggesting that light vibrations are *transverse*. A very interesting optical material for the production or analysis of polarised light is polaroid. This consists of sheets of cellulose filled with minute crystals of an organic compound all having their axes parallel to the same direction. By forcing a mixture of cellulose and herapathite crystals through a narrow slit, the needle-like crystals orientate themselves in the flowing plastic material,

APPENDIX

APPENDIX

PHYSICAL CONSTANTS AND MATHEMATICAL TABLES

The values of the constants are taken from the Smithsonian Physical Tables, the International Critical Tables, *Physical and Chemical Constants*, by Kaye and Laby, *Physical Constants* by W. H. J. Childs, and papers by Professor R. T. Birge.

The mathematical tables are reproduced from Mr. F. Castle's *Logarithmic and other Tables for Schools* (Macmillan & Co., Ltd.), by kind permission of the publishers.

MATHEMATICAL CONSTANTS

Number	Logarithm to base 10
$\pi = 3.1416$	0.49715
$\pi^2 = 9.8696$	0.99430
$\frac{1}{\pi} = 0.3183$	1.50285
$\frac{1}{2}\pi = 4.1888$	0.62209
$e = 2.7183$	0.43429

Numbers frequently occurring—

2	0.30103
3	0.47712
$\sqrt{2} = 1.4142$	0.15052
$\sqrt{3} = 1.7321$	0.23856
981	2.99167
30.48	1.48401
2.540	0.40483
453.59	2.65666
760	2.88081
273	2.43616
4.2	0.62325

$$\log_e 10 = 2.30258$$

One radian (unit angle, for which the arc equals the radius) = $57^\circ.2958$
 $= 57^\circ 17' 45'' = 206265''$.

FORMULAE IN MENSURATION

Circumference of a circle, radius r	$= 2\pi r$
Area of a circle	$= \pi r^2$
Area of an ellipse, semi-axes a and b	$= \pi ab$
Surface of a sphere	$= 4\pi r^2$
Volume of a sphere	$= \frac{4}{3}\pi r^3$
Volume of a cylinder	$= \pi r^2 \times \text{height}$
Volume of a cone	$= \frac{1}{3}\pi r^2 \times \text{height}$
Volume of a pyramid	$= \frac{1}{3} \text{area of base} \times \text{height}$
Volume of a prism	$= \text{area of base} \times \text{height}$

MOMENTS OF INERTIA

Moments of Inertia about an axis of symmetry.

Circular ring or hoop, radius a ,

$$I = Ma^2.$$

Rectangular bar about an axis through the centre of gravity perpendicular to the edges of length $2a$ and $2b$,

$$I = M \frac{a^2 + b^2}{3}.$$

Elliptic plate, semi-axes a and b , about an axis through the centre of gravity perpendicular to its plane,

$$I = M \frac{a^2 + b^2}{4}.$$

The circular plate is a particular case, $a = b$ and

$$I = M \frac{a^2}{2}.$$

Solid ellipsoid, semi-axes a , b , c about the axis c ,

$$I = M \frac{a^2 + b^2}{5}.$$

The sphere is a particular case, $a = b = c$,

$$I = \frac{2}{5} Ma^2.$$

These results are summarised in Routh's rule, which states that the moment of inertia, I , about an axis of symmetry is given by—

$$I = \frac{\text{Mass (sum of squares of perpendicular semi-axes)}}{3, 4 \text{ or } 5}.$$

The denominator is to be 3, 4, or 5, according as the body is rectangular, elliptical, or ellipsoidal.

Thus for a *Cylinder*, length $2a$, radius b , about an axis perpendicular to its length, the section parallel to a is rectangular in type while the section parallel to b is elliptical in type, so that

$$I = M \left(\frac{a^2}{3} + \frac{b^2}{4} \right).$$

For a *Circular disk* radius, a , about a diameter,

$$I = M \frac{a^2}{4}.$$

BRITISH IMPERIAL AND METRIC MEASURES

LENGTH		AREA	
1 inch	= 2.5400 cm.	1 sq. inch	= 6.4516 sq. cm.
1 foot	= 30.480 cm.	1 sq. foot	= 929.03 sq. cm.
1 yard	= 91.4399 cm.	1 sq. yard	= 8361.27 sq. cm.
1 metre	= 39.370 in.	1 sq. metre	= 1550.0 sq. in.
MASS		CAPACITY	
1 grain	= 64.8 milligrams.	1 pint	= 0.568 litres.
1 ounce	= 28.350 gm.	1 quart	= 1.136 litres.
1 pound	= 453.59 gm.	1 gallon	= 4.546 litres.
1 kilogram	= 2.2046 lbs.	1 fluid ounce	= 23.6815 c.c.

FUNDAMENTAL PHYSICAL CONSTANTS (1941)

Velocity of light	.	.	$c = 2.99776 \times 10^{10}$ cm. sec. ⁻¹
Electron charge	.	.	$e = 4.8025 \times 10^{-10}$ e.s.u.
Faraday's constant	.	.	$F = 9.6487 \times 10^3$ e.m.u. (gm. equiv.) ⁻¹
Avogadro's constant	.	.	$N = 6.0228 \times 10^{23}$ mole ⁻¹
Mass of the electron	.	.	$m = 9.1066 \times 10^{-28}$ gm.
Mass of the proton	.	.	$M_P = 1.67248 \times 10^{-24}$ gm.
Gas constant for 1 mole	.	.	$R_M = 8.31436 \times 10^7$ erg. deg. ⁻¹ mole ⁻¹
Volume of one mole at N.T.P.	.	.	= 22.414 litres.
One electron volt	.	.	= 1.60203×10^{-12} erg.
Joule's equivalent	.	.	$J = 4.1855$ joule cal. ⁻¹
Ice point	.	.	$T_0 = 273.16^\circ$ K.

ELASTIC MODULI IN DYNES PER SQUARE CM.

Material	Young's Modulus	Modulus of Rigidity
Aluminium	7.2 to 7.5×10^{11}	2.5 to 3.4×10^{11}
Brass	8.5 to 10.5×10^{11}	3.5 to 3.7×10^{11}
Copper	10.5 to 13.2×10^{11}	4.2 to 4.8×10^{11}
Iron	about 20×10^{11}	5.2 to 8.2×10^{11}
Platinum	15 to 17×10^{11}	6.2 to 6.6×10^{11}
Silver	7.1 to 7.4×10^{11}	2.5 to 3.0×10^{11}
Glass	6 to 8×10^{11}	2.3 to 2.7×10^{11}

DENSITY OR MASS IN GRAMS PER C.C.

SOLIDS

Elements	Common Substances
Aluminium 2.70	Boxwood 0.95-1.16
Antimony 6.62	Cork 0.22-0.26
Bismuth 9.80	Pitch Pine 0.83-0.85
Copper 8.30-8.95	Yellow Pine 0.37-0.60
Gold 19.3	Mahogany 0.85
Iron 7.5-7.9	Oak 0.60-0.90
Lead 11.3	Walnut 0.64-0.70
Magnesium 1.74	Beeswax 0.96-0.97
Nickel 8.6-8.9	Ebonite 1.15
Osmium 22.5	Glass, common 2.4-2.8
Platinum 21.45	Glass, flint 2.9-5.9
Silver 10.5	Ice 0.917
Tin 7.3	Paraffin wax 0.87-0.91
Zinc 7.1	Brass 8.4-8.7

LIQUIDS

	Grams per c.c.	Temp. in °C.
Alcohol, ethyl	0.807	0°
" methyl	0.810	0°
Anilin	1.035	0°
Carbon disulphide	1.293	0°
Chloroform	1.480	18°
Ether	0.736	0°
Glycerin	1.260	0°
Paraffin	0.878	0°
Petrol	0.70 to 0.80	15°
Mercury	{ 13.596	0°
	{ 13.546	20°

GASES

Grams per c.c. at 0° C.
and 76 cm. pressure

Air	0.0012928
Aqueous vapour (calculated)	0.000814
Carbon dioxide	0.0019768
Hydrogen	0.00009004
Nitrogen	0.0012514
Oxygen	0.0014292

COEFFICIENTS OF LINEAR EXPANSION

The value quoted is the mean coefficient of linear expansion between 0° C. and 100° C.

Aluminium	0.000022	Lead	0.000027
Brass	0.000019	Platinum	0.000009
Copper	0.000017	Silver	0.000019
Glass	0.000008–0.000009	Tin	0.000023
Gold	0.000014	Zinc	0.000029
Iron	0.000011	Fused Quartz	0.000005

SPECIFIC HEATS

Thermal capacity of unit mass in calories (gram)⁻¹ (degree C.)⁻¹

SOLIDS

Aluminium	0.217	Lead	0.031
Brass	0.092	Platinum	0.032
Copper	0.093	Silver	0.056
Glass	0.19	Tin	0.055
Gold	0.031	Zinc	0.092
Iron	0.113	Quartz	0.191

LIQUIDS

Alcohol (17° C.)	0.58	Mercury	0.033
Anilin	0.514	Paraffin	0.511
Glycerin	0.576	Turpentine	0.43

COEFFICIENTS OF THERMAL CONDUCTIVITY

Calories, cm.⁻¹, sec.⁻¹ (deg. C.)⁻¹

Aluminium	0.48	Lead	0.08
Brass	(about) 0.2	Platinum	0.17
Copper	0.9	Silver	1.0
Glass	(about) 0.001	Tin	0.15
Iron	0.10–0.14	Zinc	0.26
Pasteboard	(about) 0.0004		
Rubber	(about) 0.0003		

PRESSURE OF SATURATED AQUEOUS VAPOUR

Pressures in mm. of mercury

Temp.	Pressure	Temp.	Pressure
0° C.	4.6	13° C.	11.2
1	4.9	14	12.0
2	5.3	15	12.8
3	5.7	16	13.6
4	6.1	17	14.5
5	6.5	18	15.5
6	7.0	19	16.5
7	7.5	20	17.5
8	8.0	21	18.7
9	8.6	22	19.8
10	9.2	23	21.0
11	9.8	24	22.4
12	10.5	25	23.8

REFRACTIVE INDICES FOR SODIUM LIGHT

Temperature	μ
Water (17.5° C.)	1.3332
Alcohol (15.0° C.)	1.3635
Anilin (20.0° C.)	1.5863
Benzene (21.6° C.)	1.5004
Carbon disulphide (20.0° C.)	1.6276
Bromnaphthalin (20.0° C.)	1.6582
Crown glass (ordinary)	1.53
" (heavy)	1.61
Flint glass (ordinary)	1.65
" (heavy)	1.74
Quartz (ordinary ray)	1.5442
" (extraordinary ray)	1.5533
" (fused)	1.45843

WAVE-LENGTHS

Wave-lengths are usually expressed in Angstrom Units (A.U.) or Tenth Metres (10^{-10} metre). 1 A.U. = 10^{-8} cm.

Wave-lengths are sometimes expressed in a unit ten times larger, viz. the micromillimetre ($m\mu$).

Primary Standard λ Red cadmium line 6438.4696 A.U.

The Solar Spectrum		Emission Spectra	
Atmospheric	A	Potassium (red)	7700
"	B	Lithium (red)	6708
Hydrogen α	C	" (orange)	6104
Sodium	D ₁	Sodium (yellow)	5896
"	D ₂	"	5890
Iron	E	Neon (yellow)	5853
Magnesium	b ₁	Mercury (yellow)	5791
Hydrogen β	F	"	5770
Hydrogen γ		" (green)	5461
Iron	G	Thallium (green)	5351
Hydrogen δ	h	Strontium (blue)	4608
Calcium	H	Mercury (violet)	4358
"	K	Calcium (blue)	4227
		Potassium (violet)	4047
		"	4044

RESISTIVITY OR SPECIFIC RESISTANCE

The resistance in ohms of a wire 1 cm. in length, 1 sq. cm. in cross section.
The unit of resistivity is the ohm cm.

Elements	Temp.	Resistivity	Temp. Coefficient
Aluminium	(20°)	0.0000028	0.0039
Copper	(20°)	0.0000017	0.0040
Iron (pure)	(0°)	0.0000088	0.0062
„ (piano wire) . . .	(0°)	0.0000118	0.0032
Lead	(0°)	0.0000204	0.0043
Magnesium	(0°)	0.0000044	0.0038
Mercury	(20°)	0.0000957	0.00088
Nickel	(0°)	0.0000069	0.0062
Platinum	(0°)	0.0000110	0.0037
Silver	(18°)	0.0000016	0.0040
Tin	(0°)	0.0000130	0.0046
Zinc	(0°)	0.0000057	0.0040
Alloys			
Brass	(about)	0.000007	0.0010
Manganin	(about)	0.000043	0.00002
Platinoid	(about)	0.000034	0.00025
Constantan or Eureka		0.000048	± 0.0001
Nichrome		0.000110	0.00017

ELECTROCHEMICAL EQUIVALENTS

The electrochemical equivalent of silver is here assumed to be 0.001118 gm. per coulomb.

Element	Atomic Weight (1941) (0 = 16)	Valency	E.C.E. (grams per coulomb)
Aluminium	26.97	3	0.0000932
Copper	63.57	(1)2	0.0003294
Gold	197.2	(1)3	0.0006809
Hydrogen	1.008	1	0.0001045
Oxygen	16.00	2	0.0000829
Nickel	58.69	2(3)	0.0003041
Silver	107.88	1	0.001118
Zinc	65.38	2	0.0003388

BRITISH STANDARD WIRE GAUGE

W.G.	Diameter		S.W.G.	Diameter	
	Inch	Mm.		Inch	Mm.
0	0.324	8.23	26	0.0180	0.457
2	0.276	7.01	28	0.0148	0.376
4	0.232	5.89	30	0.0124	0.315
6	0.192	4.88	32	0.0108	0.274
8	0.160	4.06	34	0.0092	0.234
10	0.128	3.25	36	0.0076	0.193
12	0.104	2.64	38	0.0060	0.152
14	0.080	2.03	40	0.0048	0.122
16	0.064	1.63	42	0.0040	0.102
18	0.048	1.22	44	0.0032	0.081
20	0.036	0.914	46	0.0024	0.061
22	0.028	0.711	48	0.0016	0.041
24	0.022	0.559	50	0.0010	0.025

MEAN VALUES OF THE MAGNETIC ELEMENTS AT MAGNETIC OBSERVATORIES

Much assistance has been given by the Superintendent of the Magnetic Department, The Royal Observatory, Greenwich.

Place	Latitude	Longitude	Declination	Inclination	H	V	Year
	^N			^N	^γ	^γ	
N. Mag. Pole	74° 54'	101° 0' W.*	..	90° 0'	..	[59000]	1960
Lerwick	60° 8'	1° 11' W.	10° 9' W.	72° 57'	14464	47156	1955
Lovo	59° 21'	17° 50' E.	0° 19' E.	72° 8'	15244	47271	1955
Sitka	57° 3'	135° 20' W.	29° 2' E.	74° 11'	15573	54948	1955
Eskdalemuir	55° 19'	3° 12' W.	10° 56' W.	69° 47'	16668	45250	1955
Meanook	54° 37'	113° 21' W.	24° 46' E.	77° 45'	12872	59248	1951
Niemegk	52° 4'	12° 41' E.	2° 26' W.	67° 12'	18446	43879	1954
Valentia	51° 56'	10° 15' W.	13° 40' W.	67° 44'	18195	44424	1956
Hartland	51° 0'	4° 29' W.	10° 5' W.	66° 45'	18681	43484	1959
Chambon-la-Forêt	48° 1'	2° 16' E.	6° 52' W.	64° 8'	20251	41793	1955
Agincourt	43° 47'	79° 16' W.	7° 16' W.	74° 34'	15522	56209	1954
Ebro	40° 49'	0° 30' E.	7° 1' W.	57° 2'	23914	36879	1954
Coimbra	40° 12'	8° 25' W.	10° 21' W.	56° 58'	23914	36766	1957
Cheltenham	38° 44'	76° 50' W.	7° 12' W.	70° 59'	18518	53927	1955
San Fernando	36° 28'	6° 12' W.	9° 29' W.	52° 23'	25836	33527	1954
Tucson	32° 15'	110° 50' W.	13° 16' E.	59° 28'	25939	43975	1957
Dehra Dun	30° 19'	78° 3' E.	1° 31' E.	45° 38'	32915	33655	1954
Kakioka	36° 14'	140° 11' E.	6° 23' W.	49° 17'	30123	35002	1957
Honolulu	21° 18'	158° 6' W.	11° 37' E.	38° 59'	28414	22993	1957
Teoloyucan	19° 45'	99° 11' W.	9° 11' E.	47° 6'	30312	32616	1956
Alibag	18° 39'	72° 52' E.	0° 44' W.	24° 40'	38566	17714	1954
	^S			^S			
Kuyper	6° 2'	106° 44' E.	1° 21' E.	32° 18'	37471	-23684	1957
	^N			^N			
Huancayo	12° 3'	75° 20' W.	6° 12' E.	2° 1'	29102	1028	1949
	^S			^S			
Apia	13° 48'	171° 46' W.	11° 41' E.	30° 20'	34913	-20435	1953
Mauritius	20° 6'	57° 33' E.	16° 14' W.	53° 51'	22300	-30533	1954
La Quiaca	22° 8'	65° 43' W.	2° 45' E.	13° 23'	25556	-6083	1948
Vassouras	22° 24'	43° 39' W.	15° 38' W.	21° 40'	22802	-9059	1955
Watheroo	30° 19'	115° 53' E.	2° 42' W.	64° 34'	24842	-52234	1957
Pilar	31° 40'	63° 53' W.	4° 25' E.	27° 16'	23417	-12065	1950
Toolangi	37° 32'	145° 28' E.	10° 7' E.	68° 4'	22715	-56433	1957
Amberley	43° 10'	172° 43' E.	20° 3' E.	68° 6'	22160	-55119	1954
Heard Island	53° 2'	73° 22' E.	50° 20' W.	68° 37'	18485	-47277	1954
Macquarie Island	54° 30'	158° 57' E.	24° 40' E.	78° 19'	13338	-64490	1955
Laurie Island	60° 45'	44° 47' W.	2° 21' E.	54° 7'	22764	-31474	1948
S. Mag. Pole	67° 6'	142° 36' E.*	..	90° 0'	..	[-68500]	1960

* Deduced positions.

In the values of the Horizontal Force, H, and the Vertical Force, V, 1γ corresponds to 1×10^{-8} C.G.S. unit. The last figure is not reliable.

In consequence of the increased use of electric railways and of electric power in cities it has been found necessary to establish magnetic observatories in country districts, as at Hartland Point, North Devon, in England, for Greenwich, Eskdalemuir in Scotland, Niemegk for Potsdam, Chambon-la-Forêt for Val Joyeux (Paris).

ATOMIC NUMBERS AND ATOMIC WEIGHTS OF ELEMENTS

Isotopes have the same nuclear charge but different atomic weights.

Atomic Number	Element	Symbol	Atomic Weight	Principal Isotopes Mass Numbers
1	Hydrogen .	H	1.0080	1, 2, (3)
	Deuterium .	D	2.0142	—
	Tritium .	T	—	—
2	Helium .	He	4.003	4, 3, (6)
3	Lithium .	Li	6.940	7, 6
4	Beryllium *	Be	9.02	9, 10, 7
5	Boron .	B	10.82	11, 10
6	Carbon .	C	12.011	12, 13
7	Nitrogen .	N	14.008	14, 15
8	Oxygen .	O	16.0000	16, 18, (17)
9	Fluorine .	F	19.00	19
10	Neon .	Ne	20.183	20, 22, (21)
11	Sodium .	Na	22.994	23
12	Magnesium .	Mg	24.32	24, 25, 26
13	Aluminium .	Al	26.97	27
14	Silicon .	Si	28.06	28, 29, 30
15	Phosphorus .	P	30.98	31
16	Sulphur .	S	32.06	32, 34, 33
17	Chlorine .	Cl	35.457	35, 37
18	Argon .	A	39.944	40, 36, (38)
19	Potassium .	K	39.096	39, 41
20	Calcium .	Ca	40.08	40, 44, 42, (48), (43)
21	Scandium .	Sc	45.10	45
22	Titanium .	Ti	47.90	48, 46, 47, 49, 50
23	Vanadium .	V	50.95	51
24	Chromium .	Cr	52.01	52, 53, 50, 54
25	Manganese .	Mn	54.93	55
26	Iron .	Fe	55.85	56, 54, 57
27	Cobalt .	Co	58.94	59
28	Nickel .	Ni	58.69	58, 60, 62
29	Copper .	Cu	63.57	63, 65
30	Zinc .	Zn	65.38	64, 66, 68, 67, 70
31	Gallium .	Ga	69.72	69, 71
32	Germanium .	Ge	72.60	74, 72, 70, 73, 76
33	Arsenic .	As	74.91	75
34	Selenium .	Se	78.96	80, 78, 76, 82, 77, 74
35	Bromine .	Br	79.916	79, 81
36	Krypton .	Kr	83.7	84, 86, 82, 83, 80, 78
37	Rubidium .	Rb	85.48	85, 87
38	Strontium .	Sr	87.63	88, 86, 87
39	Yttrium .	Y	88.92	89
40	Zirconium .	Zr	91.22	90, 94, 92, 91, 96
41	Niobium †	Nb	92.91	93
42	Molybdenum .	Mo	95.95	98, 96, 95, 92, 94, 100, 97
43	Masurium .	Ma	—	—
44	Ruthenium .	Ru	101.7	102, 101, 104, 100, 99, 96, 98
45	Rhodium .	Rh	102.91	103
46	Palladium .	Pd	106.7	106, 108, 105, 110, 104
47	Silver .	Ag	107.880	107, 109
48	Cadmium .	Cd	112.41	114, 112, 110, 111, 113, 116
49	Indium .	In	114.76	115, 113
50	Tin .	Sn	118.70	120, 118, 116, 119, 117, 124, 122, 121, 112, 114, 115

Or Glucium (Gl).

† Or Columbium (Cb).

ATOMIC NUMBERS AND ATOMIC WEIGHTS OF ELEMENTS

The number of isotopes is now very great ; many are radioactive.*

Atomic Number	Element	Symbol	Atomic Weight	Principal Isotopes Mass Numbers
51	Antimony . .	Sb	121.76	121, 123
52	Tellurium . .	Te	127.61	130, 128, 126, 125, 124, 122, 123, (127)
53	Iodine . . .	I	126.915	127
54	Xenon . . .	Xe	131.3	129, 132, 131, 134, 136, 130, 128, 126, 124
55	Caesium . .	Cs	132.91	133
56	Barium . . .	Ba	137.36	138, 137, 136, 135, 134
57	Lanthanum . .	La	138.92	139
58	Cerium . . .	Ce	140.13	140, 142
59	Praseodymium .	Pr	140.92	141
60	Neodymium . .	Nd	144.27	142, 144, 146, 143, 145, 148
61	Illinium . . .	Il	—	—
62	Samarium . .	Sm	150.43	152, 154, 147, 149, 148
63	Europium . .	Eu	152.0	153, 151
64	Gadolinium . .	Gd	156.9	158, 160, 156, 157, 157
65	Terbium . . .	Tb	159.2	159
66	Dysprosium . .	Dy	162.46	164, 163, 162, 161
67	Holmium . . .	Ho	164.94	165
68	Erbium . . .	Er	167.2	166, 168, 167, 170
69	Thulium . . .	Tm	169.4	169
70	Ytterbium . .	Yb	173.04	174, 172, 173, 171, 176
71	Lutecium . . .	Lu	174.99	175, 176
72	Hafnium . . .	Ha	178.6	180, 178, 177, 179, 176
73	Tantalum . . .	Ta	180.88	181
74	Tungsten . . .	W	183.91	184, 183, 182
75	Rhenium . . .	Re	186.31	187, 185
76	Osmium . . .	Os	190.2	192, 190, 189, 188, 187, 186
77	Iridium . . .	Ir	193.1	193, 191
78	Platinum . . .	Pt	195.23	195, 194, 196, 198, (192)
79	Gold	Au	197.2	197
80	Mercury . . .	Hg	200.61	202, 200, 199, 201, 198, 204, 196, 197, 203
81	Thallium . . .	Tl	204.39	205, 203
82	Lead	Pb	207.22	208, 206, 207, 204, 209, 210, 203, 205
83	Bismuth . . .	Bi	209.00	209
84	Polonium . . .	Po	210	—
85	—	—	—	—
86	Radon † . . .	Rn	222	—
87	—	—	—	—
88	Radium . . .	Ra	226.05	—
89	Actinium . . .	Ac	226.7	—
90	Thorium . . .	Th	232.12	232
91	Uranium X ₂ . .	Ux ₂	234	—
91	Protactinium .	Pa	—	—
92	Uranium . . .	U	238.07	238, 235, 234, 239
93	Neptunium . .	Np	(239)	237, 239
94	Plutonium . .	Pu	(239)	239
95	Americium . .	Am	—	241
96	Curium . . .	Cm	—	240, 242

* For a lengthy list of isotopes, see *Rev. Modern Physics*, 16, pp. 1-32 (1944). For the trans-uranium elements, see *Nature*, 159, p. 863 (1947).

† Or Niton (Nt), Radium Emanation.

LOGARITHMS

	0	1	2	3	4	5	6	7	8	9	1 2 3	4 5 6	7 8 9
10	0000	0043	0086	0128	0170						4 9 13	17 21 26	30 34 38
11	0414	0453	0492	0531	0569	0212	0253	0294	0334	0374	4 8 12	16 20 24	28 32 36
12	0792	0828	0864	0899	0934	0607	0645	0682	0719	0755	4 8 12	15 19 23	27 31 35
13	1139	1173	1206	1239	1271	0969	1004	1038	1072	1106	4 7 11	15 19 22	26 30 33
14	1461	1492	1523	1553	1584	1303	1335	1367	1399	1430	3 7 10	14 18 21	25 28 32
15	1761	1790	1818	1847	1875	1614	1644	1673	1703	1732	3 7 10	14 17 20	24 27 31
16	2041	2068	2095	2122	2148	1903	1931	1959	1987	2014	3 7 10	13 16 19	22 25 29
17	2304	2330	2355	2380	2405	2175	2201	2227	2253	2279	3 6 9	12 15 19	22 25 28
18	2553	2577	2601	2625	2648	2430	2455	2480	2504	2529	3 6 9	12 15 17	20 23 26
19	2788	2810	2833	2856	2878	2672	2695	2718	2742	2765	3 6 9	11 14 17	20 23 26
20	3010	3032	3054	3075	3096	2900	2923	2945	2967	2989	3 6 8	11 14 17	19 22 25
21	3222	3243	3263	3284	3304	3139	3160	3181	3201	3221	3 5 8	11 14 16	19 22 24
22	3424	3444	3464	3483	3502	3345	3365	3385	3404	3424	3 5 8	10 13 16	18 21 23
23	3617	3636	3655	3674	3692	3541	3560	3579	3598	3617	3 5 8	10 13 15	18 20 23
24	3802	3820	3838	3856	3874	3711	3729	3747	3766	3784	2 5 7	10 12 15	17 20 22
25	3979	3997	4014	4031	4048	3892	3909	3927	3945	3962	2 5 7	9 12 14	16 19 21
26	4150	4166	4183	4200	4216	4065	4082	4099	4116	4133	2 5 7	9 11 14	16 18 21
27	4314	4330	4346	4362	4378	4249	4265	4281	4298	4314	2 4 6	9 11 13	16 18 20
28	4472	4487	4502	4518	4533	4409	4425	4440	4456	4472	2 4 6	8 11 13	15 17 19
29	4624	4639	4654	4669	4683	4564	4579	4594	4609	4624	2 3 5	8 10 12	14 16 18
30	4771	4786	4800	4814	4829	4698	4713	4728	4742	4757	2 3 5	8 10 12	14 15 17
31	4914	4928	4942	4955	4969	4843	4857	4871	4886	4900	2 3 5	7 10 11	13 15 16
32	5051	5065	5079	5092	5105	4983	4997	5011	5024	5038	2 3 5	6 8 9	11 13 14
33	5185	5198	5211	5224	5237	5119	5132	5145	5159	5172	2 3 5	6 8 9	11 12 14
34	5315	5328	5340	5353	5366	5250	5263	5276	5289	5302	1 3 4	6 7 9	10 12 13
35	5441	5453	5465	5478	5490	5378	5391	5403	5416	5428	1 3 4	5 6 8	9 10 11
36	5563	5575	5587	5599	5611	5502	5514	5527	5539	5551	1 2 4	5 6 7	8 10 11
37	5682	5694	5705	5717	5729	5611	5623	5635	5647	5658	1 2 4	5 6 7	8 10 11
38	5798	5809	5821	5832	5843	5729	5740	5752	5763	5775	1 2 3	5 6 7	8 9 10
39	5911	5922	5933	5944	5955	5843	5855	5866	5877	5888	1 2 3	5 6 7	8 9 10
40	6021	6031	6042	6053	6064	5955	5967	5977	5988	5999	1 2 3	4 5 7	8 9 10
41	6128	6138	6149	6160	6170	6064	6075	6085	6096	6107	1 2 3	4 5 6	8 9 10
42	6232	6243	6253	6263	6274	6170	6180	6191	6201	6212	1 2 3	4 5 6	7 8 9
43	6335	6345	6355	6365	6375	6284	6294	6304	6314	6325	1 2 3	4 5 6	7 8 9
44	6435	6444	6454	6464	6474	6385	6395	6405	6415	6425	1 2 3	4 5 6	7 8 9
45	6532	6542	6551	6561	6571	6484	6493	6503	6513	6522	1 2 3	4 5 6	7 8 9
46	6628	6637	6646	6656	6665	6580	6590	6600	6609	6618	1 2 3	4 5 6	7 8 9
47	6721	6730	6739	6749	6758	6665	6675	6684	6693	6702	1 2 3	4 5 6	7 7 8
48	6812	6821	6830	6839	6848	6767	6776	6785	6794	6803	1 2 3	4 5 5	6 7 8
49	6902	6911	6920	6928	6937	6866	6875	6884	6893	6902	1 2 3	4 4 5	6 7 8
50						6946	6955	6964	6972	6981	1 2 3	4 4 5	6 7 8

LOGARITHMS

	0	1	2	3	4	5	6	7	8	9	123	456	789
50	6990	6998	7007	7016	7024	7033	7042	7050	7059	7067	1 2 3	3 4 5	6 7 8
51	7076	7084	7093	7101	7110	7118	7126	7135	7143	7152	1 2 3	3 4 5	6 7 8
52	7160	7168	7177	7185	7193	7202	7210	7218	7226	7235	1 2 2	3 4 5	6 7 7
53	7243	7251	7259	7267	7275	7284	7292	7300	7308	7316	1 2 2	3 4 5	6 6 7
54	7324	7332	7340	7348	7356	7364	7372	7380	7388	7396	1 2 2	3 4 5	6 6 7
55	7404	7412	7419	7427	7435	7443	7451	7459	7466	7474	1 2 2	3 4 5	5 6 7
56	7482	7490	7497	7505	7513	7520	7528	7536	7543	7551	1 2 2	3 4 5	5 6 7
57	7559	7566	7574	7582	7589	7597	7604	7612	7619	7627	1 2 2	3 4 5	5 6 7
58	7634	7642	7649	7657	7664	7672	7679	7686	7694	7701	1 1 2	3 4 4	5 6 7
59	7709	7716	7723	7731	7738	7745	7752	7760	7767	7774	1 1 2	3 4 4	5 6 7
60	7782	7789	7796	7803	7810	7818	7825	7832	7839	7846	1 1 2	3 4 4	5 6 6
61	7853	7860	7868	7875	7882	7889	7896	7903	7910	7917	1 1 2	3 4 4	5 6 6
62	7924	7931	7938	7945	7952	7959	7966	7973	7980	7987	1 1 2	3 4 4	5 6 6
63	7993	8000	8007	8014	8021	8028	8035	8041	8048	8055	1 1 2	3 4 4	5 5 6
64	8062	8069	8075	8082	8089	8096	8102	8109	8116	8122	1 1 2	3 4 4	5 5 6
65	8129	8136	8142	8149	8156	8162	8169	8176	8182	8189	1 1 2	3 3 4	5 5 6
66	8195	8202	8209	8215	8222	8228	8235	8241	8248	8254	1 1 2	3 3 4	5 5 6
67	8261	8267	8274	8280	8287	8293	8299	8306	8312	8319	1 1 2	3 3 4	5 5 6
68	8325	8331	8338	8344	8351	8357	8363	8370	8376	8382	1 1 2	3 3 4	4 5 6
69	8388	8395	8401	8407	8414	8420	8426	8432	8439	8445	1 1 2	2 3 4	4 5 6
70	8451	8457	8463	8470	8476	8482	8488	8494	8500	8506	1 1 2	2 3 4	4 5 6
71	8513	8519	8525	8531	8537	8543	8549	8555	8561	8567	1 1 2	2 3 4	4 5 5
72	8573	8579	8585	8591	8597	8603	8609	8615	8621	8627	1 1 2	2 3 4	4 5 5
73	8633	8639	8645	8651	8657	8663	8669	8675	8681	8686	1 1 2	2 3 4	4 5 5
74	8692	8698	8704	8710	8716	8722	8727	8733	8739	8745	1 1 2	2 3 4	4 5 5
75	8751	8756	8762	8768	8774	8779	8785	8791	8797	8802	1 1 2	2 3 3	4 5 5
76	8808	8814	8820	8825	8831	8837	8842	8848	8854	8859	1 1 2	2 3 3	4 5 5
77	8865	8871	8876	8882	8887	8893	8899	8904	8910	8915	1 1 2	2 3 3	4 4 5
78	8921	8927	8932	8938	8943	8949	8954	8960	8965	8971	1 1 2	2 3 3	4 4 5
79	8976	8982	8987	8993	8998	9004	9009	9015	9020	9025	1 1 2	2 3 3	4 4 5
80	9031	9036	9042	9047	9053	9058	9063	9069	9074	9079	1 1 2	2 3 3	4 4 5
81	9085	9090	9096	9101	9106	9112	9117	9122	9128	9133	1 1 2	2 3 3	4 4 5
82	9138	9143	9149	9154	9159	9165	9170	9175	9180	9186	1 1 2	2 3 3	4 4 5
83	9191	9196	9201	9206	9212	9217	9222	9227	9232	9238	1 1 2	2 3 3	4 4 5
84	9243	9248	9253	9258	9263	9269	9274	9279	9284	9289	1 1 2	2 3 3	4 4 5
85	9294	9299	9304	9309	9315	9320	9325	9330	9335	9340	1 1 2	2 3 3	4 4 5
86	9345	9350	9355	9360	9365	9370	9375	9380	9385	9390	1 1 2	2 3 3	4 4 5
87	9395	9400	9405	9410	9415	9420	9425	9430	9435	9440	0 1 1	2 2 3	3 4 4
88	9445	9450	9455	9460	9465	9470	9474	9479	9484	9489	0 1 1	2 2 3	3 4 4
89	9494	9499	9504	9509	9513	9518	9523	9528	9533	9538	0 1 1	2 2 3	3 4 4
90	9542	9547	9552	9557	9562	9566	9571	9576	9581	9586	0 1 1	2 2 3	3 4 4
91	9590	9595	9600	9605	9609	9614	9619	9624	9628	9633	0 1 1	2 2 3	3 4 4
92	9638	9643	9647	9652	9657	9661	9666	9671	9675	9680	0 1 1	2 2 3	3 4 4
93	9685	9689	9694	9699	9703	9708	9713	9717	9722	9727	0 1 1	2 2 3	3 4 4
94	9731	9736	9741	9745	9750	9754	9759	9763	9768	9773	0 1 1	2 2 3	3 4 4
95	9777	9782	9786	9791	9795	9800	9805	9809	9814	9818	0 1 1	2 2 3	3 4 4
96	9823	9827	9832	9836	9841	9845	9850	9854	9859	9863	0 1 1	2 2 3	3 4 4
97	9868	9872	9877	9881	9886	9890	9894	9899	9903	9908	0 1 1	2 2 3	3 4 4
98	9912	9917	9921	9926	9930	9934	9939	9943	9948	9952	0 1 1	2 2 3	3 4 4
99	9956	9961	9965	9969	9974	9978	9983	9987	9991	9996	0 1 1	2 2 3	3 3 4

ANTILOGARITHMS

	0	1	2	3	4	5	6	7	8	9	1 2 3	4 5 6	7 8 9
00	1000	1002	1005	1007	1009	1012	1014	1016	1019	1021	0 0 1	1 1 1	2 2 2
01	1023	1026	1028	1030	1033	1035	1038	1040	1042	1045	0 0 1	1 1 1	2 2 2
02	1047	1050	1052	1054	1057	1059	1062	1064	1067	1069	0 0 1	1 1 1	2 2 2
03	1072	1074	1076	1079	1081	1084	1086	1089	1091	1094	0 0 1	1 1 1	2 2 2
04	1096	1099	1102	1104	1107	1109	1112	1114	1117	1119	0 1 1	1 1 2	2 2 2
05	1122	1125	1127	1130	1132	1135	1138	1140	1143	1146	0 1 1	1 1 2	2 2 2
06	1148	1151	1153	1156	1159	1161	1164	1167	1169	1172	0 1 1	1 1 2	2 2 2
07	1175	1178	1180	1183	1186	1189	1191	1194	1197	1199	0 1 1	1 1 2	2 2 2
08	1202	1205	1208	1211	1213	1216	1219	1222	1225	1227	0 1 1	1 1 2	2 2 3
09	1230	1233	1236	1239	1242	1245	1247	1250	1253	1256	0 1 1	1 1 2	2 2 3
10	1259	1262	1265	1268	1271	1274	1276	1279	1282	1285	0 1 1	1 1 2	2 2 3
11	1288	1291	1294	1297	1300	1303	1306	1309	1312	1315	0 1 1	1 1 2	2 2 3
12	1318	1321	1324	1327	1330	1334	1337	1340	1343	1346	0 1 1	1 1 2	2 2 3
13	1349	1352	1355	1358	1361	1365	1368	1371	1374	1377	0 1 1	1 1 2	2 2 3
14	1380	1384	1387	1390	1393	1396	1400	1403	1406	1409	0 1 1	1 1 2	2 3 3
15	1413	1416	1419	1422	1426	1429	1432	1435	1439	1442	0 1 1	1 1 2	2 3 3
16	1445	1449	1452	1455	1459	1462	1466	1469	1472	1476	0 1 1	1 1 2	2 3 3
17	1479	1483	1486	1489	1493	1496	1500	1503	1507	1510	0 1 1	1 1 2	2 3 3
18	1514	1517	1521	1524	1528	1531	1535	1538	1542	1545	0 1 1	1 1 2	2 3 3
19	1549	1552	1556	1560	1563	1567	1570	1574	1578	1581	0 1 1	1 1 2	2 3 3
20	1585	1589	1592	1596	1600	1603	1607	1611	1614	1618	0 1 1	1 1 2	2 3 3
21	1622	1626	1629	1633	1637	1641	1644	1648	1652	1656	0 1 1	1 1 2	2 3 3
22	1660	1663	1667	1671	1675	1679	1683	1687	1690	1694	0 1 1	1 1 2	2 3 3
23	1698	1702	1706	1710	1714	1718	1722	1726	1730	1734	0 1 1	1 1 2	2 3 4
24	1738	1742	1746	1750	1754	1758	1762	1766	1770	1774	0 1 1	1 1 2	2 3 4
25	1778	1782	1786	1791	1795	1799	1803	1807	1811	1816	0 1 1	1 1 2	2 3 4
26	1820	1824	1828	1832	1837	1841	1845	1849	1854	1858	0 1 1	1 1 2	2 3 4
27	1862	1866	1871	1875	1879	1884	1888	1892	1897	1901	0 1 1	1 1 2	2 3 4
28	1905	1910	1914	1919	1923	1928	1932	1936	1941	1945	0 1 1	1 1 2	2 3 4
29	1950	1954	1959	1963	1968	1972	1977	1982	1986	1991	0 1 1	1 1 2	2 3 4
30	1995	2000	2004	2009	2014	2018	2023	2028	2032	2037	0 1 1	1 1 2	2 3 4
31	2042	2046	2051	2056	2061	2065	2070	2075	2080	2084	0 1 1	1 1 2	2 3 4
32	2089	2094	2099	2104	2109	2113	2118	2123	2128	2133	0 1 1	1 1 2	2 3 4
33	2138	2143	2148	2153	2158	2163	2168	2173	2178	2183	0 1 1	1 1 2	2 3 4
34	2188	2193	2198	2203	2208	2213	2218	2223	2228	2234	1 1 2	2 3 3	4 4 5
35	2239	2244	2249	2254	2259	2265	2270	2275	2280	2286	1 1 2	2 3 3	4 4 5
36	2291	2296	2301	2307	2312	2317	2323	2328	2333	2339	1 1 2	2 3 3	4 4 5
37	2344	2350	2355	2360	2366	2371	2377	2382	2388	2393	1 1 2	2 3 3	4 4 5
38	2399	2404	2410	2415	2421	2427	2432	2438	2443	2449	1 1 2	2 3 3	4 4 5
39	2455	2460	2466	2472	2477	2483	2489	2495	2500	2506	1 1 2	2 3 3	4 5 5
40	2512	2518	2523	2529	2535	2541	2547	2553	2559	2564	1 1 2	2 3 4	4 5 5
41	2570	2576	2582	2588	2594	2600	2606	2612	2618	2624	1 1 2	2 3 4	4 5 5
42	2630	2636	2642	2649	2655	2661	2667	2673	2679	2685	1 1 2	2 3 4	4 5 6
43	2692	2698	2704	2710	2716	2723	2729	2735	2742	2748	1 1 2	2 3 4	4 5 6
44	2754	2761	2767	2773	2780	2786	2793	2799	2805	2812	1 1 2	2 3 4	4 5 6
45	2818	2825	2831	2838	2844	2851	2858	2864	2871	2877	1 1 2	2 3 4	5 5 6
46	2884	2891	2897	2904	2911	2917	2924	2931	2938	2944	1 1 2	2 3 4	5 5 6
47	2951	2958	2965	2972	2979	2985	2992	2999	3006	3013	1 1 2	2 3 4	5 5 6
48	3020	3027	3034	3041	3048	3055	3062	3069	3076	3083	1 1 2	2 3 4	5 6 6
49	3090	3097	3105	3112	3119	3126	3133	3141	3148	3155	1 1 2	2 3 4	5 6 6

ANTILOGARITHMS

	0	1	2	3	4	5	6	7	8	9	1 2 3	4	5	6	7	8	9
50	3162	3170	3177	3184	3192	3199	3206	3214	3221	3228	1 1 2	3	4	4	5	6	7
51	3236	3243	3251	3258	3266	3273	3281	3289	3296	3304	1 2 2	3	4	5	5	6	7
52	3311	3319	3327	3334	3342	3350	3357	3365	3373	3381	1 2 2	3	4	5	5	6	7
53	3388	3396	3404	3412	3420	3428	3436	3443	3451	3459	1 2 2	3	4	5	6	6	7
54	3467	3475	3483	3491	3499	3508	3516	3524	3532	3540	1 2 2	3	4	5	6	6	7
55	3548	3556	3565	3573	3581	3589	3597	3606	3614	3622	1 2 2	3	4	5	6	7	7
56	3631	3639	3648	3656	3664	3673	3681	3690	3698	3707	1 2 3	3	4	5	6	7	8
57	3715	3724	3733	3741	3750	3758	3767	3776	3784	3793	1 2 3	3	4	5	6	7	8
58	3802	3811	3819	3828	3837	3846	3855	3864	3873	3882	1 2 3	4	4	5	6	7	8
59	3890	3899	3908	3917	3926	3936	3945	3954	3963	3972	1 2 3	4	5	5	6	7	8
60	3981	3990	3999	4009	4018	4027	4036	4046	4055	4064	1 2 3	4	5	6	6	7	8
61	4074	4083	4093	4102	4111	4121	4130	4140	4150	4159	1 2 3	4	5	6	7	8	9
62	4169	4178	4188	4198	4207	4217	4227	4236	4246	4256	1 2 3	4	5	6	7	8	9
63	4266	4276	4285	4295	4305	4315	4325	4335	4345	4355	1 2 3	4	5	6	7	8	9
64	4365	4375	4385	4395	4406	4416	4426	4436	4446	4457	1 2 3	4	5	6	7	8	9
65	4467	4477	4487	4498	4508	4519	4529	4539	4550	4560	1 2 3	4	5	6	7	8	9
66	4571	4581	4592	4603	4613	4624	4634	4645	4656	4667	1 2 3	4	5	6	7	9	10
67	4677	4688	4699	4710	4721	4732	4742	4753	4764	4775	1 2 3	4	5	6	7	8	9
68	4786	4797	4808	4819	4831	4842	4853	4864	4875	4887	1 2 3	4	6	7	8	9	10
69	4898	4909	4920	4932	4943	4955	4966	4977	4989	5000	1 2 3	5	6	7	8	9	10
70	5012	5023	5035	5047	5058	5070	5082	5093	5105	5117	1 2 4	5	6	7	8	9	11
71	5129	5140	5152	5164	5176	5188	5200	5212	5224	5236	1 2 4	5	6	7	8	10	11
72	5248	5260	5272	5284	5297	5309	5321	5333	5346	5358	1 2 4	5	6	7	9	10	11
73	5370	5383	5395	5408	5420	5433	5445	5458	5470	5483	1 3 4	5	6	8	9	10	11
74	5495	5508	5521	5534	5546	5559	5572	5585	5598	5610	1 3 4	5	6	8	9	10	12
75	5623	5636	5649	5662	5675	5689	5702	5715	5728	5741	1 3 4	5	7	8	9	10	12
76	5754	5768	5781	5794	5808	5821	5834	5848	5861	5875	1 3 4	5	7	8	9	11	12
77	5888	5902	5916	5929	5943	5957	5970	5984	5998	6012	1 3 4	5	7	8	10	11	12
78	6026	6039	6053	6067	6081	6095	6109	6124	6138	6152	1 3 4	6	7	8	10	11	13
79	6166	6180	6194	6209	6223	6237	6252	6266	6281	6295	1 3 4	6	7	9	10	11	13
80	6310	6324	6339	6353	6368	6383	6397	6412	6427	6442	1 3 4	6	7	9	10	12	13
81	6457	6471	6486	6501	6516	6531	6546	6561	6577	6592	2 3 5	6	8	9	11	12	14
82	6607	6622	6637	6653	6668	6683	6699	6714	6730	6745	2 3 5	6	8	9	11	12	14
83	6761	6776	6792	6808	6823	6839	6855	6871	6887	6902	2 3 5	6	8	9	11	13	14
84	6918	6934	6950	6966	6982	6998	7015	7031	7047	7063	2 3 5	6	8	10	11	13	15
85	7079	7096	7112	7129	7145	7161	7178	7194	7211	7228	2 3 5	7	8	10	12	13	15
86	7244	7261	7278	7295	7311	7328	7345	7362	7379	7396	2 3 5	7	8	10	12	13	15
87	7413	7430	7447	7464	7482	7499	7516	7534	7551	7568	2 3 5	7	9	10	12	14	16
88	7586	7603	7621	7638	7656	7674	7691	7709	7727	7745	2 4 5	7	9	11	12	14	16
89	7762	7780	7798	7816	7834	7852	7870	7889	7907	7925	2 4 5	7	9	11	13	14	16
90	7943	7962	7980	7998	8017	8035	8054	8072	8091	8110	2 4 6	7	9	11	13	15	17
91	8128	8147	8166	8185	8204	8222	8241	8260	8279	8299	2 4 6	8	9	11	13	15	17
92	8318	8337	8356	8375	8395	8414	8433	8453	8472	8492	2 4 6	8	10	12	14	15	17
93	8511	8531	8551	8570	8590	8610	8630	8650	8670	8690	2 4 6	8	10	12	14	16	18
94	8710	8730	8750	8770	8790	8810	8831	8851	8872	8892	2 4 6	8	10	12	14	16	18
95	8913	8933	8954	8974	8995	9016	9036	9057	9078	9099	2 4 6	8	10	12	15	17	19
96	9120	9141	9162	9183	9204	9226	9247	9268	9290	9311	2 4 6	8	11	13	15	17	19
97	9333	9354	9376	9397	9419	9441	9462	9484	9506	9528	2 4 7	9	11	13	15	17	20
98	9550	9572	9594	9616	9638	9661	9683	9705	9727	9750	2 4 7	9	11	13	16	18	20
99	9772	9795	9817	9840	9863	9886	9908	9931	9954	9977	2 5 7	9	11	14	16	18	20

NATURAL SINES

Degrees.	0°	6'	12'	18'	24'	30'	36'	42'	48'	54'	Mean Differences.				
	0°.0	0°.1	0°.2	0°.3	0°.4	0°.5	0°.6	0°.7	0°.8	0°.9	1	2	3	4	5
0	.0000	.0017	.0035	.0052	.0070	.0087	.0105	.0122	.0140	.0157	3	6	9	12	15
1	.0175	.0192	.0209	.0227	.0244	.0262	.0279	.0297	.0314	.0332	3	6	9	12	15
2	.0349	.0366	.0384	.0401	.0419	.0436	.0454	.0471	.0488	.0506	3	6	9	12	15
3	.0523	.0541	.0558	.0576	.0593	.0610	.0628	.0645	.0663	.0680	3	6	9	12	15
4	.0698	.0715	.0732	.0750	.0767	.0785	.0802	.0819	.0837	.0854	3	6	9	12	15
5	.0872	.0889	.0906	.0924	.0941	.0958	.0976	.0993	.1011	.1028	3	6	9	12	14
6	.1045	.1063	.1080	.1097	.1115	.1132	.1149	.1167	.1184	.1201	3	6	9	12	14
7	.1219	.1236	.1253	.1271	.1288	.1305	.1323	.1340	.1357	.1374	3	6	9	12	14
8	.1392	.1409	.1426	.1444	.1461	.1478	.1495	.1513	.1530	.1547	3	6	9	12	14
9	.1564	.1582	.1599	.1616	.1633	.1650	.1668	.1685	.1702	.1719	3	6	9	12	14
10	.1736	.1754	.1771	.1788	.1805	.1822	.1840	.1857	.1874	.1891	3	6	9	12	14
11	.1908	.1925	.1942	.1959	.1977	.1994	.2011	.2028	.2045	.2062	3	6	9	11	14
12	.2079	.2096	.2113	.2130	.2147	.2164	.2181	.2198	.2215	.2232	3	6	9	11	14
13	.2250	.2267	.2284	.2300	.2317	.2334	.2351	.2368	.2385	.2402	3	6	8	11	14
14	.2419	.2436	.2453	.2470	.2487	.2504	.2521	.2538	.2554	.2571	3	6	8	11	14
15	.2588	.2605	.2622	.2639	.2656	.2672	.2689	.2706	.2723	.2740	3	6	8	11	14
16	.2756	.2773	.2790	.2807	.2823	.2840	.2857	.2874	.2890	.2907	3	6	8	11	14
17	.2924	.2940	.2957	.2974	.2990	.3007	.3024	.3040	.3057	.3074	3	6	8	11	14
18	.3090	.3107	.3123	.3140	.3156	.3173	.3190	.3206	.3223	.3239	3	6	8	11	14
19	.3256	.3272	.3289	.3305	.3322	.3338	.3355	.3371	.3387	.3404	3	5	8	11	14
20	.3420	.3437	.3453	.3469	.3486	.3502	.3518	.3535	.3551	.3567	3	5	8	11	14
21	.3584	.3600	.3616	.3633	.3649	.3665	.3681	.3697	.3714	.3730	3	5	8	11	14
22	.3746	.3762	.3778	.3795	.3811	.3827	.3843	.3859	.3875	.3891	3	5	8	11	14
23	.3907	.3923	.3939	.3955	.3971	.3987	.4003	.4019	.4035	.4051	3	5	8	11	14
24	.4067	.4083	.4099	.4115	.4131	.4147	.4163	.4179	.4195	.4210	3	5	8	11	13
25	.4226	.4242	.4258	.4274	.4289	.4305	.4321	.4337	.4352	.4368	3	5	8	11	13
26	.4384	.4399	.4415	.4431	.4446	.4462	.4478	.4493	.4509	.4524	3	5	8	10	13
27	.4540	.4555	.4571	.4586	.4602	.4617	.4633	.4648	.4664	.4679	3	5	8	10	13
28	.4695	.4710	.4726	.4741	.4756	.4772	.4787	.4802	.4818	.4833	3	5	8	10	13
29	.4848	.4863	.4879	.4894	.4909	.4924	.4939	.4955	.4970	.4985	3	5	8	10	13
30	.5000	.5015	.5030	.5045	.5060	.5075	.5090	.5105	.5120	.5135	3	5	8	10	13
31	.5150	.5165	.5180	.5195	.5210	.5225	.5240	.5255	.5270	.5284	2	5	7	10	12
32	.5299	.5314	.5329	.5344	.5358	.5373	.5388	.5402	.5417	.5432	2	5	7	10	12
33	.5446	.5461	.5476	.5490	.5505	.5519	.5534	.5548	.5563	.5577	2	5	7	10	12
34	.5592	.5606	.5621	.5635	.5650	.5664	.5678	.5693	.5707	.5721	2	5	7	10	12
35	.5736	.5750	.5764	.5779	.5793	.5807	.5821	.5835	.5850	.5864	2	5	7	10	12
36	.5878	.5892	.5906	.5920	.5934	.5948	.5962	.5976	.5990	.6004	2	5	7	9	12
37	.6018	.6032	.6046	.6060	.6074	.6088	.6101	.6115	.6129	.6143	2	5	7	9	12
38	.6157	.6170	.6184	.6198	.6211	.6225	.6239	.6252	.6266	.6280	2	5	7	9	11
39	.6293	.6307	.6320	.6334	.6347	.6361	.6374	.6388	.6401	.6414	2	4	7	9	11
40	.6428	.6441	.6455	.6468	.6481	.6494	.6508	.6521	.6534	.6547	2	4	7	9	11
41	.6561	.6574	.6587	.6600	.6613	.6626	.6639	.6652	.6665	.6678	2	4	7	9	11
42	.6691	.6704	.6717	.6730	.6743	.6756	.6769	.6782	.6794	.6807	2	4	6	9	11
43	.6820	.6833	.6845	.6858	.6871	.6884	.6896	.6909	.6921	.6934	2	4	6	8	11
44	.6947	.6959	.6972	.6984	.6997	.7009	.7022	.7034	.7046	.7059	2	4	6	8	10

NATURAL SINES

Degrees.	0° 0'	0° 1'	0° 2'	0° 3'	0° 4'	0° 5'	0° 6'	0° 7'	0° 8'	0° 9'	Mean Differences.				
											1	2	3	4	5
45	.7071	.7083	.7096	.7108	.7120	.7133	.7145	.7157	.7169	.7181	2	4	6	8	10
46	.7193	.7206	.7218	.7230	.7242	.7254	.7266	.7278	.7290	.7302	2	4	6	8	10
47	.7314	.7325	.7337	.7349	.7361	.7373	.7385	.7396	.7408	.7420	2	4	6	8	10
48	.7431	.7443	.7455	.7466	.7478	.7490	.7501	.7513	.7524	.7536	2	4	6	8	10
49	.7547	.7558	.7570	.7581	.7593	.7604	.7615	.7627	.7638	.7649	2	4	6	8	9
50	.7660	.7672	.7683	.7694	.7705	.7716	.7727	.7738	.7749	.7760	2	4	6	7	9
51	.7771	.7782	.7793	.7804	.7815	.7826	.7837	.7848	.7859	.7869	2	4	5	7	9
52	.7880	.7891	.7902	.7912	.7923	.7934	.7944	.7955	.7965	.7976	2	4	5	7	9
53	.7986	.7997	.8007	.8018	.8028	.8039	.8049	.8059	.8070	.8080	2	3	5	7	9
54	.8090	.8100	.8111	.8121	.8131	.8141	.8151	.8161	.8171	.8181	2	3	5	7	8
55	.8192	.8202	.8211	.8221	.8231	.8241	.8251	.8261	.8271	.8281	2	3	5	7	8
56	.8290	.8300	.8310	.8320	.8329	.8339	.8348	.8358	.8368	.8377	2	3	5	6	8
57	.8387	.8396	.8406	.8415	.8425	.8434	.8443	.8453	.8462	.8471	2	3	5	6	8
58	.8480	.8490	.8499	.8508	.8517	.8526	.8536	.8545	.8554	.8563	2	3	5	6	8
59	.8572	.8581	.8590	.8599	.8607	.8616	.8625	.8634	.8643	.8652	1	3	4	6	7
60	.8660	.8669	.8678	.8686	.8695	.8704	.8712	.8721	.8729	.8738	1	3	4	6	7
61	.8746	.8755	.8763	.8771	.8780	.8788	.8796	.8805	.8813	.8821	1	3	4	6	7
62	.8829	.8838	.8846	.8854	.8862	.8870	.8878	.8886	.8894	.8902	1	3	4	5	7
63	.8910	.8918	.8926	.8934	.8942	.8949	.8957	.8965	.8973	.8980	1	3	4	5	6
64	.8988	.8996	.9003	.9011	.9018	.9026	.9033	.9041	.9048	.9056	1	3	4	5	6
65	.9063	.9070	.9078	.9085	.9092	.9100	.9107	.9114	.9121	.9128	1	2	4	5	6
66	.9135	.9143	.9150	.9157	.9164	.9171	.9178	.9184	.9191	.9198	1	2	3	5	6
67	.9205	.9212	.9219	.9225	.9232	.9239	.9245	.9252	.9259	.9265	1	2	3	4	6
68	.9272	.9278	.9285	.9291	.9298	.9304	.9311	.9317	.9323	.9330	1	2	3	4	5
69	.9336	.9342	.9348	.9354	.9361	.9367	.9373	.9379	.9385	.9391	1	2	3	4	5
70	.9397	.9403	.9409	.9415	.9421	.9426	.9432	.9438	.9444	.9449	1	2	3	4	5
71	.9455	.9461	.9466	.9472	.9478	.9483	.9489	.9494	.9500	.9505	1	2	3	4	5
72	.9511	.9516	.9521	.9527	.9532	.9537	.9542	.9548	.9553	.9558	1	2	3	3	4
73	.9563	.9568	.9573	.9578	.9583	.9588	.9593	.9598	.9603	.9608	1	2	2	3	4
74	.9613	.9617	.9622	.9627	.9632	.9636	.9641	.9646	.9650	.9655	1	2	2	3	4
75	.9659	.9664	.9668	.9673	.9677	.9681	.9686	.9690	.9694	.9699	1	1	2	3	4
76	.9703	.9707	.9711	.9715	.9720	.9724	.9728	.9732	.9736	.9740	1	1	2	3	3
77	.9744	.9748	.9751	.9755	.9759	.9763	.9767	.9770	.9774	.9778	1	1	2	3	3
78	.9781	.9785	.9789	.9792	.9796	.9799	.9803	.9806	.9810	.9813	1	1	2	2	3
79	.9816	.9820	.9823	.9826	.9829	.9833	.9836	.9839	.9842	.9845	1	1	2	2	3
80	.9848	.9851	.9854	.9857	.9860	.9863	.9866	.9869	.9871	.9874	0	1	1	2	2
81	.9877	.9880	.9882	.9885	.9888	.9890	.9893	.9895	.9898	.9900	0	1	1	2	2
82	.9903	.9905	.9907	.9910	.9912	.9914	.9917	.9919	.9921	.9923	0	1	1	2	2
83	.9925	.9928	.9930	.9932	.9934	.9936	.9938	.9940	.9942	.9943	0	1	1	1	2
84	.9945	.9947	.9949	.9951	.9952	.9954	.9956	.9957	.9959	.9960	0	1	1	1	2
85	.9962	.9963	.9965	.9966	.9968	.9969	.9971	.9972	.9973	.9974	0	0	1	1	1
86	.9976	.9977	.9978	.9979	.9980	.9981	.9982	.9983	.9984	.9985	0	0	1	1	1
87	.9986	.9987	.9988	.9989	.9990	.9990	.9991	.9992	.9993	.9993	0	0	0	1	1
88	.9994	.9995	.9995	.9996	.9996	.9997	.9997	.9997	.9998	.9998	0	0	0	0	0
89	.9998	.9999	.9999	.9999	.9999	1-000	1-000	1-000	1-000	1-000	0	0	0	0	0
90	1-000														

NATURAL COSINES

Degrees.	0'	6'	12'	18'	24'	30'	36'	42'	48'	54'	Mean Differences.				
	0°-0	0°-1	0°-2	0°-3	0°-4	0°-5	0°-6	0°-7	0°-8	0°-9	1	2	3	4	5
0	1.000	1.000	1.000	1.000	1.000	1.000	.9999	.9999	.9999	.9999	0	0	0	0	0
1	.9998	.9998	.9998	.9997	.9997	.9997	.9996	.9996	.9995	.9995	0	0	0	0	0
2	.9994	.9993	.9993	.9992	.9991	.9990	.9990	.9989	.9988	.9987	0	0	0	1	1
3	.9986	.9985	.9984	.9983	.9982	.9981	.9980	.9979	.9978	.9977	0	0	1	1	1
4	.9976	.9974	.9973	.9972	.9971	.9969	.9968	.9966	.9965	.9963	0	0	1	1	1
5	.9962	.9960	.9959	.9957	.9956	.9954	.9952	.9951	.9949	.9947	0	1	1	1	2
6	.9945	.9943	.9942	.9940	.9938	.9936	.9934	.9932	.9930	.9928	0	1	1	1	2
7	.9925	.9923	.9921	.9919	.9917	.9914	.9912	.9910	.9907	.9905	0	1	1	2	2
8	.9903	.9900	.9898	.9895	.9893	.9890	.9888	.9885	.9882	.9880	0	1	1	2	2
9	.9877	.9874	.9871	.9869	.9866	.9863	.9860	.9857	.9854	.9851	0	1	1	2	2
10	.9848	.9845	.9842	.9839	.9836	.9833	.9829	.9826	.9823	.9820	1	1	2	2	3
11	.9816	.9813	.9810	.9806	.9803	.9799	.9796	.9792	.9789	.9785	1	1	2	2	3
12	.9781	.9778	.9774	.9770	.9767	.9763	.9759	.9755	.9751	.9748	1	1	2	3	3
13	.9744	.9740	.9736	.9732	.9728	.9724	.9720	.9715	.9711	.9707	1	1	2	3	3
14	.9703	.9699	.9694	.9690	.9686	.9681	.9677	.9673	.9668	.9664	1	1	2	3	4
15	.9659	.9655	.9650	.9646	.9641	.9636	.9632	.9627	.9622	.9617	1	2	2	3	4
16	.9613	.9608	.9603	.9598	.9593	.9588	.9583	.9578	.9573	.9568	1	2	2	3	4
17	.9563	.9558	.9553	.9548	.9542	.9537	.9532	.9527	.9521	.9516	1	2	3	3	4
18	.9511	.9505	.9500	.9494	.9489	.9483	.9478	.9472	.9466	.9461	1	2	3	4	5
19	.9455	.9449	.9444	.9438	.9432	.9426	.9421	.9415	.9409	.9403	1	2	3	4	5
20	.9397	.9391	.9385	.9379	.9373	.9367	.9361	.9354	.9348	.9342	1	2	3	4	5
21	.9336	.9330	.9323	.9317	.9311	.9304	.9298	.9291	.9285	.9278	1	2	3	4	5
22	.9272	.9265	.9259	.9252	.9245	.9239	.9232	.9225	.9219	.9212	1	2	3	4	6
23	.9205	.9198	.9191	.9184	.9178	.9171	.9164	.9157	.9150	.9143	1	2	3	5	6
24	.9135	.9128	.9121	.9114	.9107	.9100	.9092	.9085	.9078	.9070	1	2	4	5	6
25	.9063	.9056	.9048	.9041	.9033	.9026	.9018	.9011	.9003	.8996	1	3	4	5	6
26	.8988	.8980	.8973	.8965	.8957	.8949	.8942	.8934	.8926	.8918	1	3	4	5	6
27	.8910	.8902	.8894	.8886	.8878	.8870	.8862	.8854	.8846	.8838	1	3	4	5	7
28	.8829	.8821	.8813	.8805	.8796	.8788	.8780	.8771	.8763	.8755	1	3	4	6	7
29	.8746	.8738	.8729	.8721	.8712	.8704	.8695	.8686	.8678	.8669	1	3	4	6	7
30	.8660	.8652	.8643	.8634	.8625	.8616	.8607	.8599	.8590	.8581	1	3	4	6	7
31	.8572	.8563	.8554	.8545	.8536	.8526	.8517	.8508	.8499	.8490	2	3	5	6	8
32	.8480	.8471	.8462	.8453	.8443	.8434	.8425	.8415	.8406	.8396	2	3	5	6	8
33	.8387	.8377	.8368	.8358	.8348	.8339	.8329	.8320	.8310	.8300	2	3	5	6	8
34	.8290	.8281	.8271	.8261	.8251	.8241	.8231	.8221	.8211	.8202	2	3	5	7	8
35	.8192	.8181	.8171	.8161	.8151	.8141	.8131	.8121	.8111	.8100	2	3	5	7	8
36	.8090	.8080	.8070	.8059	.8049	.8039	.8028	.8018	.8007	.7997	2	3	5	7	9
37	.7986	.7976	.7965	.7955	.7944	.7934	.7923	.7912	.7902	.7891	2	4	5	7	9
38	.7880	.7869	.7859	.7848	.7837	.7826	.7815	.7804	.7793	.7782	2	4	5	7	9
39	.7771	.7760	.7749	.7738	.7727	.7716	.7705	.7694	.7683	.7672	2	4	6	7	9
40	.7660	.7649	.7638	.7627	.7615	.7604	.7593	.7581	.7570	.7559	2	4	6	8	9
41	.7547	.7536	.7524	.7513	.7501	.7490	.7478	.7466	.7455	.7443	2	4	6	8	10
42	.7431	.7420	.7408	.7396	.7385	.7373	.7361	.7349	.7337	.7325	2	4	6	8	10
43	.7314	.7302	.7290	.7278	.7266	.7254	.7242	.7230	.7218	.7206	2	4	6	8	10
44	.7193	.7181	.7169	.7157	.7145	.7133	.7120	.7108	.7096	.7083	2	4	6	8	10

NATURAL COSINES

Degrees.	0°	6'	12'	18'	24'	30'	36'	42'	48'	54'	Mean Differences.				
	0° 0	0° 1	0° 2	0° 3	0° 4	0° 5	0° 6	0° 7	0° 8	0° 9	1	2	3	4	5
45	.7071	7059	7046	7034	7022	7009	6997	6984	6972	6959	2	4	6	8	10
46	.6947	6934	6921	6909	6896	6884	6871	6858	6845	6833	2	4	6	8	11
47	.6820	6807	6794	6782	6769	6756	6743	6730	6717	6704	2	4	6	9	11
48	.6691	6678	6665	6652	6639	6626	6613	6600	6587	6574	2	4	7	9	11
49	.6561	6547	6534	6521	6508	6494	6481	6468	6455	6441	2	4	7	9	11
50	.6428	6414	6401	6388	6374	6361	6347	6334	6320	6307	2	4	7	9	11
51	.6293	6280	6266	6252	6239	6225	6211	6198	6184	6170	2	5	7	9	11
52	.6157	6143	6129	6115	6101	6088	6074	6060	6046	6032	2	5	7	9	12
53	.6018	6004	5990	5976	5962	5948	5934	5920	5906	5892	2	5	7	9	12
54	.5878	5864	5850	5835	5821	5807	5793	5779	5764	5750	2	5	7	9	12
55	.5736	5721	5707	5693	5678	5664	5650	5635	5621	5606	2	5	7	10	12
56	.5592	5577	5563	5548	5534	5519	5505	5490	5476	5461	2	5	7	10	12
57	.5446	5432	5417	5402	5388	5373	5358	5344	5329	5314	2	5	7	10	12
58	.5299	5284	5270	5255	5240	5225	5210	5195	5180	5165	2	5	7	10	12
59	.5150	5135	5120	5105	5090	5075	5060	5045	5030	5015	3	5	8	10	13
60	.5000	4985	4970	4955	4939	4924	4909	4894	4879	4863	3	5	8	10	13
61	.4848	4833	4818	4802	4787	4772	4756	4741	4726	4710	3	5	8	10	13
62	.4695	4679	4664	4648	4633	4617	4602	4586	4571	4555	3	5	8	10	13
63	.4540	4524	4509	4493	4478	4462	4446	4431	4415	4399	3	5	8	10	13
64	.4384	4368	4352	4337	4321	4305	4289	4274	4258	4242	3	5	8	11	13
65	.4226	4210	4195	4179	4163	4147	4131	4115	4099	4083	3	5	8	11	13
66	.4067	4051	4035	4019	4003	3987	3971	3955	3939	3923	3	5	8	11	14
67	.3907	3891	3875	3859	3843	3827	3811	3795	3778	3762	3	5	8	11	14
68	.3746	3730	3714	3697	3681	3665	3649	3633	3616	3600	3	5	8	11	14
69	.3584	3567	3551	3535	3518	3502	3486	3469	3453	3437	3	5	8	11	14
70	.3420	3404	3387	3371	3355	3338	3322	3305	3289	3273	3	5	8	11	14
71	.3256	3239	3223	3206	3190	3173	3156	3140	3123	3107	3	6	8	11	14
72	.3090	3074	3057	3040	3024	3007	2990	2974	2957	2940	3	6	8	11	14
73	.2924	2907	2890	2874	2857	2840	2823	2807	2790	2773	3	6	8	11	14
74	.2756	2740	2723	2706	2689	2672	2656	2639	2622	2605	3	6	8	11	14
75	.2588	2571	2554	2538	2521	2504	2487	2470	2453	2436	3	6	8	11	14
76	.2419	2402	2385	2368	2351	2334	2317	2300	2284	2267	3	6	8	11	14
77	.2250	2233	2215	2198	2181	2164	2147	2130	2113	2096	3	6	9	11	14
78	.2079	2062	2045	2028	2011	1994	1977	1959	1942	1925	3	6	9	11	14
79	.1908	1891	1874	1857	1840	1822	1805	1788	1771	1754	3	6	9	11	14
80	.1736	1719	1702	1685	1668	1650	1633	1616	1599	1582	3	6	9	12	14
81	.1564	1547	1530	1513	1495	1478	1461	1444	1426	1409	3	6	9	12	14
82	.1392	1374	1357	1340	1323	1305	1288	1271	1253	1236	3	6	9	12	14
83	.1219	1201	1184	1167	1149	1132	1115	1097	1080	1063	3	6	9	12	14
84	.1045	1028	1011	0993	0976	0958	0941	0924	0906	0889	3	6	9	12	14
85	.0872	0854	0837	0819	0802	0785	0767	0750	0732	0715	3	6	9	12	15
86	.0698	0680	0663	0645	0628	0610	0593	0576	0558	0541	3	6	9	12	15
87	.0523	0506	0488	0471	0454	0436	0419	0401	0384	0366	3	6	9	12	15
88	.0349	0332	0314	0297	0279	0262	0244	0227	0209	0192	3	6	9	12	15
89	.0175	0157	0140	0122	0105	0087	0070	0052	0035	0017	3	6	9	12	15
90	.0000														

NATURAL TANGENTS

	0'	6'	12'	18'	30'	42'	48'	54'	Mean Differences.						
	0°-0	0°-1	0°-2	0°-3	0°-4	0°-5	0°-6	0°-7	0°-8	0°-9	1	2	3	4	5
	·0000	0017	0035	0052	0070	0087	0105		0140	0157	3	6	9	12	15
	·0175	0192	0209	0227	0244	0262	0279		0314	0332	3	6	9	12	15
	·0349	0367	0384	0402	0419	0437	0454		0489	0507	3	6	9	12	15
	·0524	0542	0559	0577	0594	0612	0629		0664	0682	3	6	9	12	15
	·0699	0717	0734	0752	0769	0787	0805		0840	0857	3	6	9	12	15
	·0875	0892	0910	0928	0945	0963	0981		1016	1033	3	6	9	12	15
	·1051	1069	1086	1104	1122	1139	1157		1192	1210	3	6	9	12	15
	·1228	1246	1263	1281	1299	1317	1334		1370	1388		6	9	12	15
	·1405	1423	1441	1459	1477	1495	1512		1548	1566		6	9	12	15
	·1584	1602	1620	1638	1655	1673	1691		1727	1745		6	9	12	15
10	·1763	1781	1799	1817	1835	1853	1871		1908	1926	3	6	9	12	15
11	·1944	1962	1980	1998	2016	2035	2053		2089	2107	3	6	9	12	15
12	·2126	2144	2162	2180	2199	2217	2235		2272	2290	3	6	9	12	15
13	·2309	2327	2345	2364	2382	2401	2419		2456	2475	3	6	9	12	15
14	·2493	2512	2530	2549	2568	2586	2605		2642	2661	3	6	9	12	16
15	·2679	2698	2717	2736	2754	2773	2792		2830	2849	3	6	9	13	16
16	·2867	2886	2905	2924	2943	2962	2981		3019	3038	3	6	9	13	16
17	·3057	3076	3096	3115	3134	3153	3172		3211	3230	3	6	10	13	16
18	·3249	3269	3288	3307	3327	3346	3365		3404	3424	3	6	10	13	16
19	·3443	3463	3482	3502	3522	3541	3561		3600	3620	3	7	10	13	16
20		3659	3679	3699	3719	3739	3759		3799	3819	3	7	10	13	17
21		3859	3879	3899	3919	3939	3959		4000	4020	3	7	10	13	17
22		4061	4081	4101	4122	4142	4163		4204	4224	3	7	10	14	17
23		4265	4286	4307	4327	4348	4369		4411	4431	3	7	10	14	17
24		4473	4494	4515	4536	4557	4578		4621	4642	4	7	11	14	18
25		4684	4706	4727	4748	4770	4791		4834	4856		7	11	14	18
26		4899	4921	4942	4964	4986	5008		5051	5073		7	11	15	18
27		5117	5139	5161	5184	5206	5228		5272	5295		7	11	15	18
28		5340	5362	5384	5407	5430	5452		5498	5520		8	11	15	19
29		5566	5589	5612	5635	5658	5681		5727	5750		8	12	15	19
30		5797	5820	5844	5867	5890	5914		5961	5985		8	12	16	20
31		6032	6056	6080	6104	6128	6152		6200	6224		8	12	16	20
32		6273	6297	6322	6346	6371	6395		6445	6469		8	12	16	20
33		6519	6544	6569	6594	6619	6644		6694	6720		8	13	17	21
34		6771	6796	6822	6847	6873	6899		6950	6976		9	13	17	21
35		7028	7054	7080	7107	7133	7159		7212	7239		9	13	18	22
36		7292	7319	7346	7373	7400	7427		7481	7508		9	14	18	23
37		7563	7590	7618	7646	7673	7701		7757	7785		9	14	18	23
38		7841	7869	7898	7926	7954	7983		8040	8069		9	14	19	24
		8127	8156	8185	8214	8243	8273		8332	8361	5	10	15	20	24
40		8421	8451	8481	8511	8541	8571		8632	8662	5	10	15	20	25
41		8724	8754	8785	8816	8847	8878		8941	8972	5	10	16	21	26
42		9036	9067	9099	9131	9163	9195		9260	9293	5	11	16	21	27
43		9358	9391	9424	9457	9490	9523		9590	9623	6	11	17	22	28
44		9691	9725	9759	9793	9827	9861		9930	9965	6	11	17	23	29

NATURAL TANGENTS

Degrees.	0°	6'	12'	18'	24'	30'	36'	42'	48'	54'	Mean Differences.				
	0°-0	0°-1	0°-2	0°-3	0°-4	0°-5	0°-6	0°-7	0°-8	0°-9	1	2	3	4	5
45	1-0000	0035	0070	0105	0141	0176	0212	0247	0283	0319	6	12	18	24	30
46	1-0355	0392	0428	0464	0501	0538	0575	0612	0649	0686	6	12	18	25	31
47	1-0724	0761	0799	0837	0875	0913	0951	0990	1028	1067	6	13	19	25	32
48	1-1106	1145	1184	1224	1263	1303	1343	1383	1423	1463	7	13	20	27	33
49	1-1504	1544	1585	1626	1667	1708	1750	1792	1833	1875	7	14	21	28	34
50	1-1918	1960	2002	2045	2088	2131	2174	2218	2261	2305	7	14	22	29	36
51	1-2349	2393	2437	2482	2527	2572	2617	2662	2708	2753	8	15	23	30	38
52	1-2799	2846	2892	2938	2985	3032	3079	3127	3175	3222	8	16	24	31	39
53	1-3270	3319	3367	3416	3465	3514	3564	3613	3663	3713	8	16	25	33	41
54	1-3764	3814	3865	3916	3968	4019	4071	4124	4176	4229	9	17	26	34	43
55	1-4281	4335	4388	4442	4496	4550	4605	4659	4715	4770	9	18	27	36	45
56	1-4826	4882	4938	4994	5051	5108	5166	5224	5282	5340	10	19	29	38	48
57	1-5399	5458	5517	5577	5637	5697	5757	5818	5880	5941	10	20	30	40	50
58	1-6003	6066	6128	6191	6255	6319	6383	6447	6512	6577	11	21	32	43	53
59	1-6643	6709	6775	6842	6909	6977	7045	7113	7182	7251	11	23	34	45	56
60	1-7321	7391	7461	7532	7603	7675	7747	7820	7893	7966	12	24	36	48	60
61	1-8040	8115	8190	8265	8341	8418	8495	8572	8650	8728	13	26	38	51	64
62	1-8807	8887	8967	9047	9128	9210	9292	9375	9458	9542	14	27	41	55	68
63	1-9626	9711	9797	9883	9970	2-0057	2-0145	2-0233	2-0323	2-0413	15	29	44	58	73
64	2-0503	0594	0686	0778	0872	0965	1060	1155	1251	1348	16	31	47	63	78
65	2-1445	1543	1642	1742	1842	1943	2045	2148	2251	2355	17	34	51	68	85
66	2-2460	2566	2673	2781	2889	2998	3109	3220	3332	3445	18	37	55	73	92
67	2-3559	3673	3789	3906	4023	4142	4262	4383	4504	4627	20	40	60	79	99
68	2-4751	4876	5002	5129	5257	5386	5517	5649	5782	5916	22	43	65	87	108
69	2-6051	6187	6325	6464	6605	6746	6889	7034	7179	7326	24	47	71	95	119
70	2-7475	7625	7776	7929	8083	8239	8397	8556	8716	8878	26	52	78	104	131
71	2-9042	9208	9375	9544	9714	9887	3-0061	3-0237	3-0415	3-0595	29	58	87	116	145
72	3-0777	0961	1146	1334	1524	1716	1910	2106	2305	2506	32	64	96	129	161
73	3-2709	2914	3122	3332	3544	3759	3977	4197	4420	4646	36	72	108	144	180
74	3-4874	5105	5339	5576	5816	6059	6305	6554	6806	7062	41	81	122	163	204
75	3-7321	7583	7848	8118	8391	8667	8947	9232	9520	9812	46	93	139	186	232
76	4-0108	0408	0713	1022	1335	1653	1976	2303	2635	2972	53	107	160	213	267
77	4-3315	3662	4015	4374	4737	5107	5483	5864	6252	6646	Mean differences cease to be sufficiently accurate.				
78	4-7046	7453	7867	8288	8716	9152	9594	5-0045	5-0504	5-0970					
79	5-1446	1929	2422	2924	3435	3955	4486	5026	5578	6140					
80	5-6713	7297	7894	8502	9124	9758	6-0405	6-1066	6-1742	6-2432					
81	6-3138	3859	4596	5350	6122	6912	7720	8548	9395	7-0264					
82	7-1154	2066	3002	3962	4947	5958	6996	8062	9158	8-0285					
83	8-1443	2636	3863	5126	6427	7769	9152	9-0579	9-2052	9-3572					
84	9-5144	9-677	9-845	10-02	10-20	10-39	10-58	10-78	10-99	11-20					
85	11-43	11-66	11-91	12-16	12-43	12-71	13-00	13-30	13-62	13-95					
86	14-30	14-67	15-06	15-46	15-89	16-35	16-83	17-34	17-89	18-46					
87	19-08	19-74	20-45	21-20	22-02	22-90	23-86	24-90	26-03	27-27					
88	28-64	30-14	31-82	33-69	35-80	38-19	40-92	44-07	47-74	52-08					
89	57-29	63-66	71-62	81-85	95-49	114-6	143-2	191-0	286-5	573-0					
90	∞														

INDEX

INDEX

Proper names in italics

- Abscissa, 9
- Absolute Instrument, 381, 475
- Absolute Temperature, 285, 297
- Absorption lines, 246
- A.C. *See* Alternating Current
- Acceleration, 51, 76, 102, 105, 106, 107-8, 114
 - angular, 114
 - due to gravity, 76, 106, 108, 111, 130, 131-3, 135-6
- Accommodation, 236
- Accumulator, 371, 372
- Accuracy of observations, 5, 264
- Acoustics, 162.
- Activity, units of, 76, 78, 85, 441-2
- Adjustment, normal, 234
 - of spectrometer, 241, 245
- Advantage, mechanical, 78-9
- Aerial, 495, 497, 501
- Air, expansion of, 280
 - thermometer, 282
- Alternating current, 451-3, 454, 462, 464
 - E.M.F., 451-3
- Altitude, 195
- Amber, 363
- Ammeter, 384, 481
 - attracted iron, 97, 384, 481
 - calibration of, 385
 - correction factor of, 387
 - hot wire, 384, 481
 - moving coil, 384, 482
 - shunt for, 481
- Ampere, the (or amp.), 381, 384, 433, 440
- Amplifier, 524, 527
- Amplitude, 123, 125
- Amaler*, 29
- Aneroid barometer, 141
- Angle, critical, 200
- Angle of contact, 157
- Angle of, prism, measurement of, 200, 242
 - minimum deviation, 199, 200, 243
- Ångström's unit (A.U.), 245, 563
- Angular and linear motion compared, 112, 114
- Angular, scale and vernier, 18
 - simple harmonic motion, 125
- Anion, 432
- Anode, 432
- Anticathode, 450
- Antilogarithmic tables, 506, 570-71
- Antinode, 167, 174
- Aperture, of mirror, 206; of lens, 212
- Apparent thickness, 202, 205
- Aqueous vapour, 318, 563
 - mass per litre, 322
- Archimedes, principles of, 42
- Area, measurement of, 27
- Armature, 456
- Arms of a balance, 12
 - of Wheatstone's bridge, 412
 - conjugate, 413; ratio, 419
- Arrestment of balance, 12, 15
- Astatic combination, 476
- Atmosphere, 137
 - aqueous vapour in, 318, 322
 - pressure of, 137-9; in absolute units, 138, 143
 - standard, 139
- Atom, 362
- Atomic energy, 362
 - nucleus, 362
 - number, 362, 566-7
 - weight, 362, 564, 566-7
- Atwood, George*, 109
- Atwood's machine, 108
 - pillar type, 109
 - ribbon pattern, 111
- A.U., angstrom unit, 245, 563
- Avogadro's constant, 561
- Axes of rotation, 112-14, 118-19, 560
- Axiom, 191
- Axis, magnetic, 327, 334
- Azimuth, 195
- Back E.M.F., 434
- Bakelite, 364, 556
- Balance, 12-16
 - arms, 12
 - ballistic, 103
 - hydrostatic, 43-4
 - magnetic, 346
 - null method, 5-6
 - spring, 96
 - of Jolly, 97
 - Wheatstone's bridge, 412, 417, 421
- Ballistic balance, 103
 - galvanometer, 451, 470, 478
- Bar, unit of pressure, 139
 - pendulum, 135

- Barometer, 138
 aneroid, 141
 Fortin's, 139
 U-tube, 139
 Barometer, correction for temperature, 142
Barton, E. H., 164, 176
 Base, time, 510
 Battery. *See* Cell
 Beam, Young's Modulus for, 91
 Beats, 175, 185, 468, 538
 Bench, optical, 224
 Bichromate cell, 372
Birge, Raymond T., 559, 561
Blackburn, H., 178
 Board of Trade unit, 440
Bohr, N., 362
 Boiling point or steam point, 265, 268, 272
 pure liquid, 271-2; solution, 272
 Bore of tube, measurement of 152, 269
 Box, Post-Office, 419
 Box, resistance, 385, 488
Boyle, Robert, 86, 145
 Boyle's Law, 137, 145, 149, 285
Branly, E., 493
 Bridge, Carey Foster's, 423
 Wheatstone's, 6, 411, 414
 Bright-emitter valve, 506
 British Imperial Measures, 560
 standard wire gauge, 564
 Bunsen burner, 294
 cell, 372
 photometer, 250

 C.G.S. units, 2, 10, 76, 106, 580
 Cadmium cell, 372
Caignard de la Tour, 171
 Calculations, 6
 Calibration of, ammeter, 385, 481-2
 planimeter, 33
 spectrometer, 245
 spring, 96
 thermometer, 269
 Callendar's apparatus, 310
 Callipers, inside and outside, 17
 vernier, 19
 Caloric, 264
 Calorie, 264, 310
 gram or small, 286
 kilogram or large, 287, 440-41
 Calorifer, 290
 Calorimeter, 287
 Calorimetry, 286
 correction for radiation, 291
 Candle-power, 247
 Candle, standard, 247
 Capacitance, 463, 470
 Capacitor, 465, 470
 Capacity, electric, 368-9, 470
 Capacity, thermal, 286
 Capacity of condenser, 368, 470
 Capillarity, 150

 Cardboard, thermal conductivity of, 307
 Care of cells, 372
 magnets, 336
 thermometers, 265, 272
 weights, 14
 Carey Foster's method, 423, 425, 426
 Cathetometer, 152
 Cathode, 432, 506
 Cathode Rays, 449, 504
 Cathode ray oscillograph, 179, 509
 tube, 509
 Cations, 432
 Caustic curve, 247
 Cell, electric, 253, 370, 371
 E.M.F. of. *See* Electromotive Force
 polarity of, 370, 374, 432, 490-91
 primary, 371
 resistance of. *See* Resistance
 secondary, 372, 405, 491
 Centimetre, the, 2, 10
 Centre, of gravity, 63, 65
 of inertia, 63, 65
 of oscillation, 134
 of suspension, 134
 optic, 212
 Characteristic curves of a diode, 516
 triode, 520, 525
 Charge, electric, 363-4, 367
 and potential, 367
 space-, 504
 Charles, Law of, 281, 285, 341
 Chemical action in cell, 371, 395
 in electrolysis, 432
 equivalent, 432
 Choking coil or choke, 519
 Circle, Area of, 28, 32
 Circular current, 378, 381
 Clark cell, 372
 Clocks, 24, 26
 Coefficient, of expansion, linear, 273, 562; cubical, 277-8; apparent, 280; of gases, 280, 284-5
 of friction, 91
 of mutual induction, 447
 of thermal conductivity, 304, 305-9, 562
 Coefficient, temperature, of resistance, 427, 564
 Coherer, 493, 494
 Coil, Ruhmkorff's, 448
 spinning, 452
 Coils for induction, 444
 Collimator, 241, 242, 245
 adjustment of, 242, 245
 Colour, 239, 246, 248
 of thin films, 254
 Column, positive, 449
 Combustion, 362
 Commutator, 383, 385, 452, 484
 Comparison of capacities, 470
 electromotive forces, 398, 401

- Comparison of magnetic fields, 338-9, 340-44, 347-348
 - resistances, 429
- Compass, beam, 17
 - needle, 328
- Composition of forces, 51
 - of harmonic vibrations, 176
 - of vectors, 51
- Compound-winding, 459
- Computation, graphic methods, 4, 9, 65, 69
- Condenser discharge, oscillatory nature of, 492
- Condenser, electric, 369, 447-8, 465, 492
 - electrolytic, 519
 - optical, 237-8
- Conductance, 368, 392, 411
- Conduction, electric, 366
- Conductivity, electric, 416
 - of a gas, 450
 - thermal, 304, 670
- Conductor, electric, 363
- Conjugate arms of network, 413
 - foci, 209, 214, 226-7
- Connecting an electric circuit, 372
- Consequent pole, 336
- Conservation of energy, 8, 11, 58, 77, 97-99, 104-5, 310
- Conservation of momentum, 102
- Constant of galvanometer, 382-3, 475
- Constants, mathematical, 559
 - physical, 561
- Contact angle, 157
- Continuous wave-trains, 495-9, 535
 - detection of, 530, 539
- Control magnet, 477
- Controlling field, 476
- Conventions of sign, 190, 210, 545
- Cooling, Laws of, 297
 - curve of, 291, 298, 299
 - method of, for specific heat, 300
- Copper, electrochemical equivalent of, 437, 564
- Corpuscular theory, 254
- Correction factor of ammeter, 387
 - for radiation, 291
 - of steam point, 266
- Cosines, table of, 574-5
- Coulomb*, 335
- Coulomb, the, 433
- Couple or Torque, 114
- Coupling, transformer, 529
- Critical angle, 200
- Crookes's tube, 449
- Crystal detector, 497-9, 502-3
- Current, electric, 371
 - field of straight, 374; circular, 378, 381
 - induced, 444
 - measurement of, 381, 408, 473; absolute, 475
 - saturation, 505
- Current, thermionic, 504
 - heating effect of, 440
 - unit of, 381, 433, 473
- Curvature, 38, 207, 208
 - measurement of, 38, 207, 208, 210, 219
 - of wave-front, 212
 - radius of, 36, 37, 206, 207, 208, 210, 211, 217, 219, 225, 228, 548-9
- Cusp of caustic, 204, 205
- D.C., direct current, 452-3, 459
- Damped wave-trains, 496-7
- Daniell, Alfred*, 176
- Daniell, J. F.*, 319, 372
- Daniell cell, 372
- Daniell's hygrometer, 319
- Declination, magnetic, 363, 565
- Deflection magnetometer, 337
- Deflection methods, 5
- Density, 36, 40, 184, 271, 561-2
 - and temperature, 276, 278, 285
 - relative, 40
- Detection of electro-magnetic radiations, 495-500, 538
- Detector, triode as, 530
- Deviation, 198
 - minimum, 199, 200, 239, 243, 298
- Dew point, 318
- Dewar's vacuum vessel or flask, 287, 296
- Diameter, measurement of, 46, 152, 564
- Differential wheel and axle, 82
- Diffraction grating, 257
- Dilatation, coefficient of, 275
- Dilatometer, 280
- Dimensions, physical, 39
- Diode, 505, 516, 517
- Dioptre, 38, 207, 212, 545
- Dip, magnetic, 353, 356, 454, 565
 - circle, 357
- Disk, moment of inertia of, 120, 560
- Displacement, a vector, 51
 - effective, 58
 - in S.H.M., 123
- Distance-piece, 224
- Dry cell, 372
- Dull-emitter valves, 506
- Dynamic equivalent of heat, 264, 310, 317
- Dynamic friction, 72-3
- Dynamics, 101
- Dynamometer, 313-4
- Dynamos, 456-461
- Dyne, the, 2, 76, 106
- Ear and eye estimations, 25
- Earth inductor, 454
- Earth, magnetic field of, 353
- Ebonite, 363
- Edison*, 505

- Efficiency, 77, 79
 of electric lamp, 443
 of motor, 462
Einstein, 254, 362
 Elasticity, 86, 163, 561
 Electric charge, 363-4, 367
 current, 364, 381
 potential, 367
 Electricity, 363, 364
 resinous (-), 363
 vitreous (+), 363
 Electrochemical equivalent, 433, 564
 of hydrogen, 433, 564
 of copper, 437, 564
 of silver, 433, 564
 Electrodes, 432, 449
 Electrolysis, 432
 Electrolyte, 432
 Electrolytic bath, cell or vat, 432
 Electromagnet, 373-4
 Electromagnetic, induction, 444, 446
 machines, 456
 radiation, 493
 unit of capacity, 470; current, 381;
 potential difference, 440-41, 457;
 resistance, 388
 Electromotive force, 372, 388, 395,
 444, 447, 452, 457
 forces, comparison of, 398; back,
 434
 oscillating, 448
 Electron, 254, 362, 364, 450, 504, 561
 Electron volt, 561
 Electrophorus, 366
 Electroscopes, 364
 condensing, 369
 Electrostatics, 363
 Elements, table of, 566-7
 Ellipse, area of, 35
 Emission of electrons, 504
 Emitter, bright and dull, 506
 Energy, conservation of, 8, 11, 77, 97-
 99, 104-5
 heat, 310-17, 440
 kinetic, 99, 104-5, 112, 114
 of strained body, 97, 99
 potential, 99, 104
 surface, 150
 units of, 2, 76, 97, 440
 Engine, 77
 Equilibrant, 52
 Equilibrium, 51, 59
 Equivalence of mass and energy, 362
 Equivalent, chemical, 432
 electro-chemical, 433
 mechanical, of heat, 264, 310, 317
 water, 286
 Erg, the, 2, 76, 97
 Exercises, additional, electricity, 540
 heat, 323
 light, 260
 magnetism, 359
 properties of matter, 159
 Exercises, sound, 187
 Expansibility of gases, 137
 Expansion, linear, 89, 273, 562
 cubical, 277-8
 apparent, 280
 of gases, 280
 of liquids, 275
 Exponential law, 74, 298
 Exposure, photographic, 253
 Eye and ear estimations, 25
 Eye-lens, 22, 23, 231-2, 234
 Eye-ring, 233

 F. See Farad
 F.P.S. units, 2, 560
 Factor of galvanometer, 383, 389
 Farad, the, 470
Faraday, Michael, 363, 432, 444, 458
 Faraday, the, 433, 561
 Faraday's Ice-Pail, 366
 Law, 444, 457
 ring transformer, 451
 Field, magnetic, 327, 328, 338
 earth's, 330, 353, 355
 of bar magnet, 331, 333, 340
 of circular coil, 378
 of current, 373, 374, 378
 of single pole, 331, 339, 349
 of solenoid, 373
 Fields, comparison of magnetic, 339,
 343, 347
 Figure of merit of galvanometer, 477
 Filament, 506
 Fission, nuclear, 362
 Fixed points of thermometer, 266
 Flame spectra, 246, 563
Fleming, Sir Ambrose, 457, 496, 506
 Fleming's rules, 458
Fletcher, W. C., 106
 Fletcher's trolley apparatus, 106
 Flicker Photometer, 248
 Fluorescence, 450-1
 Flux, luminous, 247
 magnetic, 444, 447
 Flywheel, Moment of Inertia of, 115-19
 Focal length, concave mirror, 206-7,
 209, 210, 219, 225
 convex mirror, 206-7, 210, 217-19
 lens, 211, 212, 219, 220, 222, 267,
 291
 concave lens, 213, 215, 220, 228
 convex lens, 213, 220, 226, 228
 Focal plane, 212, 234
 power, 212
 Focus, adjustment of, 23
 conjugate, 209, 214
 principal, 206, 211, 212, 220
 Foot-candle, 247
 Foot-pound-second units, 2, 560
 Force, 51, 53, 69, 76, 101
 in S.H.M., 125
 moment of, 59
 unit of, 76, 102

- Force, magnetic, 327 ; Law of, 381 ;
 tractive, 335
Force Ratio, 78, 79
Forces, composition of, 52-8
 parallel, 63
Fortin's Barometer, 139
Fraunhofer lines, 246, 563
Freezing point or Ice point, 265, 267
Frequency, 123, 162, 164-5, 169, 171,
 175, 177, 462, 468, 501
Fresnel, 254
Friction, 171, 311
 between metal cones, 311
 correction for, 108, 110, 117
 in Callendar's apparatus, 313
 of rope over pulley, 74
Frictional electricity, 363
Fringes, diffraction, 257
Fulcrum, 60
Fundamental physical contacts, 561
Funicular polygon, 69
Fusion, latent heat of, 292
- Galvanometer, ballistic, 451, 478
 constant of, 382-3, 475
 damping oscillations of, 481
 dead-beat, 480
 factor of, 383, 389
 Helmholtz, 439
 low resistance, 477
 reduction factor, 383, 389
 resistance of, 392, 418, 422
 sensitivity of, 475, 480
 shunt for, 329, 420
 suspended coil, 478
 suspended needle, 475
 tangent, 380, 381, 383, 473
Gas constant, 285, 561
Gases, 188, 137, 280, 562
 electric conductivity, 450
 expansion of, 281, 285
Gauguin, 474
Gauge, micrometer screw, 21
Gauss, Johann K. E., 353
Gauss, the, 328
Gearing wheel, 84
Gee, W. W. Haldane, 380
Generation of electrical oscillations,
 534
Glass, electrical charge on, 363-4
 thermal conductivity of, 309
Glow, negative, 449
Gold-leaf electroscope, 364, 368
Gradient, temperature, 304
Graduation of thermometer, 268, 270
Gram, the, 2, 10, 76
Gram-molecule, 285
Graphic methods, 4, 9, 85, 69, 197,
 200, 226, 267, 550
 Statics, 69
Graphs, 9, 131, 135, 245, 267-8, 291,
 298-9
Grating, diffraction, 257
- Gravity, acceleration due to, 76, 106,
 108, 111, 130, 131-3, 135-6
 Centre of, 63, 65
Grease-spot Photometer, 250
Grid, of a valve, 506
 -bias, 508-9
 -circuit, 533
 -coupling condenser, 534-5
 current, 507, 523
 potential, 507
Grove cell, 372
Gun, electron, 510
- H, determination of, 353
 horizontal magnetic field, 331, 565
 the henry, 447
Half-wave rectification, 497
Hammer-break, 448
Hard valves, 509
Hare's apparatus, 49
Harmonic vibrations, 176
Harmonograph, 179
Heat, as a form of energy, 264
 latent, 292, 294
 mechanical equivalent of, 264, 310,
 317, 440
 quantity of, 264, 286
 unit of, 286-7, 310
Heating effect of electric current, 440-
 443
Height, measurement of, by barometer,
 142 ; by sextant, 195
Helmholtz galvanometer, 439, 473-5
Henry, the, 447
Hertz, 449, 493
Hertzian Waves, 483
Heterodyne beats, 538-9
Hibbert's Magnetic Balance, 346
Hicks's Ballistic Balance, 103
High-frequency oscillations (electrical),
 448, 492-5, 500-3, 534-9
Hooke, Robert, 86, 254
Hooke's Law, 86, 88, 96
Horizon, artificial, 195
Horizon-glass, 194
Horizontal component, 353
Horse power. *See* Activity
Hughes, 493
Humidity, 318
Huygens, Christian (1690), 254
Hydrogen, electrochemical equivalent
 of, 433, 564
Hydrometers, 46-8
Hydrostatic balance, 43-4
Hygrometry, 318, 321-2, 563
Hypsometer, 266-7
Hysteresis, 511
- Ice, latent heat of fusion of, 292
Ice-Pail, Faraday's, 366
Ice Point, 265, 561
Illumination, 247, 252

- Image, optical**, 190, 191, 193, 545, 555
 real, 190, 208, 209, 213
 virtual, 190, 210, 213
Impedance, 463-4
 of valve, 521-3
Inclination. *See* Dip
Inclined plane, 56-7, 73-4
 solid rolling on, 118
Index glass, 194
Induced currents, 444
Inductance, 446
Induction, electrostatic, 365, 367
 coil, 447
 electromagnetic, 444
 laws, 444-6
 mutual, 446
 self, 444, 448
Inductor, 465
 Earth, 454
Inertia, Moment of, 87, 112, 114, 354, 560
Insulator, 363
Intensity, luminous, 247
 magnetic, 327, 505
 of illumination, 247
 of magnetisation, 355-6
 of sound, 162
 source, 247
Interrupter, 448-9
Interval, musical, 165
Ionisation effects in valves, 511
 in gases, 511, 513
Ions, 432, 512
Isothermal, 285
Isotopes, 362, 566-7
Jolly, 97, 283
Joly's Photometer, 251
Joule, J. P., 264, 310, 317, 440, 442
Joule, the, 2, 11, 76, 264, 310, 440, 441
Joule's equivalent, 264, 310, 317
Joule's Law, 440
Kater's Pendulum, 135
Kathode. *See* Cathode
Kation. *See* Cation
Kelvin, Lord, 285, 413, 430
Kelvin, the, or kilowatt hour, 440
Kelvin or Absolute scale of temperature, 285, 561
Kelvin's method for galvanometer resistance, 413, 418, 422
Kelvin's Double Bridge, 430
Keys, electric, 486
Kilogram, 2, 10, 106
Kilowatt, the, 440-41
Kinetic energy, 99, 104, 112, 114
Kinetic friction, 72
Kirchhoff, Laws of, 394, 414, 431
Kundt's tube, 173
Lag, 464
Lamp, electric, 247, 249
 Pentane, 247. *See* Photometry
Lantern, optical, 237
Latent heat, 292, 294
Lead, 464
Least Count, 17
Leclanché cell, 372
Lees, C. H., 306
Lenard, 449
Length, measurement of, 5, 6, 10, 11, 16, 19, 23, 46
 unit of, 2, 5, 6, 560
Lens, 211, 219, 278, 545-556
 converging, 211, 226
 diverging, 211
 (See Focal Length)
 magnifying power of, 230, 551
 projection, 237
 refractive index of, 222
Lenz, law of, 452
Lever, 60-62
Leyden jar, 449, 492-3
Limit, elastic, 86, 89
Lines of magnetic force, 328, 373-4
 induction, 328, 444
Link polygon, 69
Lissajou, J. A., 176, 179
Lissajou's figures, 176, 179; 510
Lodestone, 326
Logarithmic law, 74, 298
 tables, 7-8, 568-9
Logarithms, 10, 574
Loudness, 162
Lumen, 247
Lummer-Brodhun Photometer, 251
Lux, 247
M.K.S. units, 2, 11, 76, 106
Machines, 77, 108
 electric influence, 366
Magnet, 326, 327, 336
 ball-ended, 327, 331
 bar, 327, 332, 335
 oscillating, 128, 347, 354, 376
Magnetic action of current, 373
 axis, 327, 334
 balance, 346
 detector, 495
 elements, 565
 field, 327, 328, 374
 flux, 444
 meridian, 327, 334
 observatories, 565
 pole, 327, 331, 339
Magnetite, 326
Magneto-dynamo, 461
 -machine, 459
 -motor, 461
Magnetometer, deflection, 337, 376, 379, 380, 382-3
 mirror, 337
 oscillation, 354
Magnification, linear, 237, 552
Magnifying power of lens, 230, 551-2
 microscope, 22, 231, 551-2

- Magnifying power of telescope, 234, 551-2
- Mains, lighting, 490
- Mance's method, 414, 418, 423
- Marconi, 495
- Mariotte, 137
- Mass, measurement of, 5, 6, 12
unit of, 2, 10, 11, 560
- Mass number, 362, 566-7
and weight, 12, 85, 106
- Mathematical Tables, Appendix, 559
- Maxwell, Clerk, 5, 254, 327, 493
- Maxwell, the, 447
- Mayer, J. R., 264
- Mechanical, advantage, 78
equivalent of heat, 264, 304, 310, 317
powers. *See* Machines
- Melde's experiment, 185, 468
- Melting point, 270, 284, 299
- Mensuration, 559
- Mercury, angle of contact, 157
capillarity, 139, 151, 152
- Meridian, magnetic, 327, 334, 353, 382
- Metre, 2, 11, 23, 560
Bridge, 414, 417
- Metric measures, 2, 560
- Microfarad, the, 470
- Micrometer eyepiece, 22, 153, 269
screw, 20, 274
- Micromillimetre (10^{-6} mm.), 245, 563
- Microscope, 22, 203, 231
micrometer, 22
travelling or vernier, 22, 152, 269, 274
- Milliammeter, 384, 387
- Mirror, plane, 192, 553-4
concave, 206, 208, 210, 225, 545, 548-9
convex, 206, 210, 217, 545, 548-9
rotation of, 193, 337
sphere on concave, 131
- Mixtures, method of, in electricity, 472
in heat, 286
- Modulated wave, 498, 539
- Modulus, Bulk, 88
of Elasticity, 86
of Rigidity, 87, 93, 136, 561
Young's, 87, 88, 91, 92, 174, 561
- Mole or Gram-molecule, 285, 561
- Molecular, weight, 285
- Molecule, 151, 434
- Moment, of a force, 59, 60
of Inertia, 67, 112, 114, 354, 560
of Momentum, 112
- Moments, magnetic, 332-3, 351
comparison of, 340, 343
- Momentum, 101
Angular, 112, 114
Conservation of, 102
Electrical, 492
- Monochoord, 181
- Motion, angular, 112, 114
linear, 114
- Motors, 456-61
- Multiple-electrode valves, 508
- Music, 162
- Musical scale, 164
- Mutual induction, 544
- Napierian logarithms, 74
- Neon lamp, 246
time base, 514
tube, 513
- Neumann, 444, 457
- Neutral point, 329, 331, 332, 375
- Neutron, 362
- Newton, Sir Isaac, 239, 254
the newton, 2, 106
- Newton's Laws of Motion, 101-106
Law of Cooling, 297
rings, 255
views of nature of light, 254
- Nicholson's hydrometer, 47
- Nichrome, 487-8
- Noakes, G. R., 190
- Node, 167, 174
- Non-conductors, 363
- Note-books, 4
- Null methods, 5
- Object glass or objective, 231, 234, 237
- Observatories, magnetic, 565
- Oersted, Hans Christian, 448
- Oersted, the, 328
- Ohm, the, 388
coil, construction of, 426
- Ohm's Law, 388, 411
departure from, 496, 499
- Omega or Ω . *See* Ohm
- Onesti, 493
- Optic centre, 212, 546
- Optical bench, 224
instruments, 230, 551
lantern, 237, 552
- Optics, geometrical, 190, 191; Supplement, 545
- Ordinate, 9
- Oscillations of a magnet, 128, 347, 353-354, 376
of a material body, 24-6
of a quartz crystal, 26
high-frequency electrical, 448, 492-495, 500-3, 534-9
- Oscillator, 534-7
- Oscillograph, cathode ray, 179, 509
- Oscilloscope, 509
- Paraffin-wax photometer, 251
- Parallax, 17, 191, 265, 337, 364
- Parallel, resistances in, 391-2
- Parallelogram, of forces, 51, 55
of vectors, 51
- Paraxial rays, 548
- Pendulum, Blackburn's, 178
- Pendulum, Kater's, 135
- Pendulum, Shortt's, 26
- Pendulum, simple, 24, 126, 129, 130

- Pendulum, compound, 127, 133
 simple equivalent, 133
 torsion, 128, 136
 Pentane lamp, 302
 Period, 123, 125-30, 133-6, 176, 181
 of oscillating magnet, 128, 347
 Periodic motion, 123, 126, 162, 163,
 171, 180, 254
 Permeability, 447
 Perrin, 449
 Phase, 123
 Photo-electricity, 253
 Photography, 240, 253, 328, 450
 Potometer, 248
 Bunsen's, 250
 Flicker, 248
 Illumination, 252
 Joly's, 251
 Lummer-Brodhun, 251
 Rumford's, 249
 Swan's, 251
 Photometry, 190, 247, 252, 253
 Photon, 254
 Physical constants, 561
 Pitch, of musical note, 162, 164-5, 184-
 185
 of screw, 20, 83-4
 Planck's constant, 254
 Plane, static inclined, 56
 focal, 212
 principal, 213
 Planimeter, 29
 Plastics, 556
 Plotting magnetic fields, 328, 374, 378
 Pohl's commutator, 582, 584
 Polarisation, 371, 398, 481, 556
 Polarity, tests for, 370, 374, 432, 480-91
 Polaroid, 556
 Pole, magnetic, 326, 327, 349-51
 of cell, 370, 374, 432, 490-91
 Polygon, link or funicular, 69
 of forces, 53, 69
 Post-Office Box, 419
 Potential, 367
 difference, 369, 371, 535, 571
 divider, 407, 465
 Potentiometer, 400, 406, 407
 Pound, 2, 560
 Poundal, 2
 Power. *See* Activity
 Power supply for A.C., 519
 Power, Weight and, 85
 Pressure, 42
 atmospheric, 49, 137, 266
 correction of boiling point for, 266-8
 definition of, 42
 in soap bubble, 153
 of aqueous vapour, 318, 528, 563
 of gases, 137, 138, 339, 144, 149
 of liquid column, 48
 units of, 42, 175, 176
 vapour, 383
 Primary cell, 371, 372
 Primary coil, 444-8
 Principal plane, 212
 Prism, 198, 241, 242
 Projection, optical, 237
 Proton, 254, 362, 561
 Pulsatance, 124, 177, 462
 Quality of sound, 162
 Quantity of electricity, 366-7
 of motion, 101
 Quantum, 254
 Quartz, fused, 364
 R, the gas constant, 285, 561
 Radiating circuits, 500-503
 Radiation, 254
 correction for, 291
 Radio, 494
 Radioactivity, 515
 Radius of curvature, 36, 37, 206, 217,
 219
 gyration, 113
 mirror, 206
 Ramsden circle, 233
 Rate of cooling, 298
 Rate of working. *See* Activity
 Ratio, Force, 78
 Velocity, 78-9
 Ray of light, 190
 Ray, in-, 212
 out-, 211
 Rayleigh, potential divider, 408
 Rays, cathode, 449
 Röntgen, 450
 X-, 450
 Reactance, 463
 Reaction coil, 534
 Receiving circuits, 500-503
 Records of results, 4
 Rectification of A.C., 453, 496
 of oscillations, 495-500, 517-8
 Rectilinear figure, 27
 propagation, 191
 Reflection, at plane surface, 192, 553
 caustic by, 204
 from face of lens, 228
 Laws of, 192
 total internal, 200
 Refraction, at plane surface, 195
 caustic by, 205
 index of, 196, 198, 199, 201, 202,
 205, 221, 222, 563
 Laws of, 195
 through glass block, 197
 through prism, 198
 Regnault, H. V., 266
 Regnault's apparatus for specific heat,
 288-290
 hygrometer, 319
 Relativity, 362
 Residual charge, 492
 Resistance, 383, 388, 411
 box, 385, 488

- Resistance, carbon, 489
 coil, 426, 488
 frame, 489
 grid, 490
 high, 430
 internal, of cell, 397, 402, 405, 406,
 414, 418, 423
 lamp, 490
 low, 430
 of a cell, 395, 397, 414, 418, 423
 of a circuit, 388
 of galvanometer, 413, 418, 422
 of wire, 416, 417, 421
 specific. *See* Resistivity
 temperature coefficient of, 427, 564
 unit of. *See* Ohm
 Wheatstone's, 489
 Resistances in series and in parallel,
 391
 comparison of, 429
 Resistivity, 416, 417, 487-8, 564
 Resistor, 383, 388, 411, 487
 Resolution of vectors, 55
 Resonance, 165, 500
 tube, 167
 Resultant, 51
 Retroaction coil, 535
 Rheostat. *See* Resistance and Resistor
 Richardson, *L. F.*, 121
 Rigidity, Modulus of, 87, 93, 136, 561
 Rings, Newton's, 255
 Robinson ray track apparatus, 190
 Robison, *John*, 171
 Röntgen rays, 450
 Root mean square, 463
 Rotation of rigid body, 59-60, 112, 114
 of mirror, 193
 Routh's rule, 560
 Rubber, thermal conductivity of, 308
 Ruhmkorff's coil, 448
 Rumford's Photometer, 249
 Rutherford, *Lord*, 362

 S.H.M. *See* Simple Harmonic Motion
 Sagitta of arc, 35, 252
 Saturation Vapour Pressure, 318, 563
 Scalars, 51
 Scale, musical, 164
 Scale of temperature, 264-5, 285
 Screw, 83
 micrometer, 20-21
 Searle's oscillating needle, 348
 torsion balance, 155
 Second, mean solar, 2, 10, 11, 24
 Secondary cell, or accumulator, 370,
 372, 405, 491
 coil, 444-7
 Seebeck, *L.*, 171
 Self induction, 444, 448
 Sensibility, of balance, 16
 Sensitiveness, 6
 Sensitivity of galvanometer, 476
 Series, resistances in, 391
 Series-winding, 450
 Sextant, 194
 Shadow photometer, 249
 Shear, 87, 93
 Short-circuiting, 372
 Shunt, galvanometer, 329, 420
 Shunt-motor, 462
 Shunt-winding, 459
 Signs, in optical formulae, 190, 206,
 210, 545
 Silica, 364
 Silver, electrochemical equivalent, 433,
 564
 Simple Harmonic Motion, 123
 Simpson's Rules, 28-9
 Sines, table of, 572-3
 Siren, 171
 Slide-rule, 8
 Slide-wire Bridge, 414, 417
 Slope, temperature, 304
 Smoothing filter, 519
 Soap solution, 154
 surface tension of, 154, 155
 Soft valves, 509, 511-12, 515
 Solenoid, 373-4, 444
 Sonometer, 181
 Sound, 161-87
 Sources of light, 225, 239, 241, 242, 246,
 248-9, 556
 Space-charge, 506
 Space, image, 553-5
 object, 553-5
 Spark, 448-9
 Spark spectra, 246
 transmitter, 498
 Spatial system, 553-5
 Specific Gravity or Relative Density,
 40
 bottle, 40
 by Archimedes' principle, 44-8
 Specific Heat, definition, 286
 of solid, 287
 of liquid, 290, 300
 table of, 562
 Specific Resistance, 416, 417
 table, 563
 Spectrometer, 240, 245
 Spectroscope, 240
 Spectrum, 239
 map of, 245
 Sphere, 36-39, 206-8, 559, 560
 Spherometer, 36-9, 208-9, 222, 274
 Spring, calibration of, 96
 balance, 97
 energy of, 97
 oscillating, 129
 State, change of, 292, 294
 Static Friction, 72
 Statics, 51
 Steam, latent heat of, 294
 Steam Point, 265-8
 Stefan's Law, 297
 Stem Exposure, effect of, 266

- Stewart, Balfour*, 380
 Straight current, 374
 Strain, 86
 Energy of, 97
 Stress, 86
 Strings, vibrations of, 180, 468
 Substitution, method of, 16, 23, 390-91
 Super-cooling, 300
 Surface Tension, 46, 49, 139, 150
Swan, William, 251
 Swan's Photometer, 251
 Switch, 385, 486-7
 Symmetric points, 227, 238

Tait, P. G., 137
 Tangent galvanometer, 381, 473
 Tangents, table of, 576-7
 Telescope, 219, 234, 241-2
 Temperature, absolute, 285
 and barometric height, 142
 and pressure, 280, 285
 and resistance, 427
 and the velocity of sound, 163
 measurement of, 264, 265
 Scale of, 264, 265
 gradient, 304
 slope, 304
 Tension, Surface, 46, 49, 139, 150
 Thermal capacity, 286, 562
 conductivity, 304, 562
 Thermionics, 504
 Thermocouple, 409, 410
 Thermoelectricity, 409
 Thermometer, calibration of, 269
 constant volume, 265-82
 fixed points, 266
 hydrogen, 265
 mercury in glass, 265
 platinum, 517
 weight, 279
 wet and dry bulb, 321
 with arbitrary scale, 270
 Thermometry, 264, 265
 Thermopile, 409
Thomson, Sir Joseph, 450
Thomson, Sir William. See Kelvin
 Three-electrode valve, 506, 520, 534, 536
 Thrust, 42-3, 71-2
 Time, measurement of, 5, 6, 10, 24, 130
 unit of, 2, 11
 Time-base, 510
 Torque. See Couple
 Tourmaline, 556
 Traces, vibration, 121
 Tractive force of magnet, 335
 Transformer, 407, 451, 465
 Transformer coupling, 529
 Translation, 114
 Transmitter, spark, 498
 Triangle of forces, 52, 55
 Triode, 506, 515, 520, 524, 534

 Trolley, Fletcher's, 107
 Tuned electrical circuits, 500-503, 534-537, 538-9
 Tuning, notes on, 185
 Tuning-fork, frequency of, 169, 170, 172
 Turn-table, 219
 Twisting a wire, 93-6
 Two-electrode valve, 505, 516

 Ultra-violet light, 450
 U-tube barometer, 139
 U-tube method for specific gravity, 48-9
 Undulatory theory, 254
 Units, fundamental and derived, 10, 50
 dynamical, 76
 gravitational, 76
 systems of, 2, 10
 Upthrust, 42-3
 Uranium, 362

 Vacuum, production of, 26
 Vacuum tube, 246, 449-51, 505-11, 511-512
 Valency, 432-3
 Valve, oscillation, 496
 thermionic, 504
 two-electrode, 505
 three-electrode, 506-9
 Valves, hard and soft, 509, 511-12, 515
 Vaporisation, latent heat of, 294
 Vapour pressure, 318
 aqueous, 318, 322, 563
 Variables, 9
Varley, 493
 Vectors, 51
 Velocity, 101, 104, 105
 angular, 112, 114, 116, 118
 of light, 561
 of sound, 163, 165, 168, 170
 of transverse waves, 180
 Velocity Ratio, 78-9
Vernier, P., 17
 Vernier callipers, 19
 microscope, 22
 principle of the, 17
 Vertical magnetic force, 565
 Vibrations, 24-6, 107, 123, 126
 electromagnetic, 448, 492-5, 500-3, 534-9
 forced, 166
 free, 166
 harmonic, 176
 longitudinal, 167
 of strings, 181
 resonance, 501-2
 stationary, 166, 181
 transverse, 180, 556
 Vibrator, 468
 traces, 121, 172-4
 Vision, least distance of distinct, 230, 236, 551

- Volt, the (V or v), 372, 388
 Volta's cell, 371, 395, 440
 Voltameter, 432
 Voltameter, hydrogen, 434, 436
 copper, 437
 Voltmeter, 403, 483
 internal resistance by, 404
 resistance of, 483
 Volume, measurement of, 8, 36, 45, 80
 of one mole, 561
 of a gas, 280, 435, 436
 units of, 50
Voss, 366
 Vulcanite, 363

 Water, latent heat of, 292
 Water equivalent, 286, 296
 vapour, 318, 322, 563
 Watt, the (or w), unit of activity, 76,
 440-41
 Wave, 162, 163, 167
 Wave-form, 162
 Wave-length, 163, 165, 256, 258, 450
 table, 563
 Wave theory, 212, 254, 556
 Waves, electromagnetic, 450
 transverse, 180, 468, 556
 Wave trains, 496-7
 Weber, the, 447
 Weighing, 12, 15, 71, 184
 Weight and mass, 12, 85, 106
 Weight thermometer, 279
 Weights, care of, 14

 Weston cell, 372
 Wet and dry bulb hygrometer, 321
 Wheatstone's bridge, 6, 411, 471, 474
 Rheostat, 489
 Wheatstone commutator, 489
 Wheel and axle, 82
 on inclined plane, 118
 Wheel gearing, 84
Wilson, W., 241
Wimshurst, 366
Wood, *Alexander*, 162
 Work, or energy, 2, 8, 11, 58, 77, 97, 310
 and heat, 310
 done by couple, 311-12
 unit of, 2, 11, 76, 97
 measurement of, 58, 97-9, 112, 114,
 440-41

 X-rays, 450

 Yard, 23
Young, *Thomas*, 254
 Young's Modulus, 87, 88, 91, 92, 561
 for a beam, 91
 for a cantilever, 92
 for a rod, 174-5
 for a wire, 89

 Zero circle of planimeter, 32
 error, 19, 21, 267
 Zero of temperature scale, 266, 561
 Absolute, 285, 297, 561
 Zero, working to a false, 13

THE END

